

# Pump and General Supply Catalogue

LIBRARY OF CONGRESS.

TJ3902

Chap. \_\_\_\_\_ Copyright No. \_\_\_\_\_


Shelf, G 7 13402

UNITED STATES OF AMERICA.










NEW PLANT OF THE GOULDS MFG. CO., ERECTED FOR THE MANUFACTURE OF THEIR CELEBRATED  
TRIPLEX POWER PUMPS.

THE WENBORNE-SUMNER CO.,  
PRINTERS AND BOOKMAKERS,  
BUFFALO, N. Y.

THIRTY-EIGHTH EDITION.  
COPYRIGHT, 1900, BY  
THE GOULDS MANUFACTURING COMPANY,  
SENECA FALLS, N. Y., U. S. A.






PARTIAL VIEW OF THE GOULDS MANUFACTURING COMPANY'S WORKS, SENECA FALLS, N. Y., U. S. A.

Works Founded in 1848.

## CATALOGUE "B"



## PUMPS and HYDRAULIC MACHINERY

✕ FOR EVERY SERVICE ✕

## Well Points and Well Supplies

IRON PIPE AND FITTINGS,

Brass Goods, Belting, Packing and Hose,

Engines and Boilers, General Supplies.

✓  
THE GOULDS MANUFACTURING CO.

Works and Main Offices: SENECA FALLS, N. Y., U. S. A.

Warerooms: 16 Murray St., NEW YORK.

## PRINCIPAL BRANCHES AND AGENCIES:

THE GOULD CO., 22-24 North Canal St., Chicago, Ill.  
 THE GOULDS MFG. CO., Power Pumps, 8 Oliver St., Boston, Mass.  
 SMITH & THAYER CO., Hand and Windmill Pumps,  
 236 Congress Street, Boston, Mass.

SCIPLE PUMP CO., 107 North Third St., Philadelphia, Pa.  
 N. O. NELSON MFG. CO., 8th and St. Charles Sts., St. Louis, Mo.  
 WOODIN & LITTLE, 312 Market St., San Francisco, Cal.  
 REINEKE, WILSON & CO., 13 Wood St., Pittsburg, Pa.

## TO THE TRADE.

WE TAKE pleasure in presenting this complete catalogue of Pumps and Hydraulic Machinery for every service, Pump Supplies, Well Tools, etc. Our Pumping Machinery has been on the market for fifty-two years; we have largely increased our facilities for manufacture, and shall endeavor to maintain the acknowledged quality which has made "Goulds Pumps" the Standard of the World for more than half a century. We also publish special catalogues devoted exclusively to "Efficient Power Pumps and their Applications," "Irrigating Pumps, Horse Powers, etc." "Spray Pumps," and will cheerfully furnish same upon application.

Soliciting a continuance of your favors, we are,

Respectfully,

SEABURY S. GOULD, *President.*  
W. P. WHITE, *Vice-President.*

JOSEPH J. SWABY, *Treasurer.*  
H. P. USHER, *Secretary.*

THE GOULDS MANUFACTURING CO.

## TERMS:

THIS PRICE LIST CANCELS all former ones and is subject to change without notice.

ALL ORDERS will be filled from stock as per catalogue unless we are expressly directed otherwise.

IN MAKING REFERENCE to any of our goods, either for the purpose of inquiry or in orders, always give the catalogue figure.

GENERAL DISCOUNT SHEETS will be furnished to the Trade only, and are subject to change without notice.

NO CLAIMS FOR ALLOWANCE will be entertained unless presented on receipt of goods; neither will we hold ourselves responsible for breakages after goods are delivered in good condition to the Railroad Company.

WITH INFORMATION AT HAND AS TO REQUIREMENTS and conditions of work, we shall be pleased to make recommendations and estimates on any Pumping outfit, and if Pumps are properly set up and cared for, will guarantee their performing all we claim for them.

ORDERS FROM STRANGERS or parties unknown to us and having no commercial rating, must be accompanied by cash or satisfactory references.

ERRORS AND OMISSIONS in this catalogue excepted.

0-5944

IG 78  
G 69  
1900



# ALPHABETICAL INDEX.

V

	PAGE.
<b>A</b> CME Elevator Buckets.....	521
“Advance” D. A. Force Pump.....	28, 29
Agitators for Spray Pumps.....	262
Air Chamber.....	81
Air Cock.....	460
Air Pumps.....	245 to 250
Air Valves .....	379
“Albany” D. A. Force Pump.....	139
Alert D. A. Hand Force Pump.....	139
“Alert” D. A. Power Force Pump.....	174
Alligator Wrenches.....	488
Altitude Gauges.....	470
Always Ready Wrenches.....	488
Ammonia Pump, Triplex.....	232
Angle Check Valves, Brass.....	369
Angle Check Valves, Brass Jenkins' Disc.....	372
Angle Check Valves, Iron Body.....	383
Angle Valves, Brass.....	369, 370
Angle Valves, Brass, Asbestos Disc.....	371
Angle Valves, Brass, Jenkins' Disc.....	372
Angle Valves, Iron Body.....	381, 382
Angle Valves, Iron Body, Asbestos Disc .....	387
Angle Valves, Iron Body, Jenkins' Disc.....	386
Angle Valves, Lunkenheimer .....	424
Angle Valves, Lunkenheimer, Composition Disc .....	427
Anti-Freezing Well Pumps .....	8 to 29
Anti-Freezing W. M. Force Pump Heads.....	50 to 55
“Apollo” Grease Cups.....	443
Areas of Circles.....	570
Armstrong's Stocks and Dies.....	483
Artesian Steam Working Head.....	113
Artesian Pump Cylinder.....	67 to 69
Artesian Well Casing Sockets .....	320
Artesian Well-Working Head.....	58, 59
Asbestos Disc Valves, Brass.....	371
Asbestos Disc Valves, Iron Body .....	387
Asbestos Packed Iron Cocks.....	387
ASBESTOS GOODS:	
Cement .....	538
Mill Board .....	538

## ASBESTOS GOODS.—Continued.

	PAGE.
Packing, Wick .....	538
Packing, Steam Rope.....	538
Paper.....	538
Pipe Covering, Asbestos and Hair Felt.....	538
Pipe Covering, Asbestos and Woolen Felt.....	538
Pipe Covering, Asbestos Moulded.....	539
Pipe Covering, “Eureka” .....	539
Pipe Covering, “W. B.”.....	539
Sheathing... ..	538
“Atlantic” D. A. Force Pumps.....	86, 87
Auger, Clay.....	309
Auger, Cobble Stone.....	309
Auger, Earth and Sand.....	309
Automatic Air Valves.....	381
Automatic Grease Cups, “Ideal”... ..	441
Automatic Grease Cups, “Jewel”... ..	442
Automatic Needle Valve Oil Feeder.....	437
Automatic Shut-off Valve.....	131
Automatic Switches, Electric.....	206, 207
Automatic Water-Lifter .....	131
Automobile Tire Pump.....	249, 250
“Aura” Well Force Pump.....	23
Awl, Belt.....	532
<b>B</b> ABBITT Ladles.....	421
Babbitt Metals.....	421
Babcocks Pipe Puller.....	312
Back Outlet Return Bends, C. I.....	335
Back Pressure Valves, Iron Body.....	388
Back Pressure Valves, “Davis” .....	388
Bailing Pumps.....	187, 235
Balance Water Gauge .....	470
Ball Check Valves. ....	425
Balls, Brass .....	425
Balls, Copper.....	404
Balls, Fuller.....	537
Ball Cocks.....	410
Ball Gauge Cocks.....	461
Ball and Socket Hangers.....	519

	PAGE.		PAGE.
Ball and Socket Post Hangers.....	520	Blow Off Valves.....	391
Bamboo Extension.....	266	Boiler Feed Pumps, Triplex Power.....	181 to 186
"Banner" Drive Well Point.....	297	Boiler Feed Pumps, Hand.....	237, 238
"Banner" Lubricators .....	440	Boiler Feed Pumps, Power.....	181 to 186, 238, 239
Barnes Pipe Cutter .....	491	Boiler Feed Pump, Steam.....	240
Barrel Pumps, Rotary .....	155	Boilers.....	544 to 550
Barrel Spray Carts.....	261	Boilers, Farm.....	544
Barrel Spray Pumps.....	254 to 257, 259	Boilers, Range.....	422
Barometric Pressure at Different Altitudes.....	569	Boilers, Tubular.....	549, 550
Bases for Valve Boxes .....	402	Boilers, Vertical.....	545 to 547
Beading Tools.....	494	Boilers, Vertical with Engine.....	545, 546
Beam Hooks.....	337	Boiler Fittings.....	355
Bells, Meneely.....	568	Boiler Stands.....	422
Bells, Steel Amalgam.....	285	Boiler Makers' Ratchets.....	494
Belt Awl.....	532	Boiler, Oil Injectors .....	438
Belt Fasteners.....	532	Boiler, Tubes .....	318
Belt Hooks.....	532	Bolts, Carriage.....	543
Belt Lace Hole Protectors.....	532	Bolts, Elevator.....	521
Belt Lacing .....	532	Bolts, Machine.....	543
Belting, Cotton, Gandy.....	522	Boxes, Service.....	401
Belting, Cotton, Solid.....	523	Boxes, Valve.....	402
Belting, Leather.....	522	Boxes, Valve-Bases.....	402
Belting, Rawhide.....	523	Branch Tees, Cast Iron.....	336
Belting, Rubber.....	522	Brass Balls.....	425
Bemis & Call Wrenches.....	488	Brass Fittings.....	367
Bench Vise.....	485	Brass Floor and Ceiling Plates.....	339
Bends, Lead.....	417, 419	Brass Guards.....	473
Bends, Return, Cast Iron.....	334, 335	Brass Jacket Drive Well Points.....	294 to 298
Bibb Washers.....	537	Brass Oil Cups .....	469
Bibbs, Compression.....	407, 408	Brass Oilers.....	496
Bibbs, Fuller.....	409	Brass Perforated Sheet .....	301
Bibbs, Hose L. H.....	407	Brass Tubing.....	368
Bibbs, Plain, L. H.....	407	Brass Valves.....	369 to 378
Bicycle Pumps.....	248 to 250	Brass Wire Cloth.....	301
Bilge Pumps .....	142 to 151	Brewery Pumps.....	180 to 189
Bit Brace Tap.....	483	Brine Cocks.....	410
Blakeslee Jet Pump.....	475	Brine Pump, Triplex.....	233
Blind or Check Valve.....	309	Brown's Pipe Tongs.....	487
Block Tin.....	420	Brushes, Flue .....	495
Blocks, Pillow.....	518	Buckles, Strap.....	523
Blocks, Pulley.....	501, 502	Bucket Pump, Brass.....	252

	PAGE.
Buckets, Elevator.....	521
Burner Pliers.....	492
Burralls Corn-Shellers .....	286
Bushings, Brass.....	368
Bushings, Cast Iron .....	330
Bushings, Eccentric .....	330
Bushings, Hose.....	529
Bushings, Malleable.....	354
Bushings, Wood.....	503
Butterfly Valves, Brass.....	373
Butterfly Valves, Iron Body.....	385
By-Pass Valves, Mason.....	185, 392

CALDWELL Hose Straps.....	530
Candle Wick.....	538
Canvas Belt.....	522
Capacities of Different Standard Gallons of Water.....	569
Capacity of Pump, Table.....	570
Capacity of Pumps at 30 Strokes per Minute, Table.....	
Capacity of Tanks and Cisterns, Table.....	573
Caps, Brass.....	368
Caps, Cast Iron.....	329
Caps, Hose.....	529
Caps, Malleable.....	352
Carriage Bolts.....	543
Casing Sockets .....	320
Casing Fittings.....	320
Casing Inserted Joint.....	319
Casing Screw and Socket .....	319
Cast Brass Floor Plates.....	339
Cast Iron Fittings .....	327 to 349
Cast Iron Fittings, Extra Heavy.....	347
Cast Iron Fittings, Flanged.....	342 to 344
Cast Iron Fittings, Stock Sizes.....	348, 349
Cast Iron Floor and Ceiling Plates.....	338, 339
Cast Iron Pipe .....	313
Cast Iron Pipe Specials.....	314, 315
Caulking Tool.....	494
Ceiling Plates.....	338, 339
Ceiling Plates, Brass.....	339
Ceiling Plates, Russell's.....	339

	PAGE.
Cellar Traps.....	291
Cement, Asbestos.....	538
Cement, Gas Fitters'.....	499
Cement, Steam Fitters'.....	499
Centrifugal Pumps.....	168 to 173
Cess Pools.....	291
Cess Pool Pumps.....	147, 148
Chace's Zinc Oilers.....	496
Chain Tongs.....	487
"Challenge" D. A. Hand Force Pump.....	142 to 144
"Challenge" D. A. Power Force Pump.....	175
"Champion" Rod Oil Cups.....	451
Chandelier Hooks and Loops.....	354
Check Valves, Angle, Brass.....	369
Check Valves, Blind.....	309
Check Valves, Iron Body.....	383-384
Check Valves, Brass.....	369, 370
Check Valves, Brass Jenkins' Disc .....	372
Check Valves, Iron.....	72
Check Valves, Iron Body .....	383
Check Valves, Iron Jenkins' Disc.....	386
Check Valves, Swing, Brass.....	370
Check Valves, Swing, Iron Body.....	384
Check Valves, Lunkenheimer.....	425, 426
Check Valves, Lunkenheimer, Ball.....	425
Check Valves, Lunkenheimer, Swing.....	426
Chemical Pumps.....	231
"Chief" Injector.....	477
Chime Whistles.....	433, 462
Church Bells.....	285
Cider Press Screws .....	287
Cipher Code.....	XVI, XVII
Cipher, Pipe.....	316
Circulating Boiler Fittings.....	355
Circulating Pumps.....	169, 180
Cistern Suction Pumps.....	1 to 6
Clamps, Hose.....	530
Clamps, Hydrants.....	355
Clamps, Water Pipe.....	326
Classification Malleable Fittings.....	358
Cleaners, Flue.....	495



	PAGE.
"Clip" Gate Valves.....	428
Cloth, Brass Wire.....	301
Clutches, Friction.....	516
Cock Spout.....	81
Cocks, Air.....	460
Cocks, Ball.....	410
Cocks, Ball Gauge.....	461
Cocks, Brine.....	410
Cocks, Compression Bibb.....	81
Cocks, Compression Gauge.....	461
Cocks, Compression Sill.....	410
Cocks, Corporation.....	414 to 416
Cocks, Cylinder.....	461
Cocks, Gas.....	457 to 458
Cocks, Gas Stove.....	458
Cocks, Hydrant.....	404
Cocks, Iron.....	459
Cocks, Packed.....	387
Cocks, Meter.....	458
Cocks, Mississippi Gauge.....	469
Cocks, Rain and Well Water.....	410
Cocks, Service.....	457
Cocks, Sill.....	410
Cocks, Steam.....	456
Cocks, Steam Gauge.....	461
Cocks, Stop.....	403 to 406
Cocks, Syphon.....	475
Coe's Wrenches.....	488
Coins, Values of Foreign.....	575
Collars, Shafting.....	517
Columbia Pressure Recorder.....	472
"Columbus" Steel Sinks.....	288
Columns, Water.....	463
Combination Ferrules, Lead.....	419
Combination Steam and Water Gauges.....	464
Combination Water Pressure Gauge.....	471
Compression Bibbs.....	407, 408
Compression Gauge Cocks.....	461
Compression Radiator Air Valves.....	379
Compression Sill Cocks.....	410
Compression Stops.....	408

	PAGE.
Connection for Hose and Iron Pipe.....	265
Connecting Rod.....	70
Cookers, Feed.....	544
Cook's Seamless Brass Slotted Strainer.....	300
Copper Balls.....	404
Copper Ferrules.....	318
Corn Shellers.....	286, 566, 567
Corner Sinks.....	290
Corporation Cocks.....	414, 416
Cotton Belting, Gandy.....	522
Cotton, Belting, Solid.....	523
Cotton Hose, Rubber-Lined.....	524
Cotton Waste.....	499
Counters, Revolution.....	474
Counter Shafts.....	102, 103
Couplings, Brass.....	368
Couplings, Casing.....	320
Couplings, Hose.....	528
Couplings, Hydraulic.....	322
Couplings, Malleable.....	321
Couplings, Offset Reducing, Cast Brass.....	331
Couplings, Offset Reducing, Malleable.....	354
Couplings, Plain Brass.....	416
Couplings, Recessed.....	322
Couplings, Rod, Iron and Wood.....	302
Couplings, Shafting.....	517
Couplings, Special.....	322
Couplings, Standard, Pipe.....	321
Couplings, Well Tool.....	309
Coupling Wood Sucker Rod.....	70
Covered Crank Pumps.....	236
Coverings, Pipe.....	538, 539
Creamery Pumps.....	157, 236
"Crescent" Hydrants and Street Washers.....	280, 281
Crosby Pressure Recorder.....	472
Crosses, Cast Iron.....	329
Crosses, Extra Heavy.....	347
Crosses, Flanged.....	344
Crosses, Long Radius.....	341
Crosses, Malleable.....	352
Crossover Fittings.....	351

	PAGE.
Cross Valves, Brass.....	369
Cross Valves, Brass Asbestos Disc.....	371
Cross Valves, Brass Iron Body.....	381, 382
Cross Valves, Lunkenheimer.....	424
"Crown" Oil Cups.....	448
Curb Block.....	284
Curb Box, Adjustable.....	284, 401
Cutters, Glass Tube.....	473
Cutters, Lace.....	532
Cutters, Pipe.....	491
Cutting Pliers.....	492
"Cyclone" Spray Nozzles.....	264
Cylinder Cocks.....	461
Cylinder, Irrigation.....	89
Cylinders, Pump.....	61 to 69, 71
Cylindrical Glasses.....	455

<b>D</b> AVIS Back Pressure Valves.....	388
Davis Back Pressure Regulators.....	389
Deck Pumps.....	142 to 151
Deep Well Force Pump Standards.....	38, 39
Deep Well Power Working Heads.....	99, 104 to 112
Deep Well Pump Cylinders.....	61 to 69, 70
Deep Well Lift Pump Standards.....	34
Deep Well Steam Working Head.....	113
Deep Well Wind Mill Standards.....	44 to 55
Detroit Lubricators.....	467
Detroit Radiator Valves.....	377
"Dewey" Stock Fountains.....	567
Diameter of Cylinder, Extreme Outside.....	61
Diaphragm Force Pump.....	148
Diaphragm Suction Pumps.....	147
Die Stocks.....	480 to 483
Die, Taper.....	311
Differential Power Working Heads.....	104 to 112
Dises, Jenkins.....	386
Distributing Pump Heads.....	50 to 55
Dixon's Graphite.....	499
Double-Acting Hand Force Pumps, Horizontal..	139 to 145
Double-Acting Pump Cylinder.....	66
Double-Acting Well Force Pumps.....	23 to 29

	PAGE.
Double Branch Y, Bends, Malleable.....	353
Double Disc Gate Valves.....	429
Double Long Radius Tees, C. I.....	342
Drag Scrapers.....	560, 561
Dredging-Pump, Centrifugal.....	172
Dressers Emery Wheels.....	540
Drift Pipe.....	303
Drills, Enlarging.....	307
Drills, Expansion.....	308
Drills, Hydraulic and Jetting.....	307
Drills, Paddy.....	308
Drills, Pipe.....	484
Drills for Ratchets.....	494
Drills, Twist.....	493
Drip Pump, Plumbers'.....	244
Drive Cap.....	303
Drive Head, Steel.....	303
Drive Plate.....	303
Drive Shoe, Steel.....	303
Drive Top.....	303
Drive Well Points.....	294, 299
Driving Shafts.....	102, 103
Driving Shaft and Treble Barrel Pump.....	110
Drop Elbows, Malleable.....	351
Drop Tees.....	351
"Duplex" Die Stocks.....	481
"Duplex" Flue Scrapers.....	495
"Duplex, New," Water Lifter.....	131

<b>E</b> CCENTRIC Bushings, Cast Iron.....	330
Eccentric Tees, Cast Iron.....	328
Eclipse Fire Hydrants.....	400
Ejectors, "H. D.".....	479
Ejectors, "X. L.".....	476
Elbows, Brass.....	367
Elbows, Cast Iron.....	327
Elbows, Cast Iron, Extra Heavy.....	347
Elbows, Cast Iron, Flanged.....	343
Elbows, Cast Iron, Long Radius.....	341
Elbows, Cast Iron, Reducing.....	327
Elbows, Malleable.....	350, 351

	PAGE.		PAGE.
Elbows, 45° .....	350	Extension Valve Boxes.....	402
Elbows, 45° Drop .....	350	Extensions for spraying.....	266
Elbows, 45° Long Drop.....	351	Extension Stroke Guide.....	46, 47
Elbows, 45° Side Outlet.....	350	Extra Heavy Cast Iron Fittings .....	347
Elbows, 45° Street .....	350	Extra Heavy Flange Unions.....	332
Elbows, 45° Union.....	356		
Elbows, Union Radiator.....	378	<b>F</b> ACED Bushings, Cast Iron.....	330
Electric House Pumps.....	205	Faced Bushings, Malleable.....	354
Electric Mine Pumps .....	188, 201, 208, 210 to 212, 213	Factory Hose Carts .....	277
Electric Pumps, Triplex.....	188, 201, 205, 208, 212	Farm Bells.....	285
Electric Rotary Pumps.....	167	Fasteners, Belt.....	532
Electric Switches.....	206, 207	Feed Cookers.....	544
Elevator Bolts.....	521	Feed Water for Boilers .....	185
Elevator Buckets.....	521	Feet Head of Water into Pressure per Square Inch, Table.....	571
Elevator Pumps .....	181 to 183, 188, 189	Felt, Hair.....	538
Elgin Adjustable Wrenches.....	488	Felthousen's Oil Pumps.....	469
"Emerald" Boiler Oil Injectors.....	438	Ferrules, Copper.....	318
Emery Wheels .....	540	Ferrules, Lead Combination.....	419
Emery Wheel Dressers.....	540	Filter Press Pump.....	187
"Empire" Double-Acting Force Pump.....	26, 27	Fire Alarm Whistle.....	434
Engine and Boiler, Vertical.....	545, 546	Fire Engines, Hand.....	267 to 276
Engine Governors.....	465, 466	Fire Hose .....	524
Engine Oilers.....	453	Fire Hydrants.....	400
Engines, Garden or Fire.....	267 to 276	Fire Pumps, Rotary.....	164 to 166
Engines, Gasoline.....	555, 556	Fire Streams, Notes and Tables.....	161
Engines, Steam .....	545 to 554	Fittings, Boiler.....	355
Engineers' Flue Scrapers.....	495	Fittings, Brass .....	367
Engineers' Oilers.....	496	Fittings, Casing.....	320
Engineers Wrenches.....	488	Fittings, Cast Iron.....	327 to 349
"Enterprise" Pipe Vise.....	486	Fittings, Cast Iron, Extra Heavy.....	347
"Enterprise" Ratchet Stock .....	489	Fittings, Cast Iron, Stock Sizes.....	348, 349
Equalizing Pipes, Table.....	573	Fittings, Crossover .....	351
"Eureka" Tubular Well Cylinder.....	304	Fittings, Circulating Boiler, Malleable.....	355
Excelsior Pipe Insulator .....	338	Fittings, Malleable.....	350 to 357
Expansion Joints, Brass.....	380	Fittings, Malleable Classification.....	358 to 366
Expansion Joints, Iron Body.....	390	Fittings, Railings, Malleable.....	357
Expansion Pipe Hangers .....	340	Flange Crosses, Cast Iron... ..	344
Expansion Plates.....	337	Flange Elbows, Cast Iron .....	343
Expansion Tanks .....	422	Flange Tees, Cast Iron.....	344
Extension Pieces, Malleable.....	354	Flange Unions, Cast Iron.....	332
Extension Service Boxes .....	401		



	PAGE.
Flange Unions, Cast Iron, Extra Heavy.....	332
Flange Y Branches, Cast Iron.....	344
Flanges, Cast Iron.....	333
Flanges, Standard .....	345, 346
Flanges, Templates for Drilling.....	346
Flap Valves .....	173
Floor Plates .....	338, 339
Floor Plates, Brass .....	339
Floor Plates, Cast Brass.....	339
Flue Blower, Red Jacket.....	495
Flue Brushes.....	495
Flue Expanders, Prosser.....	494
Flue Expanders, Roller.....	494
Foot Valves.....	72, 391
Force Pump Heads.....	56 to 59
Force Pump Heads, Distributing.....	50 to 55
Force Pumps, Double-Acting Horizontal.....	139 to 145
Force Pumps, House.....	114 to 129
Force Pumps, Portable Brass.....	252
Force Pumps, Rotary.....	152 to 157
Force Pumps, Set Length Well.....	16, 18 to 29
Force Pump Standards.....	35 to 39
Force Pumps, Two-Cylinder, Vertical.....	144, 149, 150
Force Pumps, Wind Mill.....	25 to 29, 52 53, 82, 88
Force Pumps, with W. M. Tops .....	20
Fountains, Dewey.....	567
Four-way Tees, Malleable.....	351
Friction Clutches.....	516
Friction Gears.....	166
Friction of Water in Pipes, Table.....	571
"Fruitall" Spray Pump.....	256
Fuller Balls .....	537
Fuller Bibbs.....	409
Fusible Plugs.....	469

GARDEN Hose Valves.....	374
Garden or Fire Engines.....	267 to 276
Gardner Governors.....	465, 466
Gas Cocks .....	457, 458
Gas Companies' Drip Pump .....	244
Gas Companies' Proving Pump.....	245

	PAGE.
Gas Fitters' Cement.....	499
Gas Hooks .....	337
Gas or Air Pump.....	245, 247
Gas Pliers.....	492
Gas Stove Cocks.....	458
Gas Works Pumps .....	247, 248
Gaskets.....	536, 537
Gaskets, Cloth Insertion.....	536
Gaskets, "Eclipse" .....	534
Gaskets, Fibrous.....	536
Gaskets, Metals.....	537
Gaskets, Pure Rubber .....	536
Gasoline Engines .....	555, 556
Gate Hose Valves.....	374
Gate Valves, Brass.....	393, 394
Gate Valves, Iron.....	398
Gate Valves, Iron Body.....	395 to 397
Gate Valves, Lunkenheimer "Clip" .....	428
Gate Valves, Lunkenheimer Double Disc.....	429
Gate Valves, Lunkenheimer "Handy" .....	431
Gate Valves, Lunkenheimer Quick Opening.....	429
Gate Valves, Lunkenheimer "Victor" .....	430
Gauge Cocks, Compression .....	461
Gauge Cocks, Mississippi .....	469
Gauge Cocks, Register.....	461
Gauge Cocks, Steam .....	461
Gauge Glass Washers.....	473
Gauges, Altitude.....	470
Gauges, Combination Water and Steam.....	464
Gauges, Oil.....	454
Gauges, Pressure Recording.....	472
Gauges, Steam .....	471
Gauges, Water.....	463
Gauge, Water Pressure.....	470, 471
Gears, Rule for Size and Speed .....	572
"Gem" Plain Brass Grease Cups .....	445
"Gem" Nozzles.....	527
Glass Body Oil Pump.....	436
Glass Cutters.....	473
Glass Tubes.....	473
Glasses, Oil Cup.....	455

	PAGE.		PAGE.
Globe Suction Basket.....	529	Holder, Pipe.....	312
Globe Valves, Brass.....	369, 370	Hook Plates, Cast Iron.....	337
Globe Valves, Brass, Asbestos Disc.....	371	Hook Rope.....	310
Globe Valves, Brass, Jenkins' Disc.....	372	Hooks, Beam.....	337
Globe Valves, Iron Body.....	381, 382	Hooks, Belt.....	532
Globe Valves, Iron Body, Asbestos Disc.....	387	Hooks, Chandelier.....	354
Globe Valves, Iron Body, Jenkins' Disc.....	386	Hooks, Gas.....	337
Globe Valves, Lunkenheimer, Brass.....	424	Hooks, Ring.....	340
Globe Valves, Lunkenheimer, Jenkins' Disc.....	427	Horizontal Check Valves, Brass.....	369
Goose Neck or Spout.....	81	Horizontal Check Valves, Jenkins' Disc.....	372
Goose Necks, Lead.....	416	Horizontal Check Valves, Iron Body.....	383
Governors, Engine.....	465, 466	Horizontal Engines and Boilers.....	549 to 553
Grab, Tubular Well Tool.....	311	Horse Gear and Double Barrel Pump.....	97
Graphite, Dixon's.....	499	Horse Gear Pumping Apparatus.....	94, 95, 97
Grease Cups, "Apollo" Iron.....	443	Horse Gear and Triplex Pump Combined.....	92
Grease Cups, "Gem" Plain Brass.....	445	Horse Power Belting will Transmit.....	592
Grease Cups, "Ideal" Automatic.....	441	Horse Power of Pumping, Table.....	203
Grease Cups, "Jewel" Automatic.....	442	Horse Power Transmitted by Shafting, Table.....	572
Grease Cups, "Marine" Screw Feed.....	443	Horse Powers.....	93 to 95
Grease Cups, "Rex" Spun Top.....	445	Hose Carts.....	277
Grease Cups, "Tiger" Plain Brass.....	444	Hose, Cotton, Rubber Lined.....	524
Guards, Brass.....	473	Hose, Cotton, Mill Fire.....	524
<b>H</b> ACK Saws.....	497	Hose, Hard Rubber Suction.....	525
"H. D." Injectors.....	479	Hose, Linen.....	524
Hair Felt.....	538	Hose, Rubber.....	524
Ham Curing Pump.....	244	Hose, Steam.....	525
Hammers, Machinists'.....	493	Hose, Suction.....	525
Hancock Inspirators.....	479	Hose Bibbs.....	407
Hand Fire Engines.....	267 to 276	Hose Bushings.....	529
Hand Taps, Machinists'.....	484	Hose Caps.....	529
Handles, Hydrant.....	355	Hose Clamps.....	530
"Handy" Gate Valves.....	431	Hose Couplings.....	528
Hangers, Ball and Socket.....	519, 520	Hose Menders.....	530
Hangers, Expansion Pipe.....	340	Hose Nipples.....	529
Hard Rubber Suction Hose.....	525	Hose Nozzles.....	527
Heads, Distributing Well Force Pumps.....	50 to 55	Hose Pipes.....	527
Heads, Differential Power.....	104 to 112	Hose Pipes, Underwriters'.....	530
Heads, Well Working.....	56 to 59	Hose Pipe Sprinklers.....	529
Hexagon Nipples.....	354	Hose Rack-Swinging.....	526
Hinge Vise.....	486	Hose Reducers.....	529
		Hose Reels.....	526

	PAGE.
Hose Splices.....	530
Hose Spanners.....	529
Hose Sprinklers.....	531
Hose Strainers.....	529
Hose Straps .....	530
Hose Strap Fasteners.....	530
Hose Valves.....	374
House Force Pumps.....	115 to 129
Hydrant Clamps.....	355
Hydrant Cocks .....	404
Hydrant Handles.....	355
Hydrant Sockets.....	355
Hydrants, Fire.....	400
Hydrants, Yard .....	278 to 283
Hydrants, Wall.....	284
Hydraulic Couplings.....	322
Hydraulic Elevator Pumps.....	181 to 183, 188, 189
Hydraulic Pressure Pump, Triplex.....	187, 235
Hydraulic Rams .....	134 to 137
Hydraulic Test Pumps .....	241, 243
Hydraulic Water Lifters.....	130 to 133

ICE Plant Pumps.....	232, 233
“Ideal” Automatic Grease Cup .....	441
Index to Figs.....	591 to 596
Indicators, Speed .....	498
Injectors, “Chief” .....	477
Injectors, “Emerald” Boiler Oil.....	438
Injectors, “Metropolitan” .....	477
Injectors, “Pemberthy” .....	476
Injectors, “U. S.” .....	478
Injectors, “World” .....	478
Inserted Joint Casing.....	319
Inspirator, Hancock .....	479
Insulator, Pipe, .....	338
Iron Body Valves.....	381 to 388
Iron Body Valves, Jenkins’ Disc.....	386
Iron Body Valves, Asbestos Disc.....	387
Iron Cocks .....	459
Iron Cocks, Asbestos Packed. ....	387
Iron Cocks, with Brass Plug .....	459

Iron Cocks, Three-Way.....	459
Iron Pulleys.....	509 to 514
Iron Rod Couplings.....	302
Irrigating Pumps .....	89, 91 to 97
Irrigation Pump Cylinder.....	89
Irrigation Table .....	574

JACK Screws.....	286, 541
Jarecki Screw Plates.....	481
Jenkins’ Discs.....	386
Jet Pump, Blakeslee.....	475
“Jewel” Engines.....	552
“Jewel” Grease Cups.....	442
Joints, Expansion, Brass.....	380
Joints, Expansion, Iron Body.....	390
Joints, Swing.....	380
“Junior” Lubricators.....	435

KEROSENE Spray Pumps .....	253, 259, 260
“Kerowater” Spray Pumps .....	253, 259, 260
Keys, Lock and Shield Valves.....	378
Keystone Unions.....	356
Knapsack Spray Pumps.....	253

LACE Cutters.....	532
Lace Hole Protectors.....	532
Lace, Rawhide .....	522
Lace, Tanned.....	522
Lacing Belt .....	532
Ladles, Babbitt.....	421
Lag, Screws. ....	542
Lard Press Screws .....	287
Lawn Hydrants .....	278 to 283
Lawn Sprinklers.....	531
Lead, Pig .....	420
Lead, Bends.....	417 to 419
Lead, Combination Ferrules .....	419
Lead, Goose Necks .....	416
Lead, Pipe .....	420
Lead Sheet.....	420



	PAGE.
Lead, Traps.....	417, 418
Leather .....	301
Leather Belting.....	522
Leather, Valve and Plunger.....	301
Lennox Tapping Machine.....	413
Lever Handle Bibbs .....	407
Lever Handle Oil Pumps.....	469
Lever Handle Valves, Lunkenheimer.....	431
Lift Pumps, for Cisterns and Wells .....	1 to 17
Lift Pump Standards.....	31 to 34
Lifter, Rod.....	310
"Lightning" Dies and Holder .....	483
"Lightning" Hand Air Pumps .....	350
"Lightning" Screw Plates.....	483
"Lightning" Taps.....	483
Linen Hose .....	524
"Little Giant" Pipe Holder.....	312
"Little Giant" Screw Plates .....	482
Little's Automatic Pipe Holder.....	312
Lock Gas Service Cocks.....	458
Lock Nuts, Brass.....	368
Lock Nuts, Cast Iron.....	329
Lock Nuts, Malleable.....	354
Lock Nuts, Nipples.....	326
Lock Nuts, Threads .....	326
Lock Shield Valves.....	370
Lock Union Water Cocks.....	458
Long Drop Elbows, Malleable.....	351
Long Screws .....	326
Long Radius Crosses.....	341
Long Radius Ells.....	341
Long Radius Ells, Double Branch.....	341
Long Radius Tees .....	341
Long Radius Reducing .....	342
Long Radius Double .....	342
Loops, Chandelier .....	354
Loose Pulley Oilers.....	453
Low Pressure Safety Valves .....	373
Lubricators, "Banner".....	440
Lubricators, "Detroit".....	467
Lubricators, "Junior".....	435

	PAGE.
Lubricators, "Senior".....	435
Lubricators, "Swift".....	468
Lubricators "Vulcan".....	440
Lubricators, "Zero".....	467
Lubricators, Lunkenheimer .....	435, 439, 440
Lubricators, Wood Handle.....	467
LUNKENHEIMER GOODS:	
Brass Balls.....	425
Gate Valves, "Clip".....	428
Gate Valves, Double Disc.....	429
Gate Valves, "Handy".....	431
Gate Valves, Quick Opening.....	429
Gate Valves, "Victor".....	430
Throttle Valves, Lever.....	431
Grease Cups, "Apollo," Iron.....	443
Grease Cups, "Gem," Plain Brass.....	445
Grease Cups, "Ideal," Automatic .....	441
Grease Cups, "Jewel," Automatic.....	442
Grease Cups, "Marine," Screw Feed.....	443
Grease Cups, "Rex," Spun Top.....	445
Grease Cups, "Tiger," Plain Brass .....	444
Injectors, "Emerald," Boiler Oil.....	438
Injectors, Standard Boiler Oil.....	438
Lubricators, "Banner".....	440
Lubricators, "Junior".....	435
Lubricators, "Paragon".....	439
Lubricators, "Senior" .....	435
Lubricators, "Vulcan".....	440
Oil Cups, "Crown" Sight Feed.....	448
Oil Cups, "Pioneer" Slide Top.....	446
Oil Cups, "Royal" Sight Feed.....	449
Oil Cups, "Sentinel" Sight Feed.....	450
Oil Cups, "Victor" Index.....	447
Oil Cup Glasses.....	455
Oilers, Engine, Plain Glass.....	453
Oilers, Loose Pulley.....	453
Oilers, Shaft .....	452
Oil Feeder, Automatic Needle Valve.....	437
Oil Gauges.....	454
Oil Pumps.....	436
Oil Pumps, Lever Handle.....	436



	PAGE.
LUNKENHEIMER GOODS.— <i>Continued.</i>	
Pop Safety Valves.....	432
Rod Cups, Automatic.....	451
Rod Cups, "Champion".....	451
Valves, Angle, Regrinding.....	424
Valves, Angle, Composition Disc.....	427
Valves, Check, Regrinding.....	425
Valves, Check, Ball Regrinding.....	425
Valves, Check, Swing Regrinding, Brass.....	426
Valves, Check, Swing Regrinding, Iron Body.....	426
Valves, Cross.....	424
Valves, Gate.....	428 to 431
Valves, Globe, Regrinding.....	424
Valves, Globe, Composition Disc.....	427
Valves, Pop Safety.....	432
Valves, Radiator.....	427
Valves, Throttle Lever.....	431
Valves, Whistle.....	433
Whistles, Chime.....	433
Whistles, Fire Alarm.....	434
Whistles, Mocking Bird.....	433

MACHINE Bolts.....	543
Machinists' Hammers.....	493
Machinists' Hand Taps.....	484
Magnolia Metal.....	421
Malleable Drive Cap.....	303
Malleable Iron Fitting.....	350 to 357
Malleable Iron Fittings, Classification Price List.....	358 to 366
Malleable Iron Oilers.....	496
Malleable Iron Saddles.....	326
Malleable Iron Suction Strainers.....	300
Malleable Iron Unions.....	356
Malleable Vises.....	486
Manila Rope.....	499
Manual or Power Pumping Apparatus.....	99 to 101
"Marine" Grease Cup.....	443
Marsh Automatic Air Valves.....	379
Mason By-Pass Valves.....	392
Mason Rheostat Regulator.....	392
"Masson" Spray Nozzle.....	264

	PAGE.
Measures and Weights, Table.....	575
Meneely Bells.....	568
Metal, Babbitt.....	421
Metal, Gaskets.....	537
Metal, Magnolia.....	421
Metal, Manhole Gaskets.....	537
Metallic Lower Valves.....	61
Meter Cocks, Lock Union.....	458
"Metropolitan" Injectors.....	477
Mill Board, Asbestos.....	538
Mill Hose.....	524
Mill Pumps.....	180 to 187
Miller's Pipe Cutter.....	491
Miller's Ratchet Stock.....	480
Mine Pumps.....	208 to 213
Mississippi Gauge Cocks.....	469
"Mocking Bird" Whistle.....	433
Molasses Pump.....	3
"Monitor" Pipe Holder.....	312
Motor Pumps.....	130 to 133
Mueller Corporation Cocks.....	414, 415
Mueller's Patent Stops.....	406
Mueller's Rough Stops.....	405, 406
Mueller's Tapping Machines.....	411, 412
Mushroom Strainers.....	72

NASON Steam Trap.....	399
Natural Gas Pump.....	245
"Never Slip" Rod Tongs.....	489
"New Deluge" Suction Pumps.....	146
"New Era" Steel Sinks.....	288
Nippers, Cutting.....	492
Nipples, Brass.....	368
Nipples, Hexagon.....	354
Nipples, Hose.....	529
Nipples, Lock Nut.....	326
Nipples, Right and Left, Hex Centre.....	354
Nipples, Soldering.....	416
Nipples, Wrought Iron.....	323 to 325
"No Shock" Self-Closing Hydrants.....	283
Nozzles, "Gem".....	527

	PAGE.
Nozzles, Hose .....	527
Nozzles, Spray.....	263, 264
Nuts, Waste .....	354
<b>O</b> AKUM .....	499
Offsets, Cast Iron.....	331
Offset Reducing Couplings.....	331
Offset Reducing Couplings, Malleable.....	354
Oil Cups, Brass.....	469
Oil Cup, "Crown" Sight Feed.....	448
Oil Cup, "Pioneer" Slide Top.....	446
Oil Cup, "Royal" Sight Feed .....	449
Oil Cup, "Sentinel" Sight Feed.....	450
Oil Cup, "Victor" Index.....	447
Oil Cup Glasses.....	455
Oil Feeders, Automatic Needle Valve.....	437
Oil Fillers, Steel.....	496
Oil Gauges.....	454
Oil Injectors, "Emerald" Boiler .....	438
Oil Injectors, "Standard" Boiler.....	438
Oil Pump, Glass Body.....	436
Oil Pump, "Felthousen's".....	469
Oil Pump, Lever Handle.....	469
Oil Pump, Special Rotary.....	156
Oil Pump, Special .....	244
Oil Sets, Engineers .....	496
Oil Waste Can.....	499
Oilers, Loose Pulley.....	453
Oilers, Plain Engine.....	453
Oilers, Shaft.....	452
Oilers, Brass or Copperized Steel.....	496
Oilers, Malleable Iron .....	496
Oilers, Chace's Zinc .....	496
Oilers, Railroad .....	496
Oilers, Sight Feed.....	448 to 450
Oster Die Stocks .....	482
<b>"P</b> ACIFIC" Well Force Pumps.....	85
Packer Ratchets.....	494
Packing, Asbestos Wick and Rope .....	538
Packing, Candlewick.....	538

	PAGE.
Packing, Cloth Insertion.....	533
Packing, "Eclipse".....	534
Packing, "Empire" Gum Core.....	535
Packing, "Eureka" Piston.....	535
Packing, Garlock's Ring.....	535
Packing, Garlock's Spiral.....	535
Packing, Hard Pump.....	533
Packing, Hydraulic.....	534
Packing, Italian Hemp .....	534
Packing, Jenkins' Standard.....	534
Packing, Plumbago Sheet.....	534
Packing, Pure Rubber Sheet.....	533
Packing, Rainbow.....	534
Packing, Square Braided Flax .....	535
Packing, Square Duck Rubber Back.....	533
Packing, Square and Round Duck.....	533
Packing Tuck's Rounded .....	534
Packing Box Heads.....	56
Paddy Drills .....	308
Paper Asbestos .....	538
Paper and Pulp Mill Pumps.....	214 to 230
"Paragon" Lubricator .....	439
Parker's Combination Vise .....	485
Patent Stops, Mueller .....	406
Pave Washes.....	280 to 283
Peases' Combination Pliers .....	492
"Penberthy" Injector .....	476
Perforated Sheet Brass.....	301
"Phoenix" Pipe Vise.....	486
Pig Lead.....	420
Pillow Blocks .....	518
"Pioneer" Oil Cups.....	446
Pipe Coverings.....	538 to 539
Pipe Cutters.....	491
Pipe Drift.....	303
Pipe Drills .....	484
Pipe Hangers, Expansion.....	340
Pipe Holder and Lifter, Babcocks.....	312
Pipe Holder, Little's Automatic.....	312
Pipe Holder, "Little Giant" .....	312
Pipe Holder, "Monitor" .....	312

	PAGE.
Pipe Holder and Lifter, Standard Automatic .....	312
Pipe Insulator.....	338
Pipe Lifting Clevis.....	311
Pipe Puller.....	312
Pipe Reamer .....	484
Pipe Rings.....	340
Pipe Rod Couplings.....	302
Pipe Saddles .....	326
Pipe Tap and Drill.....	484
Pipe Taps.....	484
Pipe Telegraphic Cipher .....	316
Pipe Threads.....	326
Pipe Tongs .....	487 to 490
Pipe Vises .....	485 to 486
Pipe Wrenches.....	488 to 490
Pipe, Cast Iron.....	313
Pipe, Cast Iron Specials .....	314 to 315
Pipe, Lead .....	420
Pipe Reamer .....	484
Pipe, Spiral Riveted.....	318
Pipe, Wrought Iron.....	316, 317
Pipe Extension and Stop Cock .....	266
Piping Diagram, Water Lifters .....	130
Pitcher Spout Pumps.....	4 to 6
Plates, Ceiling .....	338 to 339
Plates, Ceiling, Brass.....	339
Plates, Expansion .....	337
Plates, Floor.....	338, 339
Plates, Floor, Brass .....	339
Plates, Floor, Cast Brass.....	339
Plates, Hook .....	337
Plates, Pump.....	483
Plates, Screw .....	480 to 483
Plates, Wall .....	354
Pliers, Gas.....	492
Plugs, Brass .....	368
Plugs, Cast Iron.....	330
Plugs, Fusible.....	469
Plumbers Brass Force Pumps .....	243
Plunger Leathers .....	301
Plunger Leathers, Crimped .....	301

	PAGE.
Plungers for Pump Cylinders .....	61
Points, Drive Well .....	294 to 299
"Pomona" Spray Pump .....	257
Pop Safety Valves, Lunkenheimer .....	432
Portable Brass Force Pump.....	252
Post Hangers.....	520
Power Force Pumps .....	162 to 236
Power Pumps, Triplex.....	179 to 235
Power Rotary Pumps .....	157, 161 to 167
Power to Operate Triplex Pumps.....	203
Power Working Heads or Apparatus... 99 to 101, 104 to 112	
Press Screws .....	287
Pressure Gauge.....	471, 472
Pressure per Square Inch into Feet Head of Water	
Table .....	571
Pressure Recorders .....	472
Pressure Regulator, Davis' .....	389
Prosser's Flue Expander.....	494
Proving Pump.....	245
Puller, Pipe.....	312
Pulley Blocks .....	501, 502
Pulleys, Iron .....	509 to 514
Pulleys, Rule for Size and Speed.....	572
Pulleys, Wood Split.....	503 to 508
Pump Cylinders .....	61 to 69, 71
Pump Plates .....	483
Pump Standards.....	31 to 55
Pumps, "Felthousen's" Oil.....	469
Pumps, Glass Body, Oil.....	436
Pumps, Lever Handle Oil.....	469
Pumps, Wood.....	558
Punched Washers, Wrought Iron.....	542
Pure Rubber Valves.....	536

QUICK Opening Gate Valves, Lunkenheimer ..... 429  
 Quick Opening Gate Valves, Standard.. .... 393, 397

RACK, Swinging Hose .....
 526 |

Radiators .....
 399 |

Radiator Air Valves .....
 379 |

Radiator Valves.....
 375 to 378 |



	PAGE.		PAGE.
Radiator Valves, Asbestos Disc.....	371	Repairs, Pump.....	576 to 590
Radiator Valves, Lunkenheimer.....	427	Return Bends, Cast Iron.....	334 to 335
Railing Fittings.....	357	Return Bends, Malleable.....	353
Rain and Well Water Cocks.....	410	Revolution Counters.....	474
Ram, Hydraulic.....	134 to 137	Revolving Sprinklers.....	531
Range Boilers.....	422	"Rex" Spun Top Grease Cup.....	445
Ratchets.....	494	Rheostat Regulator, Mason.....	392
Ratchet Pipe Cutters.....	491	Rings, Pipe.....	340
Ratchet Stocks, Miller.....	480	Rivet Set.....	494
Ratchet Stocks, Oster.....	482	Road Cart Pump.....	250
Ratchet Stocks, Enterprise.....	489	Robbins' Chain Tongs.....	487
Rawhide Belting.....	523	"Rocker" D. A. Force Pump.....	140, 141
Rawhide Lace.....	522	Rod, Connecting.....	70
Reamer, End Pipe.....	309	Rod, Valve for Artesian Cylinder.....	70
Reamer, Pipe.....	484	Rod, Wood Sucker and Coupling.....	70
Reamer, Pipe, "Enterprise".....	489	Rod, Couplings.....	302
Recessed Couplings.....	322	Rod Couplings, Hexagon.....	302
Recorders, Pressure.....	472	Rod Couplings, Reducer.....	302
Red Jacket Flue Blowers.....	495	Rod Couplings, Wood.....	70
Red Reflecting Gauge Glasses.....	473	Rod Cups, Automatic.....	451
Reducers, Cast Iron.....	331	Rod Guide Roller.....	96
Reducers, Hose.....	529	Rod Lifter.....	310
Reducers, Malleable.....	352	Rod Joint.....	96
Reducing Couplings, Offset, Cast Iron.....	331	Rod Oil Cups.....	451
Reducing Couplings, Offset, Malleable.....	354	Rod Sockets, Hydrant.....	355
Reducing Crosses, Cast Iron.....	329	Rod Tongs.....	489
Reducing Elbows, Cast Iron.....	327	Rod Tongs, "Never Slip".....	489
Reducing Tees, Cast Iron.....	328	Rod Wrenches, Reed's.....	489
Reducing Tees, Cast Iron, Flanged.....	343 to 344	Root's Spiral Riveted Pipe.....	318
Reducing Tees, Cast Iron, Long Radius.....	341 to 342	Roller Guide and Coupling.....	96
Reed's Pipe Vise.....	486	Roller Tube Expander.....	494
Reed's Pipe Wrench.....	489	Rope Hook.....	310
Reels, Hose.....	526	Rope, Manila.....	499
Reels, Hose Wall.....	526	Rope Packing.....	538
Register Gauge Cocks.....	461	Rope Wire.....	500
Regulator, Davis' Pressure.....	389	Rotary Barrel Pumps.....	155
Regulator, Force Pump Head.....	55	Rotary Fire Pump, Description.....	160, 161
Regulator, Force Pump Head, Description.....	50	Rotary Fire Pumps.....	164 to 166
Regulator, Mason Rheostat.....	392	Rotary Force Pumps.....	152 to 157, 162 to 167
Relief Valves, Water.....	392	Rotary Pumps, Description.....	152
Relief Valves, Water, Mason.....	392	Rough Stops.....	403, 404

	PAGE.
Rough Stops, Mueller .....	405, 406
" Royal " Oil Cup.....	449
Rubber Belting.....	522
Rubber Gaskets and Rings.....	536
Rubber Hose.....	525
Rubber Tubing.....	525
Rubber Valves .....	536
Russell's Floor and Ceiling Plates.....	339

<b>S</b> ADDLES, Pipe.....	326
Safety Valves, Brass .....	373
Safety Valves, Low Pressure.....	373
Safety Valves, Iron Body.....	385
Safety Valves, Iron Body, Jenkins' Disc.....	385
Safety Valves, Pop, Lunkenheimer.....	432
Salem Elevator Buckets.....	521
Sand Pump and Drill .....	307
Saunders' Pipe Cutter .....	491
Saws, Hack .....	497
School Bells.....	285
Scrapers, Drag.....	559, 561
Scrapers, Tongue .....	561
Scrapers, Wheel.....	562
Screws, Lag.....	542
Screws, Long.....	326
Screws, Jack .....	286, 287, 541
Screws, Press.....	287
Screw Plates.....	480 to 482
Screw and Socket Casing .....	319
Seamless Brass Slotted Strainers, Cooks'.....	300
Seamless Brass Tubing .....	368
Seating Tool " Eureka " Cylinder .....	304
" Senior " Lubricator.....	435
Semi-Fluid Hand Suction Pump.....	3
Semi-Fluid Triplex Pump.....	231
Semi-Rotary " Clock " Force Pumps.....	158, 159
" Seneca " D. A. Force Pump.....	25, 29
" Seneca " Three-Way Distributing Head.....	51
" Seneca " Spray Nozzle .....	264
" Sentinel " Glass Oil Cup.....	450
" Sentinel " Spray Pump.....	258

	PAGE.
Separator Strap Buckles .....	523
Service Boxes .....	401
Service Cocks .....	457
Set Length Well Pumps.....	8 to 29
Sewage Pump, Hand.....	3, 147, 148
Sewage Pumps, Power .....	169, 170, 231
Sewer Traps.....	291
Shaft Oilers.....	452
Shafting .....	517
Shafting Collars.....	517
Shafting Couplings.....	517
Shallow Well Pump Cylinders.....	61 to 66
Sheet Brass, Perforated.....	301
Sheet Lead.....	420
Sheffy Pipe Wrench.....	489
Shellers, Corn.....	566, 567
Ship Pumps.....	142 to 151
Ship Pumps, Description.....	138
Shut-Off Valve, Automatic .....	131
Shut-Offs, Spray .....	265
Side Outlet Elbows, Malleable .....	350
Sill Cocks .....	410
Single Screen Well Points .....	298
Sinks .....	288 to 289
Sink Backs .....	288, 292
Sink Bolts.....	292
Sink Brackets .....	288, 289
Sink Couplings.....	292
Sink Strainer.....	292
Sleeve Ratchets .....	494
Slop Sinks .....	291
Smith's Combination Vise .....	485
Soap Pumps.....	230
Sockets, Casing .....	320
Soda Water Pumps.....	242
Solder .....	420
Soldering Nipples.....	416
Soldering Unions.....	416
" Southern " Force Pump Standard .....	49
" Southern " Star Pumps .....	7
Special Couplings .....	322

	PAGE.		PAGE.
"Special" Drive Well Points.....	297	Steam Traps.....	399
Speed Indicators .....	498	Steam and Water Gauge Combination.....	464
Spiral Riveted Pipe.....	318	Steam Whistles.....	462
Splices, Hose.....	530	Steam Working Head .....	113
Spout, Cock.....	81	Steel Sinks.....	288
Spout or Goose Neck .....	81	Stillson Wrenches.....	490
Spray Cart, Barrel.....	261	Stock Fountains.....	567
Spray Nozzles .....	263 to 265	"Stock" Pumps .....	15
Spray Pumps.....	251 to 261	Stock Tanks.....	423
Spray Pumps, Description .....	251	Stocks and Dies. ....	480 to 483
Spray Stop Cock .....	265	Stock and Reamer, "Enterprise".....	489
Sprinklers, Hose.....	529	Stop Cock, Spray.....	265
Sprinklers, Lawn.....	531	Stops, Compression .....	407, 408
Standard Boiler Oil Injector .....	438	Stops, Rough .....	403, 404
Standard Flanges.....	345 to 346	Stops, Rough, Mueller.....	405, 406
Standard Threads.....	326	Stove Cocks, Gas.....	458
Standards, Well Pump .....	37 to 55	Straightway Valves, Brass .....	393, 394
Standards, Wind Mill Pump.....	42 to 55	Straightway Valves, Iron.....	398
Stands, Boiler.....	422	Straightway Valves, Iron Body. ....	395 to 397
Stanwood Pipe Cutter.....	491	Strainers, Brass Slotted.....	300
"Star" Hydrants.....	282	Strainers, for Suction Pipe.....	72, 300
"Star" Force Pumps.....	18 to 21	Strainers, Malleable Suction .....	300
"Star" Force Pump Standards .....	35 to 37	Strainers, Water Works .....	300
"Star" Lift Pumps.....	8 to 14	Strainers, Suction Hose.....	529
"Star" Lift Pump Standards .....	31 to 33	Strap Buckles, Separator.....	523
"Star" Street Washers .....	282	Straps, Hose .....	530
"Star" Wind Mill Force Pump .....	20, 21	Straps, Hose Fasteners .....	530
"Star" Wind Mill Force Pump Standards.....	42 to 55	Straps, Tinned .....	338
Steam Boiler Feed Pump .....	240	Street Elbows, Malleable .....	350
Steam Cocks .....	456	Street Washers.....	280 to 283
Steam Cock Wrenches.....	456	Stuff Pumps, Triplex Power .....	228 to 230
Steam Engines.....	545, 554	Sucker Rod and Coupling, Wood.....	70
Steam Fitters' Cement.....	499	Suction Hose.....	525
Steam Flue Blowers.....	495	Suction Hose Baskets.....	529
Steam Gauge Cocks.....	461	Suction Hose Strainers .....	529
Steam Gauges.....	470	Suction Pumps for Paper Machines.....	216 to 225
Steam Gauge Syphons.....	475	"Sun" Hydrants and Street Washers.....	283
Steam Hose .....	525	"Swan-Neck" Village Fire Engine.....	273 to 275
Steam Hose Couplings.....	528	"Swift" Lubricators.....	468
Steam Jet Pumps.....	475	Swing Check Valves, Brass .....	370
Steam Packing.....	533 to 538	Swing Check Valves, Iron Body .....	384



	PAGE.
Swing Check Valves, Lunkenheimer .....	426
Swing Joints, Brass .....	380
Swinging Hose Racks .....	526
Switches, Electric.....	206, 207
Swivel, Casing .....	310
Swivel, Hydraulic.....	310
Swivel, Rope.....	310
Swivel, Water .....	310
Syphon Cocks.....	475
Syphon W. M. Force Pump .....	82
Syphons, Iron.....	475

T	ABLES.....	569 to 575
T	anks, Expansion .....	422
T	ank Float.....	81
T	anks, Stock.....	423
T	ank Switch, Electric.....	206, 207
T	ank Valve.....	81
T	anned Lace .....	522
T	annery Pumps .....	162 to 170
T	ap, Bit Brace .....	483
T	ap, Lightning.....	483
T	ap, Pipe .....	484
T	ap and Drill .....	484
T	ap, Taper.....	311
T	aps, Machinists' Hand.....	484
T	apping Machines.....	411 to 413
T	ees, Branch.....	336
T	ees, Brass.....	367
T	ees, Cast Iron.....	328
T	ees, Drop.....	342
T	ees, Eccentric.....	328
T	ees, Extra Heavy .....	347
T	ees, Flanged .....	343, 344
T	ees, Flanged Reducing.....	343, 344
T	ees, Long Radius.....	341, 342
T	ees, Long Radius Reducing .....	341, 342
T	ees, Malleable.....	351
T	ees, Reducing.....	328
T	ees, Union Malleable.....	356
T	elegraphic CIPHER, Pipe.....	316

Template for Drilling.....	346
Terms.....	IV
Test Pumps, Hydraulic.....	241 to 243
Threads, Lock Nut .....	326
Threads, Pipe.....	326
Three-Way Cocks, Iron.....	459
Three-Way D. A. Force Pump.....	27, 29
Three-Way Distributing Pump Heads.....	50 to 55
Three-Way Steam Cocks.....	456
"Thresher" Tank Pump.....	145
Throttle Valves .....	373
Throttle Valves, Lunkenheimer.....	431
"Tiger" Plain Grease Cups.....	444
Tin, Block.....	420
Tinned Straps.....	338
Tongs, Pipe.....	487 to 490
Tongs, Tubular Well Tool .....	311
Tongue Scraper .....	561
Tools, Beading and Caulking.....	494
Tools, Well.....	309
Traps, Lead .....	417, 418
Traps, Steam.....	399
Trimo Wrenches.....	490
Triplex Irrigating or Tank Pump.....	91
Triplex Power Pumps .....	178 to 235
Triplex Pump and Horse Power Combined.....	92
Tubes, Boiler.....	318
Tubes, Scotch Glass .....	473
Tube Cleaners.....	495
Tube Expanders. ....	494
Tubing, Brass.....	368
Tubing, Rubber .....	525
Tubing, Wood.....	558
Tubular Boilers .....	549 to 551
Tubular Well Points.....	296 to 297
Tubular Well Cylinder Shoe.....	303
Tubular Well Pump Standards .....	43
Tubular Well Valves .....	306
Tubular Well Valve Rubber.....	301
Twist Drills.....	493
Two-Cylinder Force Pumps.....	144, 150, 151

	PAGE.
UNDERWRITERS' Fire Pumps.....	164 to 166
Underwriters' Hose Pipe.....	530
Unions, Brass .....	367
Unions, Flange.....	332
Unions, Flange, Extra Heavy.....	332
Unions, Keystone.....	356
Unions, Malleable .....	356
Unions, Soldering .....	416
Union Elbows, Brass .....	378
Union Elbows, Malleable .....	356
Union Tees, Malleable.....	356
"Universe" House Force Pump.....	119
"Universal" Bronze Valve and Seat.....	61
Urn-Shaped Glasses .....	455
"U. S." Injectors .....	478
"Utility" Well Force Pump.....	23
Useful Notes.....	XXV
Useful Information.....	569 to 575

VACUUM Base Pitcher Pump .....	6
Vacuum Gauges.....	471
Vacuum Pumps.....	216 to 224, 247 to 249
Vacuum Valves.....	373
Valve Boxes.....	402
Valve Boxes, Bases.....	402
Valve, "Universal," Bronze .....	61
Valve Rod for Artesian Well.....	70
Valves, Air.....	379
Valves, Air, Automatic .....	379
Valves, Angle, Brass.....	369, 370
Valves, Angle, Brass, Asbestos Disc.....	371
Valves, Angle, Brass, Jenkins' Disc.....	372
Valves, Angle, Brass, Lunkenheimer.....	424
Valves, Angle, Brass, Lunkenheimer, Jenkins' Disc....	427
Valves, Angle, Iron Body .....	381, 382
Valves, Angle, Iron Body, Asbestos Disc.....	387
Valves, Angle, Iron Body, Jenkins' Disc .....	386
Valves, Angle Check, Brass.....	369
Valves, Angle Check, Iron.....	72
Valves, Angle Check, Iron Body .....	383
Valves, Back Pressure, Davis .....	388

	PAGE.
Valves, Back Pressure, Iron Body.....	388
Valves, Ball Check, Lunkenheimer.....	425
Valves, Blind or Check .....	309
Valves, Blow-Off .....	391
Valves, Butterfly, Brass.....	373
Valves, Butterfly, Iron Body.....	385
Valves, By-Pass, Mason.....	392
Valves, Check, Brass.....	369, 370
Valves, Check, Brass, Jenkins' Disc .....	372
Valves, Check, Brass, Lunkenheimer.....	424
Valves, Check, Iron Body.....	383, 384
Valves, Check, Iron Body, Jenkins' Disc.....	386
Valves, Check Swing, Brass.....	370
Valves, Check Swing, Iron Body .....	384
Valves, Check, Brass, Lunkenheimer.....	426
Valves, Cross, Brass .....	369
Valves, Cross, Brass, Asbestos Disc.....	371
Valves, Cross, Lunkenheimer .....	424
Valves, Cross, Iron Body.....	381, 382
Valves, Cross, Iron Body, Jenkins' Disc .....	386
Valves, Foot.....	391
Valves, Gate, Brass.....	393, 394
Valves, Gate, Hose .....	374
Valves, Gate, Iron.....	398
Valves, Gate, Iron Body.....	395 to 397
Valves, Gate, Lunkenheimer.....	428 to 431
Valves, Globe, Brass.....	369, 370
Valves, Globe, Brass, Asbestos Disc .....	371
Valves, Globe Brass, Jenkins' Disc.....	372
Valves, Globe, Brass, Lunkenheimer.....	424
Valves, Globe, Brass, Lunkenheimer, Jenkins' Disc....	427
Valves, Globe, Iron Body.....	381, 382
Valves, Globe, Iron Body, Asbestos Disc.....	387
Valves, Globe, Iron Body, Jenkins' Disc.....	386
Valves, Hose .....	374
Valves, Leather.....	301
Valves, Lock Shield.....	370
Valves, Radiator.....	375 to 378
Valves, Radiator Asbestos Disc .....	371
Valves, Radiator Air .....	379
Valves, Radiator, Lunkenheimer.....	427

	PAGE.
Valves, Relief.....	392
Valves, Rubber.....	536
Valves, Safety, Brass.....	373
Valves, Safety, Iron Body.....	385
Valves, Safety, Low Pressure.....	373
Valves, Safety Pop, Lunkenheimer.....	432
Valves, Tank.....	81
Valves, Throttle.....	373
Valves, Throttle, Lunkenheimer.....	431
Valves, Vacuum.....	373
Valves, Tubular Well.....	306
Valves, Water Relief.....	392, 296
Valves, Whistle.....	462
"Vermorel" Spray Nozzles.....	263
Vertical Boilers.....	544 to 547
Vertical Engines.....	545 to 548
Vertical Engines and Boilers, Combined.....	545, 546
Vertical Check Valves, Brass.....	369
Vertical Check Valves, Brass, Jenkins' Disc.....	372
Vertical Check Valves, Iron Body.....	384
"Victor" Automatic Air Valves.....	379
"Victor" Gate Valves.....	430
"Victor" Oil Cups.....	447
"Vim" Wind Mill Force Pump.....	83
Village Fire Engines.....	273 to 276
Vises, Pipe.....	485, 486
"Vulcan" Lubricators.....	440
"Vulcan" Pipe Tongs.....	487
<b>W</b> ALL Hose Reel.....	526
Wall Plates.....	354
Wash Paves.....	280 to 283
Washer, Street.....	279 to 283
Washers, Bibb.....	537
Washer, Drive Well Point.....	299
Washers, Gauge Glass.....	473
Washers, Wrought Iron Punched.....	542
Waste Cotton.....	499
Waste Nuts.....	354
Water Columns.....	463
Water Conductor.....	81

	PAGE.
Water Gauges.....	463
Water Gauge, Balance.....	470
Water Gauge, Combination.....	464
Water Gauge, Glasses.....	473
Water Gauge Rods.....	473
Water Motor Pumps.....	130 to 133
Water Lifters.....	130 to 133
Water Pressure Gauges.....	470, 471
Water Relief Valves Standard.....	392
Water Relief Valves, Mason.....	392
Water Supply Pumps, Triplex.....	180 to 186
Water Works Strainer.....	300
Water Works Well Point.....	299
Water Works Pumps, Triplex.....	190 to 197
Weight of Different Standard Gallons of Water.....	575
Weights and Measures, Tables.....	575
Weirs, Table of Discharge.....	574
Well Force Pumps, Anti-Freezing.....	18 to 29
Well Force Pump Heads, Anti-Freezing.....	50 to 55
Well Force Pumps, Wind Mill.....	52, 53, 82 to 88
Well Force Pumps with Wind Mill Tops.....	20, 21
Well Lift Pumps, Anti-Freezing.....	8 to 17
Well Points, Drive.....	294 to 299
Well Point Extension.....	296
Well Pump Standards.....	31 to 55
Well Pump Working Heads.....	99 to 101
Well Shoe.....	303
Well Tools.....	309 to 311
Well Working Heads, Wind Mill.....	57 to 59
Wheelbarrows, Garden.....	564
Wheelbarrows, Railroad "K. & J.".....	563
Wheelbarrows, Railroad "Scioto".....	563
Wheelbarrows, Tubular Steel.....	565
Wheel Scrapers.....	562
Wheels, Emery.....	540
Whistles, Chime.....	433, 462
Whistles, Fire Alarm.....	434
Whistles, Lunkenheimer.....	433, 434
Whistles, "Mocking Bird".....	433
Whistles, Steam.....	462
Whistles, Valves.....	462



	PAGE.
Wick Packing .....	538
Wind Mill Force Pumps .....	52, 53, 82 to 88
Wind Mills, Pumping Capacity of.....	41
Wind Mill Pump Standards.....	42 to 55
Wind Mill Pumps, Description .....	40 to 41
Wind Mill Regulator Force Pump Head.....	55
Wind Mill Tank Valves.....	81
Wind Mill Top Set Length Pumps .....	20, 21
Wind Mill Working Heads .....	50 to 59
Wine Press Screws .....	287
Wire Cloth, Brass.....	301
Wire Rope .....	500
Wood Bushings .....	503
Wood Connecting Rod.....	70
Wood Handle Lubricators.....	467
Wood Pumps and Tubing.....	558
Wood Rod Couplings.....	70, 302
Wood Split Pulleys.....	503 to 508
Working Barrels or Cylinders.....	61 to 69
Working Heads, Power.....	104 to 112
Working Heads, Steam.....	113

	PAGE.
Working Heads, Well Pump.....	99 to 101
Working Heads, Wind Mill.....	50 to 59
"World" Injectors.....	478
Wrenches, Pipe.....	487 to 490
Wrenches, Steam Cock .....	456
Wrought-Iron Couplings.....	321
Wrought-Iron Nipples.....	323 to 325
Wrought-Iron Pipe.....	316, 317
 "X L." Ejector.....	 476
 Y BENDS, Malleable .....	 353
Y Branches, Cast Iron.....	335
Y. Branches, Cast Iron Flanged.....	344
Yard Pumps .....	8 to 29
Yard Hydrants .....	278 to 283
 "ZERO" Lubricators .....	 467
Zinc Oilers.....	496

ON

## PUMPS AND HYDRAULIC MACHINERY.

There are certain conditions requisite to the successful operation of any Pumps—these factors are briefly :

**SUCTION PIPE.**—This is the pipe below the lower valves, whether the valves are in the Pump itself or in the cylinder a number of feet below the Pump (yet above the surface of the water), and in practical working should not exceed twenty-five feet in vertical height at sea level, and proportionately less at higher levels. See Table of Barometric Pressure, page 569. This pipe may, however, extend almost any distance horizontally, if care is taken that it fall evenly along its entire length from Pump or Cylinder to water supply. In this connection, as well as in long vertical suction pipes, we urge the use of a foot or check valve, provided pipe is protected from frost, as it retains water when Pump is not in use. Properly, the suction pipe of Single-Acting Cylinders and Pumps should be half the diameter of working barrel, and in suction pipes 100 feet or more in length, or with Pumps working fast, it may be increased, as is true of Double-Acting Pumps.

**CONNECTING OR DELIVERY PIPES.**—The first term is applied only to pipe between Pump Standard and Lower Barrel or Cylinder, and the last to same pipe as well, but more especially to describe pipe carrying water beyond Pump to any point. These pipes in Single-Acting Pumps may be a trifle smaller than suction pipe. In Double-Acting Pumps they should be same size, and care should be exercised that both are amply large.

**HOT WATER.**—No Pump will draft hot liquids any distance for the reason that the vapor or steam rising from the liquid passes through the suction pipe into the Pump and fills it with vapor instead of water. Therefore, for pumping hot liquids, the Pump should be placed as near supply as practicable, or better, under flooded suction, forcing the liquid upward instead of lifting it by suction. A hot-water Pump always requires metal valves throughout, and should be so ordered.

**LIFT AND FORCE.**—In connection with each Pump we give approximate or safe working limit (feet head of water or equivalent pressure) to which Pumps are adapted. While there are many factors, such as time of service, care and condition of Pumps which cannot be estimated or considered, we think our recommendations will generally answer a perplexing question.

*See pages 569 to 575 for Tables of Pump Capacities, Power, Speed, etc., together with rules for estimating same.*

## TELEGRAPHIC CIPHER CODE.

Wishing to give our correspondents every facility for transmitting telegraphic or cable inquiries, orders, etc., at the least possible expense, we have adopted the following expressions with cipher words opposite. We also use the A. B. C., Lieber, and Commercial Cable Codes. Any of these codes may be used in addressing us and we can reply by same medium.

## GENERAL EXPRESSIONS.

SAPLUFO.....What cable code do you use ?  
 SAPLUHI.....We are waiting to hear from you in reply to our letter of ——  
 SCOXAT.....Have sent you at —— important communication relating to ——  
 SCOYAN.....Have received no remittance from —— please investigate.  
 SITE.....Please reply immediately by telegram.  
 SKATER.....Have sent you this address important communication relating to ——  
 STAUDOT.....We do not understand the —— word of cable.

## RELATIVE TO PRICES AND TERMS.

## INQUIRY.

SEENAT.....Quote lowest price on ——  
 SHOWER.....Quote us lowest price by wire on ——  
 STATIDU.....Will you accept order for —— at —— per  
                   cent discount from list ?  
 STATIEL.....Will you accept order for —— at \$——  
                   boxing extra ?

## ANSWER.

SERFOAL.....We quote for immediate acceptance.  
 SERFOBS.....We will accept your order at prices named.  
 SERFODO.....We cannot accept your order at prices  
                   named.  
 SERFUBR.....Terms cash with order.  
 SERFVAN.....Terms cash on receipt of invoice.  
 SERFVET.....Terms sight draft with bill of lading.  
 SERFVOW.....Terms thirty days net.  
 STATEOP.....Our lowest price on —— boxing extra is  
                   \$——  
 STATEUS.....Our lowest price on —— boxing free is  
                   \$——  
 STATICO.....The highest discount we can give is ——  
                   per cent.  
 STAUCK.....We have already given you our lowest quo-  
                   tations and cannot reduce them.



## RELATIVE TO GOODS IN STOCK.

## INQUIRY.

SAPLUGO.....How soon can you ship?  
 SHOW.....At what price and how soon can you furnish?  
 SIGH.....Have you in stock for immediate shipment?  
 SIZER.....Have order for —. How soon can you ship?

## ANSWER.

SEEMIG.....We can ship at once from stock.  
 SEEMOT.....Could ship in — days.  
 SEEMUP.....Could ship promptly if ordered immediately.  
 STATEMO....Cable received. Will ship immediately.  
 STATENU....Cable received. Will ship in a few days.

## RELATIVE TO ORDERS AND SHIPMENTS.

SCRIACK.....When will you ship — ?  
 SCRIADO.....Has shipment been made of our order? —  
 SCRIAET.....Send tracer after goods not received.  
 SEER.....Ship at once by railroad.  
 SEEK.....Ship by sailing vessel.  
 SEINE.....Ship at once by express.  
 SEDGE.....Ship via steamer.  
 SHIRLER.....Duplicate our order of —  
 SHOER.....Delay shipping order —. Have written.  
 SIEVE.....Give preference over all others to order —.  
 SILLER.....Enter order for —, and ship as soon as possible.  
 SKIFFEN.....Telegraph when you will ship our order —.  
 TUP.....Prepare for immediate shipment against receipt of our letter this day.

SCRIAFS.....We will ship today.  
 SEABAB.....We will ship promptly.  
 SEABATH.....We will ship on receipt of order.  
 SEABELL...We have entered your order and will ship as soon as possible.  
 SEABENT....Your order is completed. Please send shipping instructions immediately.  
 SEABERB....Will ship in one week.  
 SEABESO.....Will ship middle of this week.  
 SEABIBS.....Will ship last of this week.  
 SEABICT.....Will ship in two weeks.  
 SEABIDU.....Will ship in ten days.  
 SEABIFD.....Shipment has been made.  
 TILTIVE.....If order or shipment — has not been shipped, hold for further advices.

## RELATIVE TO CLASSES OF GOODS.

SALTIOT.....Cistern Pumps.  
 SALTIUL.....Well Lift and Force Pumps.  
 SALTIVA.....Well Pump Standards and Working Heads.  
 SALTIWG.....Wind Mill Pump Standards.  
 SALTIXO.....Wind Mill Force Pumps.  
 SALTOB.....Pump Cylinders.  
 SALTOCK.....Irrigating Pumps.  
 SALTODS.....Centrifugal Pumps.  
 SALTOES.....Power Pumps.  
 SALTOFA.....Spray Pumps.  
 SALTOGL.....Rotary Pumps.  
 SALTUBS.....Yard Hydrants, Street Washers, etc.

SALTUFO.....Hydraulic Rams.  
 SALTUGX.....Church and School Bells.  
 SALUBA.....Pump repairs.  
 SALUCK.....Well Points.  
 SALUDVO.....Garden and Fire Engines.  
 SALUEN.....Hose Carts, etc.  
 SALUFOS.....Double-Acting Force Pumps.  
 SAPLODO.....Iron Fitted.  
 SAPLUB.....Brass Fitted.  
 SAPLUCK.....Regular suction and discharge.  
 SAPLUDS.....Suction and discharge —.




## CISTERN PUMPS, PITCHER SPOUT PUMPS AND WELL PUMPS

are, perhaps, the best known and in more general use than any other class.

The Cistern Pump may be placed over a cistern near the house, although it is more often situated under cover, especially in cold climates.

The Pitcher Spout Pump is largely used for the same purposes as the Cistern Pump and, in addition, is many times used in warm climates, over shallow dug or driven wells.

Well Pumps shown are but two of our many styles of Lift and Force Pumps which can be adapted, by changing location of cylinder, for dug, driven or drilled wells from 25 to 50 feet deep. See pages 6 to 29.





# GOULDS CISTERN SUCTION PUMP.

XXIX

WITH ADJUSTABLE EARS AND BRASS VALVE SEAT.

Fig. 1165 represents our new Cistern Suction Pump with revolving standard. The Cylinder is held in place by two adjustable ears, so that the spout can be placed in any position, and the valves are of easy access. The Nos. 0, 1, 2, 3 and 4 are fitted with brass tube valve seat, and the Nos. 5, 6 and 8 with brass bushed valve seat, fitted for either iron or lead pipe to order.




FIG. 1165. SIZES, PRICES, ETC.

FIG. 1165

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		BRASS LINED.	
						Cipher.	Price.	Cipher.	Price.
0	2 in.	3 $\frac{3}{4}$ in.	.042 gals.	1 in. pipe	25 ft.	Valewo	\$3.50	Itensa	\$5.50
1	2 $\frac{1}{4}$ "	5 "	.072 "	1 "	25 "	Valfaw	4.00	Itento	6.00
2	2 $\frac{1}{2}$ "	5 "	.088 "	1 $\frac{1}{4}$ "	25 "	Valfel	4.50	Itenui	6.50
3	2 $\frac{3}{4}$ "	6 $\frac{3}{4}$ "	.145 "	1 $\frac{1}{4}$ "	25 "	Valffac	5.00	Itenvo	7.25
4	3 "	6 $\frac{3}{4}$ "	.171 "	1 $\frac{1}{2}$ "	25 "	Valgac	5.50	Itenuwu	8.00
5	3 $\frac{1}{4}$ "	7 $\frac{1}{4}$ "	.217 "	1 $\frac{1}{2}$ "	25 "	Valged	6.50	Iteoba	9.50
6	3 $\frac{1}{2}$ "	7 $\frac{1}{4}$ "	.250 "	1 $\frac{1}{2}$ "	25 "	Valgis	8.00	Jambat	11.50
8	4 "	7 $\frac{1}{4}$ "	.327 "	2 "	25 "	Valgig	10.00	Jambig	15.00

*Brass Cylinder Pumps* have Brass Plungers. *Brass Pumps* having all parts brass except lever, bearer and base furnished to order. We can fit any of our Cistern Pumps with brass lower valves and metal plunger to adapt them for hot water, at extra prices given below :

No. 0.	No. 1.	No. 2.	No. 3.	No. 4.	No. 5.	No. 6.	No. 8.
\$1.15	\$1.15	\$1.40	\$1.40	\$1.40	\$1.75	\$1.75	\$2.10

We can pack in an ordinary hogshead or cask about the following number of this and similar Pumps, according to sizes.

No. 0.	No. 1.	No. 2.	No. 3.	No. 4.	No. 5.	No. 6.	No. 8.
40	36	32	24	20	15	12	10



# GOULDS CISTERN SUCTION PUMP.

WITH REVOLVING BEARER TOP AND SCREW BASE.




FIG. 198

Fig. 198, represented by cut, is one of our Cistern Suction Pumps. Revolving bearer top permits lever to be used in any desired position. The cylinder screws on outside of base. Brass suction tube is threaded to take wrought-iron pipe coupling, if gas pipe is used, or cast-iron nut with brass tube, if lead pipe is used. Fitted for either lead or wrought-iron pipe, or both, as ordered. *Brass Cylinder Pumps* have Brass Plungers. *Brass Pumps* having all parts brass except lever, bearer and base furnished to order.

FIG. 198. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction Fitted For.	Lift.	IRON.		BRASS-LINED.	
						Cipher.	Price.	Cipher.	Price.
0	2 in.	5 in.	.07 gal.	1 in. pipe	25 ft.	Abet	\$3.50	Jambot	\$5.50
1	2 1/4 "	6 "	.10 "	1 "	25 "	Able	4.00	Jambug	6.00
2	2 1/2 "	6 "	.13 "	1 1/4 "	25 "	Ablush	4.50	Jambyx	6.50
3	2 3/4 "	6 "	.15 "	1 1/4 "	25 "	Abut,	5.00	Jamcab	7.25
4	3 "	6 "	.18 "	1 1/4 "	25 "	Ace	5.50	Jamcil	8.00
5	3 1/4 "	6 "	.22 "	1 1/2 "	25 "	Ached	6.50	Jamcod	9.50
6	3 1/2 "	6 "	.25 "	1 1/2 or 2 "	25 "	Acid	8.00	Jamcug	11.50
8	4 "	6 "	.33 "	2 in.	25 "	Acme	10.00	Jarrodd	15.00

# GOULDS CISTERN SUCTION PUMP.

WITH REVOLVING BEARER TOP AND BOLTED BASE.




FIG. 199

Fig. 199 is another popular style of Cistern Pump. The lever can be turned to any convenient position. The valve seat is formed by brass tube and flange, and the end of tube threaded to take wrought-iron pipe coupling if gas pipe is used or cast-iron nut with brass tube is supplied, if lead pipe is used. Will fit for lead or wrought-iron pipe as ordered.

To prevent freezing, trip the lower valve by raising lever to extreme height, thus allowing water to leave cylinder. *Brass Cylinder Pumps* have Brass Plungers. *Brass Pumps* having all parts brass except lever, bearer and base furnished to order.

FIG. 199. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		BRASS-LINED.		*BRASS-CYLINDER.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	5 in.	.07 gal.	1 in. pipe	25 ft.	Acrue	\$3.50	Jarrub	\$5.50	Vicious	\$5.50
1	2 1/4 "	6 "	.10 "	1 "	25 "	Actal	4.00	Jarryl	6.00	Vicount	6.00
2	2 1/2 "	6 "	.13 "	1 1/4 "	25 "	Adden	4.50	Jarsad	6.50	Victim	7.00
3	2 3/4 "	6 "	.15 "	1 1/4 "	25 "	Afaro	5.00	Jarsic	7.25	Victond	8.00
4	3 "	6 "	.18 "	1 1/4 "	25 "	Aftez	5.50	Jarsils	8.00	Victory	10.00
5	3 1/4 "	6 "	.22 "	1 1/2 "	25 "	Ageda	6.50	Jarsob	9.50	Victres	13.00
6	3 1/2 "	6 "	.25 "	1 1/2 "	25 "	Aider	8.00	Jarsum	11.50	Victual	18.00
8	4 "	6 "	.33 "	2 "	25 "	Aimed	10.00	Jettist	15.00	Viduah	25.00

\*Brass Cylinder Pumps have brass plungers. Brass Pumps having all parts brass except lever, bearer and base furnished to order.

We can fit our Cistern Pumps with brass lower valves and metallic packing for hot water, at an extra price. (See page XV.)

# GOULDS CISTERN SUCTION PUMP.

1

WITH REVOLVING BEARER TOP AND BOLTED BASE.

The cut shows our Fig. 200, with broad bearing and high base.

A substantial hub on the under side of the base has threads on it for coupling on an iron nut with gas-pipe threads cut in it for connecting wrought-iron pipe. Soldering tube is fitted in this nut when connection to lead pipe is desired. To prevent freezing, raise lever to extreme height, thus allowing water to leave cylinder.

FIG. 200 SIZES, PRICES, ETC.




FIG. 200

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		BRASS-LINED.		*BRASS CYL.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	5 in.	.07 gal.	1 in. pipe	25 ft.	Aired	\$3.50	Jetton	\$5 50	Ember	\$5.50
1	2 1/4 "	6 "	.10 "	1 "	25 "	Airy	4 00	Jettort	6 00	Emboss	6.00
2	2 1/2 "	6 "	.13 "	1 1/4 "	25 "	Akin	4 50	Jettose	6 50	Emery	7.00
3	2 3/4 "	6 "	.15 "	1 1/4 "	25 "	Alas	5.00	Jetua	7.25	Emit	8.00
4	3 "	6 "	.18 "	1 1/4 "	25 "	Allied	5 50	Jetubc	8 00	Empty	10.00
5	3 1/4 "	6 "	.22 "	1 1/2 "	25 "	Ally	6.50	Jetuck	9.50	Enact	13.00
6	3 1/2 "	6 "	.25 "	1 1/2 "	25 "	Alms	8.00	Jetuds	11 50	End	18.00
8	4 "	6 "	.33 "	2 "	25 "	Alsod	10.00	Juggob	15.00	Vigor	25.00

# GOULDS CISTERN SUCTION PUMP.

WITH REVOLVING BEARER TOP AND BRACKETS.

The cut, Fig. 202 1/2, represents our new style Revolving Top Cistern Pump with brackets. This is in many instances a more convenient form than a Pump on base. It can be secured to the wall in any place desired, and made to take the least possible room. Has a brass valve seat with tube threaded to take wrought-iron pipe coupling, if gas pipe is used, or nut with soldering tube, if lead pipe is used.

FIG. 202 1/2. SIZES, PRICES, ETC.




FIG. 202 1/2

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		BRASS-LINED.		*BRASS CYL.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	5 in.	.07 gal.	1 in. pipe	25 ft.	Axe	\$3.50	Juggul	\$5.50	Epic	\$5.50
1	2 1/4 "	6 "	.10 "	1 "	25 "	Black	4.00	Juggso	6.00	Epoch	6.00
2	2 1/2 "	6 "	.13 "	1 1/4 "	25 "	Bad	4.50	Juggta	6.50	Equal	7.00
3	2 3/4 "	6 "	.15 "	1 1/4 "	25 "	Bagged	5.00	Jughab	7.25	Equip	8.00
4	3 "	6 "	.18 "	1 1/4 "	25 "	Bail	5.50	Jughid	8.00	Era	10.00
5	3 1/4 "	6 "	.22 "	1 1/2 "	25 "	Baited	6.50	Jughot	9.50	Erect	13.00
6	3 1/2 "	6 "	.25 "	1 1/2 "	25 "	Bake	8.00	Jughus	11.50	Err	18.00

We can fit our Cistern Pumps with brass lower valves and metallic packing for hot water, at an extra price. (See page XIX.)

\*Brass Cylinder Pumps have brass plungers. Brass Pumps, having all parts brass, except lever, bearer and base, furnished to order.

## GOULDS CISTERN SUCTION PUMP.

WITH REVOLVING BEARER TOP AND BOLTED BASE.

Fig. 201 represents a Cistern Suction Pump, with revolving bearer top and bolted base. It is rather taller than Fig. 200, on preceding page. Base is bolted to Pump with leather packing between. Fitted for lead or wrought-iron pipe, or both, as ordered. To prevent freezing, raise the lever to extreme height, thus allowing water to leave cylinder.

FIG. 201. SIZES, PRICES, ETC.




FIG. 201

No.	Dia. Cyl.	Suc.	Capacity per Stroke.	IRON.		BRASS-LINED.	
				Cipher.	Price.	Cipher.	Price.
0	2 in.	1 in.	.08 gal.	Alum	\$4.00	Jughyl	\$6.00
1	2 1/4 "	1 "	.10 "	Amid	4.50	Jugica	6.50
2	2 1/2 "	1 1/4 "	.12 "	Arc	5.00	Jugido	7.00
3	2 3/4 "	1 1/4 "	.15 "	Arch	5.75	Jugify	8.00
4	3 "	1 1/4 "	.18 "	Arm	6.25	Juglga	8.75
5	3 1/4 "	1 1/2 "	.20 "	Army	6.75	Justlzo	9.75
6	3 1/2 "	1 1/2 "	.25 "	Art	8.00	Jusuba	11.50
8	4 "	2 "	.33 "	Ask	10.00	Jusuck	15.00

## GOULDS CISTERN SUCTION PUMP.

WITH REVOLVING BEARER TOP, DOUBLE ROD AND GUIDE.

The cut shows one of our Cistern Pumps, with double rods and guide rod. So constructed, they work with more uniform stroke, and are on this account much preferred in some localities. In other respects they are just like our other Cistern Pumps.

Fitted for lead or wrought-iron pipe, or both, as ordered.

FIG. 210. SIZES, PRICES, ETC.




FIG. 210

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction Fitted for.	Lift.	IRON.		BRASS-LINED.		*BRASS CYLINDER.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	2 1/4 in.	6 in.	.10 gal.	1 1/4 in. pipe.	25 ft.	Scofed	\$5.00	Jusudo	\$7.00	Virtual	\$7.00
2	2 1/2 "	6 "	.13 "	1 1/4 "	25 "	Scoff	5.50	Jusufu	7.50	Virtue	8.00
3	2 3/4 "	6 "	.15 "	1 1/4 "	25 "	Birdseye	6.00	Jusuga	8.25	Bonded	9.00
4	3 "	6 "	.18 "	1 1/4 "	25 "	Scoop	6.50	Jusugil	9.00	Virulen	11.00
6	3 1/2 "	6 "	.25 "	1 1/2 "	25 "	Scope	9.00	Keepjan	12.50	Virus	19.00
8	4 "	6 "	.32 "	2 "	25 "	Score	11.00	Keepku	16.00	Visage	26.00

We can fit our Cistern Pumps with brass lower valves and metal packing for hot water, at extra price. (See page XIX.)

\* Brass Cylinder Pumps have brass plungers. Brass Pumps, having all parts brass, except lever, bearer and base, furnished to order.



# GOULDS SEMI-FLUID SUCTION PUMP.

3

WITH REVOLVING BEARER TOP AND DOUBLE ROD AND GUIDE. METALLIC FITTED

The cut represents our Fig. 444, built for pumping molasses, syrups of any kind, tar, oil, or any other liquids of any consistency, either hot or cold. The piston, piston rod, valves and connecting tube of the iron Pumps are made of brass, while the balance is constructed of iron. When ordered of brass, the whole Pump is made of that metal except the base, top and lever, and is so constructed that no iron is brought into contact with the liquid.

When used for hot liquids we would urge placing the Pump as close to them as possible, as the vapors arising will qualify the vacuum produced by the Pump.

Fitted for lead or wrought-iron pipe connections, as ordered.

FIG. 444. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		BRASS.	
						Cipher.	Price.	Cipher.	Price.
2	2½ in.	6 in.	.13 gal.	1¼ in. pipe	25 ft.	Folly	\$12.00	Forcep	\$20.00
4	3½ "	6 "	.18 "	1½ "	25 "	Fond	15.00	Ford	25.00
6	3½ "	6 "	.25 "	1½ "	25 "	Fontal	17.00	Forel	30.00
8	4 "	6 "	.33 "	2 "	25 "	Food	21.00	Forge	36.00
10	4½ "	6 "	.41 "	2½ "	25 "	Fopab	25.00	Forky	42.00




FIG. 444

# GOULDS SEWAGE SUCTION PUMP.

WITH BALL VALVES.

Fig. 1082, Sewage Suction Pump, has revolving bearer top, held in place by set screw, iron cylinder provided with brackets, and bolted lower attachment.

The valves are bronze balls, with bronze valve seats. This Pump is adapted for pumping sewage and similar work.

FIG. 1082. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	Cipher.	Price.
6	3½ in.	6 in.	.25 gal.	1½ in.	25 ft.	Rudeds	\$18.50
8	4 "	6 "	.33 "	2 "	25 "	Rudeel	21.50




FIG. 1082

## GOULDS SPECIAL PITCHER-SPOUT PUMP.

*WITH CLOSED REVOLVING BEARER TOP AND BOLTED BASE.*

Fig. 923 is our new closed-top Pitcher-Spout Pump. It is of less weight and bulk than our regular stock Pitcher Pump, but on that account not lacking in either strength or capacity, for it possesses both.

Again, one thousand of these Pumps can be transported for two-thirds the cost of same number of regular Pumps.

We build but the leading size specified below, and fit for iron or lead pipe or both, to order.




FIG. 923

FIG. 923. SIZE, PRICE, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.	
						Cipher.	Price.
2	3 in.	4 in.	.12 gal.	1¼ in. pipe	25 ft.	Weyed	\$4.75

## NICKEL-PLATED CYLINDER PITCHER-SPOUT PUMP.

*WITH CLOSED REVOLVING BEARER TOP AND BOLTED BASE.*

Fig. 1170 represents our new Pitcher-Spout Pump, which we offer with Nickel-Plated Seamless-Drawn Brass Cylinder. This Seamless-Drawn Brass Cylinder offers the most serviceable form of Cylinder and admits of attractive finish. Pump has revolving bearing top, galvanized plunger and rod; cut-off base and connections for iron or lead pipe, to order. Our design and construction will recommend itself where a neat, compact Pump, in keeping with good surroundings, is required.




FIG. 1170

FIG. 1170. SIZE, PRICE, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	NICKEL-PLATED CYLINDER.	
						Cipher.	Price.
2	3 in.	4 in.	.12 gal.	1¼ in. pipe	25 ft.	Loinac	\$7.50

# GOULDS OPEN-TOP PITCHER-SPOUT PUMP.

5

WITH OPEN REVOLVING BEARER TOP AND BOLTED BASE.

Fig. 205 shows our standard Open-Top Pitcher-Spout Pump, so generally and favorably known throughout the world. Wherever a cheap but substantial Pump for use in house or over drive-well is required this Pump (or Fig. 205½, Closed Top) is a favorite. It has revolving bearer top. By lifting lever to extreme height valve is tripped, to prevent freezing. A suction nut, tapped to receive wrought-iron pipe, is furnished on the hub underneath base. Through this is introduced a soldering tube for lead pipe connection.

FIG. 205. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		*BRASS-LINED.		*PORCELAIN-LINED.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	2½ in.	4 in.	.09 gal.	1 in. pipe	25 ft.	Baled	\$4.25	Toledo	\$6.50	Churuc	\$6.50
2	3	4	.12	1¼	25	Balky	4.75	Toiles	7.25	Churva	7.25
3	3½	4	.17	1¼	25	Ball	5.25	Tolel	8.00	Churvic	8.00
4	4	4	.22	1½	25	Balmo	6.25	Tolling	9.00	Churwoc	9.00
5	4½	5	.34	1½	25	Band	9.50	Tombey	12.50	Chusab	12.50
6	5	5	.43	2½	25	Kidfat	17.00	Kidfig	22.00	Kidgob	22.00

\*Brass-Lined and Porcelain-Lined Pumps are furnished with galvanized plungers and rods.



FIG. 205

# GOULDS CLOSED-TOP PITCHER-SPOUT PUMP.

WITH CLOSED REVOLVING BEARER TOP AND BOLTED BASE.

Fig. 205½ shows our standard Tight-Top Pitcher-Spout Pump, so generally and favorably known throughout the world. It fills the requirement for a cheap but substantial Pump for use in house, over cistern or over drive wells. Lever can be turned to any desired position, and by raising lever to extreme height valves are tripped and cylinder emptied, to prevent freezing. A suction nut tapped to receive wrought-iron pipe is furnished on the hub underneath base. Through this is introduced a soldering tube for lead pipe connection.

FIG. 205½. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		*BRASS-LINED.		*PORCELAIN-LINED.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	2½ in.	4 in.	.09 gal.	1 in. pipe	25 ft.	Banked	\$4.25	Bonafide	\$6.50	Cleaba	\$6.50
2	3	4	.12	1¼	25	Barb	4.75	Briefness	7.25	Cleaboc	7.25
3	3½	4	.17	1¼	25	Barky	5.25	Cabinet	8.00	Cleabul	8.00
4	4	4	.22	1½	25	Barned	6.25	Casined	9.00	Clebber	9.00
5	4½	5	.34	1½	25	Keepa	9.50	Keeplog	12.50	Kidest	12.50
6	5	5	.43	2½	25	Keeplit	17.00	Kiddog	22.00	Kidetu	22.00

\*Brass-Lined and Porcelain-Lined Pumps furnished with galvanized plungers and rods.




FIG. 205½



# GOULDS VACUUM BASE PITCHER-SPOUT PUMP.

WITH CLOSED REVOLVING BEARER TOP AND PATENT VACUUM BASE.

Fig. 208 is the same as our Fig. 205½ (page 5), and in addition it has an improvement in the base of the Pump. Oftentimes in driven wells, where the soil is so close as to make an air-tight joint around the pipe, an ordinary Pump will not work well; while with the Vacuum Base Pump all difficulty is obviated, for by creating a vacuum in the base and permitting the water to form there a reservoir, a constant supply of water is obtained for the Pump. We fit them always for wrought-iron pipe, with the thread cut in the hub of the base.




FIG. 208

FIG. 208. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		*BRASS-LINED.		*PORCELAIN-LINED.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	2½ in.	4 in.	.09 gal.	1 in. pipe.	25 ft.	Birdy	\$4.75	Chusif	\$7.00	Croctic	\$7.00
2	3 " "	4 " "	.12 " "	1¼ " "	25 " "	Bite	5.25	Chusom	7.75	Crotan	7.75
3	3½ " "	4 " "	.17 " "	1½ " "	25 " "	Blast	5.75	Chusud	8.50	Crotco	8.50

\* Brass-lined and Porcelain-lined Pumps have galvanized plungers and rods.

## GOULDS ROUND-SPOUT PITCHER PUMP.

WITH CLOSED REVOLVING BEARER TOP AND BOLTED BASE.

Fig. 209 shows our new style Pitcher Pump, with a round spout. This construction prevents water from slopping over spout, and also provides means of hanging bucket upon the spout. This Pump is made like our other Pitcher Pumps, with revolving brake, bolt fastenings and cut-off base.

Fitted for wrought-iron pipe unless otherwise ordered.

To prevent freezing, raise lever to extreme height, thus allowing water to leave cylinder.



FIG. 209

FIG. 209. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction Fitted for.	Lift.	IRON.		*BRASS-LINED.		*PORCELAIN-LINED.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	2½ in.	4 in.	.09 gal.	1 in. pipe.	25 ft.	Waled	\$4.25	Clebjac	\$6.50	Cleblok	\$6.50
2	3 " "	4 " "	.12 " "	1¼ " "	25 " "	Bleat	4.75	Clebkub	7.25	Clecac	7.25
3	3½ " "	4 " "	.17 " "	1½ " "	25 " "	Walk	5.25	Cleblip	8.00	Clecim	8.00

\* Brass-lined and porcelain-lined Pumps have galvanized plungers and rods.

# GOULDS "SOUTHERN STAR" LIFT PUMP.

7

FOR OUT-DOOR USE IN WARM CLIMATES.

We have frequent calls for a Suction and Lift Pump taller and heavier than our largest Cistern and Pitcher Pumps, and offer Fig. 607, which we build about 41 inches high.

It is provided with revolving bearer top and has a long heavy lever. The Pump stock acts as a cylinder, in which is the plunger, and can be emptied of water by raising the lever, thus tripping valve seated on the base. A strong brace gives rigidity to the Pump.

FIG. 607. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Well Rod.	Lift.	Cipher.	Iron.
4	3 in.	6 in.	.18 gal.	1 $\frac{1}{4}$ in. pipe	7-16 in.	25 ft.	Moredy	\$8.50
5	3 $\frac{1}{4}$ "	6 "	.22 "	1 $\frac{1}{2}$ "	7-16 "	25 "	Morned	9.00




FIG. 607

# GOULDS "SOUTHERN STAR" FORCE PUMP.

FOR OUT-DOOR USE IN WARM CLIMATES.

This Pump is about 50 inches high, has revolving brake or fulcrum, a strong, heavy lever, and is in every way calculated to render good service. A thread is cut on the end of the spout, and with each Pump is sent a half hose coupling and nut for attaching hose.

As in Fig. 607, shown above, the plunger works in the stock of Pump, which can be emptied of water by raising the lever, thus tripping the valve in the base.

When ordered with cock spout we add \$2.50 to list price.

FIG. 608. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Well Rod.	Discharge Fitted for	*Lift and Force.	Cipher.	Iron.
4	3 in.	6 in.	.18 gal.	1 $\frac{1}{4}$ in. pipe	7-16 in.	1 in. hose	50 ft.	Mort	\$13.00
5	3 $\frac{1}{4}$ "	6 "	.22 "	1 $\frac{1}{2}$ "	7-16 "	1 "	50 "	Mossy	14.00
6	3 $\frac{1}{2}$ "	6 "	.25 "	1 $\frac{3}{4}$ "	7-16 "	1 "	40 "	Mostack	15.00




FIG. 608

\*Total lift and force from supply to point of delivery, Pump not more than 25 ft. above water.


# GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

*ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.*




*FIG. 1018*

Light Standard.



*FIG. 550*

Medium Standard.



*FIG. 551*

Heavy Standard.

For description, table of sizes, prices, etc., see opposite page.



# GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

9

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

The Pumps illustrated on opposite page represent our line of Revolving Open-Top Anti-Freezing Well Lift Pumps, for out-door cisterns and shallow wells—dug, drilled or driven—where water is not more than 25 feet below ground line. These Pumps are similar in design, differing only in size and weight of Standard. As listed, Pumps are adapted for wells about 28 feet deep. By lowering cylinder to within 15 feet of the water, Pumps can be used in wells 40 to 50 feet in depth. Pumps are tapped and receive connecting pipe near spout, not at base. Pump base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.

FIG. 1018. SIZE, PRICE, ETC.

No.	Cyl.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYL.		BRASS-TUBE CYL.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
4	3 x 10 in.	6 in.	.18 gal.	1 1/4 in. pipe	30 ft.	Diestock	\$8.00	Altitudinal	\$10.50	Biology	\$12.50

FIG. 550. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
3	2 3/4 x 10 in.	6 in.	.15 gal.	1 1/4 in. pipe	40 ft.	Vased	\$8.25	Blushing	\$10.75
4	3 x 10 "	6 "	.18 "	1 1/4 "	30 "	Vassal	8.50	Brinded	11.00
6	3 1/2 x 10 "	6 "	.25 "	1 1/2 "	30 "	Eobead	9.50	Broadcl	12.50

FIG. 551. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
3	2 3/4 x 10 in.	6 in.	.15 gal.	1 1/4 in. pipe	50 ft.	Vastley	\$8.75	Bunstable	\$11.25
4	3 x 10 "	6 "	.18 "	1 1/4 "	40 "	Vasty	9.00	Canacu	11.50
6	3 1/2 x 10 "	6 "	.25 "	1 1/2 "	40 "	Vastel	10.00	Crotidun	13.00
8	4 x 10 "	6 "	.33 "	2 "	40 "	Eobeds	11.50	Crotjox	15.00

\* Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water.

# GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

*ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.*



FIG. 1019

Light Standard.



FIG. 848½

Medium Standard.



FIG. 848

Heavy Standard.

For description, table of sizes, prices, etc., see opposite page.

# GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

11

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

The Pumps, Figs. 1019, 848½ and 848, represented on opposite page, illustrate our line of Revolving Tight-Top, Anti-Freezing Set Length Pumps for shallow wells and cisterns. They are fitted with Tight Top, Polished Rod and Links above. This construction keeps plunger rod in perfect alignment and prevents all foreign substances getting into working parts of Pump. The general adaptations and capacities are tabulated below. Pumps are tapped and receive connecting pipe near spout, not at base. Pump base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61), "Universal " Bronze Valve and Seat, to order at extra price.

FIG. 1019. SIZE, PRICE, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.		BRASS-TUBE CYLINDER.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
4	3 x 10 in.	6 in.	.18 gal.	1¼ in. pipe	30 ft.	Divela	\$8.75	Cusale	\$11.25	Dancmul	\$13.25

FIG. 848½. SIZES, PRICES, ETC

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	50 ft.	Weltud	\$9.00	Diastem	\$11.50
4	3 x 10 "	6 "	.18 "	1¼ "	30 "	Weltvd	9.25	Draclym	11.75
6	3½ x 10 "	6 "	.25 "	1½ "	30 "	Erripic	10.25	Dripal	13.25

FIG. 848. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	50 ft.	Wamble	\$9.50	Elytah	\$12.00
4	3 x 10 "	6 "	.18 "	1¼ "	40 "	Wammel	9.75	Elytale	12.25
6	3½ x 10 "	6 "	.25 "	1½ "	40 "	Easlade	10.75	Elytamb	13.75
8	4 x 10 "	6 "	.33 "	2 "	40 "	Easloot	12.25	Exaba	15.75

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water.



# GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

*ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.*



FIG. 1039

Light Standard.



FIG. 553

Medium Standard.



FIG. 554

Heavy Standard.

For description, tables of sizes, prices, etc., see opposite page.

# GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

13

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

Figs. 1039, 553, 554 represent our Anti-Freezing Lift Pumps, with revolving tight top, for shallow wells. In this style of Pump the rod is guided above and moves up and down in a vertical line without oscillating. It also constitutes a tight top, preventing all foreign substance from getting into working parts.

Pumps are tapped and receive wrought-iron connecting pipe near spout.

With special long, flat rods for wind mill, 50 cents extra list.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.

FIG. 1039. SIZE, PRICE, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
4	3 x 10 in.	6 in.	.18 gal.	1 1/4 in. pipe	30 ft.	Divellac	\$9.00	Fieldab	\$11.50

FIG. 553. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
3	2 3/4 x 10 in.	6 in.	.15 gal.	1 1/4 in. pipe	40 ft.	Vection	\$9.25	Fieldip	\$11.75
4	3 x 10 "	6 "	.18 "	1 1/4 "	30 "	Vector	9.50	Flemit	12.00
6	3 1/2 x 10 "	6 "	.25 "	1 1/2 "	30 "	Erripol	10.50	Firema	13.50

FIG. 554. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
3	2 3/4 x 10 in.	6 in.	.15 gal.	1 1/4 in. pipe	50 ft.	Veda	\$9.75	Firfal	\$12.25
4	3 x 10 "	6 "	.18 "	1 1/4 "	40 "	Vedet	10.00	Flickon	12.50
6	3 1/2 x 10 "	6 "	.25 "	1 1/2 "	40 "	Fierno	11.00	Flujnob	14.00
8	4 x 10 "	6 "	.32 "	2 "	40 "	Fireout	12.50	Flushzd	16.00

\* Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water.

# 14 GOULDS "STAR" ANTI-FREEZING WELL LIFT PUMPS.

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.




FIG. 206

Fig. 206 is adapted for out-door cisterns and shallow wells, where water is not to be lifted over 15 or 25 feet. It is composed of a standard, cast-iron connecting pipe and cylinder, having the valves in it. The internal diameter of the standard is a trifle larger than that of the cylinder; hence the plunger can be drawn up through it, repaired and replaced, if ever necessary. This Pump has screwed base.

Pump base to bottom of cylinder,  $3\frac{1}{2}$  feet.

Fig. 207 is similar in design to Fig. 206, but has wrought-iron connecting pipe. By adding to the connecting pipe and piston rod, and so dropping the cylinder farther into the well, until the cylinder is within, say, 15 to 20 feet of the surface of the water, this Pump could be used in wells from 30 to 40 feet deep. This Pump has bolted base. Base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.




FIG 207

FIG. 206. SIZES, PRICES, ETC.

No.	Dia. Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
1	2 in.	6 in.	.08 gal.	1 in. pipe	25 ft.	Basreli	\$7.00	Rawedo	\$9.50
3	2½ in.	6 in.	.13 "	1¼ in. pipe	25 "	Beamed	8.00	Raweef	10.50
5	3 in.	6 in.	.18 "	1½ in. pipe	25 "	Beard	9.00	Rawefs	11.50

FIG. 207. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Iron.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	40 ft.	Bendam	\$8.00	Rawego	\$10.50
4	3 x 10 "	6 in.	.18 "	1½ in. pipe	30 "	Bent	8.50	Rawehi	11.00
6	3½ x 10 "	6 in.	.24 "	1½ in. pipe	30 "	Eobale	9.50	Raweid	12.50

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water.



# GOULDS ANTI-FREEZING "STOCK" PUMPS.

## LIFT PUMPS OF LARGE CAPACITY.

Pumps shown on this page have large pumping capacity and have come into such general use among farmers having many head of stock to water that they are known to the trade as "Stock Pumps." They are also well suited for Town Pumps in shallow wells.

Fig. 552 stands 4 feet tall. The standard is of cast-iron, with revolving bearer top. Spout is large and waterways ample. Pipe used in set length is 1½ and 2-inch and screws into the standard just below the spout.

Fig. 1261 is made with wind mill top, having adjustable stroke 6, 8 or 10 inches. Equally adapted for pumping by hand or by wind mill. Spout is large, as is also the upper portion of the standard, which positively prevents any "slopping over," however fast the Pump is worked. Lower portion of standard is formed by a continuation of the 2-inch wrought-iron pipe which forms the set lengths. Base is adjustable.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.



FIG. 552




FIG. 1261

FIG. 552. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
6	3½ x 10 in.	6 in.	.25 gal.	1½ in.	40 ft.	Kidhat	\$11.00	Kidhil	\$14.00
8	4 x 10 "	6 "	.32 "	2 "	40 "	Vectuum	12.50	Kidkiss	16.00

FIG. 1261. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke at 10-in. Stroke.	Suction.	*Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
8	4 x 16 in.	{ Adjustable } { 6, 8, 10 in. }	.54 gal.	2 in.	40 ft.	Knowf	\$16.50	Knowvo	\$20.00
10	4½ x 16 "		.69 "	2 "	40 "	Knowug	18.50	Knowyx	22.50

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water.

# GOULDS WELL LIFT AND FORCE PUMPS.

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

Figs. 1252 and 1153 illustrate our new Set Length Lift and Force Pumps with adjustable base and brace, syphon spout and revolving bearer top.

The principal feature of these new Pumps is the wrought-iron pipe stock with base and brace, which can be adjusted to meet any requirements of height of lever and spout. Under the base is a heavy malleable pipe nut, connecting standard with set length. This permits extension of set length with the least possible trouble. When so ordered, we can furnish stock or standard complete without set length, adapting it for any style of lower working cylinder.

Under Fig. 1252 we list Set Length Lift Pump, without stuffing box and hose coupling. Under Fig. 1153 Set Length Force Pump with stuffing box and hose coupling. Base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.




FIG. 1252




FIG. 1153

FIG. 1252. SIZE, PRICE, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON.		BRASS-LINED CYLINDER.		BRASS-TUBE CYLINDER.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
4	3 x 10 in.	5 in.	.15 gals.	1 1/4 in. pipe	25 ft.	Harevu	\$8.00	Harfab	\$10.50	Knuba	\$12.50

FIG. 1153. SIZE, PRICE, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED CYLINDER.		BRASS-TUBE CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
4	3 x 10 in.	5 in.	.15 gals.	1 1/4 in. pipe	3/4 in. hose	40 ft.	Harfact	\$11.50	Harfbu	\$14.00	Knubel	\$16.00

\* Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# HEAVY ANTI-FREEZING LIFT AND FORCE PUMPS.

17

ADAPTED FOR 'UNIVERSAL' BRONZE VALVE AND SEAT.

Fig. 1206 shows an open-top Well Lift Pump, for deep wells. It has heavy cast-iron stock, fitted with wrought-iron set length and cylinder; set length measures 48 inches from base of Pump to bottom of cylinder.

Fitted in this manner, Pump is adapted for wells of depth not exceeding 25 feet. Where required for deeper wells, cylinder may be lowered. We can supply extra lengths of pipe and rod for wells of any depth.

No. 6 Pump has 1½-inch pipe in set length.

No. 8 Pump has 2-inch pipe in set length.

Fig. 1207 shows our heavy Well Force Pump. General description of Lift Pump, Fig. 1206, will apply to this Pump also.

When so ordered, we can furnish Fig. 1207 with Compression Cock on spout at \$2.50 extra list.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.




FIG. 1206



FIG. 1207

FIG. 1206. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
6	3½ x 10 in.	6 in.	.25 Gal.	1½ in. pipe	25 ft.	Dagho	\$12.00	Knubid	\$15.00
8	4 x 10 "	6 "	.32 "	2 " "	25 "	Dagliac	14.00	Knubju	17.50

FIG. 1207. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
6	3½ x 10 in.	6 in.	.25 gal.	1½ in.	1 in. hose	45 ft.	Churob	\$18.00	Knubki	\$21.00
8	4 x 10 "	6 "	.32 "	2 "	1 "	30 "	Chikam	20.00	Knubly	23.50

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water, or total lift and force from supply to point of delivery.



# 18 GOULDS "STAR" ANTI-FREEZING WELL FORCE PUMPS.

*ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.*




FIG. 1244

Medium Standard,  
Bolted Spout.




FIG. 852½

Heavy Standard,  
Bolted Spout.




FIG. 1245

Medium Standard,  
Cock Spout.




FIG. 882½

Heavy Standard,  
Cock Spout.

For description and table of sizes, prices, etc. see opposite page

# GOULDS "STAR" ANTI-FREEZING WELL FORCE PUMPS. 19

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

Figs. 1254, 1255, 852½ and 882½ represent our "Star" Anti-Freezing Force Pumps. This style is especially adapted for garden, yard and stable use, being fitted for hose discharge. All have an outlet at back of spout for attaching pipe. They are tapped and receive connecting pipe near spout, not at base.

Figs. 1245 and 882½ have cock spout. Pump base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.

FIG. 1244. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Fopross	\$12.25	Fropbo	\$14.75
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Frecofs	12.50	Fropcol	15.00
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Fropac	13.50	Fuchtac	16.50

FIG. 852½. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Wared	\$12.75	Fucibad	\$15.25
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Wareful	13.00	Fucidul	15.50
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Erripus	14.00	Gavaot	17.00

FIG. 1245. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Gavaux	\$14.75	Genesun	\$17.25
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Gavavo	15.00	Gipta	17.50
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Genesol	16.00	Giptale	19.00

FIG. 882½. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gal.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Warest	\$15.25	Gintam	\$17.75
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Warfare	15.50	Giptanc	18.00
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Erripy	16.50	Giptik	19.50

\* Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# 20 GOULDS "STAR" ANTI-FREEZING WELL FORCE PUMPS.

*ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.*



FIG. 1247

Medium Standard,  
Bolted Spout.



FIG. 424

Heavy Standard,  
Bolted Spout.




FIG. 1248

Medium Standard,  
Cock Spout.




FIG. 426

Heavy Standard,  
Cock Spout.

For description and table of sizes, prices, etc., see opposite page.



# GOULDS "STAR" ANTI-FREEZING WELL FORCE PUMPS. 21

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

Figs. 1247, 424, 1248 and 426 illustrate our "Star" Anti-Freezing Force Pumps, with Revolving Wind Mill Top. Our construction keeps plunger rod in perfect alignment, thus working in cylinder smoothly and evenly. Figs. 1248 and 426 have cock spouts. All are fitted with hose discharge. Pumps are tapped and receive connecting pipe near spout, not at base. Pump base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.

FIG. 1247. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gals.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Giptome	\$13.25	Glujwu	\$15.75
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Gipula	13.50	Glujwyn	16.00
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Glujvo	14.50	Glukac	17.50

FIG. 424. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gals.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Vell	\$13.75	Glukade	\$16.25
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Vellet	14.00	Glukid	16.50
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Endnadu	15.00	Glukief	18.00

FIG. 1248. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gals.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Goldid	\$15.75	Grandid	\$18.25
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Goldiel	16.00	Grandog	18.50
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Gradka	17.00	Granduc	20.00

FIG. 426. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2¾ x 10 in.	6 in.	.15 gals.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	60 ft.	Vogle	\$16.25	Glukifs	\$18.75
4	3 x 10 "	6 "	.18 "	1¼ "	1¼ " " ¾ "	60 "	Voglite	16.50	Glukode	19.00
6	3½ x 10 "	6 "	.25 "	1½ "	1¼ " " ¾ "	45 "	Endnip	17.50	Glukock	20.50

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS ANTI-FREEZING WELL FORCE PUMPS.

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.




FIG. 854

Fig. 854 represents a new Well Force Pump with revolving bearer top, polished rod and links above. The cut will show its construction, and at the very low price it is offered, it represents good value. We aim at simplicity of parts, and these adequately strong for purpose they are intended. Cock spouts furnished at \$2.50 extra list.

Pump base to bottom of cylinder, 4 feet.

Fig. 264 is a modification of our House Force Pump, rendered anti-freezing and adapted for outdoor wells, or those of any depth, by addition of set length and placing working parts—plunger and valve—below frost line and within suction distance of water. Water may be forced through upper discharge into pipe, or delivered at spout.

Pump base to bottom of cylinder, 4 feet.

Fig. 1229 (page 61) "Universal" Bronze Valve and Seat to order at extra price.




FIG. 264

FIG. 854. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
3	2 $\frac{3}{4}$ x 10 in.	6 in.	.15 gal.	1 $\frac{1}{4}$ in. pipe	1 $\frac{1}{4}$ in. pipe and $\frac{3}{4}$ in. hose	60 ft.	Watchin	\$14.75	Knucab	\$17.25
4	3 x 10 "	6 "	.18 "	1 $\frac{1}{4}$ " pipe	1 $\frac{1}{4}$ " " " $\frac{3}{4}$ "	60 "	Watchma	15.00	Knucud	17.50
6	3 $\frac{1}{2}$ x 10 "	6 "	.25 "	1 $\frac{1}{2}$ " "	1 $\frac{1}{4}$ " " " $\frac{3}{4}$ "	45 "	Raptwed	16.00	Knudad	19.00

FIG. 264. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharges.	*Lift and Force.	IRON CYLINDER.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
2	2 $\frac{1}{2}$ x 10 in.	6 in.	.13 gal.	1 $\frac{1}{4}$ in. pipe	1 $\frac{1}{4}$ in. pipe and 1 in. hose	70 ft.	Clanish	\$16.00	Knudec	\$18.50
4	3 x 10 "	6 "	.18 "	1 $\frac{1}{4}$ " pipe	1 $\frac{1}{4}$ " " " 1 "	70 "	Clapped	18.00	Knufac	20.50

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS "UTILITY" ANTI-FREEZING FORCE PUMP. 23

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

Fig. 1111 is a combined Lift and Force Pump. It has brass cylinder, and is adapted to deep or shallow wells. Reversible lever. Bearer top allows no side wear. Tight top and large air chamber, provided with pet cock, making it a lift or a force Pump at will. Base and brace adjustable. Discharge fitted for  $\frac{3}{4}$ -inch hose. No. 2 Pump will go inside 3-inch well casing and No. 4 inside  $3\frac{1}{2}$ -inch casing. Strainer supplied with each Pump.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.

FIG. 1111. SIZES, PRICES, ETC.

No.	Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift and Force.	Cipher.	Brass Body Cylinder.
2	$2\frac{1}{2} \times 16$ in.	$9\frac{1}{2}$ in.	.21 gal.	$1\frac{1}{4}$ in. pipe	100 ft.	Figbab	\$17.00
4	$3 \times 16$ "	$9\frac{1}{2}$ "	.30 "	$1\frac{1}{4}$ "	60 "	Figbace	18.00

\*Depth of Wells to which Pumps may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

## "AURA" ANTI-FREEZING FORCE PUMP.

ADAPTED FOR "UNIVERSAL" BRONZE VALVE AND SEAT.

Fig. 1113 is a Double-Acting Pneumatic Force Pump, with brass cylinder and adjustable base and brace. Adapted to either shallow or deep wells.

Deep-well arrangement is accomplished by lowering cylinder with pipe connected and lengthening plunger rod. Pump has large air chamber capacity, producing a strong, steady stream. Price includes both upper and lower cylinders. No. 2 Pump will go inside 4-inch well casing, and No. 4 inside  $4\frac{1}{2}$ -inch casing. Discharge fitted for  $\frac{3}{4}$ -inch hose. Malleable strainer sent with each Pump.

Fig. 1229 (page 61), "Universal" Bronze Valve and Seat to order at extra price.

FIG. 1113. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke.	Suction.	*Lift and Force.	Cipher.	Brass Body Cylinder.
2	$2\frac{1}{2} \times 10$ in.	6 in.	.13 gal.	$1\frac{1}{4}$ in. pipe	150 ft.	Figbil	\$15.50
4	$3 \times 10$ "	6 "	.18 "	$1\frac{1}{4}$ "	75 "	Figbima	16.00

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 1111



FIG. 1113



# GOULDS DOUBLE-ACTING WELL FORCE PUMPS.

FOR SHALLOW OR DEEP WELLS.



FIG. 1025



FIG. 1146

This line is fully illustrated and described on pages 25 to 29.

FOR SHALLOW OR DEEP WELLS.




FIG. 1274

Fig. 1274, "Seneca" Double-Acting Force Pump, is adapted for shallow or deep wells. Wrought-iron pipe is used to form both set length and standard. Base is adjustable; spout revolving. Pumps work easily and deliver smooth, unbroken stream. The smooth discharge is effected by using 2-inch brass differential or force cylinder, which has one-half the displacement of the 3-inch brass suction cylinder furnished.

Brass differential cylinder can be replaced by a stuffing box or a plunger tube (as used in Figs. 1277 and 1278, page 51), when standard is wanted for use with tubular well cylinder or other sizes of cylinder.

Fig. 1275 is same as Fig. 1274, with wind mill top, arranged for 10-inch stroke mill and 5-inch stroke by hand.




FIG. 1275

FIG. 1274. SIZE, PRICE, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke, 10 in.	Suction.	Discharge.	BRASS BODY CYLINDER.	
						Cipher.	Price.
4	3 x 10½ in.	5 in.	.15 gal.	1¼ in. pipe	¾ in. hose	Maltvo	\$14.50

FIG. 1275. SIZE, PRICE, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke, 10 in.	Suction.	Discharge.	BRASS BODY CYLINDER.	
						Cipher.	Price.
4	3 x 16 in.	{ 5 in. hand, 10 " mill, }	.31 gal.	1¼ in. pipe	¾ in. hose	Maltwe	\$16.00



26 GOULDS "EMPIRE" DOUBLE-ACTING WELL FORCE PUMPS.

WITH "UNIVERSAL" BRONZE VALVE AND SEAT.

Fig. 1025 illustrates our "Empire " Double-Acting Well Force Pump, with Common Top, as adapted for shallow or deep wells. Pump consists of a standard, with bearer top in one piece, cast in two half sections, strongly bolted and holding securely in place the two supporting pipes which form respectively the air chamber and discharge pipes, connecting with upper cylinder. This upper cylinder is brass-lined and has differential plunger, contributing to an even and uniform discharge of water. We dispense with all stuffing boxes or glands, avoid all undue friction, and secure the easiest possible working Pump. Pump is furnished complete, with brass-lined or brass-body lower cylinder, with "Universal " Bronze Valve and Seat, and universal bushing for either shallow or deep wells. *No. 2 Pump will go inside 4-inch well casing; No. 4 Pump inside 5-inch well casing.*




FIG. 1025

Fig. 1026 is similar to Fig. 1025, but has wind mill top. Unless otherwise ordered, we ship all "Empire " Pumps put up for shallow Wells. *Where wanted for deep wells, unscrew lower cylinder from upper cylinder and attach universal bushing to bottom of upper cylinder and top cap to lower cylinder, and connect with pipe and rod required for any depth of well.* Universal bushing, adapting Pumps for shallow or deep wells, strainer and hose connection go with each Pump and are included in prices given below.



FIG. 1026

FIG. 1025. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	BRASS-LINED CYL.		BRASS BODY CYL.	
								Cipher.	Price.	Cipher.	Price.
2	2½ x 10½ in.	6 in.	.13 gals.	1¼ in. pipe	¾ in. hose	¾ in.	100 ft.	Chestoc	\$14.00	Chestpo	\$15.00
4	3 x 10½ "	6"	.18 "	1½ "	¾ "	¾ "	75 "	Chestabu	14.50	Chestil	15.50

FIG. 1026. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	BRASS-LINED CYL.		BRASS BODY CYL.	
								Cipher.	Price.	Cipher.	Price.
2	2½ x 10½ in.	6 in.	.13 gals.	1¼ in. pipe	¾ in. hose	¾ in.	100 ft.	Chetja	\$15.00	Chetjob	\$16.00
4	3 x 10½ "	6 "	.18 "	1½ "	¾ "	¾ "	75 "	Chetkab	15.50	Chetiub	16.50

\*Depth of Wells to which Pumps may be adapted by lowering Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.



# GOULDS "EMPIRE" DOUBLE-ACTING WELL FORCE PUMPS. 27

WITH "UNIVERSAL" BRONZE VALVE AND SEAT.




FIG. 1027

Fig. 1027 represents our "Empire" Double-Acting Well Force Pump, with Common Top, Brass Three-way Cock and Connecting Rod, for shallow or deep wells. Details of construction and adaptations will be found on page 24. The addition of Three-Way Cock and Connecting Rod for distributing water to any part of premises, house, barns, etc., will increase the usefulness of this Pump for many purposes.

Fig. 1028 is similar to Fig. 1027, but has Wind Mill Top.

Unless otherwise ordered, we ship all "Empire" Pumps put up for shallow wells; that is, with lower working cylinder screwed into upper cylinder and the universal bushing for bottom of upper cylinder and top attachment for lower cylinder tied on. *Where wanted for deep wells, unscrew lower cylinder from upper cylinder and attach universal bushing to bottom of upper cylinder and top cap to lower cylinder, and connect with pipe and rod required for any depth of well.* Universal bushing, adapting Pumps for shallow or deep wells, strainer and hose connection go with each Pump and are included in prices given below.




FIG. 1028

FIG. 1027. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lower Discharge.	Upper Discharge.	*Lift and Force.	BRASS-LINED CYLINDER.		BRASS BODY CYLINDER.	
								Cipher.	Price.	Cipher.	Price.
2	2½ x 10½ in.	6 in.	.13 gal.	1¼ in. pipe	1 in. pipe	¾ in. hose	100 ft.	Chetman	\$16.50	Chetnel	\$17.50
4	3 x 10½ in.	6 "	.18 "	1¼ "	1 "	¾ "	75 "	Chetnob	17.00	Chetolu	18.00

FIG. 1028. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lower Discharge.	Upper Discharge.	*Lift and Force.	BRASS-LINED CYLINDER.		BRASS BODY CYLINDER.	
								Cipher.	Price.	Cipher.	Price.
2	2½ x 10½ in.	6 in.	.13 gal.	1¼ in. pipe	1 in. pipe	¾ in. hose	100 ft.	Chetpat	\$17.50	Chetqub	\$18.50
4	3 x 10½ in.	6 "	.18 "	1¼ "	1 "	¾ "	75 "	Chetral	18.00	Cheuact	19.00

\* Depth of Wells to which Pumps may be adapted by lowering Cylinders to within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# 28 GOULDS "ADVANCE" DOUBLE-ACTING FORCE PUMPS.

WITH 'UNIVERSAL' BRONZE VALVE AND SEAT.




FIG. 1146

Fig. 1146, "Advance" Double-Acting Well Force Pump, has common top for hand power, adapted for shallow or deep wells—open, driven, drilled or cased. It is constructed with seamless brass differential cylinder and brass-lined or brass body lower cylinder, having inside attachments and "Universal" Bronze Valve and Seat.

Fig. 1147 is of same construction as Fig. 1146, with change of top for 10-inch stroke wind mill or 6-inch stroke by hand.

*No. 2 Pumps, with brass body cylinder, will go inside of 3-inch well casing, and with brass-lined cylinder inside 3¼-inch casing.*

*No. 4 Pumps, with brass body cylinder, will go inside of 3½-inch well casing, and with brass-lined cylinder inside 3¾-inch casing.*

Unless otherwise ordered, we ship all "Advance" Pumps put up for shallow wells; that is, with lower working cylinder screwed into upper cylinder and the top attachment for lower cylinder tied on. *Where wanted for deep wells, unscrew lower cylinder from upper cylinder and attach top cap to lower cylinder, and connect with pipe and rod for any depth of well.* Top cap, hose connection and strainer go with each Pump, and are included in price given below.




FIG. 1147

FIG. 1146. SIZES, PRICES, ETC.

No.	Lower Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	BRASS-LINED CYLINDER.		BRASS BODY CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
2	2½ x 10½ in.	5 in.	.11 gal.	1¼ in. pipe	¾ in. hose	Fiendub	\$14.50	Hareta	\$15.50
4	3 x 10½ "	5 "	.15 "	1¼ "	¾ "	Fiepal	15.00	Hareula	16.00
6	3½ x 10½ "	5 "	.21 "	1½ "	1 "	Knuffig	18.00	Knufut	19.50
8	4 x 10½ "	5 "	.27 "	2 "	1 "	Knufol	20.00	Lamebs	22.00

FIG. 1147. SIZES, PRICES, ETC.

No.	Lower Cyl.	Stroke.	Capacity per Stroke, 10 inch.	Suction.	Discharge.	BRASS-LINED CYLINDER.		BRASS BODY CYLINDER.	
						Cipher.	Price.	Cipher.	Price.
2	2½ x 16 in.	{ 6 in. hand and 10 in. mill }	.21 gal.	1¼ in. pipe	¾ in. hose	Mostub	\$16.00	Mostve	\$17.00
4	3 x 16 "		.31 "	1¼ "	¾ "	Mostwo	16.50	Mostxu	17.50
6	3½ x 16 "		.42 "	1½ "	1 "	Lameck	20.00	Lamefa	21.50
8	4 x 16 "		.54 "	2 "	1 "	Lamedu	22.00	Lamegu	24.00

# GOULDS DOUBLE-ACTING WELL FORCE PUMPS.

29

WITH "UNIVERSAL" BRONZE VALVE AND SEAT.




FIG. 1148

Fig. 1148 represents our "Advance" Double-Acting Force Pump, with Wind Mill Top and Three-Way Distributing Valve, by which water may be distributed about the premises. When operated by hand, Pump has 6-inch stroke, and when wind mill is used the stroke is 10-inch. Lower cylinder is either brass or brass-lined, with "Universal" Bronze Valve and Seat.

Unless otherwise ordered, we ship all "Advance" Pumps put up for shallow wells; that is, with lower working cylinder screwed into upper cylinder and the top attachment for lower cylinder tied on. *Where wanted for deep wells, unscrew lower cylinder from upper cylinder and attach top cap to lower cylinder, and connect with pipe and rod for any depth of well.* Top cap, hose connection and strainer go with each Pump, and are included in price given below.

Fig. 1276, "Seneca" Double-Acting Pump, has Wind Mill Top and Three-Way Distributing Valve. Pump has 10-inch stroke by mill and 5-inch stroke by hand. Spout is revolving. Base adjustable. We ship Pump with lower cylinder detached.

An even flow of water is obtained by using differential cylinder of one-half the area of lower cylinder. Other sizes of lower cylinder can be used by replacing the differential cylinder with an attachment having either stuffing box or plunger tube. A 2-inch Tubular Well Cylinder can be drawn through the working-head. Strainer and hose connection included with each Pump.




FIG. 1276

FIG. 1148. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke, 10 inch.	Suction.	Lower Discharge.	Upper Discharge.	BRASS-LINED CYLINDER.		BRASS BODY CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
2	2½ x 16 in.	{ 6 in. hand, { 10 in. mill, }	.21 gal.	1¼ in. pipe	1 in. pipe	¾ in. hose	Motab	\$19.50	Motem	\$20.50
4	3 x 16 "		.31 "	1¼ "	1 "	¾ "	Motenu	20.00	Moteux	21.00

FIG. 1276. SIZES, PRICES, ETC.

No.	Lower Cylinder.	Stroke.	Capacity per Stroke, 10 inch.	Suction.	Discharge.	BRASS BODY CYLINDER.	
						Cipher.	Price.
4	3 x 16 in.	{ 6 in. hand, { 10 in. mill, }	.31 gals.	1¼ in. pipe	¾ in. hose	Lameho	\$20.00



## Deep Well Pump Standards and Cylinders

have an almost universal application where water supply is derived from open, driven or drilled and cased deep wells.


The open, or dug and curbed well is, perhaps, the most common and usually made where water channels are not more than 50 feet below surface of ground.

Drilled and cased wells are generally made where rock is encountered and the water is considerable distance below ground. The general plan is to line the well with casing down to the rock. In this manner a practically closed well is secured, free from drainage or pollution from any source



We show Fig. 237, Force Pump Standard (page 38), operating Fig. 1230, Deep Well Cylinder (page 62). Also Fig. 547, Manual Pumping Apparatus (page 100), operating Fig. 1231, Deep Well Pump Cylinder (page 62).

This class of Pump Standards will be found on pages 31 to 39 and pages 99 to 101, and Pump Cylinders, pages 62 to 65.



# GOULDS "STAR" WELL LIFT PUMP STANDARDS.

31

WITH REVOLVING OPEN TOP AND SOLID BASE.



FIG. 1023

Light.




FIG. 846, No. 3

Medium.




FIG. 846, No. 4

Heavy.




FIG. 846, No. 5

Extra Heavy.

Fig. 1023 represents our Light Well Lift Pump Standard, adapted for shallow wells—dug, drilled or driven. It has revolving bearer top, with recess for priming, if necessary.

Fig. 846 represents our "Star" Well Pump Standard, fitted with revolving bowl top and solid base. This style is a great favorite with well drillers. We offer in three sizes and weights.

## SIZES AND PRICES.

	No.	Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
Fig. 1023	3	6 in.	1 $\frac{1}{4}$ in. pipe	$\frac{3}{8}$ in.	$\left. \begin{array}{l} 2\frac{1}{2} \text{ in. cylinder, } 40 \text{ ft.} \\ 3 \text{ " " " " } 30 \text{ " } \end{array} \right\}$	Dosedab	\$4.50
Fig. 846	3	6 in.	1 $\frac{1}{4}$ in. pipe	$\frac{3}{8}$ in.	2 $\frac{3}{4}$ in. cylinder, 40 ft.	Wallow	\$5.00
Fig. 846	4	6 "	1 $\frac{1}{4}$ " "	$\frac{3}{8}$ "	3 " " " " 40 "	Wallpie	5.50
Fig. 846	5	6 "	1 $\frac{1}{4}$ " "	$\frac{3}{8}$ "	3 $\frac{1}{2}$ " " " 40 "	Wallroc	6.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.

# 32 GOULDS "STAR" WELL LIFT PUMP STANDARDS.

WITH REVOLVING TIGHT TOP AND SOLID BASE.




FIG. 1024

Light.




FIG. 850, No. 3

Medium.




FIG. 850, No. 4

Heavy.




FIG. 850, No. 5

Extra Heavy.

Figs. 1024 and 850 represent our Well Pump Standards fitted with revolving tight top, polished rod and links above, and solid base. These Pumps are especially desirable for public places, for the tight top precludes the possibility of stones or sticks being thrown into Pump

Always tapped near the spout for sizes of wrought-iron pipe given below, although we can fit for 1½ or 2-inch, if so ordered.

FIG. 1024. SIZE, PRICE, ETC.

No.	Stroke.	Suction,	Well Rod.	*Lift.	Cipher.	Price.
3	6 in.	1¼ in. pipe	¾ in.	{ 2½ in. Cylinder, 40 ft. { 3 " 30 "	Dosedac	\$5.25

FIG. 850. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
3	6 in.	1¼ in. pipe	¾ in.	2½ in. Cylinder, 40 ft.	Walrut	\$5.75
4	6 "	1½ " "	¾ "	3 " 40 "	Walrvu	6.25
5	6 "	1¾ " "	¾ "	3½ " 40 "	Walt	6.75

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and cost extra.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells,



# GOULDS WELL LIFT PUMP STANDARD.

33

WITH SOLID BEARER AND BASE.

Fig. 486 represents our Well Lift Pump Standard for deep or shallow wells. The very strong bearer top and long and heavy lever adapt this Standard for wells of more than ordinary depth, and it is sometimes used over very deep wells. The Standard is tapped for wrought-iron pipe near the spout. We can fit for 1½ or 2-inch pipe, if so ordered, but always fit for 1¼ inch unless otherwise directed.

FIG. 486. SIZE, PRICE, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
8 in.	1¼ in. pipe.	7-16 in.	$\left\{ \begin{array}{l} 2\frac{1}{2} \text{ in. Cylinder, 75 ft.} \\ 3 \text{ " " 50 " } \\ 4 \text{ " " 30 " } \end{array} \right\}$	Harm	\$6.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and cost extra.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.




FIG. 486

## WELL LIFT PUMP STANDARD AND CYLINDER.

FOR DEEP OR SHALLOW WELLS.

We have dropped Fig. 559, under which we formerly listed a combination of Pump Standard and Cylinder, and show herewith

Fig. 845, "Star" Lift Pump Standard, with removable bolt base; convenient for making pipe and rod connections. Connecting pipe screws into base.

Cylinder shown on pages 62 to 66 can be used with this standard.

Fig. 559½ is iron Cylinder surmounted with air chamber, which arrangement relieves the jerk and strain and affords uniform discharge. We offer only two sizes and advise their use with the size standards opposite them in the table below. Other sizes will be found under same Fig., page 66.

FIGS. 845 AND 559½. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Well Rod.	Lift.	FIG. 845, PUMP STANDARD.		FIG. 559½. IRON CYLINDER.			
					Cipher.	Price.	Size.	Cipher.	Price.	
1	6 in.	1 in. pipe	3⁄8 in.	2½ in. Cyl., 40 ft.	Walker	\$4.25				
2	6 "	1¼ "	3⁄8 "	2½ " " 40 "	Walkin	4.75				
3	6 "	1½ "	3⁄8 "	2¾ " " 40 "	Wally	5.00				
4	6 "	1¾ "	3⁄8 "	3 " " 30 "	Waller	5.50	3 x 12 in.	Lawn	\$9.00	
5	6 "	1¾ "	3⁄8 "	3¼ " " 30 "	Wallfo	5.75				
8	6 "	2 "	½ "	4 " " 45 "	Raptwif	8.00	4 x 12 "	Laxd	11.50	




FIG. 845



FIG. 559½

# GOULDS DEEP WELL LIFT PUMP STANDARD.

WITH TIGHT TOP GUIDE.




FIG. 236

Fig. 236 represents our Heavy Deep Well Lift Pump Standard, with tight top, for wells up to 100 feet deep. The Standard is bolted together near the spout with an intermediate flange, which will be found a great convenience in making pipe and rod connections. Fig. 236 has been a great favorite with the Trade for years. It is built for every-day indiscriminate use. Any size pipe from  $1\frac{1}{4}$ -inch to 2-inch can be used with this Standard, but always fitted for  $1\frac{1}{4}$ -inch unless otherwise ordered.

FIG. 236 SIZE, PRICE, ETC.

Stroke.	Suction.	Well Rod,	*Lift.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	7-16 in.	$\left\{ \begin{array}{l} 2\frac{1}{2} \text{ in. cyl., } 100 \text{ ft.} \\ 3 \quad \quad \quad 60 \quad \quad \end{array} \right\}$	Cane	\$10.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.

# GOULDS DEEP WELL LIFT PUMP STANDARD.

WITH TIGHT TOP GUIDE.




FIG. 592.

The cut accurately represents our Heavy Deep Well Lift Pump Standard. The manner of construction in two sections, with flange between, is plainly visible, and will be esteemed a very great convenience by those who have to set up these Pumps. It is very strong and heavy, has balanced handle, and will answer to use on wells from 100 to 200 feet deep.

Any size from  $1\frac{1}{4}$ -inch to  $2\frac{1}{2}$ -inch pipe can be used with this Standard, but always fitted as below unless ordered otherwise.

FIG. 592. SIZE, PRICE, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
6 in.	$1\frac{1}{2}$ in. pipe	7-16 in.	$\left\{ \begin{array}{l} 2\frac{1}{2} \text{ in. cyl., } 150 \text{ ft.} \\ 3 \quad \quad \quad 100 \quad \quad \end{array} \right\}$	Milled	\$16.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.

# GOULDS "STAR" WELL FORCE PUMP STANDARDS.

35

WITH REVOLVING TOP AND SOLID BASE.




FIG. 853, No. 0

Light.




FIG. 853, No. 1

Medium.




FIG. 853, No. 2

Heavy.

Fig. 853 represents our admirable "Star" Well Force Pump Standard arranged with tight top, polished rod and links above. In this Standard the air chamber is made by enlarging stock at the top.

All these Standards are tapped for pipe near the spout. Each one has an outlet back of the spout for attaching pipe, and the spout is provided with hose tube and nut to screw on, and not with a clap-trap of a clamp.

Always tapped as below, unless otherwise ordered.

FIG. 853. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	Cipher.	Price.
0	6 in.	1 1/4 in. pipe	1 1/4 in. pipe and 3/4 in. hose	7-16 in.	(2 1/2 in. cyl., 60 ft.)	Broadgauge	\$8.50
1	6 "	1 1/4 " "	1 1/4 " " 3/4 "	7-16 "	2 3/4 " 50 "	Washa	9.00
2	6 "	1 1/4 " "	1 1/4 " " 3/4 "	7-16 "	3 " 40 "	Washabl	10.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.



## GOULDS "STAR" WELL FORCE PUMP STANDARDS.

WITH REVOLVING TOP AND COCK SPOUT.




FIG. 883, No. 0

Light.




FIG. 883, No. 1

Medium.




FIG. 883, No. 2

Heavy.

This is the same Force Pump Standard in all respects as our Fig. 853, more fully described on preceding page, except that it has a cock spout. When pipe is connected to the opening behind the spout, there must be some means for closing the spout opening, and a cock does this. Thus one Pump may be made to supply water at the house, or any part of the premises as well.

The Standards are always tapped for pipe near the spout, as below, unless otherwise ordered.

FIG. 883. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	Cipher.	Price.
0	6 in.	1 <sup>1</sup> / <sub>4</sub> in. pipe	1 <sup>1</sup> / <sub>4</sub> in. pipe and <sup>3</sup> / <sub>4</sub> in. hose	7-16 in.	( 2 <sup>1</sup> / <sub>2</sub> in. cyl., 60 ft. )	Lamfag	\$11.00
1	6 "	1 <sup>1</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>4</sub> " " <sup>3</sup> / <sub>4</sub> "	7-16 "	( 2 <sup>3</sup> / <sub>4</sub> " " 50 " )	Washbal	11.50
2	6 "	1 <sup>1</sup> / <sub>4</sub> "	1 <sup>1</sup> / <sub>4</sub> " " <sup>3</sup> / <sub>4</sub> "	7-16 "	( 3 " " 40 " )	Washbow	12.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard, and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# “NORTHERN STAR” WELL FORCE PUMP STANDARD.

37

WITH REVOLVING TOP AND SOLID BASE.

Fig. 855 represents our “Northern Star” Force Pump Standard, with air chamber on spout, tight top and polished rod and links above. It is simple in construction, strong and compact, and offers good value for a Pump of this class at the low price at which we are able to sell it.

It is tapped near the spout for sizes of wrought-iron pipe given in our table below, although it could be changed, if desired. Cock spouts furnished at \$2 50 extra list.

FIG. 855. SIZE, PRICE, ETC

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	1 1/4 in. pipe	1 1/4 in. pipe and 3/4 in. hose	7-16 in.	2 1/2 in. cyl., 60 ft. 3        “        45    “	Wash	\$11.00




FIG. 855

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.

# GOULDS “STAR” WELL FORCE PUMP STANDARD.

WITH REVOLVING TOP. SOLID BASE.

Fig. 858 is similar in appearance and construction to Fig. 855, given above, except the standard is built in two sections, with intermediate flange between, into which the suction pipe is screwed. This flange is interchangeable and can be screwed for any size of pipe up to and including 2 1/2-inch, but always shipped as below unless otherwise ordered. Cock spout furnished at \$2.50 extra list.

FIG. 858. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	1 1/4 in. pipe	1 1/4 in. pipe and 3/4 in. hose	7-16 in.	2 1/2 in. cyl., 100 ft. 3        “        60    “	Washoff	\$12.50




FIG. 858

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.

# GOULDS DEEP-WELL FORCE PUMP STANDARD.

WITH AIR CHAMBER ON SPOUT.

Fig. 237 represents our Deep-Well Force Pump Standard, with sectional construction, etc., and the addition of an air chamber on the spout. There is a half-hose coupling and tube for attaching hose on the spout.

Always fitted for  $1\frac{1}{4}$ -inch pipe, unless ordered to the contrary, but we can fit them for  $1\frac{1}{2}$  or 2-inch pipe when desired.




FIG. 237

FIG. 237. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	$1\frac{1}{4}$ in. pipe and 1 in. hose	7-16 in.	$\left\{ \begin{array}{l} 2 \text{ in. cyl., 150 ft.} \\ 2\frac{1}{2} \text{ " } 100 \text{ " } \\ 3 \text{ " } 60 \text{ " } \end{array} \right\}$	Cannon	\$13.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of the water, or total lift and force from supply to point of delivery.

# GOULDS DEEP-WELL FORCE PUMP STANDARD.

WITH AIR CHAMBER AND COCK SPOUT.

Fig. 887 represents our Fig. 237, Deep-Well Force Pump Standard, described above, arranged with cock spout on air chamber; closing this cock allows discharge to pass through top of air chamber. A hose coupling is screwed on end of cock for attaching hose.

Always fitted for  $1\frac{1}{4}$ -inch pipe, unless ordered to the contrary, but we can fit them for  $1\frac{1}{2}$  or 2-inch pipe when so desired.




FIG. 887

FIG. 887. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	$1\frac{1}{4}$ in. pipe and 1 in. hose	7-16 in.	$\left\{ \begin{array}{l} 2 \text{ in. cyl., 150 ft.} \\ 2\frac{1}{2} \text{ " } 100 \text{ " } \\ 3 \text{ " } 60 \text{ " } \end{array} \right\}$	Cape	\$15.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.



# GOULDS DEEP-WELL FORCE PUMP STANDARD.

39

WITH AIR CHAMBER ON SPOUT.

The cut represents our Heavy Deep-Well Force Pump Standard. It has sectional standard, tight top with polished rod and links above, heavy balanced lever and two supporting braces, adapting it for hard duty. Always fitted for 1½-inch pipe unless otherwise ordered, but we can fit them for pipe up to 2½-inches. Table gives complete data.

FIG. 593. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
1	6 in.	1½ in. pipe	1½ in. pipe and 1 in. hose	7-16 in.	{ 2 in. Cyl., 225 ft.	Milt	\$20.00
2	Same as No. 1 with cock	spout.		7-16 "	{ 2½ " 150 "	Milton	22.50
					{ 3 " 100 "		

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\* Depth of Wells of which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 593

# GOULDS DEEP-WELL FORCE PUMP STANDARD.

WITH BRAKE TOP AND WOOD LEVERS.

The cut represents our Heavy Deep-Well Force Pump Standard, arranged with brake top, so that either one or two men can operate Pump. Intermediate flange below spout is of considerable convenience in making pipe connections. Standard has two supporting braces. Always fitted for 1½-inch pipe unless otherwise ordered, but we can fit them for pipe up to 2½ inches.

FIG. 763. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
1	6 in.	1½ in. pipe	1½ in. pipe and 1 in. hose	7-16 in.	{ 2 in. Cyl., 225 ft.	Waterag	\$21.00
2	Same as above with cock	spout.		7-16 "	{ 2½ " 150 "	Waterbu	23.50
					{ 3 " 100 "		

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\* Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 763

## Wind Mill Pumps.

Probably no greater labor-saving and useful device has ever been invented than the Wind Mill, and perhaps their greatest usefulness is for pumping water.

Our illustration shows, to the right, Fig. 762, Lift Pump Standard, operating Fig. 1231, Pump Cylinder, in drilled and cased well. Pump Standard will be found on page 42; Cylinder, pages 62 and 63.

To the left we show Fig. 423, Force Pump Standard (page 47), operating



Fig. 1230, Pump Cylinder, in open well and discharging through back outlet to elevated tank. The application of these and our many other styles of Wind Mill Pumps are almost limitless. This class of Pumps will be found on pages 42 to 49.





# PUMPING CAPACITY OF WIND MILLS.

41

## SIZE OF CYLINDER TO USE.

Below we give table designed to aid in the selection of suitable size Wind Mill and Cylinder or Pump to perform a required amount of pumping. Selection should be determined by the quantity of water desired per hour, the height or pressure against which it must be pumped, and the velocity of the wind.

Figures in table below are based upon 10-mile wind, which is not far from the mean average velocity for the United States. The power of the wind is as the square of its velocity. To figure on a 12-mile wind, increase one-third the number of gallons given in table below, and select Cylinder having one-third greater *area* than given in table. (Areas of Cylinders of different diameters are given on page 318.)

To figure on 15-mile wind, double the number of gallons and *area* of Cylinder.

ELEVATION.	8-FT. DIRECT STROKE MILL OR 6-FT. MILL GEARED BACK $4\frac{1}{4}$ TO 1.			10-FT. DIRECT STROKE MILL OR 8-FT. MILL GEARED BACK $2\frac{3}{4}$ TO 1.		
	Total from Water Level to Point of Delivery.	Approximate No. Gals. per Hour Mill will Pump.	Size Single-Acting Pump or Cylinder to Use. With 4-in. Stroke.      With 7-in. Stroke.	Approximate No. Gals. per Hour Mill will Pump.	Size Single-Acting Pump or Cylinder to Use. With 5-in. Stroke.      With 8-in. Stroke.	
10 ft.	560	4 or $4\frac{1}{4}$ in. cyl.	$2\frac{3}{4}$ or 3 in. cyl.	1,100	$5\frac{3}{4}$ or 6 in. cyl.	$4\frac{1}{2}$ or $4\frac{3}{4}$ in. cyl.
20 "	300	$2\frac{3}{4}$ " 3 "	$2\frac{1}{4}$ " $2\frac{1}{2}$ "	710	$4\frac{1}{4}$ " $4\frac{1}{2}$ "	$3\frac{1}{2}$ " $3\frac{3}{4}$ "
30 "	210	$2\frac{1}{2}$ " $2\frac{3}{4}$ "	2 " "	475	$3\frac{3}{4}$ " 4 "	$2\frac{3}{4}$ " 3 "
40 "	175	$2\frac{1}{2}$ " "	$1\frac{3}{4}$ " "	380	$3\frac{1}{4}$ " $3\frac{1}{2}$ "	$2\frac{1}{2}$ " $2\frac{3}{4}$ "
50 "	140	$2\frac{1}{2}$ " "	$1\frac{1}{2}$ " $1\frac{3}{4}$ "	300	$2\frac{3}{4}$ " 3 "	$2\frac{1}{4}$ " $2\frac{1}{2}$ "
75 "	85	$1\frac{3}{4}$ " "		275	$2\frac{3}{4}$ " "	2 " $2\frac{1}{4}$ "
100 "	70	$1\frac{1}{2}$ " "		190	$2\frac{1}{2}$ " $2\frac{3}{4}$ "	2 " "
125 "				150	$2\frac{1}{4}$ " "	$1\frac{3}{4}$ " "
150 "				125	2 " "	$1\frac{1}{2}$ " "
175 "				100	$1\frac{3}{4}$ " "	$1\frac{1}{8}$ " "
200 "				75	$1\frac{1}{2}$ " "	

ELEVATION.	12-FT. DIRECT STROKE MILL OR 10-FT. MILL GEARED BACK $2\frac{1}{4}$ TO 1.			18-FT. DIRECT STROKE MILL (13-FT. MILL GEARED BACK $2\frac{1}{2}$ TO 1 HAS ABOUT $\frac{2}{3}$ AS MUCH PUMPING CAPACITY.)		
	Total from Water Level to Point of Delivery.	Approximate No. Gals. per Hour Mill will Pump.	Size Single-Acting Pump or Cylinder to Use. With 8-in. Stroke.      With 10-in. Stroke.	Approximate No. Gals. per Hour Mill will Pump.	Size Single-Acting Pump or Cylinder to Use. With 10-in. Stroke.      With 12-in. Stroke.	
10 ft.			5 or $5\frac{1}{4}$ in. cyl.	7,200	10 in. cyl.	$9\frac{1}{2}$ or 10 in. cyl.
20 "	1,440	$4\frac{1}{4}$ " $4\frac{1}{2}$ "	$4\frac{1}{2}$ or $4\frac{3}{4}$ in. cyl.	3,600	$7\frac{3}{4}$ " "	7 " "
30 "	960	$3\frac{1}{2}$ " $3\frac{3}{4}$ "	$3\frac{3}{4}$ " 4 "	2,400	$6\frac{1}{4}$ " "	$5\frac{3}{4}$ " "
40 "	720	$3\frac{1}{2}$ " $3\frac{1}{2}$ "	$3\frac{1}{4}$ " "	1,800	$5\frac{1}{4}$ or $5\frac{1}{2}$ in. cyl.	$4\frac{3}{4}$ " 5 "
50 "	575	$2\frac{3}{4}$ " $2\frac{1}{2}$ "	$2\frac{3}{4}$ " 3 "	1,500	$4\frac{3}{4}$ " 5 "	$4\frac{1}{2}$ " "
75 "	385	$2\frac{3}{4}$ " "	$2\frac{1}{4}$ " $2\frac{1}{2}$ "	960	$3\frac{3}{4}$ " 4 "	$3\frac{1}{2}$ " $3\frac{3}{4}$ "
100 "	290	$2\frac{1}{4}$ " $2\frac{1}{2}$ "	2 " $2\frac{1}{4}$ "	720	$3\frac{3}{4}$ " "	$3\frac{1}{4}$ " "
125 "	230	2 " "	$1\frac{3}{4}$ " "	575	3 " $3\frac{1}{4}$ "	$2\frac{3}{4}$ " "
150 "	190	2 " "	$1\frac{3}{4}$ " "	480	$2\frac{3}{4}$ " "	$2\frac{1}{2}$ " "
175 "	160	$1\frac{3}{4}$ " "	$1\frac{1}{2}$ " "	400	$2\frac{1}{2}$ " "	$2\frac{1}{4}$ " "
200 "	140	$1\frac{1}{2}$ " "		360	$2\frac{1}{4}$ " $2\frac{1}{2}$ "	2 " $2\frac{1}{4}$ "
250 "				300	$2\frac{1}{4}$ " "	2 " "



# 42 GOULDS "STAR" WELL LIFT PUMP STANDARDS.

WITH REVOLVING TOP. FOR WINDMILL AND HAND.




FIG. 1032, No. 3  
Light.




FIG. 762, No. 3  
Medium.




FIG. 762, No. 4  
Heavy.




FIG. 762, No. 5  
Extra Heavy.

Our new line of Well Pump Standards with Wind Mill Tops, as shown above, contain all the advantages suggested by the most recent practice, and will be found to be the best of the kind made by any manufacturer. They are tapped for pipe near the spout, have supporting brace, and are a most suitable Standard every way. We can fit the 6-inch or 10-inch stroke Pumps for  $1\frac{1}{4}$ ,  $1\frac{1}{2}$  or 2-inch pipe (No. 5 Standard can be tapped  $2\frac{1}{2}$  inch), but always fit as below, unless otherwise directed. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod. We do not send wind mill slides, except when specially ordered.

FIG. 1032. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	7-16 in.	$2\frac{1}{2}$ in. cyl., 40 ft.	Dreaded	\$6.50
10 "	2 " pipe	7-16 in. and 1 in.	3 " 30 "	Dreadic	7.50

FIG. 762. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	No. 3.		No. 4.		No. 5.	
				Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	7-16 in.	$2\frac{1}{2}$ in. cyl., 100 ft.	Vauntfr	\$7.00	Vauntful	\$7.50	Vauntin	\$8.00
10 "	2 " pipe	7-16 and 1 in.	3 " 60 "	Raweck	8.00	Veader	8.50	Veal	9.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standards may be adapted by placing Cylinders within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.

# GOULDS WELL LIFT PUMP STANDARD.

43

WITH SWELL TOP AND SOLID BASE.

Fig. 1055 represents our Wind Mill Lift Pump Standard with swell top, adapted to drilled or tubular wells. The peculiar advantage of this formation of top is that it prevents the water from splashing out, as is sometimes the case when pumping very fast with other standards. Standard is provided with revolving bearer and has guided rod. Tapped near the spout for wrought-iron connecting pipe, which may be  $1\frac{1}{4}$ ,  $1\frac{1}{2}$  or 2-inch, but always  $1\frac{1}{4}$ -inch unless otherwise ordered. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod. Wind mill slides are not furnished unless specially ordered.

FIG. 1055. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
6 in. 10 "	$1\frac{1}{4}$ in. pipe 2 "	7-16 in. 7-16 "	$1\frac{1}{2}$ in. cyl., 100 ft. $\frac{1}{3}$ " " 60 "	Figast Figaub	\$7.50 8.50

Cylinders like Fig. 1230 and 1231, pages 62 and 63, are required with this Pump Standard, and cost extra.

\* Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.




FIG. 1055

# GOULDS WELL LIFT PUMP TOP AND BASE.

FOR TUBULAR WELLS

Fig. 1056 represents a Wind Mill Lift Pump Top and Base, adapted for tubular wells, or where cylinder is formed inside wrought-iron pipe. The stock is formed principally by the tubular well pipe, which is connected immediately under the spout. This pipe may be 2,  $2\frac{1}{2}$  or 3 inches in diameter, but we invariably fit standard for 2-inch pipe unless otherwise ordered. The base may be attached to pipe at any desired point, and thus the standard may be raised and lowered to suit convenience. Pumps have coupling for 1-inch wood rod.

FIG. 1056. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
6 in. 10 "	2 in. pipe 2 "	7-16 and 1 in. 7-16 " 1 "	$1\frac{1}{2}$ in. cyl., 150 ft. 2 " " 100 "	Figate Figava	\$6.50 7.50

For Tubular Well Cylinder for use with above, see Fig. 142, page 74.

\* Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water; smaller Cylinders in proportionately deeper wells.




FIG. 1056

# GOULDS "STAR" WELL LIFT PUMP STANDARD.

WITH REVOLVING TOP. FOR HAND OR WIND MILL.




FIG. 412

Fig. 412, Wind Mill Pump Standard, may be used over wells up to 150 feet deep. The Standard is in two sections, bolted together just below the spout. Between the two sections is interposed a flange into which the connecting pipe is screwed. These flanges are all of a size and drilled exactly alike, so that they will interchange and can be cut for either  $1\frac{1}{4}$ ,  $1\frac{1}{2}$ , 2 or  $2\frac{1}{2}$ -inch wrought-iron pipe. Always fitted as below unless otherwise directed. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod. We do not send wind mill slides unless specially ordered.

FIG. 412. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	7-16 in.	$2\frac{1}{2}$ in. cyl. 100 ft.	Lain	\$10.00
10 "	2 " "	7-16 and 1 in.	$\frac{2}{3}$ " " 60 "	Laird	11.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and cost extra.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water; smaller cylinders in proportionately deeper wells.

# GOULDS "STAR" WELL LIFT PUMP STANDARD.

ADJUSTABLE STROKE.



FIG. 780

Fig. 780 represents our Adjustable Stroke Pump Standard with Wind Mill top, and is particularly adapted to all kinds of drilled or tubular wells, and those in which working barrels are formed inside of 2-inch pipe.

This Pump can be changed 6, 8 or 10-inch stroke, to suit the length of cylinder and amount of water required.

The stock is tapped immediately below the spout for 2-inch pipe, unless otherwise ordered; and if a Standard is wanted for larger than 2-inch pipe we can arrange our Fig. 412, with variable top, at extra list price. Pumps have coupling for 1-inch wood rod.

Wind mill slides are not furnished unless specially ordered.

FIG. 780. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	*Lift.	No. 4.		No. 5.	
				Cipher.	Price.	Cipher.	Price.
6, 8 or 10 in.	2 in. pipe	7-16 and 1 in.	$\left\{ \begin{array}{l} 2\frac{1}{2} \text{ in. cyl. 100 ft.} \\ 3 \text{ " " 60 " } \end{array} \right\}$	Tomer	\$9.00	Tomeda	\$9.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and cost extra.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water.



# GOULDS DEEP WELL LIFT PUMP STANDARD.

45

FOR HAND AND WIND MILL.

Fig 764 represents one of our best known Extra-Heavy Deep-Well Pump Standards, being bolted together underneath the spout, with intermediate flange, and arranged with wind mill top. It is the strongest and best built Standard ever offered to the trade, and for wind mill use is admirably adapted for heavy and constant work. They are successfully used on wells from 100 to 200 feet deep.

Any size from  $1\frac{1}{4}$ -inch to  $2\frac{1}{2}$ -inch pipe can be used with this Standard, but always fitted as below, unless otherwise ordered. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod.

Wind mill slides are not furnished unless specially ordered.

FIG. 764. SIZES, PRICES, ETC

Stroke.	Suction.	Well Rod.	* Lift.	Cipher.	Price.
6 in. 10 "	$1\frac{1}{2}$ in. pipe 2 " "	7-16 in. 7-16 " and 1 in.	( $2\frac{1}{2}$ in. cyl., 150 ft. 3 " " 100 "	Valise Valley	\$17.00 18.50




FIG. 764.

*Cylinders* like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\* Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water ; smaller Cylinders in proportionately deeper wells.

# GOULDS DEEP WELL FORCE PUMP STANDARD.

FOR HAND AND WIND MILL.

Fig. 765 represents our new Wind Mill Deep-Well Force Pump Standard of extra heavy pattern, and constructed in two sections with flange between. This last feature is considered a very great advantage by all who put up these Pumps, for by a change of flanges they can readily be fitted for any size from  $1\frac{1}{4}$  to  $2\frac{1}{2}$ -inch pipe, thus readily adapting them for every need. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod. Always fitted as below unless otherwise ordered. Wind mill slides are not sent unless specially ordered.

FIG. 765. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in. 10 "	$1\frac{1}{2}$ in. pipe 2 " "	$1\frac{1}{4}$ in. pipe and 1 in. hose $1\frac{1}{4}$ " " 1 "	7-16 in. 7-16 " and 1 in.	( $2\frac{1}{2}$ in. cyl., 150 ft. 3 " " 100 "	Vellum Valor	\$21.00 22.50




FIG. 765.

*Cylinders* like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\* Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS "STAR" WELL FORCE PUMP STANDARDS.

WITH REVOLVING TOP. FOR HAND AND WIND MILL.




FIG. 422, No. 0

Light.




FIG. 422, No. 1

Medium.




FIG. 422, No. 2

Heavy.

Our well-known Fig. 422, Wind Mill Force Pump Standard, we now offer in three sizes. Air chamber is formed by enlarging stock above spout. Revolving bearer top is attached by strong through bolts. Outlet is provided back of spout for attaching pipe if desired. All spouts are flanged and bolted, permitting easy exchange for cock spout. Tapped for suction pipe near the spout. Furnished with nut and hose tube, also brace. Standards can be tapped for any size connecting pipe up to and including 2-inch, but unless otherwise ordered, we tap 1½-inch. With Standards tapped 2-inch we furnish coupling for 1-inch wood sucker rod. Wind mill slides are not sent unless specially ordered. Our new No. 0 Standard has Extension Stroke Guide (see cut), adapting it for 10-inch stroke with wind mill. It has 6-inch stroke by hand.

FIG. 422. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	No. 0.		No. 1.		No. 2.	
					Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
6 in.	1¼ in. pipe	1¼ in. pipe and ¾ in. hose	7-16 in.	{ 2½ in. cyl., 100 ft. 3 " " 60 " }	Grandyl	\$9.50	Vehemen Vehicled	\$10.00 11.00	Vehicl Veil	\$11.00 12.00
10 "	2 "	1¼ " " ¾ "	7-16 and 1 in.							

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standard can be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS "STAR" WELL FORCE PUMP STANDARDS.

47

WITH COCK SPOUT AND REVOLVING TOP, FOR HAND OR WIND MILL.




FIG. 423, No. 0

Light.




FIG. 423, No. 1

Medium.




FIG. 423, No. 2

Heavy.

Fig. 423, Wind Mill Force Pump Standard, is in all respects same as Fig. 422, more fully described on opposite page, except that it has a Cock Spout. When water is forced upward through pipe connected at back of Standard, the cock offers the necessary means for closing spout.

These Force Standards are exceptionally strong and neat of design. Brace and hose connection are furnished. Tapped to receive suction pipe inside of Standard, near the spout.

Can be tapped for any size connecting pipe up to and including 2-inch, but unless otherwise ordered, we tap  $1\frac{1}{4}$  inch. With Standards tapped 2 inch we furnish a coupling for 1-inch wood sucker-rod. Wind mill slides not sent unless specially ordered. Our new No. 0 Standard has Extension Stroke Guide (see cut), adapting it for 10-inch stroke with wind mill. It has 6-inch stroke by hand.

FIG. 423. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharges.	Well Rod.	* Lift and Force.	No. 0.		No. 1.		No. 2.	
					Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in pipe	$1\frac{1}{4}$ in. pipe and $\frac{3}{4}$ in. hose	7-16 in.	$2\frac{1}{2}$ in. cyl., 100 ft.	Granfis	\$12.00	Veina	\$12 50	Veined	\$13.50
10 "	2 "	$1\frac{1}{4}$ " " $\frac{3}{4}$ "	7-16 and 1 in.	$\frac{1}{3}$ " " 60 "	.....	.....	Veinles	13.50	Veinly	14.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery



# GOULDS "STAR" WELL FORCE PUMP STANDARD.

WITH AIR CHAMBER ON SPOUT. FOR HAND OR WIND MILL.




FIG. 401

Fig. 401 represents one of our best forms of Wind Mill Force Pumps, with revolving top, and while not one of the cheapest, possesses features which will commend it to practical men.

The gas pipe is connected in the body, close under the spout, and either 1, 1 $\frac{1}{4}$ , 1 $\frac{1}{2}$  or 2-inch can be used if so ordered, but always fitted as below unless otherwise directed. We *cannot* fit this standard for 2 $\frac{1}{2}$ -inch pipe. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod.

Wind mill slides are not furnished unless specially ordered.

FIG. 401. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	1 $\frac{1}{4}$ in. pipe	1 $\frac{1}{4}$ in. pipe and 3 $\frac{3}{4}$ in. hose.	7-16 in.	{ 2 $\frac{1}{2}$ in. cyl., 100 ft.	Meat	\$13.00
10 "	2 "	1 $\frac{1}{4}$ " " 3 $\frac{3}{4}$ "	7-16 and 1 in.	{ 3 " " 60 "	Meek	14.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and cost extra.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS "STAR" WELL FORCE PUMP STANDARD.

WITH AIR CHAMBER ON SPOUT. FOR HAND OR WIND MILL.




FIG. 402

Fig. 402 is similar in appearance and construction to Fig. 401, described above, except the Standard is built in two sections, with intermediate flange, which is a great convenience in making pipe connections near the spout.

The intermediate flange can be cut for any size of pipe up to and including 2 $\frac{1}{2}$ -inch, but always shipped as below unless otherwise ordered. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod.

Wind mill slides are not furnished unless specially ordered.

FIG. 402. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	1 $\frac{1}{4}$ in. pipe	1 $\frac{1}{4}$ in. pipe and 3 $\frac{3}{4}$ in. hose	7-16 in.	{ 2 $\frac{1}{2}$ in. cyl., 100 ft.	Minec	\$13.50
10 "	2 "	1 $\frac{1}{4}$ " " 3 $\frac{3}{4}$ "	7-16 and 1 in.	{ 3 " " 60 "	Mint	14.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and cost extra.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS "SOUTHERN" WELL FORCE PUMP STANDARD. 49

WITH COCK SPOUT. FOR HAND AND WIND MILL.

This Wind Mill Force Pump Standard has the intervening flange inserted just above the base. There is a check valve underneath the air chamber, so that these Standards are only adapted to warm climates. The flanges can be screwed for any size of pipe up to and including 3 inches. The upper discharge of air chamber is always fitted for pipe and the nose of the cock for hose. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod. Wind mill slides are not furnished unless specially ordered. Fitted as below unless otherwise directed.

FIG. 413. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	Cipher.	Price.
6 in.	1 1/4 in. pipe	1 1/4 in. pipe and 1 in. hose	7-16 in.	{ 2 1/2 in. cyl., 100 ft.	Roada Roand	\$16.00
10 "	2 " "	1 1/4 " " 1 "	7-16 and 1 in.	{ 3 " " 60 "		17.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 413

## GOULDS DEEP WELL FORCE PUMP STANDARD.

WITH COCK SPOUT. FOR HAND AND WIND MILL.

Fig. 1141, Wind Mill Force Pump Standard, is constructed in two sections, with intermediate flange which may be cut for any size pipe up to and including 2 1/2 inches. We always ship as below, unless otherwise ordered. Pump has revolving top, well balanced lever and is fitted with new pattern compression bibb. It has a 2-inch outlet at back of spout. Wind mill slides are not sent unless specially ordered. Price includes a 1-inch wood rod coupling.

FIG. 1141. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharges.	Well Rod.	*Lift and Force.	Cipher.	Price.
10 in.	2 in. pipe	2 in. pipe and 1 in. hose	7-16 and 1 in.	3 in. cyl., 75 ft.	Lumtyn	\$16.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard and *cost extra*.

\*Depth of Wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG 1141

### Anti-Freezing Force Pumps.

Our Anti-Freezing Wind Mill Force Pump, with Regulator, represents the acme of economic pumping. The position of supply tank, the system of piping, etc., is something that the conditions and requirements will determine.



A wind mill pumping plant like the above is complete and self-contained, requires no attendance and almost no care. The working of the regulator is such that the Pump is automatically started and stopped, as the water may fall or rise in the tank. We illustrate this type of Pump under Fig. 1061, page 55; other Pumps of similar class, pages 52 to 54.





# WIND MILL DISTRIBUTING FORCE PUMP HEADS.

51

WITH VERTICAL THREE-WAY VALVES.




FIG. 1278

Fig. 1278, "Seneca" Three-Way Distributing Pump Head, is made with wrought pipes extending through the base and forming the standard. A substantial wind mill top is attached to the air chamber pipe. This is so designed, that while allowing 10-inch stroke of wind mill, when lever is attached, the stroke by hand is but 5-inch and work proportionally easier. Base is adjustable. Working head has brass stuffing box. Three-way valve is operated by the single movement of small hand lever.

Fig. 1277 differs from Fig. 1278, in that it is provided with a small packing cylinder or plunger tube, which takes the place of a stuffing box.

*Plunger, of two-inch Tubular Well Cylinder, can be withdrawn through these working heads without taking up pump, or disturbing distributing pipe. Specially desirable for tubular wells. Working heads are tapped for 2-inch pipe, but can be bushed to 1¼ or 1½-inch.*




FIG. 1277

FIG. 1278. SIZE, PRICE, ETC.

Stroke.	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	Cipher.	Price.
10 in. mill and 5 in. hand, }	2 in. pipe	1¼ in. pipe	¾ in. hose	7-16 in.	Maltxan	\$15.00

FIG. 1277. SIZE, PRICE, ETC.

Stroke.	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	Cipher.	Price.
10 in. mill and 5 in. hand, }	2 in. pipe	1¼ in. pipe	¾ in. hose	7-16 in.	Maltyac	\$15.00

*Cylinders like Figs. 1230, 1231, pages 62 and 63, or Fig. 142, page 74, are required with these working heads, and cost extra.*

## WIND MILL DISTRIBUTING FORCE PUMP HEADS.

WITH VERTICAL THREE-WAY VALVE.




FIG. 1031

Fig. 1031, Wind Mill Distributing Force Pump Head, has 1½-inch air chamber pipe, vertical distributing valve and elbow attachment at bottom outlet. This distributing valve is placed in lower working head beyond the reach of frost, and is opened and closed by turning the wheel above stuffing box in discharge piece. The valve and working parts may be examined and repaired by withdrawing discharge pipe through platform base. By removing cap on lower working head and plate on platform, a 2-inch or 2¾-inch plunger can be drawn up and repaired without removing Pump from well. Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod.

Fig. 1048 is the same as Fig. 1031, but arranged with Fig. 1230, Brass Body Cylinder. Fitted in this manner, Pump may be used in wells up to 30 feet in depth.

FIG. 1031 SIZES, PRICES, ETC.

Stroke,	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	Cipher.	Price.
6 in.	1½ in. pipe	1½ in. pipe	¾ in. hose	7-16 in.	Aslake	\$17.00
Adjustable, 6, 8, or 10 in. }	2 "	1½ "	¾ "	7-16 and 1 in.	Awless	18.50




FIG. 1048

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with Fig. 1031 and *cost extra*.

FIG. 1048. SIZES, PRICES, ETC.

Stroke.	With Brass Body Cylinder.	Suction.	Lower Discharge.	Upper Discharge.	*Lift and Force.	WITH BRASS BODY CYLINDER.	
						Cipher.	Price.
6 in.	2½ x 10½ in.	1½ in. pipe	1½ in. pipe	¾ in. hose	125 ft.	Bonce	\$21.00
Adjustable, 6, 8 or 10 in. }	2½ x 14 "	1½ "	1½ "	¾ "	75 "	Bondhol	23.50

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

## WITH VERTICAL THREE-WAY VALVE.

Fig. 1033, Wind Mill Distributing Force Pump Head, has 2-inch air chamber pipe, vertical distributing valve and elbow attachment at bottom outlet.

In these Pumps, we have embodied all the best features of Pumps in this class. The distributing valve is placed in lower working head beyond the reach of frost, and is opened and closed by turning the wheel above stuffing box in discharge piece. This valve and working parts may be examined and repaired by withdrawing discharge pipe through platform base. By removing cap of lower working head and plate on platform, a 2-inch or  $2\frac{3}{4}$ -inch plunger can be drawn up and repaired without removing Pump from the well.

Pumps tapped for 2-inch pipe have coupling for 1-inch wood rod.

Fig. 1045 is practically the same as Fig. 1033, and is arranged with Fig. 1230, Brass Body Cylinder, as ordered, screwed into lower working head, thus adapting it in this form for shallow wells of 30 feet depth.




FIG. 1033




FIG. 1045

FIG. 1033. SIZES, PRICES, ETC.

Stroke.	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	Cipher.	Price.
6 in. Adjustable, } 6, 8 or 10 in. }	$1\frac{1}{4}$ in. pipe 2 "	$1\frac{1}{4}$ in. pipe $1\frac{1}{4}$ "	$\frac{3}{4}$ in. hose $\frac{3}{4}$ "	7-16 in. 7-16 and 1 in.	Asleep Awlwort	\$18.00 19.50

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with Figs. 1033, and *cost extra*.

FIG. 1045. SIZES, PRICES, ETC.

Stroke.	With Brass Body Cylinder.	Suction.	Lower Discharge.	Upper Discharge.	*Lift and Force.	WITH BRASS BODY CYLINDER.	
						Cipher.	Price.
6 in. Adjustable, } 6, 8 or 10 in. }	$2\frac{1}{2} \times 10\frac{1}{2}$ in, $2\frac{1}{2} \times 14$ "	$1\frac{1}{4}$ in. pipe $1\frac{1}{4}$ "	$1\frac{1}{4}$ in. pipe $1\frac{1}{4}$ "	$\frac{3}{4}$ in. hose $\frac{3}{4}$ "	125 ft. 75 "	Bonair Bonbon	\$22.00 24.50

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



## WIND MILL DISTRIBUTING FORCE PUMP HEADS.

WITH VERTICAL THREE-WAY VALVE



FIG. 862

Fig. 862, Distributing Head, has stock formed by two handsome sides bolted together over the wrought pipes. Bearer top revolves to any point. The stuffing boxes are both below ground and cannot be affected by the frost. At the lower working head both the top and bottom attachments are bolted to it, and by simply removing these the plunger and rod may be drawn up through the standard. The distributing valve is placed in a brass-lined chamber, and is raised and lowered by a single movement of the small handle shown at side of standard. Air chamber pipe is  $1\frac{1}{2}$ -inch; discharge pipe  $1\frac{1}{4}$ -inch.

Fig. 866 (not illustrated) is same as Fig. 862, except it has adjustable 6, 8 or 10-inch stroke.

Fig. 863 is very similar to Pumps above described, but somewhat lighter, having  $1\frac{1}{4}$ -inch air-chamber pipe and 1-inch discharge pipe. Always fitted for  $1\frac{1}{4}$ -inch suction.

Prices below include hose tube for spout and elbow for lower discharge. Wind mill slides are not sent unless especially ordered.




FIG 863

FIGS. 862 AND 866. SIZES, PRICES, ETC.

	Stroke.	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	Cipher.	Price.
Fig. 862	6-in.	$1\frac{1}{4}$ in. pipe	$1\frac{1}{4}$ in. pipe	$\frac{3}{4}$ in. hose	7-16 in.	Vow	\$18.50
" 866	{ Adjustable. }	2 "	$1\frac{1}{4}$ "	$\frac{3}{4}$ "	{ 7-16 in. iron }	Wafture	20.00
	{ 6, 8, 10 in. }				{ 1 " wood }		

FIG. 863. SIZE, PRICE, ETC.

Stroke.	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	Cipher.	Price.
6 in.	$1\frac{1}{4}$ in. pipe	$1\frac{1}{4}$ in. pipe	$\frac{3}{4}$ in. hose	7-16 in.	Wag	\$15.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, are required with these Pump Heads and cost extra.

## WITH VERTICAL THREE-WAY VALVE.




FIG. 1061  
Wheel in operation.

Fig. 1061, Regulator Force Pump Head (shown to the left when wheel is in operation and to the right when wheel is held out of gear) is a modification of our Fig. 1033, Anti-Freezing Force Pump Head, more fully described on page 53, to which we refer. In operation, the Regulator controls automatically the Wind Mill. The arrangement is such that when the supply tank is full, a common float valve closes inlet to tank and the discharge is forced into hydraulic cylinder, shown raised in engraving to the left. By this operation, the hydraulic cylinder is forced down, as shown in engraving to the right, carrying with it the connecting rod and chain, actuating the cam or chain sheave above, which in turn, by connecting wire, throws mill out of gear. As the water in the tank may lower, the inlet in pipe is re-opened and the operation reversed. The advantages of this automatic control can hardly be overestimated. It should not be forgotten that Pump and Mill work only when tank requires filling, and thus saves the wear and tear. Pumps have coupling for 1-inch wood rod.



FIG. 1061  
Wheel held out of gear.

## FIG. 1061. SIZE, PRICE, ETC

Adjustable Stroke.	Suction.	Lower Discharge.	Upper Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
6, 8 or 10 in.	2 in. pipe	1¼ in. pipe	¾ in. hose	7-16 and 1 in.	{ 2½ in. cyl., 125 ft. } 3 " 85 "	Chicaw	\$30.00

*Cylinders* like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Head and *cost extra*.

\*Depth of Well to which Pump may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS WELL FORCE PUMP PACKING-BOX HEADS.

FOR WIND MILLS.

We represent herewith our several styles Wind Mill Packing-Box Heads with brass glands and brass-cased rods. Fig. 1007 represents an all-brass Packing-Box Head for open or drilled wells. The discharge is formed by screwing a tee in suction pipe below. This, however, is not included in our price.




FIG 216

FIG. 217

FIG. 216. SIZES, PRICES, ETC.

Size Pipe.	Length Stroke	Well Rod.	Cipher.	Price.
1 1/4 in.	12 in.	7-16 in.	Diveless	\$5.00
1 1/2 "	12 "	7-16 "	Listnis	5.50
2 "	12 "	7-16 "	Listnoz	6.00
2 1/2 "	12 "	1/2 "	Listnun	7.00
3 "	12 "	1/2 "	Loagan	7.50
4 "	12 "	5/8 "	Loageg	9.00

FIG. 217. SIZES, PRICES, ETC.

Size Pipe.	Length Stroke	Well Rod	Cipher.	Price.
1 1/4 in.	12 in.	7-16 in.	Dodging	\$5.00
1 1/2 "	12 "	7-16 "	Loagim	5.50
2 "	12 "	7-16 "	Loagus	6.00
2 1/2 "	12 "	1/2 "	Lumpod	7.00
3 "	12 "	1/2 "	Lumour	7.50
4 "	12 "	5/8 "	Lumrat	9.00




FIG. 707

FIG. 1007

FIG. 707. SIZES, PRICES, ETC.

Size Pipe.	Length Stroke	Well Rod.	Cipher.	Price.
1 in.	12 in.	7-16 in.	Lumrig	\$3.00
1 1/4 "	12 "	7-16 "	Lumroe	3.00
1 1/2 "	12 "	7-16 "	Lumrum	3.00
2 "	12 "	1/2 "	Lumryl	3.00
2 1/2 "	12 "	1/2 "	Lumsab	3.75

FIG. 1007. SIZES, PRICES, ETC.

Size Pipe.	Length Stroke	Well Rod.	Cipher.	Price.
1 in.	12 in.	7-16 in.	Lumsin	\$4.00
1 1/4 "	12 "	7-16 "	Lumsod	4.00
1 1/2 "	12 "	7-16 "	Lumsus	5.00
2 "	12 "	7-16 "	Lumthc	6.00
2 1/2 "	12 "	7-16 "	Lumtim	7.50
3 "	12 "	1/2 "	Lumtope	10.00

## GOULDS FORCE PUMP HEAD.

WITH WIND MILL TOP AND WOOD LEVER.

Fig. 1260 is offered as a very desirable Force Head for operating by wind mill or by hand. It is compact and strong. Has double guide for polished rod. With wind mill allows 10-inch stroke, for hand 5-inch stroke. A powerful leverage is afforded, making easy work. We regularly furnish tapped for 1 1/4-inch pipe, but can tap for 1 1/2 or 2-inch if so ordered.




FIG. 1260

FIG. 1260. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	Cipher.	Price.
10 in. Mill and 5 in. Hand	2 in. pipe	3/4 in. hose and 1 in. pipe	7-16 in.	Lumtux	\$7.50



FOR HAND AND WIND MILL.




FIG. 685



FIG. 686




FIG. 690

These Working Heads are fitted with revolving top and sectional base. They are exceptionally strong and heavy, and adapted for use wherever wind mill or other power can be used. Flange is fitted for 1, 1¼, 1½, 2 or 2½-inch pipe, as ordered. Working heads tapped for 2-inch pipe have coupling for 1-inch wood rod. Forked rod furnished at extra price. Wind mill slides are not furnished unless especially ordered.

## SIZES, PRICES, ETC.

Fig.	Suction.	Discharge.	Well Rod.	*Lift and Force.	6-INCH STROKE.		10-INCH STROKE.	
					Cipher.	Price.	Cipher.	Price.
Fig. 685	1½ in. pipe	1½ in. pipe	7-16 to 1 in.	2½ in. cyl., 100 ft.	Sashaa	\$13.00	Sate	\$14.00
" 686	1¼ " "	1¼ " "	7-16 " 1 "	3 " " 60 "	Toll	15.00	Toller	16.00
" 690	1¼ " "	1¼ " "	7-16 " 1 "	3 " " 60 "	Topap	17.00	Topman	18.00

*Cylinders* as shown, pages 62 to 69, are required with these Working Heads, and *cost extra*.

\*Depth of Wells to which Working Heads may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS ARTESIAN WELL WORKING HEADS.

WITH DOUBLE ROD GUIDE AND POWER CONNECTION.




FIG. 979

FIG. 1249

Fig. 979 is especially designed to use with our Artesian Pump Cylinders. Piston rod is kept in perfect alignment by double guides at side, while stuffing box below adapts it for forcing equally as well as raising water. The power attachment is hinged and made to fit wood rod of wind mill, though it may be readily adapted for any other power and connecting rod.

Fig. 1249 is of same construction as Fig. 979, with the addition of a large air chamber, which adapts it for working against heavy head. Wood rod coupling will be furnished when ordered, at extra price. Well rod is size iron or wood rod ordered.

FIGS. 979 AND 1249. SIZES, PRICES, ETC.

No.	Stroke.	Suction.	Discharge.	*Lift and Force.	Fig. 979. (Hendajl)	Fig. 1249. (Hendibs)
1	16 in.	2, 2 $\frac{1}{2}$ or 3 in. pipe	1, 1 $\frac{1}{4}$ or 1 $\frac{1}{2}$ in. pipe	2 $\frac{3}{4}$ in. cyl., 300 ft.	\$15.00	\$25.00
1	24 "	2, 2 $\frac{1}{2}$ or 3 "	1, 1 $\frac{1}{4}$ or 1 $\frac{1}{2}$ "	2 $\frac{3}{4}$ " 300 "	17.50	27.50
2	24 "	3 $\frac{1}{2}$ , 4 or 4 $\frac{1}{2}$ "	1 $\frac{1}{2}$ , 2 or 2 $\frac{1}{2}$ "	4 $\frac{1}{4}$ " 250 "	30.00	40.00
2	30 "	3 $\frac{1}{2}$ , 4 or 4 $\frac{1}{2}$ "	1 $\frac{1}{2}$ , 2 or 2 $\frac{1}{2}$ "	4 $\frac{1}{4}$ " 250 "	32.50	42.50
3	24 "	5 or 6 "	2 $\frac{1}{2}$ or 3 "	5 $\frac{3}{4}$ " 200 "	35.00	50.00
3	30 "	5 or 6 "	2 $\frac{1}{2}$ or 3 "	5 $\frac{3}{4}$ " 200 "	37.50	52.50
3	36 "	5 or 6 "	2 $\frac{1}{2}$ or 3 "	5 $\frac{3}{4}$ " 200 "	40.00	55.00

With Cipher always specify number of Head and length of Stroke.

## DIFFERENTIAL POWER WORKING HEAD.

FOR OPERATING DEEP WELL PUMPS.

In Fig. 978 we illustrate a Power Pump Head with Differential Plunger, to be used with our Fig. 650, Geared Driving Shaft, page 103, for operating Artesian Cylinders in deep wells.

We should always be advised diameter of Lower Working Cylinder, that we may proportionate this Upper Differential Plunger to have one-half the displacement of Plunger in Lower Cylinder. This contributes to even delivery of water and distribution of power.

Pump Head may be operated by Wind mill or other machine power.

FIG. 978. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
10 in.	2 to 6 in.	2 to 4 in.	For size iron or wood rod ordered	3 $\frac{1}{4}$ in. cyl., 500 ft.	Altrical	\$90.00
12, 16, 18 "	2 to 6 "	2 to 4 "		3 $\frac{3}{4}$ " 400 "	Altrices	95.00
20, 22, 24 "	2 to 6 "	2 to 4 "		4 $\frac{3}{4}$ " 300 "	Caper	100.00
26, 28, 30 "	2 to 6 "	2 to 4 "		5 $\frac{3}{4}$ " 200 "	Careful	115.00
36 "	2 to 6 "	2 to 4 "			Watery	135.00

See Pages 67 to 69 for Brass Artesian Cylinders, adapted for use with these heads.

\* Vertical lift and force, from surface of water to point of delivery, to which Working Head can be adapted by placing Cylinder within 15 or 20 feet of water. For pumping to less elevations larger Cylinders can be used and for greater elevations smaller Cylinders.



FIG. 978

# GOULDS ARTESIAN WELL WORKING HEAD.

59

WITH FORKED ROD, PITMAN AND GUIDE.

Fig. 1127, Artesian Well Working Head, is provided with stuffing box, guide, guide rod, brass-cased piston rod and pitman for machine power. It has an intermediate flange for pipe, connection, sizes up to and including 3-inch. Discharge for size pipe up to and including 3-inch. Forked rod is supplied with each Working Head.

We can furnish everything complete for wells of any depth.

Always specify size suction and discharge pipe.

FIG. 1127. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
10 in. 16 "	1 $\frac{1}{4}$ to 3 in. pipe 1 $\frac{1}{4}$ to 3 "	1 $\frac{1}{4}$ to 3 in. pipe 1 $\frac{1}{4}$ to 3 "	For size iron or wood rod ordered.	$\left\{ \begin{array}{l} 2\frac{3}{4} \text{ in. cyl., 225 ft.} \\ 3\frac{1}{4} \text{ " " 175 " } \\ 3\frac{3}{4} \text{ " " 100 " } \end{array} \right\}$	Dotgade Dotgib	\$30.00 35.00

Cylinders like Figs. 1230, 548, 904, pages 62 to 69, are required with this Working Head and cost extra.

\*Depth of Well to which Working Head may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 1127

# GOULDS ARTESIAN WELL WORKING HEAD.

Fig. 446 shows a Working Head provided with piston rod, stuffing box, guide, guide rod, pitman and stub end, for operating Fig. 904, Artesian Pump Cylinder, or other long stroke Working Barrels.

This Pump Head may be operated by any machine power and is connected to cylinder by pipe and rod of sufficient length to reach to the bottom of the well or mine.

We can furnish everything complete for wells of any depth.

Always specify size suction and discharge pipe.

FIG. 446. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	Cipher.	Price.
16 in. 18 " 24 " 30 " 36 "	2 to 5 in. pipe 2 to 5 " 2 to 5 " 2 to 5 " 2 to 5 "	1 $\frac{1}{2}$ to 2 $\frac{1}{2}$ in. pipe 1 $\frac{1}{2}$ to 2 $\frac{1}{2}$ " 1 $\frac{1}{2}$ to 2 $\frac{1}{2}$ " 1 $\frac{1}{2}$ to 2 $\frac{1}{2}$ " 1 $\frac{1}{2}$ to 2 $\frac{1}{2}$ "	For size iron or wood rod ordered.	$\left\{ \begin{array}{l} 2\frac{3}{4} \text{ in. cyl., 400 ft.} \\ 3\frac{1}{4} \text{ " " 300 " } \\ 3\frac{3}{4} \text{ " " 225 " } \\ 4\frac{3}{4} \text{ " " 150 " } \end{array} \right\}$	Dingier Direful Dished Torsel Tortvd	\$50.00 55.00 60.00 70.00 80.00

Cylinders like Figs. 1230, 548, 904, pages 62 to 69, are required with this Working Head and cost extra.

\*Depth of Well to which Working Head may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.







FIG. 446



# 60 PLANS FOR PLACING WORKING HEADS, CYLINDERS, ETC.

GIVING TECHNICAL TERMS USED IN OUR CATALOGUE.



# IMPROVED PUMP CYLINDERS OR WORKING BARRELS.

61

FOR OPEN, DUG, DRIVEN OR BORED AND CASED WELLS.

We have remodeled our entire line of Pump Cylinders or Working Barrels. These changes afford substantial improvements and render more simple and in a larger measure interchangeable.

Briefly: We offer under a single Fig. in each class, Iron, Brass Lined, Brass Body and all Brass Cylinders, as follows:



"AA"  
PLUNGER

- Fig. 1230, with screwed outside caps and leather lower valve.
- Fig. 1231, with screwed inside caps and leather lower valve.
- Fig. 1235, with screwed outside caps and metal lower valve.
- Fig. 1236, with screwed inside caps and metal lower valve.
- Fig. 1267, with bolted outside caps and leather lower valve.
- Fig. 1268, with bolted outside caps and metal lower valve.



"BB"  
PLUNGER

Ten and one half-inch Body Cylinders have "AA" plunger with metal poppet and single crimped leather.

Twelve-inch, 14-inch, 16-inch, 18-inch, 20-inch and 22-inch Body Cylinders have "BB" plunger with metal poppet and double crimped leathers.

## "UNIVERSAL" BRONZE VALVE AND SEAT.

(PATENT APPLIED FOR.)

Fig. 1229, "Universal" Bronze Valve and Seat, is interchangeable with leather valve in all of our Cylinders, both inside and outside capped. Dealers can carry in stock and effect change to suit demand. Our engravings show construction, and we assert there is not a simpler, more effective or durable Lower Valve made. The valve seat is made a part of the valve, saving the expense of separate brass valve seat.




FIG. 1229

Shown in an "outside"  
Cylinder attachment.

FIG. 1229. SIZES, PRICES. ETC.

Diameter of Cylinders.....	2 $\frac{1}{2}$ , 2 $\frac{3}{4}$ , 3 ins.	3 $\frac{1}{4}$ and 3 $\frac{1}{2}$ ins.	4 and 4 $\frac{1}{2}$ ins.
For Cylinders with attachments tapped..	1 $\frac{1}{4}$ in.	1 $\frac{1}{2}$ in.	2 in.
Price, Fig. 1229 Compl. (not including Cylinder attachment).....	\$1.25	\$1.75	\$2.50




FIG. 1229

Shown in "inside"  
Cylinder attachment.

TABLE SHOWING EXTREME OUTSIDE DIAMETER OF CYLINDERS.

Inside Diameter, Inches.....	2	2 $\frac{1}{4}$	2 $\frac{1}{2}$	2 $\frac{3}{4}$	3	3 $\frac{1}{4}$	3 $\frac{1}{2}$	4	4 $\frac{1}{2}$	5	6	8
EXTREME OUTSIDE DIAMETER.												
Figs. 1230 and 1235, Iron and Brass Lined.....	3 3-16	3 $\frac{7}{8}$	3 11-16	3 15-16	4 3-16	4 7-16	4 11-16	5 $\frac{1}{4}$	5 $\frac{7}{8}$	6 $\frac{1}{2}$	7 $\frac{1}{2}$	9 $\frac{3}{4}$
Figs. 1230 and 1235, Brass Body.....	2 $\frac{5}{8}$	2 $\frac{7}{8}$	3 $\frac{1}{8}$	3 $\frac{3}{8}$	3 $\frac{5}{8}$	3 $\frac{7}{8}$	4 $\frac{1}{8}$	4 11-16	5 $\frac{1}{2}$	6	7	
Figs. 1231 and 1236, Iron and Brass Lined.....	2 $\frac{5}{8}$	2 $\frac{7}{8}$	3 $\frac{1}{8}$	3 $\frac{3}{8}$	3 $\frac{5}{8}$	3 15-16	4 3-16	4 $\frac{3}{4}$	5 $\frac{1}{8}$	5 $\frac{3}{8}$	6 $\frac{3}{4}$	8 $\frac{3}{4}$
Figs. 1231 and 1236, Brass Body.....	2 $\frac{1}{4}$	2 $\frac{1}{2}$	2 $\frac{3}{4}$	3	3 $\frac{1}{4}$	3 $\frac{1}{2}$	3 $\frac{3}{4}$	4 $\frac{1}{4}$	4 $\frac{7}{8}$	5 $\frac{3}{8}$	6 $\frac{3}{8}$	8 $\frac{3}{8}$



# GOULDS PUMP CYLINDERS OR WORKING BARRELS.

FIGS. 1230, 1231—10½ INCHES LONG. "AA" PLUNGER AND LEATHER LOWER VALVE.



FIG. 1230  
Outside  
Attachment.




FIG. 1230  
Outside  
Attachment.

Diameter and Length.	FIG. 1230.		FIG. 1231.		Size Pipe.	Well Rod.	Iron.	Brass Lined. Brass Cage and Valve Plunger.	Brass Body. All Brass Plunger.	All Brass.
	Stroke.	Capacity per Stroke.	Stroke.	Stroke.						
2 x 10½ in.	6 in.	.08 gal.	6 in.	1 in.	3/8 in.		\$3.75	\$7.50	\$8.00	\$10.75
2¼ x 10½ "	6 "	.10 "	6 "	1 "	3/8 "		4.00	7.75	8.25	11.00
2½ x 10½ "	6 "	.13 "	6 "	1¼ "	3/8 "		4.35	8.00	8.50	12.25
2¾ x 10½ "	6 "	.15 "	6 "	1¼ "	3/8 "		4.70	8.50	9.00	12.75
3 x 10½ "	6 "	.18 "	6 "	1¼ "	3/8 "		5.00	9.00	9.75	13.50
3¼ x 10½ "	6 "	.21 "	6 "	1½ "	3/8 "		6.00	9.75	10.50	14.75
3½ x 10½ "	6 "	.25 "	6 "	1½ "	7-16 "		7.00	10.50	11.50	16.75
4 x 10½ "	6 "	.32 "	6 "	2 "	7-16 "		9.00	13.00	15.50	21.50

FIGS. 1230, 1231—12, 14, 16, 18 INCHES LONG, "BB" PLUNGER AND LEATHER LOWER VALVE.

Diameter and Length.	FIG. 1230.		FIG. 1231.		Size Pipe.	Well Rod.	Iron.	Brass Lined. Brass Cage and Valve Plunger.	Brass Body. All Brass Plunger.	All Brass.
	Stroke.	Capacity per Stroke.	Stroke.	Stroke.						
2 x 12 in.	8 in.	.11 gal.	6 in.	1 in.	3/8 in.		\$5.50	\$8.00	\$9.25	\$11.25
2¼ x 12 "	8 "	.14 "	6 "	1 "	3/8 "		5.75	8.25	9.50	11.50
2½ x 12 "	8 "	.17 "	6 "	1¼ "	3/8 "		6.00	8.50	9.75	12.75
2¾ x 12 "	8 "	.20 "	6 "	1¼ "	3/8 "		6.50	9.00	10.50	13.25
3 x 12 "	8 "	.24 "	6 "	1¼ "	3/8 "		7.00	9.50	11.00	14.00
3¼ x 12 "	8 "	.29 "	6 "	1½ "	3/8 "		8.00	10.25	12.00	15.25
3½ x 12 "	8 "	.33 "	6 "	1½ "	7-16 "		9.00	11.25	13.75	17.50
4 x 12 "	8 "	.44 "	6 "	2 "	7-16 "		11.50	14.25	18.00	22.50
2 x 14 "	10 "	.14 "	8 "	1 "	3/8 "		6.00	8.50	9.75	13.00
2¼ x 14 "	10 "	.17 "	8 "	1 "	3/8 "		6.25	9.00	10.25	13.50
2½ x 14 "	10 "	.21 "	8 "	1¼ "	3/8 "		6.50	9.25	10.50	14.75
2¾ x 14 "	10 "	.25 "	8 "	1¼ "	3/8 "		7.00	9.75	11.25	15.50
3 x 14 "	10 "	.30 "	8 "	1½ "	3/8 "		7.50	10.25	11.75	16.25
3¼ x 14 "	10 "	.36 "	8 "	1½ "	3/8 "		8.75	11.00	12.75	17.75
3½ x 14 "	10 "	.41 "	8 "	1½ "	7-16 "		10.00	12.25	14.75	21.00
4 x 14 "	10 "	.54 "	8 "	2 "	7-16 "		13.00	15.75	19.00	26.50
4½ x 14 "	8 "	.55 "	6 "	2 "	1½ "		17.50	24.00	28.00	36.00
5 x 14 "	8 "	.68 "	6 "	2½ "	1½ "		22.50	33.00	38.00	50.00
6 x 14 "	8 "	.98 "	6 "	3 "	5/8 "		33.50	50.00	56.00	70.00
2 x 16 "	12 "	.16 "	10 "	1 "	3/8 "		6.00	9.00	10.50	13.75
2¼ x 16 "	12 "	.21 "	10 "	1 "	3/8 "		6.50	9.75	11.25	14.50
2½ x 16 "	12 "	.26 "	10 "	1¼ "	3/8 "		7.00	10.25	11.75	16.00
2¾ x 16 "	12 "	.31 "	10 "	1¼ "	3/8 "		7.50	10.75	12.25	16.50
3 x 16 "	12 "	.37 "	10 "	1½ "	3/8 "		8.00	11.25	12.75	17.25
3¼ x 16 "	12 "	.43 "	10 "	1½ "	3/8 "		9.75	12.00	14.00	19.00
3½ x 16 "	12 "	.50 "	10 "	1½ "	7-16 "		11.25	13.50	16.00	22.25
4 x 16 "	12 "	.65 "	10 "	2 "	7-16 "		14.50	17.50	20.50	28.00
4½ x 16 "	10 "	.69 "	8 "	2 "	1½ "		18.50	25.00	30.50	38.75
5 x 16 "	10 "	.85 "	8 "	2½ "	1½ "		25.00	35.00	42.00	53.50
6 x 16 "	10 "	1.22 "	8 "	3 "	5/8 "		37.50	55.00	62.00	75.00
4½ x 18 "	12 "	.83 "	10 "	2 "	1½ "		22.50	30.00	35.00	43.25
5 x 18 "	12 "	1.02 "	10 "	2½ "	1½ "		30.00	40.00	47.00	58.50
6 x 18 "	12 "	1.47 "	10 "	3 "	5/8 "		42.50	60.00	67.00	80.00
8 x 18 "	8 "	1.74 "	6 "	4 "	3/4 "		90.00	115.00	134.00	160.00

Longer lengths and "Cipher" on next page.

NOTE—Above Cylinders are all adapted to receive our "Universal" Bronze Valve and Seat.



FIG. 1231  
Inside  
Attachment.



FIG. 1231  
Inside  
Attachment.



# GOULDS PUMP CYLINDERS OR WORKING BARRELS.

63

FIGS. 1230, 1231—20 AND 22 INCHES LONG, "BB" PLUNGER AND LEATHER LOWER VALVE.

Diameter and Length.	FIG. 1230.		FIG. 1231.		Size Pipe.	Well Rod.	Brass Body. All Brass Plunger.	All Brass.
	Stroke.	Capacity per Stroke.	Stroke.					
2 x 20 in.	16 in.	.21 gal.	14 in.	1 in.	3 in.	\$11.50	\$14.75	
2 1/4 x 20 "	16 "	.27 "	14 "	1 "	3 1/2 "	12.75	16.00	
2 1/2 x 20 "	16 "	.34 "	14 "	1 1/4 "	3 1/2 "	13.50	17.75	
2 3/4 x 20 "	16 "	.41 "	14 "	1 1/4 "	3 1/2 "	14.25	18.50	
3 x 20 "	16 "	.49 "	14 "	1 1/4 "	3 1/2 "	14.75	19.25	
3 1/4 x 20 "	16 "	.57 "	14 "	1 1/2 "	3 1/2 "	16.00	21.00	
3 1/2 x 20 "	16 "	.66 "	14 "	1 1/2 "	7-16 "	19.00	25.25	
4 x 20 "	16 "	.87 "	14 "	2 "	7-16 "	24.00	31.50	
4 1/2 x 22 "	16 "	1.10 "	14 "	2 "	5 3/8 "	43.00	52.25	
5 x 22 "	16 "	1.36 "	14 "	2 1/2 "	5 3/8 "	57.00	68.50	
6 x 22 "	16 "	1.96 "	14 "	3 "	5 3/8 "	77.00	90.00	
8 x 22 "	12 "	2.61 "	10 "	4 "	3 1/4 "	154.00	180.00	

\*Cipher—Halgap, Fig. 1230, Iron.  
 " Halgub, " 1230, Brass-Lined.  
 " Harfcot, " 1230, Brass Body.  
 " Harfduc, " 1230, All Brass.

Cipher—Hauma, Fig. 1231, Iron.  
 " Haumic, " 1231, Brass-Lined.  
 " Haumon, " 1231, Brass Body.  
 " Haumud, " 1231, All Brass.

## BOLT ATTACHMENT CYLINDERS, LEATHER LOWER VALVE.

FIG. 1267. 10 1/2 INCHES LONG, "AA" PLUNGER.

Diameter and Length.	Stroke.	Capacity per Stroke.	Size Pipe.	Well Rod.	Iron.	Brass Lined. Brass Cage and Valve Plunger.	Brass Body. All Brass Plunger.	All Brass.
2 1/2 x 10 1/2 in.	6 in.	.13 gals.	1 1/4 in.	3 in.	\$4.35	\$8.00	\$8.50	\$12.25
3 x 10 1/2 "	6 "	.18 "	1 1/4 "	3 1/2 "	5.00	9.00	9.75	13.50
3 1/2 x 10 1/2 "	6 "	.25 "	1 1/2 "	7-16 "	7.00	10.50	11.50	16.75
4 x 10 1/2 "	6 "	.32 "	2 "	7-16 "	9.00	13.00	15.50	21.50

FIG. 1267—12, 14, 16, 20 INCHES LONG, WITH "BB" PLUNGER.

Diameter and Length.	Stroke.	Capacity per Stroke.	Size Pipe.	Well Rod.	Iron.	Brass Lined. Brass Cage and Valve Plunger.	Brass Body. All Brass Plunger.	All Brass.
2 1/2 x 12 in.	8 in.	.17 gal.	1 1/4 in.	3 in.	\$6.00	\$8.50	\$9.75	\$12.75
3 x 12 "	8 "	.24 "	1 1/4 "	3 1/2 "	7.00	9.50	11.00	14.00
3 1/2 x 12 "	8 "	.33 "	1 1/2 "	7-16 "	9.00	11.25	13.75	17.50
4 x 12 "	8 "	.44 "	2 "	7-16 "	11.50	14.25	18.00	22.50
2 1/2 x 14 "	10 "	.21 "	1 1/4 "	3 1/2 "	6.50	9.25	10.50	14.75
3 x 14 "	10 "	.30 "	1 1/4 "	3 1/2 "	7.50	10.25	11.75	16.25
3 1/2 x 14 "	10 "	.41 "	1 1/2 "	7-16 "	10.00	12.25	14.75	21.00
4 x 14 "	10 "	.54 "	2 "	7-16 "	13.00	15.75	19.00	26.50
2 1/2 x 16 "	12 "	.26 "	1 1/4 "	3 1/2 "	7.00	10.25	11.75	16.00
3 x 16 "	12 "	.37 "	1 1/4 "	3 1/2 "	8.00	11.25	12.75	17.25
3 1/2 x 16 "	12 "	.50 "	1 1/2 "	7-16 "	11.25	13.50	16.00	22.25
4 x 16 "	12 "	.65 "	2 "	7-16 "	14.50	17.50	20.50	28.00
2 1/2 x 20 "	16 "	.34 "	1 1/4 "	3 1/2 "	.....	.....	13.50	17.75
3 x 20 "	16 "	.49 "	1 1/4 "	3 1/2 "	.....	.....	14.75	19.25
3 1/2 x 20 "	16 "	.66 "	1 1/2 "	7-16 "	.....	.....	19.00	25.25
4 x 20 "	16 "	.87 "	2 "	7-16 "	.....	.....	24.00	31.50

\*Cipher—Haumvo, Fig. 1267, Iron.  
 " Haupa, " 1267, Brass Lined.

Cipher—Haupid, Fig. 1267, Brass Body.  
 " Haupod, " 1267, All Brass.

\*In addition always specify diameter and length of Cylinder Body.

NOTE—Above Cylinders are all adapted to receive our "Universal" Bronze Valve and Seat.




FIG. 1267



FIG. 1267

# GOULDS PUMP CYLINDERS OR WORKING BARRELS.

FIG. 1235—10½ INCHES LONG. "AA" PLUNGER AND "UNIVERSAL" BRONZE VALVE AND SEAT.




FIG. 1235  
Outside  
Attachment.




FIG. 1235  
Outside  
Attachment.

Diameter and Length.	FIG. 1235.		Size Pipe.	Well Rod.	Iron.	Brass Lined, Brass Cage and Valve Plunger.	Brass Body, All Brass Plunger.	All Brass.
	Stroke.	Capacity per Stroke.						
2 x 10½ in.	6 in.	.08 gals.	1 in.	3/8 in.	\$5.50	\$8.75	\$9.25	\$12.00
2¼ x 10½ "	6 "	.10 "	1 "	3/8 "	5.75	9.00	9.50	12.25
2½ x 10½ "	6 "	.13 "	1¼ "	3/8 "	6.10	9.25	9.75	13.50
2¾ x 10½ "	6 "	.15 "	1½ "	3/8 "	6.45	9.75	10.25	14.00
3 x 10½ "	6 "	.18 "	1¾ "	3/8 "	6.75	10.25	11.00	14.75
3¼ x 10½ "	6 "	.21 "	1½ "	3/8 "	8.25	11.50	12.25	16.50
3½ x 10½ "	6 "	.25 "	1½ "	7-16 "	9.25	12.25	13.25	18.50
4 x 10½ "	6 "	.32 "	2 "	7-16 "	12.50	15.50	18.00	24.00

FIGS. 1235, 1236—12, 14, 16 AND 18 INCHES LONG. "BB" PLUNGER AND "UNIVERSAL" BRONZE VALVE AND SEAT.

Diameter and Length.	FIG. 1235.		FIG. 1236.		Size Pipe.	Well Rod.	Iron.	Brass Lined, Brass Cage and Valve Plunger.	Brass Body, All Brass Plunger.	All Brass.
	Stroke.	Capacity per Stroke.	Stroke.							
2 x 12 in.	Made only in Fig. 1236.	.10 gals.	6 in.	Made only in Fig. 1235.	1 in.	3/8 in.	\$7.25	\$9.25	\$10.50	\$12.50
2 1/4 x 12 "		.12 "	6 "		1 "	3/8 "	7.50	9.50	10.75	12.75
2 1/2 x 12 "		.15 "	6 "		1 1/4 "	3/8 "	7.75	9.75	11.00	14.00
2 3/4 x 12 "		.18 "	6 "		1 1/4 "	3/8 "	8.25	10.25	11.75	14.50
3 x 12 "		.21 "	6 "		1 1/4 "	3/8 "	8.75	10.75	12.25	15.25
3 1/4 x 12 "	8 in.	.25 "	6 "	1 1/2 "	1 1/2 "	5/8 "	10.25	12.00	13.75	17.00
3 1/2 x 12 "		.29 "	6 "		7-16 "	11.25	13.00	15.50	19.25	
4 x 12 "		.38 "	6 "		7-16 "	15.00	16.75	20.50	25.00	
2 x 14 "		.10 "	8 in.		1 "	3/8 "	7.75	9.75	11.00	14.25
2 1/4 x 14 "		.13 "			1 "	3/8 "	8.00	10.25	11.50	14.75
2 1/2 x 14 "		.17 "			1 1/4 "	3/8 "	8.25	10.50	11.75	16.00
2 3/4 x 14 "		.20 "			1 1/4 "	3/8 "	8.75	11.00	12.50	16.75
3 x 14 "		.24 "			1 1/4 "	3/8 "	9.25	11.50	13.00	17.50
3 1/4 x 14 "	8 in.	.28 "	8 in.	1 1/2 "	1 1/2 "	3/8 "	11.00	12.75	14.50	19.50
3 1/2 x 14 "		.33 "			7-16 "	12.25	14.00	16.50	22.75	
4 x 14 "		.43 "			7-16 "	16.50	18.25	21.50	29.00	
4 1/2 x 14 "		.55 "			2 "	1 1/2 "	21.00	26.50	30.50	38.50
2 x 16 "		.14 "			8 "	1 "	3/8 "	7.75	10.25	11.75
2 1/4 x 16 "	10 in.	.17 "	8 in.	1 "	3/8 "	8.25	11.00	12.50	15.75	
2 1/2 x 16 "		.21 "			1 1/4 "	3/8 "	8.75	11.50	13.00	17.25
2 3/4 x 16 "		.25 "			1 1/4 "	3/8 "	9.25	12.00	13.50	17.75
3 x 16 "		.30 "			1 1/4 "	3/8 "	9.75	12.50	14.00	18.50
3 1/4 x 16 "		.36 "			8 in.	1 1/2 "	12.00	13.75	15.75	20.75
3 1/2 x 16 "	10 in.	.41 "	8 in.	1 1/2 "	7-16 "	13.50	15.25	17.75	24.00	
4 x 16 "		.54 "			2 "	7-16 "	18.00	20.00	23.00	30.50
4 1/2 x 16 "		.69 "			2 "	1 1/2 "	22.00	27.50	33.00	41.25
2 x 18 "		.16 "	10 in.	1 "	3/8 "	8.50	10.75	12.25	15.50	
2 1/4 x 18 "		.21 "			1 "	3/8 "	8.75	11.75	13.25	16.50
2 1/2 x 18 "		.26 "			1 1/4 "	3/8 "	9.25	12.50	14.00	18.25
2 3/4 x 18 "		.31 "			1 1/4 "	3/8 "	9.75	13.00	14.50	18.75
3 x 18 "	12 in.	.37 "		10 in.	1 1/4 "	3/8 "	10.25	13.50	15.00	19.50
3 1/4 x 18 "		.43 "			1 1/2 "	3/8 "	13.00	14.75	16.75	21.75
3 1/2 x 18 "		.50 "			1 1/2 "	7-16 "	14.75	16.50	19.00	25.25
4 x 18 "		.65 "			2 "	7-16 "	19.50	21.75	24.75	32.25
4 1/2 x 18 "		.83 "			2 "	1 1/2 "	26.00	32.50	37.50	45.75

Longer lengths and "Cipher" on next page.



FIG. 1236  
Inside  
Attachment.



FIG. 1236  
Inside  
Attachment.



# GOULDS PUMP CYLINDERS OR WORKING BARRELS.

65

FIGS. 1235: 1236-20 INCHES LONG, "BB" PLUNGER AND METAL LOWER VALVE.

Diameter and Length.	FIG. 1235.		FIG. 1236.		Size Pipe.	Well Rod.	Brass Body. All Brass Plunger.	All Brass.
	Stroke.	Capacity per Stroke.	Stroke.					
2 x 20 in.	14 in.	.19 gals.	12 in.	1 in.	3 in.		\$12.75	\$16.00
2 1/4 x 20 "	14 "	.24 "	12 "	1 "	3 3/8 "		14.00	17.25
2 1/2 x 20 "	14 "	.29 "	12 "	1 1/4 "	3 1/2 "		14.75	19.00
2 3/4 x 20 "	14 "	.36 "	12 "	1 1/4 "	3 3/4 "		15.50	19.75
3 x 20 "	14 "	.42 "	12 "	1 1/4 "	3 3/4 "		16.00	20.50
3 1/4 x 20 "	14 "	.50 "	12 "	1 1/2 "	3 3/4 "		17.75	22.75
3 1/2 x 20 "	14 "	.58 "	12 "	1 1/2 "	7-16 "		20.75	27.00
4 x 20 "	14 "	.76 "	12 "	2 "	7-16 "		26.50	34.00

Cipher—Hauptun, Fig. 1235, Iron.

Henbid, " 1235, Brass-Lined.

Henbifa, " 1235, Brass Body.

Henboc, " 1235, All Brass.

Cipher—Henbur, Fig. 1236, Iron.

Henbust, " 1236, Brass-Lined.

Hencab, " 1236, Brass Body.

Hencare, " 1236, All Brass.

In addition always specify Diameter and Length of Cylinder Body.

## BOLT ATTACHMENT CYLINDER WITH METAL LOWER VALVE.

FIG. 1268. 10 1/2 INCHES LONG WITH "AA" PLUNGER.

Diameter and Length.	Stroke.	Capacity per Stroke.	Size Pipe.	Well Rod.	Iron.	Brass-Lined, Brass Cage and Valve Plunger.	Brass Body, All Brass Plunger.	All Brass.
2 1/2 x 10 1/2 in.	6 in.	.13 gals.	1 1/4 in.	3/8 in.	\$6.10	\$9.25	\$9.75	\$13.50
3 x 10 1/2 "	6 "	.18 "	1 1/4 "		6.75	10.25	11.00	14.75
3 1/2 x 10 1/2 "	6 "	.25 "	1 1/2 "	7-16 "	9.25	12.25	13.25	18.50
4 x 10 1/2 "	6 "	.32 "	2 "	7-16 "	12.50	15.50	18.00	24.00

FIG. 1268. 12, 16, 18 AND 20 INCHES LONG, WITH "BB" PLUNGER.

Diameter and Length.	Stroke.	Capacity per Stroke.	Size Pipe.	Well Rod.	Iron.	Brass-Lined, Brass Cage and Valve Plunger.	Brass Body, All Brass Plunger.	All Brass.
2 1/2 x 12 in.	7 in.	.15 gals.	1 1/4 in.	3/8 in.	\$7.75	\$9.75	\$11.00	\$14.00
3 x 12 "	7 "	.21 "	1 1/4 "	3/8 "	8.75	10.75	12.25	15.25
3 1/2 x 12 "	7 "	.29 "	1 1/2 "	7-16 "	11.25	13.00	15.50	19.25
4 x 12 "	7 "	.38 "	2 "	7-16 "	15.00	16.75	20.50	25.00
2 1/2 x 16 "	10 "	.21 "	1 1/4 "	3/8 "	8.75	11.50	13.00	17.25
3 x 16 "	10 "	.30 "	1 1/4 "	3/8 "	9.75	12.50	14.00	18.50
3 1/2 x 16 "	10 "	.41 "	1 1/2 "	7-16 "	13.50	15.25	17.75	24.00
4 x 16 "	10 "	.54 "	2 "	7-16 "	18.00	20.00	23.00	30.50
2 1/2 x 18 "	12 "	.26 "	1 1/4 "	3/8 "	9.25	12.50	14.00	18.25
3 x 18 "	12 "	.37 "	1 1/4 "	3/8 "	10.25	13.50	15.00	19.50
3 1/2 x 18 "	12 "	.50 "	1 1/2 "	7-16 "	14.75	16.50	19.00	25.25
4 x 18 "	12 "	.65 "	2 "	7-16 "	19.50	21.75	24.75	32.25
2 1/2 x 20 "	14 "	.29 "	1 1/4 "	3/8 "			14.75	19.00
3 x 20 "	14 "	.42 "	1 1/4 "	3/8 "			16.00	20.50
3 1/2 x 20 "	14 "	.58 "	1 1/2 "	7-16 "			20.75	27.00
4 x 20 "	14 "	.76 "	2 "	7-16 "			26.50	34.00

Cipher—Hencil, Fig. 1268, Iron.

Hencud, " 1268, Brass Lined.

Cipher—Hencyx, Fig. 1268, Brass Body.

Hendac, " 1268, All Brass.

In addition always specify Diameter and Length of Cylinder Body.




FIG. 1268




FIG. 1268



# GOULDS PUMP CYLINDERS OR WORKING BARRELS.

FIG. 621. DOUBLE-ACTING PUMP CYLINDER. "H" PISTON.




FIG. 621

No.	Size.	Stroke.	Capacity per Stroke.	Fitted for	Well Rod.	IRON.		BRASS LINED.	
						Cipher.	Price.	Cipher.	Price.
1	2 1/4 x 10 1/2 in.	6 in.	.10 gal.	1 1/4 in. pipe	5/8 in.	Quibe	\$10.00	Dotesm	\$12.50
4	3 x 10 1/2 "	6 "	.18 "	1 1/2 "	5/8 "	Quick	12.00	Doteto	14.75
8	4 x 10 1/2 "	6 "	.32 "	2 "	3/4 "	Quid	14.00	Doteux	17.50
8	4 x 14 "	10 "	.54 "	2 "	3/4 "	Quiet	20.00	Dotfab	25.00

FIG. 559 1/2. DEEP WELL PUMP CYLINDER WITH AIR CHAMBER. "AA" PLUNGER.



FIG. 559 1/2

No.	Size.	Stroke.	Capacity per Stroke.	Fitted for	Well Rod.	IRON.	
						Cipher.	Price.
4	3 x 12 in.	8 in.	.24 gal.	1 1/4 in. pipe	7-16 in.	Lawn	\$9.00
8	4 x 12 "	8 "	.43 "	2 "	1/2 "	Laxd	11.50

FIG 548. DEEP WELL PUMP CYLINDER WITH AIR CHAMBER. "BB" PLUNGER.



FIG. 618

Flange Attachment.

Size.	Stroke.	Capacity per Stroke.	Fitted for	Well Rod.	IRON.		BRASS BODY.	
					Cipher.	Price.	Cipher.	Price.
2 3/4 x 16 in.	9 in.	.23 gal.	1 1/4 in. pipe	7-16 in.	Laper	\$11.00	Grujag	\$20.00
3 x 16 "	9 "	.27 "	1 1/4 "	7-16 "	Larde	11.50	Gushwa	20.75
3 1/2 x 16 "	9 "	.37 "	1 1/2 "	7-16 "	Lash	12.50	Halgar	25.75
4 x 16 "	9 "	.49 "	2 "	1/2 "	Late	14.00	Halgib	30.00

All Brass Air Chamber furnished when so ordered at extra charge.

FIG. 618. BOLTED FLANGE ATTACHMENT CYLINDER.

Size.	Stroke.	Capacity per Stroke.	Fitted For	Well Rod.	IRON.		BRASS BODY, ALL BRASS PLUNGER.	
					Cipher.	Price.	Cipher.	Price.
3 x 14 in.	10 in.	.30 gals.	1 1/2 in. pipe	3/8 in.	Gruhfx	\$15.00	Gruhge	\$28.50
3 1/2 x 14 "	10 "	.41 "	2 " "	7-16 "	Hendock	17.00	Henduga	36.00
4 x 14 "	10 "	.54 "	2 " "	7-16 "	Hendodu	21.00	Hendvan	55.00

All Brass Cylinders to order.



FIG. 548

# GOULDS BRASS ARTESIAN WELL CYLINDERS.

67



FIG. 1135

With  
Ball Valves.

Fig. 1135, Goulds Brass Artesian Cylinder or Deep Well Pump, is designed for use in connection with any of our Pump Standards or Differential Working Heads. The shell or body is seamless-drawn brass tubing with cast bronze top and bottom attachments. The plunger and lower valves are bronze balls. The plunger is supplied with cup leather packings. The plunger or lower valves may be inserted or withdrawn through the connecting pipe without removing cylinder.

Wood sucker rods with forged couplings are recommended, as is also the use of valve rod to connect the plunger and sucker rod. Standard threads are on all parts and attachments. This is a very serviceable cylinder for many places where Fig. 904, pages 68 and 69, might prove too expensive.

The demand for a lower-priced cylinder, something durable but not so heavy as our standard pattern (Fig. 904) has led us to design our Fig. 1135½. The body is seamless-drawn brass tubing with cast bronze attachments. The plunger and lower valves are of the spool type, one end being supplied with leather packing. The valves being invertable, make them either metallic or leather-faced, as service requires. The plunger has cup leather packings, and together with lower valve, may be withdrawn from the cylinder without disturbing pipe connections.



FIG. 1135½

With  
Spool Valves.

FIGS. 1135 AND 1135½. SIZES, PRICES, ETC.

Inside Diameter.	Stroke.	Capacity per Stroke.	Usual Speed and Capacity per Minute.	Outside Diameter of Caps.	Con. Pipes.	Wood Sucker Rod.	FIG. 1135. Cipher.	FIG. 1135½. Cipher.	Price, Either.
1 3/4 in.	10 in.	.104 gal.	35 revs. 3.5 gals.	2 3/4 in.	2 in.	1 in.	Flewal	Townm	\$17.50
1 3/4 "	16 "	.16 "	30 " 4.8 "	2 3/4 "	2 "	1 "	Fleweb	Townoc	19.00
2 1/4 "	10 "	.172 "	35 " 6.02 "	3 1/4 "	2 1/2 "	1 1/4 "	Flewend	Townul	26.00
2 1/4 "	16 "	.275 "	30 " 8.25 "	3 1/4 "	2 1/2 "	1 1/4 "	Flewert	Townvy	28.00
2 3/4 "	10 "	.257 "	35 " 8.99 "	3 7/8 "	3 "	1 1/2 "	Flewfar	Townwt	34.00
2 3/4 "	16 "	.411 "	30 " 12.33 "	3 7/8 "	3 "	1 1/2 "	Flewgab	Towobs	36.00
3 1/4 "	10 "	.36 "	35 " 12.56 "	4 3/8 "	3 1/2 "	2 "	Flewgot	Towock	45.00
3 1/4 "	16 "	.574 "	30 " 17.22 "	4 3/8 "	3 1/2 "	2 "	Flickus	Towoda	48.00
3 3/4 "	10 "	.478 "	35 " 16.73 "	5 "	4 "	2 1/4 "	Fliclab	Towof	67.50
3 3/4 "	16 "	.764 "	30 " 22.92 "	5 "	4 "	2 1/4 "	Fliclit	Towofl	70.00
4 3/4 "	10 "	.767 "	35 " 26.84 "	6 1/4 "	5 "	3 "	Granhod	.....	120.00
4 3/4 "	16 "	1.22 "	30 " 36.81 "	6 1/4 "	5 "	3 "	Granhug	.....	127.50
5 3/4 "	10 "	1.12 "	35 " 39.20 "	7 1/4 "	6 "	3 1/2 "	Gratafe	.....	172.50
5 3/4 "	16 "	1.78 "	30 " 53.40 "	7 1/4 "	6 "	3 1/2 "	Gratibs	.....	180.00

When especially ordered we furnish with inside attachments for the smaller connecting pipes.

## GOULDS BRASS ARTESIAN DEEP WELL CYLINDER.



FIG. 904

Fig. 904, Brass Deep Well Pump, is intended for use with our Differential Working Heads, illustrated and described on pages 104 to 113 inclusive. The working barrel or cylinder is seamless drawn brass tubing with cast bronze top and bottom attachments, which are threaded for standard wrought-iron pipe connections. At the bottom a suction pipe and strainer may be attached. The plunger and check are bronze with bronze ball valves. The plunger has cup leather packings. The plunger and lower valve can be inserted or removed through the connecting pipe, which is larger diameter than the bore of cylinder. Wood sucker rods with forged couplings (see page 70) are recommended, as is also the use of valve rod to connect the plunger and sucker rods (see page 70). The valve stems, valve rod, sucker rod couplings and lower end of differential plunger are all made with standard threads.

The price includes the Fig. 904, Deep Well Pump, complete with plunger and check valves. For prices of valve rods, sucker rods and couplings, see page 70.

FIG. 904. SIZES, CAPACITIES, ETC.

Inside Diameter.	Stroke.	Capacity Per Stroke.	Usual Speed and Capacity per Minute.	DIMENSIONS.		Top and Bottom Connecting Pipes.	Square Wood Sucker Rod.	Cipher.	All Brass.
				Length Pump Chamber.	Maximum Outside Diameter Caps.				
1 3/4 in.	10 in.	.10 gal.	35 revs. 3.5 gals.	26 in.	2 7/8 in.	2 in.	1 in.	Gratic	\$17.50
1 3/4 "	16 "	.16 "	30 " 4.8 "	32 "	2 7/8 "	2 "	1 "	Whiff	19.00
2 1/4 "	10 "	.172 "	35 " 6.02 "	26 "	3 1/4 "	2 1/2 "	1 1/4 "	Dumbol	26.00
2 1/4 "	16 "	.275 "	30 " 8.25 "	32 "	3 1/2 "	2 1/2 "	1 1/4 "	Whigy	28.00
2 3/4 "	10 "	.257 "	35 " 8.99 "	26 "	3 7/8 "	3 "	1 1/2 "	Dumpuy	34.00
2 3/4 "	14 "	.359 "	30 " 8.99 "	30 "	3 7/8 "	3 "	1 1/2 "	Endmouh	36.00
2 3/4 "	16 "	.411 "	30 " 12.33 "	32 "	3 7/8 "	3 "	1 1/2 "	Whilom	36.00
2 3/4 "	24 "	.617 "	25 " 15.42 "	40 "	3 7/8 "	3 "	1 1/2 "	Whimpe	38.00
2 3/4 "	30 "	.771 "	20 " 15.42 "	46 "	3 7/8 "	3 "	1 1/2 "	Whird	40.00
2 3/4 "	36 "	.925 "	20 " 18.50 "	52 "	3 7/8 "	3 "	1 1/2 "	Gratidl	42.00



# GOULDS BRASS ARTESIAN DEEP WELL CYLINDER.

69

FIG. 904. SIZES, CAPACITIES, ETC. (Continued.)

Inside Diameter.	Stroke.	Capacity per Stroke.	Usual Speed and Capacity per Minute.	DIMENSIONS.		Top and Bottom Connecting Pipes.	Square Wood Sucker Rod.	Cipher.	All Brass.
				Length Pump Chamber.	Maximum Outside Diameter Caps.				
3 1/4 in.	10 in.	.359 gals.	35 revs. 12.50 gals.	30 in.	4 1/2 in.	3 1/2 in.	2 in.	Dumpyb	\$45.00
3 1/4 "	14 "	.503 "	30 " 15. "	34 "	4 1/2 "	3 1/2 "	2 "	Endmove	48.00
3 1/4 "	16 "	.574 "	30 " 17.22 "	36 "	4 1/2 "	3 1/2 "	2 "	Whim	48.00
3 1/4 "	24 "	.862 "	25 " 21.55 "	44 "	4 1/2 "	3 1/2 "	2 "	Whine	52.00
3 1/4 "	30 "	1.077 "	20 " 21.54 "	50 "	4 1/2 "	3 1/2 "	2 "	Whirla	55.00
3 1/4 "	36 "	1.29 "	20 " 25.80 "	56 "	4 1/2 "	3 1/2 "	2 "	Whoop	58.00
3 3/4 "	10 "	.478 "	35 " 16.73 "	34 "	5 1/8 "	4 "	2 1/4 "	Dumqeel	67.50
3 3/4 "	14 "	.669 "	30 " 20. "	38 "	5 1/8 "	4 "	2 1/4 "	Endmuba	70.00
3 3/4 "	16 "	.764 "	30 " 22.92 "	40 "	5 1/8 "	4 "	2 1/4 "	Zylonkk	70.00
3 3/4 "	24 "	1.14 "	25 " 28.50 "	48 "	5 1/8 "	4 "	2 1/4 "	Whiners	75.00
3 3/4 "	30 "	1.43 "	20 " 28.86 "	54 "	5 1/8 "	4 "	2 1/4 "	Whisk	80.00
3 3/4 "	36 "	1.721 "	20 " 34.42 "	60 "	5 1/8 "	4 "	2 1/4 "	Wick	85.00
4 1/4 "	10 "	.614 "	35 " 21.49 "	34 "	5 3/4 "	4 1/2 "	2 1/2 "	Dumqued	87.50
4 1/4 "	14 "	.859 "	30 " 25.7 "	38 "	5 3/4 "	4 1/2 "	2 1/2 "	Endmud	90.00
4 1/4 "	16 "	.982 "	30 " 29.46 "	40 "	5 3/4 "	4 1/2 "	2 1/2 "	Zylonle	90.00
4 1/4 "	24 "	1.47 "	25 " 36.75 "	48 "	5 3/4 "	4 1/2 "	2 1/2 "	Whinny	95.00
4 1/4 "	30 "	1.84 "	20 " 36.80 "	54 "	5 3/4 "	4 1/2 "	2 1/2 "	Whisto	100.00
4 1/4 "	36 "	2.211 "	20 " 44.20 "	60 "	5 3/4 "	4 1/2 "	2 1/2 "	Widen	105.00
4 3/4 "	10 "	.767 "	35 " 26.84 "	34 "	6 1/4 "	5 "	3 "	Dumquail	120.00
4 3/4 "	14 "	1.07 "	30 " 32.1 "	38 "	6 1/4 "	5 "	3 "	Endmuck	127.50
4 3/4 "	16 "	1.22 "	30 " 36.81 "	40 "	6 1/4 "	5 "	3 "	Zylonm	127.50
4 3/4 "	24 "	1.84 "	25 " 46.02 "	48 "	6 1/4 "	5 "	3 "	Whippe	135.00
4 3/4 "	30 "	2.30 "	20 " 46. "	54 "	6 1/4 "	5 "	3 "	Whita	142.50
4 3/4 "	36 "	2.76 "	20 " 55.20 "	60 "	6 1/4 "	5 "	3 "	Wield	150.00
5 3/4 "	10 "	1.12 "	35 " 39.20 "	34 "	7 1/4 "	6 "	3 1/2 "	Dubame	172.50
5 3/4 "	14 "	1.57 "	30 " 47.1 "	38 "	7 1/4 "	6 "	3 1/2 "	Endnab	180.00
5 3/4 "	16 "	1.78 "	30 " 53.70 "	40 "	7 1/4 "	6 "	3 1/2 "	Zylonna	180.00
5 3/4 "	24 "	2.69 "	25 " 67.25 "	48 "	7 1/4 "	6 "	3 1/2 "	Dufekl	195.00
5 3/4 "	30 "	3.372 "	20 " 67.44 "	54 "	7 1/4 "	6 "	3 1/2 "	Whiz	207.50
5 3/4 "	36 "	4.014 "	20 " 80.80 "	60 "	7 1/4 "	6 "	3 1/2 "	Wight	217.50
6 3/4 "	16 "	2.479 "	30 " 74.37 "	40 "	8 1/4 "	7 "	4 "	Gratiew	280.00
6 3/4 "	24 "	3.716 "	25 " 92.9 "	48 "	8 1/4 "	7 "	4 "	Gratifa	300.00
6 3/4 "	30 "	4.646 "	20 " 92.92 "	54 "	8 1/4 "	7 "	4 "	Gratigu	320.00
6 3/4 "	36 "	5.576 "	20 " 111.52 "	60 "	8 1/4 "	7 "	4 "	Gratiha	335.00
7 3/4 "	16 "	3.26 "	30 " 97.80 "	40 "	9 1/2 "	8 "	5 "	Zylonoc	425.00
7 3/4 "	24 "	4.9 "	25 " 122.50 "	48 "	9 1/2 "	8 "	5 "	Willri	450.00
7 3/4 "	30 "	6.126 "	20 " 122.52 "	54 "	9 1/2 "	8 "	5 "	Dubal	480.00
7 3/4 "	36 "	7.34 "	20 " 146.80 "	60 "	9 1/2 "	8 "	5 "	Willga	500.00
8 3/4 "	16 "	4.164 "	30 " 124.92 "	52 "	11 "	9 "	5 1/2 "	Gratijo	685.00
8 3/4 "	24 "	6.247 "	25 " 156.17 "	60 "	11 "	9 "	5 1/2 "	Groomug	725.00
8 3/4 "	30 "	7.809 "	20 " 156.18 "	66 "	11 "	9 "	5 1/2 "	Groomva	775.00
8 3/4 "	36 "	9.37 "	20 " 187.40 "	72 "	11 "	9 "	5 1/2 "	Groomwo	825.00
9 1/2 "	24 "	7.34 "	25 " 183.50 "	78 "	12 "	10 "	6 "	Mamxat	915.00
9 1/2 "	30 "	9.18 "	20 " 183.60 "	84 "	12 "	10 "	6 "	Mamwa	955.00
9 1/2 "	36 "	11.02 "	20 " 220.40 "	90 "	12 "	10 "	6 "	Mamoz	1,000.00
11 1/2 "	24 "	10.77 "	25 " 269.25 "	78 "	14 "	12 "	7 1/4 "	Mamvid	1,150.00
11 1/2 "	30 "	13.47 "	20 " 269.40 "	84 "	14 "	12 "	7 1/4 "	Mamvae	1,200.00
11 1/2 "	36 "	16.16 "	20 " 323.20 "	90 "	14 "	12 "	7 1/4 "	Mamut	1,250.00



FIG. 904

# VALVE RODS, SUCKER RODS AND COUPLINGS.

*GOULDS CONNECTING PARTS FOR SINGLE-ACTING DEEP WELL PUMPS.*

Fig. 76, Valve Rod, is a forged wrought-iron piece used to connect the deep well plunger and the sucker rod. It is comparatively much less in cross-section than the wood sucker rod, and of a length sufficient to prevent the sucker rod from entering the top end of Pump cylinder and thereby restricting the flow of water. There is a price list below. It includes all the sizes required by the deep well Pump cylinders described on the preceding pages.

Fig. 68, Sucker Rod Couplings, are of forged wrought-iron, complete and ready to be attached to sucker rods. The price list includes all the sizes used with the deep well pumping apparatus described on the preceding pages.

Fig. 77, Wood Sucker Rods, are made of the best white ash. The prices include all necessary couplings attached.

## *SQUARE WOOD SUCKER RODS, COUPLINGS AND VALVE RODS. SIZES, PRICES, ETC.*

Size Square Wood Sucker Rods.	Couplings, Valve Rods, etc., have Connecting Threads.	Inside Diameter of Deep Well Pump.	SUCKER ROD AND COUPLING, FIG. 77.		COUPLING, FIG. 68.		VALVE ROD, FIG. 76.	
			Cipher.	Price per Foot.	Cipher.	Price per Pair.	Cipher.	Price Each.
1 in.	5/8 in. pin	1 3/4 in.	Eobamt	\$0.12 1/2	Eobase	\$1.00	Eobats	\$2.50
1 1/4 "	5/8 "	2 1/4 "	Easkoty	.15	Easimel	1.25	Easjos	3.00
1 1/2 "	7/8 "	2 3/4 "	Easkub	.20	Easinab	1.50	Easjote	3.75
2 "	1 "	3 1/4 "	Easkyd	.25	Easinig	2.50	Easjots	4.75
2 1/4 "	1 1/8 "	3 3/4 "	Easlaa	.40	Easinot	3.75	Easkad	5.25
2 1/2 "	1 1/4 "	4 1/4 "	Easlact	.50	Easinul	5.00	Easkite	6 00
3 "	1 3/8 "	4 3/4 "	Easlib	.65	Easinyx	6.25	Easkog	6.75
3 1/2 "	1 1/2 "	5 3/4 "	Easligs	.90	Easjab	8.75	Easkome	7.50
5 "	2 "	7 3/4 "	Easlja	1.25	Easjik	12.50	Easkost	15.00

FIG. 68 FIG. 76

FIG. 77





FIG. 1164



FIG. 692.

# GOULDS BRASS TUBULAR WELL CYLINDERS.

TO BE ANCHORED IN PIPE AFTER WELL IS LINED.

The construction of Fig. 1164, Brass Working Barrel or Cylinder, is plainly shown in sectional engraving. It has brass body, check and plunger, with rubber valve discs and is of special service in small bore wells or where a larger cylinder is required than well lining will admit in Artesian Cylinder of the type of Figs. 904, 1135, etc. Fig. 691 is for same purpose as Fig. 1164. It has four leather plunger and bronze ball valves.

FIGS. 1164 AND 691. SIZES, PRICES, ETC.

							FIG. 1164.		FIG. 691.		
Size of Well.	Inside Diam. of Cyl.	Length Stroke.	Length Barrel.	Capacity per Stroke.	Usual Speed and Capacity per Minute.		Square Wood Sucker Rod.	With 3 Leather Plunger and Spool Poppet Valves.		With 4 Leather Plunger and Bronze Ball Valves.	
								Cipher.	Price.	Cipher.	Price.
3½ in.	3 in.	10 in.	28 in.	.306 gals.	35 revs.	10.71 gals.	2 in.	Panike	\$19.50	Peopic	\$29.00
	3 "	14 "	32 "	.428 "	30 "	12.84 "	2 "	Pawnat	20.50	Peopod	30.00
	3 "	16 "	34 "	.489 "	30 "	14.67 "	2 "	Pawned	21.50	Peopug	31.00
	3 "	24 "	42 "	.734 "	25 "	18.35 "	2 "	Pawnis	24.00	Peopwo	33.00
4 "	3½ "	10 "	28 "	.416 "	35 "	14.56 "	2½ "	Tintis	25.00	Peopxu	39.00
	3½ "	14 "	32 "	.583 "	30 "	17.49 "	2½ "	Pawnoc	26.50	Peoqua	40.50
	3½ "	16 "	34 "	.666 "	30 "	19.98 "	2½ "	Tintom	27.00	Peoqvit	41.00
	3½ "	24 "	42 "	.999 "	25 "	24.97 "	2½ "	Tintug	29.00	Peorac	43.00
4½ "	4 "	10 "	34 "	.544 "	35 "	19.04 "	2½ "	Pawnut	32.00	Peruson	48.00
	4 "	14 "	38 "	.761 "	30 "	22.83 "	2½ "	Pawnyx	33.50	Perusud	49.50
	4 "	16 "	40 "	.87 "	30 "	26.10 "	2½ "	Peoola	34.00	Peruta	50.00
	4 "	24 "	48 "	1.30 "	25 "	32.50 "	2½ "	Peopa	35.50	Perutem	51.50
5 "	4½ "	10 "	34 "	.688 "	35 "	24.08 "	3 "	Tintvl	44.00	Perutis	64.50
	4½ "	14 "	38 "	.963 "	30 "	28.89 "	3 "	Peopel	46.00	Perutiv	66.50
	4½ "	16 "	40 "	1.10 "	30 "	33.00 "	3 "	Tintwy	47.00	Perutop	67.50
	4½ "	24 "	48 "	1.65 "	25 "	41.25 "	3 "	Tinuac	50.00	Perutug	70.50
6 "	5½ "	10 "	38 "	1.02 "	35 "	35.70 "	3½ "	.....	.....	Perutvn	82.00
	5½ "	14 "	42 "	1.44 "	30 "	43.20 "	3½ "	.....	.....	Pervac	85.00
	5½ "	16 "	44 "	1.64 "	30 "	49.20 "	3½ "	.....	.....	Perves	87.00
	5½ "	24 "	52 "	2.46 "	25 "	61.50 "	3½ "	.....	.....	Pervidy	92.00
7 "	6½ "	10 "	42 "	1.43 "	35 "	50.05 "	4 "	.....	.....	Pervifs	123.00
	6½ "	14 "	46 "	2.01 "	30 "	60.30 "	4 "	.....	.....	Pervoda	127.00
	6½ "	16 "	48 "	2.29 "	30 "	68.70 "	4 "	.....	.....	Pervoco	129.00
	6½ "	24 "	56 "	3.44 "	25 "	86 "	4 "	.....	.....	Pokist	136.00
8 "	7 7/8 "	10 "	44 "	1.88 "	35 "	65.80 "	5 "	.....	.....	Pokita	198.00
	7 7/8 "	14 "	48 "	2.63 "	30 "	78.90 "	5 "	.....	.....	Pokjid	202.00
	7 7/8 "	16 "	50 "	3. "	30 "	90 "	5 "	.....	.....	Pokjifs	204.00
	7 7/8 "	24 "	58 "	4.51 "	25 "	112.75 "	5 "	.....	.....	Pokjigo	212.00



FIG. 691

## GUM PACKERS, WITH BRASS ATTACHED.

FOR LOWERING AND SEATING WORKING BARREL IN WELL.

The usual gum packer (to which suction strainer may be attached) anchors cylinder in place in pipe. Where wells are not lined to bottom, or for any reason it is desired to attach suction pipe below cylinder, this pipe should be extended to rest on bottom of well.

FIG. 692. SIZES AND PRICES.

Diameter Well Casing.	Price.
2 in.	\$1.15
2½ "	1.60
3 "	2.10
3½ "	2.95
4 "	3.40
4½ "	4.75
5 "	5.25
6 "	6.15
7 "	8.70
8 "	11.40



# 72 GOULDS CHECK AND FOOT VALVES, STRAINERS, ETC.

## CHECK VALVES.



FIG. 667




FIG. 742

Size, Inches ...	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6
Fig. 667, Plain.	\$1.50	\$1.75	\$2.00	\$2.50	\$3.00	\$4.25	\$6.00					
Galv..	2.00	2.25	2.75	3.50	4.50	6.00	10.00					
Fig. 742, Plain.	1.00	1.25	1.50	2.00	2.75	6.00	7.50	\$10.00	\$12.00			
Galv..	1.50	1.75	2.25	3.00	4.00	9.50	12.00	15.00	17.50			
Fig. 476.....									8.75	\$10.50	\$12.75	\$16.00




FIG. 476

## FOOT VALVES AND STRAINERS.




FIG. 760,  $2\frac{1}{2}$ " AND UP



FIG. 760,  $\frac{3}{4}$  TO 2"



FIG. 471



FIG. 1259




FIG. 473




FIG. 475

Size Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	8	10	12
Fig. 760, Plain.....	\$0.42	\$0.42	\$0.48	\$0.62	\$0.82	\$1.20	\$1.70	\$2.50	\$2.75		\$4.25	\$7.00	\$16.00	\$30.00	\$60.00
Galv.....	.60	.60	.75	1.00	1.45	2.00	2.70	3.90	4.25		6.50	10.00	30.00	50.00	90.00
Fig. 471, Plain.....	1.75	2.00	2.25	2.50	3.00	3.50	4.50								
Galv.....	2.50	2.75	3.00	3.50	4.50	5.50	7.00								
Fig. 1259, Plain.....			2.25	2.50	3.00										
Galv.....			3.00	3.50	4.50										
Fig. 473.....						4.75	5.75	7.00	8.50	\$10.00					
Fig. 475.....									8.50	10.00	12.00	\$15.00			



FIG 826

## STRAINERS.

Size, Inches.....	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
Fig. 826, Plain.....			\$0.80	\$1.05	\$1.70	\$1.90	\$2.40	\$3.40
Galv.....			1.10	1.60	2.60	2.90	3.80	5.00
Fig. 1232, Plain.....	\$1.25	\$1.50	2.00	2.75				
Galv.....	1.75	2.25	3.00	4.00				




FIG. 1232

# GOULDS SUCTION STRAINERS.

73

## SIZES AND PRICES.

Size, Inches.....	1	1¼	1½	2
Fig. 658, Plain, Without Brass Gauze, Each.....	\$0.18	\$0.20	\$0.24	\$0.36
Galvanized, Without Brass Gauze, Each...	.22	.24	.26	.40
Galvanized, With Brass Gauze, Each.....	.28	.32	.36	.50
Fig. 659, Plain, Without Brass Gauze, Each.....	.18	.20	.24	.36
Galvanized, Without Brass Gauze, Each...	.22	.24	.26	.40
Galvanized, With Brass Gauze, Each.....	.28	.32	.36	.50
Fig. 660, Plain, Without Brass Gauze, Each.....	.18	.20	.24	.36
Galvanized, Without Brass Gauze, Each...	.22	.24	.26	.40
Galvanized, With Brass Gauze, Each.....	.28	.32	.36	.50



# GOULDS WATER WORKS STRAINERS.

These Strainers are made of heavy pipe, galvanized after the holes are put in, and covered with heavy woven wire cloth.



FIG 141½

Size.	No. Holes per foot.	No. Square Inches of Filtering Surface per Square Foot.	List Price per Foot.
2 in.	108	51	\$2.00
2½ "	132	62	3.00
3 "	156	74	4.00
3½ "	168	79	4.50
4 "	192	126	5.00
4½ "	216	142	5.50
5 "	240	158	6.00
6 "	288	189	7.50
8 "	336	220	10.00
9 "	370	240	12.00
10 "	408	268	15.00

# COOKS SEAMLESS BRASS SLOTTED STRAINER.




FIG. 1279. SIZES, PRICES, ETC.

Inside Diameter of Well, Inches .....	2	2½	3	3½	4	4½	5	6	7	8
Length in Feet for Coarse Sand .....	4	6	6	6	8	8	8	8	10	10
Length in Feet for Fine Sand .....	8	10	12	12	14	16	16	16	16	16
Price per Foot.....	\$2.50	\$3.00	\$4.00	\$4.50	\$5.00	\$5.75	\$6.25	\$8.00	\$10.00	\$12.00





FIG. 142  
With Poppet  
Valves.

Fig. 142 represents Goulds "Eureka" Seamless Brass Tubular Well Cylinder. It can be used in rough pipe after the well is made, using the Seating Tool attached to drill rod to crowd it down to its place, and then to expand the rubber ring to hold firmly in place. Spring dog coupling prevents cylinder from turning.

FIG. 142. SIZES, PRICES, ETC. COMPLETE WITH VALVES AND SPRING DOG COUPLING.

Size of Well.	Inside Diameter.	Stroke.	Price of Cylinder Complete With 2 Leather Plunger.	Price of Cylinder Complete, With 4 Leather Plunger and Bronze Ball Valves.	Size of Well.	Inside Diameter.	Stroke.	Price of Cylinder Complete With 2 Leather Plunger.	Price of Cylinder Complete With 4 Leather Plunger and Bronze Ball Valves.
2 in.	1 <sup>13</sup> / <sub>16</sub> in.	12 in.	\$6.40	\$9.00	4 in.	3 <sup>1</sup> / <sub>2</sub> in.	24 in.	\$42.00	\$71.00
2 "	1 <sup>1</sup> / <sub>8</sub> "	16 "	7.60	10.00	4 <sup>1</sup> / <sub>2</sub> "	4 "	16 "	50.00	82.00
2 <sup>1</sup> / <sub>2</sub> "	2 <sup>1</sup> / <sub>4</sub> "	12 "	11.00	18.00	4 <sup>1</sup> / <sub>2</sub> "	4 "	24 "	58.00	90.00
2 <sup>1</sup> / <sub>2</sub> "	2 <sup>1</sup> / <sub>4</sub> "	16 "	12.50	21.00	5 "	4 <sup>1</sup> / <sub>2</sub> "	24 "	60.00	120.00
3 "	2 <sup>3</sup> / <sub>4</sub> "	12 "	15.00	25.00	5 "	4 <sup>1</sup> / <sub>2</sub> "	36 "	80.00	140.00
3 "	2 <sup>3</sup> / <sub>4</sub> "	16 "	17.00	27.00	6 "	5 <sup>1</sup> / <sub>2</sub> "	24 "	112.00	180.00
3 <sup>1</sup> / <sub>2</sub> "	3 "	12 "	30.00	46.00	6 "	5 <sup>1</sup> / <sub>2</sub> "	36 "	136.00	208.00
3 <sup>1</sup> / <sub>2</sub> "	3 "	16 "	33.00	49.00	8 "	7 <sup>7</sup> / <sub>16</sub> "	36 "	360.00	520.00
4 "	3 <sup>1</sup> / <sub>2</sub> "	12 "	33.00	62.00	8 "	7 <sup>7</sup> / <sub>16</sub> "	42 "	400.00	600.00
4 "	3 <sup>1</sup> / <sub>2</sub> "	16 "	36.00	65.00					

## SEATING TOOL "EUREKA" CYLINDER.




FIG. 143. SIZES AND PRICES.

For 2 Inch Cylinder.....	Each, \$0.60
" 2 <sup>1</sup> / <sub>2</sub> " ".....	" .90
" 3 " ".....	" 1.20
" 4 " ".....	" 2.40
" 5 " ".....	" 4.00



FIG. 142  
With Ball  
Valves.



# GOULDS TUBULAR WELL CYLINDERS.

75

Fig. 728 illustrates our polished iron Tubular Well Cylinder, made from extra heavy pipe, bored out, *fitted with driving shoe*.

FIG. 728. SIZES, PRICES.

Diameter.	WITHOUT VALVES.				WITH THREE-FOOT WELL POINT, TWO LEATHER VALVES AND COUPLING.			
	3 FEET.		4 FEET.		3 FEET.		4 FEET.	
	Black.	Galv'd.	Black.	Galv'd.	Black.	Galv'd.	Black.	Galv'd.
2 in.	\$4.00	\$4.50	\$5.00	\$5.75	\$8.50	\$9.00	\$9.50	\$10.00
2½ "	6.65	7.50	8.50	9.25	16.50	17.00	18.50	19.00
3 "	9.00	10.00	11.50	12.25	22.50	23.50	25.00	26.00
4 "	14.00	15.75	17.50	20.00	41.00	43.00	45.00	48.00

Fig. 144, Brass Lined Cylinder, is made similar to Fig. 728, the shell being bored out to insert a lining of brass tubing. The lining is forced in and swedged in position.

FIG. 144. SIZES, PRICES.

Diameter.	Length.	Without Points or Valves, but with Shoe.	With Shoe, 3-ft. "Perfect" Well Point, Four Leather Valves and Coupling.
2 in.	3 ft.	\$7.75	\$12.25
2½ "	3 "	10.50	18.00
3 "	3 "	13.00	26.00
4 "	3 "	19.00	41.50

FIG. 728

FIG. 144

# GOULDS IRON AND WOOD ROD COUPLINGS.

## COUPLINGS FOR IRON RODS.




FIG. 232 SIZES AND PRICES.


Size Rods.	Threads to the Inch.	Galvanized. Per lb.	Plain. Per lb.	Brass. Per lb.
$\frac{3}{8}$ in.	14, regular.	\$0.20	\$0.16	\$0.50
$\frac{3}{8}$ " "	16, to order.	.20	.16	.50
$\frac{3}{8}$ x $\frac{1}{8}$ " "	12 x 14	.20	.16	.50
$\frac{1}{2}$ " "	12	.20	.16	.50
$\frac{1}{2}$ " "	12	.20	.16	.50
$\frac{5}{8}$ " "	11	.20	.16	.50
$\frac{3}{4}$ " "	10	.20	.16	.50

## HEXAGON COUPLINGS FOR IRON RODS.

FIG. 233 $\frac{1}{2}$ . SIZES AND PRICES


Size Rods.	Threads to the Inch.	Galvanized. Per lb.	Plain. Per lb.	Brass. Per lb.
$\frac{3}{8}$ in.	14, regular.	\$0.20	\$0.16	\$0.50
$\frac{3}{8}$ " "	16, to order.	.20	.16	.50
$\frac{3}{8}$ x $\frac{1}{8}$ " "	12 x 14	.20	.16	.50
$\frac{1}{2}$ " "	12	.20	.16	.50
$\frac{1}{2}$ " "	12	.20	.16	.50

## PIPE ROD COUPLINGS.

FOR  $\frac{3}{8}$ -INCH PIPE.FIG. 232 $\frac{1}{2}$ 


Pipe Thread.....	Galvanized. Per lb.	Plain. Per lb.
	\$0.22	\$0.18

## REDUCER COUPLING,

FOR  $\frac{1}{2}$  AND  $\frac{3}{4}$ -INCH PIPE AND STEEL PUMP RODS.FIG. 234 $\frac{1}{2}$ 

Size Rods.	Galvanized. Per lb.	Plain. Per lb.
$\frac{3}{8}$ in.	\$0.30	\$0.25
$\frac{1}{8}$ " "	.30	.25
$\frac{3}{8}$ " "	.30	.25
$\frac{1}{8}$ " "	.30	.25

## WOOD ROD COUPLINGS. FIG. 9.



For 1 and $1\frac{1}{8}$ -in. Rod,	plain, 2 hole,	per pair,	\$0.10
" 1 " "	galv., 2 " "	" "	.14
" 1 " "	plain, 3 " "	" "	.16
" 1 " "	galv., 3 " "	" "	.20
" $1\frac{1}{4}$ " "	plain, 3 " "	" "	.20
" $1\frac{1}{4}$ " "	galv., 3 " "	" "	.24

# GOULDS BRASS JACKET DRIVE WELL POINT.

77

FIG. 524. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	No. of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
74	1 $\frac{3}{4}$ in.	24 in.	18 in.	72	\$33.00	\$40.00	\$46.00	\$52.00	\$62.00
76	1 " "	30 " "	24 " "	96	42.00	49.00	56.00	64.00	78.00
78	1 " "	36 " "	30 " "	120	51.00	59.00	66.00	76.00	94.00
80	1 " "	42 " "	36 " "	144	60.00	68.00	76.00	88.00	120.00
82	1 " "	48 " "	42 " "	168	69.00	78.00	86.00	100.00	136.00
84	1 " "	54 " "	48 " "	197	78.00	87.00	96.00	112.00	152.00
86	1 $\frac{1}{4}$ " "	20 " "	14 " "	80	30.00	36.00	42.00	50.00	64.00
90	1 $\frac{1}{4}$ " "	24 " "	18 " "	100	36.00	44.00	52.00	60.00	80.00
94	1 $\frac{1}{4}$ " "	30 " "	24 " "	130	46.00	55.00	64.00	75.00	100.00
98	1 $\frac{1}{4}$ " "	36 " "	30 " "	165	56.00	66.00	76.00	90.00	120.00
100	1 $\frac{1}{4}$ " "	42 " "	36 " "	200	66.00	77.00	88.00	105.00	140.00
102	1 $\frac{1}{4}$ " "	48 " "	42 " "	270	76.00	88.00	100.00	120.00	160.00
106	1 $\frac{1}{4}$ " "	54 " "	48 " "	260	86.00	99.00	112.00	135.00	180.00
110	1 $\frac{1}{4}$ " "	60 " "	54 " "	290	96.00	110.00	124.00	150.00	200.00
112	1 $\frac{1}{4}$ " "	66 " "	60 " "	320	106.00	121.00	136.00	165.00	220.00
114	1 $\frac{1}{4}$ " "	72 " "	66 " "	350	116.00	132.00	148.00	180.00	240.00
136	1 $\frac{1}{2}$ " "	24 " "	18 " "	120	48.00	57.00	65.00	78.00	94.00
140	1 $\frac{1}{2}$ " "	30 " "	24 " "	162	60.00	70.00	80.00	96.00	118.00
144	1 $\frac{1}{2}$ " "	36 " "	30 " "	198	72.00	84.00	95.00	114.00	142.00
146	1 $\frac{1}{2}$ " "	42 " "	36 " "	240	84.00	97.00	110.00	132.00	166.00
148	1 $\frac{1}{2}$ " "	48 " "	42 " "	276	96.00	111.00	125.00	150.00	188.00
150	1 $\frac{1}{2}$ " "	54 " "	48 " "	312	108.00	124.00	140.00	168.00	204.00
152	1 $\frac{1}{2}$ " "	60 " "	54 " "	348	120.00	138.00	155.00	186.00	228.00
154	1 $\frac{1}{2}$ " "	66 " "	60 " "	384	132.00	151.00	170.00	204.00	252.00
156	1 $\frac{1}{2}$ " "	72 " "	66 " "	420	144.00	165.00	185.00	222.00	276.00
160	2 " "	24 " "	18 " "	144	75.00	85.00	94.00	110.00	130.00
164	2 " "	30 " "	24 " "	208	90.00	101.00	112.00	132.00	160.00
168	2 " "	36 " "	30 " "	264	105.00	118.00	130.00	154.00	190.00
170	2 " "	42 " "	36 " "	288	120.00	134.00	148.00	176.00	220.00
172	2 " "	48 " "	42 " "	336	135.00	151.00	166.00	198.00	250.00
174	2 " "	54 " "	48 " "	384	150.00	167.00	184.00	220.00	280.00
176	2 " "	60 " "	54 " "	432	165.00	184.00	202.00	242.00	310.00
178	2 " "	66 " "	60 " "	480	180.00	200.00	220.00	264.00	340.00
180	2 " "	72 " "	66 " "	528	195.00	217.00	238.00	286.00	370.00
184	2 $\frac{1}{2}$ " "	36 " "	30 " "	300	180.00	205.00	230.00	260.00	300.00
188	2 $\frac{1}{2}$ " "	48 " "	42 " "	360	230.00	265.00	300.00	340.00	400.00
192	2 $\frac{1}{2}$ " "	60 " "	54 " "	420	280.00	325.00	370.00	420.00	500.00
196	3 " "	72 " "	66 " "	480	330.00	385.00	440.00	500.00	600.00
200	3 " "	36 " "	30 " "	300	240.00	275.00	310.00	340.00	410.00
204	3 " "	48 " "	42 " "	420	300.00	345.00	390.00	430.00	520.00
208	3 " "	60 " "	54 " "	540	360.00	415.00	470.00	520.00	630.00
212	3 " "	72 " "	66 " "	660	420.00	485.00	550.00	610.00	740.00
216	4 " "	48 " "	36 " "	360	480.00	520.00	560.00	600.00	700.00
220	4 " "	72 " "	60 " "	600	630.00	695.00	760.00	840.00	1,000.00
224	4 " "	96 " "	84 " "	840	780.00	870.00	960.00	1,080.00	1,300.00
228	4 " "	120 " "	108 " "	1,080	930.00	1,045.00	1,160.00	1,320.00	1,600.00

FIG. 524

Con-  
structive  
View.



# GOULDS FLUSH OR TUBULAR WELL POINTS.

FIG. 662. SIZES, PRICES, ETC.

Trade No.	Dia. Pipe.	Length of Pipe.	Length of Jacket.	No. of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
73	1 in.	30 in.	18 in.	72	\$34.00	\$40.00	\$45.00	\$50.00	\$55.00
75	1 "	36 "	18 "	72	38.00	44.00	50.00	56.00	66.00
75½	1 "	36 "	24 "	96	43.00	49.00	55.00	62.00	77.00
77	1 "	42 "	24 "	96	47.00	54.00	60.00	68.00	82.00
77½	1 "	42 "	30 "	120	52.00	59.00	65.00	74.00	93.00
79	1 "	48 "	30 "	120	56.00	63.00	70.00	80.00	98.00
79½	1 "	48 "	36 "	144	61.00	68.00	75.00	86.00	109.00
81	1 "	54 "	36 "	144	65.00	73.00	80.00	92.00	114.00
81½	1 "	54 "	42 "	144	70.00	78.00	85.00	98.00	125.00
83	1 "	60 "	42 "	168	74.00	82.00	90.00	104.00	130.00
116	1¼ "	24 "	18 "	100	36.00	44.00	52.00	60.00	80.00
117	1¼ "	30 "	18 "	100	41.00	49.00	57.00	65.00	85.00
117½	1¼ "	30 "	24 "	130	46.00	55.00	64.00	75.00	100.00
118	1¼ "	36 "	24 "	130	51.00	60.00	68.00	80.00	105.00
119	1¼ "	42 "	24 "	130	56.00	65.00	73.00	85.00	110.00
120	1¼ "	48 "	24 "	130	61.00	70.00	78.00	90.00	115.00
121	1¼ "	36 "	30 "	165	56.00	66.00	76.00	90.00	120.00
122	1¼ "	42 "	30 "	165	61.00	71.00	80.00	95.00	125.00
123	1¼ "	48 "	30 "	165	66.00	76.00	85.00	100.00	130.00
124	1¼ "	54 "	30 "	165	71.00	81.00	91.00	105.00	135.00
125	1¼ "	42 "	36 "	200	66.00	77.00	88.00	105.00	140.00
126	1¼ "	48 "	36 "	200	71.00	82.00	92.00	110.00	145.00
127	1¼ "	54 "	36 "	200	76.00	87.00	97.00	115.00	150.00
128	1¼ "	60 "	36 "	200	81.00	92.00	102.00	120.00	155.00
129	1¼ "	48 "	42 "	230	76.00	87.00	97.00	115.00	150.00
130	1¼ "	54 "	42 "	230	81.00	92.00	104.00	125.00	165.00
130½	1¼ "	60 "	42 "	230	86.00	98.00	110.00	130.00	170.00
131	1¼ "	66 "	42 "	230	91.00	103.00	115.00	135.00	175.00
132	1½ "	60 "	48 "	260	91.00	104.00	116.00	140.00	180.00
133	1½ "	66 "	48 "	260	96.00	109.00	122.00	145.00	185.00
135	1½ "	72 "	48 "	260	101.00	114.00	127.00	150.00	190.00
137	1½ "	54 "	48 "	260	86.00	98.00	110.00	130.00	170.00
143	1¼ "	60 "	54 "	280	96.00	109.00	122.00	145.00	185.00
149	1½ "	66 "	60 "	300	106.00	119.00	132.00	155.00	195.00
151	1½ "	72 "	66 "	320	116.00	129.00	142.00	165.00	205.00

## OPEN END OR WELL POINT EXTENSIONS.

FIG. 524½. SIZES, PRICES, ETC.

Trade No.	Dia. Pipe.	Length of Pipe.	Length of Jacket.	No. of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
95	1¼ in.	30 in.	24 in.	126	\$46.00	\$55.00	\$64.00	\$75.00	\$100.00
99	1¼ "	36 "	30 "	165	56.00	66.00	76.00	90.00	120.00
101	1½ "	42 "	36 "	200	66.00	77.00	88.00	105.00	140.00
145	1½ "	36 "	30 "	198	72.00	84.00	95.00	114.00	142.00
147	1½ "	42 "	36 "	240	84.00	97.00	110.00	132.00	166.00
169	2 "	36 "	30 "	250	105.00	118.00	130.00	154.00	190.00
171	2 "	42 "	36 "	288	120.00	134.00	148.00	176.00	220.00
173	2 "	48 "	42 "	300	135.00	151.00	166.00	198.00	250.00

Can furnish any size at list of Fig. 524, page 77.




FIG. 662



FIG. 524½

# GOULDS WASHER DRIVE WELL POINTS.

79

These points are made of Galvanized Iron Pipe, bored and countersunk. Each hole is covered with gauze, held in its place by a brass washer expanded to fill the hole.

FIG. 661. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	No. of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
300	1 1/4 in.	20 in.	50	\$30.00	\$36.00	\$42.00	\$50.00	\$64.00
301	1 1/4 "	2 ft.	60	36.00	44.00	52.00	60.00	80.00
302	1 1/4 "	2 1/2 "	80	46.00	55.00	64.00	75.00	100.00
303	1 1/4 "	3 "	100	56.00	66.00	76.00	90.00	120.00
304	1 1/4 "	3 1/2 "	120	66.00	77.00	88.00	105.00	140.00
305	1 1/4 "	4 "	140	76.00	88.00	100.00	120.00	160.00
320	1 1/2 "	2 "	80	48.00	57.00	65.00	78.00	94.00
321	1 1/2 "	2 1/2 "	110	60.00	70.00	80.00	96.00	118.00
322	1 1/2 "	3 "	130	72.00	84.00	95.00	114.00	142.00
323	1 1/2 "	3 1/2 "	150	84.00	97.00	110.00	132.00	160.00
324	2 "	2 1/2 "	140	90.00	101.00	112.00	132.00	160.00
325	2 "	3 "	170	105.00	118.00	130.00	154.00	190.00
326	2 "	3 1/2 "	220	120.00	134.00	148.00	176.00	220.00

Can furnish any size. Fig. 661 is at list of Fig. 524, page 77.

## WELL POINTS FOR WATER WORKS.




FIG. 141

These prices are for Points, open end, or with plugs, as ordered, and are covered with the different mesh gauzes indicated, also with brass jacket.

FIG. 141. SIZES, PRICES, ETC.

Diameter Pipe, Black or Galvanized.	No. 60 Gauze, per Foot.	No. 70 Gauze, per Foot.	No. 80 Gauze, per Foot.	No. 90 Gauze, per Foot.	No. 100 Gauze, per Foot.
5 in.	\$5.00	\$5.75	\$6.50	\$7.25	\$8.00
6 "	5.80	6.50	7.25	8.00	9.00
7 "	7.00	7.75	8.50	9.25	10.50
8 "	8.50	9.25	10.00	11.00	12.00
10 "	13.00	14.00	15.25	16.50	18.00

For list on 4-inch or smaller, see Brass Jacket Points.



## GOULDS TUBULAR WELL TOOLS.

BRASS SAND BUCKET  
OR PUMP.

## FIG. 33. PRICE LIST.

Fitted for  $\frac{1}{2}$  in. gas pipe, for  
 $1\frac{1}{4}$  in. Drive Well Point, . . \$3.00  
 Fitted for  $\frac{1}{2}$  in. gas pipe, for  
 $1\frac{1}{2}$  in. Drive Well Point, . . 3.50

FIG. 33

## PRICES FOR FIGS. 13, 15 AND 32.

2	inch.....	\$6.00
2 $\frac{1}{2}$	".....	6.50
3	".....	7.00
3 $\frac{1}{2}$	".....	8.50
4	".....	10.00
4 $\frac{1}{2}$	".....	15.00
5	".....	20.00
6	".....	25.00

We make Augers to go inside 2-inch pipe when ordered.

MALLEABLE  
DRIVE CAP.

For  $1\frac{1}{4}$  in. pipe. 20c. each  
 "  $1\frac{1}{2}$  " " 24c. "  
 " 2 " " 44c. "

FIG. 510

## STEEL DRIVE HEADS—Solid.

For $1\frac{1}{4}$ in. pipe. each.....	\$1.50
" $1\frac{1}{2}$ " " ".....	2.00
" 2 " " ".....	2.50
" $2\frac{1}{2}$ " " ".....	6.00
" 3 " " ".....	9.00
" 4 " " ".....	16.00



FIG. 181

Sand  
and  
Clay  
Auger.Clay  
Auger.Earth and  
Sand Boring  
Auger

FIG. 13 FIG. 15 FIG. 32

## SAND PUMP AND DRILL COMBINED.

## FIG. 729. PRICE LIST.




FIG. 729

Gas Pipe Thread Connection.	Actual Size of Bit.	Price.
1 inch.....	1 $\frac{3}{4}$ inches.	\$1.25
1 ".....	2 ".....	2.00
1 ".....	2 $\frac{1}{2}$ ".....	3.00
1 $\frac{1}{4}$ ".....	3 ".....	4.00

Fig. 219. Sand Catcher,  $1\frac{1}{4}$  inch, each.....\$2.00

Sand  
Catcher.

FIG. 219





FIG. 656




FIG. 657.




FIG. 172 1/2

FIGS. 656, 657, 172 1/2, 1265. WIND MILL TANK VALVES.

Size .....	3/4 in.		1 in.		1 1/4 in.		1 1/2 in.		2 in.		2 1/2 in.		3 in.	
	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
Fig. 656 .....	Virelay	\$0.60	Virge	\$0.60	Virgo	\$0.75	Serfing	\$0.90	Grafting	\$1.25				
Fig. 657 .....	Virent	.80	Virgin	.80	Virile	1.00	Grubber	1.25	Kidding	1.50				
Fig. 172 1/2 .....									Dotgond	5.00	Dotgost	\$7.50	Dotgoud	\$10.00
Fig. 1265 .....	Scenega	1.25	Scenehi	1.38	Sceneit	1.50	Sceneju	3.00	Sceneko	5.00	Scenello	7.50	Scenemy	10.00




FIG. 407

FIG. 407. GOOSE-NECK OR SPOUT-SIZES, PRICES, ETC.

Butt, 3/4-in. Pipe. Spout, 3/4-in. Hose.		Butt 1-in. Pipe. Spout, 1-in. Hose.		Butt, 1 1/4-in. Pipe. Spout, 1 1/4-in. Hose.		Butt, 1 1/2-in. Pipe. Spout, 1 1/2-in. Hose.		Butt, 2-in. Pipe. Spout, 2-in. Hose.	
Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
Gladdest	\$0.50	Gauzy	\$0.60	Gap	\$0.90	Gouty	\$1.25	Grooming	\$1.50




FIG. 1265

FIG. 350 AIR CHAMBER-FOR USE EITHER ON SUCTION OR DISCHARGE. SIZES, PRICES, ETC.

Size of Pipe.....	3/4-in.	1-in.	1 1/4-in.	1 1/2-in.	2-in.	2 1/2-in.	3-in.	4-in.
Price .....	\$1.75	\$2.00	\$2.75	\$3.00	\$5.00	\$10.00	\$12.50	\$20.00



FIG. 350




FIG. 1067  
No. 1, \$2.00 No. 2, \$3.00

Fig. 1067 is Brass-fitted Compression Cock. Fig. 490 is Brass-fitted Plug Cock.

No. 1 Cock of either style has coupling nut which fits air chambers of our 2, 2 1/2, and 3-inch House Force Pumps: Also Figs. 401, 402, 413 Nose of No. 1 Cocks is threaded for 1-inch hose coupling.

No. 2 Cock of either style has coupling nut which fits air chamber of our 3 1/2 and larger House Force Pumps: Also Figs. 237 and 593. Nose of No. 2 Cock is cut 1 1/2-in. iron pipe thread. Nut with hose tube for either 1 or 1 1/4-in. hose, furnished *if ordered* at extra price.

Fig. 1253, Water Conductor, has swivelled bail and is regularly tapped for 1 1/4-in. pipe; fitted 1 1/2-in. to order, price, \$1.00.



FIG. 1253




FIG. 490  
No. 1.....\$2.00  
" 2..... 3.00

COPPER TANK FLOAT.


Can be bolted to a lever attached to Tank Valve to open and close automatically.

No. 4, 12 x 3 inches, \$1.50 each.  
" 6, 9 1/2 x 2 3/4 " 1.10 "



FIG. 159


# GOULDS "SYPHON" WIND MILL FORCE PUMP.

FIG 514 $\frac{1}{2}$ 

In our "Syphon" Working Barrel the water enters the reservoir, or outer chamber, at suction opening, filling it with water to that point. In this body of water the brass-lined working cylinder, provided with brass plunger, etc., is suspended, leaving suitable space between inner and outer walls and at bottom, the effect of which is that Pump is always primed and ready for use. Plunger and rod may be drawn through top of air chamber without breaking any pipe connections. Wind mill slide included with Pump at prices given below. Forked wood rod coupling or harp connection furnished when ordered at \$1.00 extra list on sizes up to and including 4-inch, and \$2.50 extra list on larger sizes.

FIG. 514 $\frac{1}{2}$ . SIZES, PRICES, ETC.

Dia. Inner Cyl.	Suction and Discharge.	8-INCH STROKE.			10-INCH STROKE.			12-INCH STROKE.		
		Capacity per Stroke.	Cipher.	Brass- Lined.	Capacity per Stroke.	Cipher.	Brass- Lined.	Capacity per Stroke.	Cipher.	Brass- Lined.
2 in.	1 $\frac{1}{4}$ in. pipe	.11 gal.	Basem	\$25.00						
2 $\frac{1}{2}$ "	1 $\frac{1}{2}$ "	.17 "	Basidi	25.00	.21 gal.	Lamfik	\$27.50	.25 gal.	Lamfud	\$30.00
3 "	1 $\frac{1}{2}$ "	.24 "	Basket	27.50	.30 "	Beardl	30.00	.37 "	Binder	32.50
3 $\frac{1}{2}$ "	2 "				.42 "	Bearer	37.50	.50 "	Binding	40.00
4 "	2 "				.54 "	Bearh	42.50	.65 "	Bindwe	45.00
4 $\frac{1}{2}$ "	2 $\frac{1}{2}$ "				.69 "	Bearho	52.50	.83 "	Binerva	55.00
5 "	2 $\frac{1}{2}$ "				.85 "	Bearing	62.50	1.02 "	Binnac	65.00
6 "	3 "				1.22 "	Befall	82.50	1.47 "	Befit	85.00

FIG 776 $\frac{1}{2}$ 

## GOULDS "SYPHON" WELL FORCE PUMP.

Fig. 776 $\frac{1}{2}$  represents "Syphon" Working Barrel described above, arranged with wind mill top and lever, for manual or wind power. Plunger and rod may be drawn through top of air chamber without breaking any pipe connections. Prices given below include spout. Wind mill slide only sent when specially ordered. Forked and harp connection furnished when so ordered at prices given above.

FIG. 776 $\frac{1}{2}$ . SIZES, PRICES, ETC.

Diameter Inner Cylinder.	Suction and Discharge.	*Lift and Force.	6-INCH STROKE.			10-INCH STROKE.		
			Capacity per Stroke.	Cipher.	Brass- Lined.	Capacity per Stroke.	Cipher.	Brass- Lined.
2 in.	1 $\frac{1}{4}$ in. pipe	100 ft.	.08 gal.	Lamfyl	\$28.50			
2 $\frac{1}{2}$ "	1 $\frac{1}{2}$ "	100 "	.13 "	Lamgag	28.50	.21 gal.	Laneck	\$31.00
3 "	1 $\frac{1}{2}$ "	100 "	.18 "	Laneba	31.00	.30 "	Lanedu	33.50
3 $\frac{1}{2}$ "	2 "	100 "				.42 "	Laneel	42.50
4 "	2 "	100 "				.54 "	Larkob	47.50
4 $\frac{1}{2}$ "	2 $\frac{1}{2}$ "	75 "				.69 "	Larkock	60.00
5 "	2 $\frac{1}{2}$ "	75 "				.85 "	Larkoda	70.00
6 "	3 "	75 "				1.22 "	Larkofa	90.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# GOULDS "SYPHON" WELL FORCE PUMP.

83

FOR MACHINE POWER.

Fig. 1091 is almost identical with our well known Fig. 514½, page 82, except that it is provided with pitman and guide, that it may be operated by any power.

In this Pump the water enters the reservoir, or outer chamber, at suction opening, located above valves, and fills it with water to that point. In this body of water, a brass inner cylinder, provided with brass plunger, etc., is suspended, leaving suitable space between inner and outer walls, the effect of which is that the Pump is always primed.

Plunger Rod may be drawn through top of Air Chamber, without breaking any pipe connections.

FIG. 1091. SIZES, PRICES, ETC.

Dia. Inner Cyl.	Suction and Discharge.	8-INCH STROKE.			10-INCH STROKE.			12-INCH STROKE.		
		Capacity per Stroke.	Cipher.	Brass-Lined.	Capacity per Stroke.	Cipher.	Brass-Lined.	Capacity per Stroke.	Cipher.	Brass-Lined.
2 in.	1¼ in. pipe.	.11 gal.	Gruff	\$35.00						
2½ "	1½ "	.17 "	Grufga	35.00						
3 "	1½ "	.24 "	Grufho	37.50	.30 gal.	Grufju	\$40.00			
3½ "	2 "				.42 "	Grufky	47.50	.50 gal.	Grugcan	\$50.00
4 "	2 "				.54 "	Gruga	57.50	.65 "	Grugcib	60 00
4½ "	2½ "				.69 "	Grugba	67.50	.83 "	Grugdo	70 00
5 "	2½ "				.85 "	Grugin	77.50	1.02 "	Grugful	80.00
5½ "	3 "				1.22 "	Grugbod	97.50	1.47 "	Gruggad	100.00




FIG 1091

# GOULDS "VIM" SYPHON FORCE PUMP.

Fig. 1192 shows our new pattern "Vim" Syphon Force Pump for wind mill or other power. Suction opening is at top of outer reservoir and consequently this reservoir is always filled with water. In this reservoir hangs the Brass Working Cylinder. This insures the pump being always primed with valves wet and ready for action. Working Cylinder, plunger and valves can be removed without breaking pipe connection. Cylinder Seamless Brass. All Brass Plunger. Lower valve cage and seat brass. Brass-cased rod and wind mill slide. When wanted with malleable forked rod (instead of wind mill slide), we add \$1.50 extra to list prices.

FIG. 1192. SIZES, PRICES, ETC.

Dia. Cyl.	Suction and Discharge.	8-INCH STROKE.			12-INCH STROKE.		
		Capacity per Stroke.	Cipher.	Brass Cyl.	Capacity per Stroke.	Cipher.	Brass Cyl.
2½ in.	1½ in. pipe.	.17 gal.	Quieul	\$18.50	.26 gal.	Quigeg	\$20.00
3 "	1½ "	.24 "	Quiifa	21.00	.37 "	Quihat	22.50
3½ "	2 "	.33 "	Quifel	25.00	.50 "	Quihen	27.50
4 "	2 "	.43 "	Quigas	30.00	.65 "	Quihid	32.00




FIG. 1192



# GOULDS WELL FORCE PUMP.

WITH OSCILLATING STUB FOR WIND OR OTHER POWER.

Fig. 266 shows a complete and cheap Force Pump, to be operated by wind mill or other power. May be used in buildings or placed in dug wells out of reach of frost, or in warm climates used above any style of well. Should not be placed more than 25 feet above water supply. Furnished with brackets and plank for attaching to beam, etc.

Fitted for wrought-iron pipe as given in table. unless otherwise ordered. Furnished with Check Valve instead of Air Chamber \$2 00 less list. Forked Wood-Rod Coupling, when required, \$1.00 extra list. Pump, less Plank, 50c less list.




FIG 266

FIG. 266. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Well Rod.	*Lift and Force.	IRON.		BRASS-LINED.	
								Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.10 gal.	1 in. pipe	1 in. pipe	5/8 in.	75 ft.	Clew	\$11.50	Larkugs	\$14.00
2	2 1/2 "	7 "	.15 "	1 1/4 "	1 1/4 "	5/8 "	75 "	Cliff	12.00	Larkwon	14.50
4	3 "	7 "	.21 "	1 1/4 "	1 1/4 "	5/8 "	75 "	Climb	12.50	Landefs	16.00
6	3 1/2 "	7 "	.29 "	1 1/2 "	1 1/2 "	5/8 "	50 "	Climber	19.00	Landego	23.50
8	4 "	7 "	.38 "	2 "	1 1/2 "	5/8 "	50 "	Climbing	21.00	Landib	26.00

\*Depth of wells in which Cylinders may be operated, or total lift and force from water to point of discharge, Pump not more than 25 feet above water.

# GOULDS DOUBLE-ACTING WELL FORCE PUMP.

FOR WIND MILL OR OTHER POWER.

Fig. 448 shows a Double-Acting Force Pump, with brackets, by many preferred for use with wind mills. The piston rod can be made with a stub end to *weld* on an additional rod or with a malleable coupling for *screwing* on the rod, as ordered. The smaller sizes are preferably employed, on account of the small degree of power requisite, while the quantity of water obtained is equal to the capacity of a single-acting cylinder of much greater size.




FIG. 448

FIG. 448. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	Well Rod.	*Lift and Force.	IRON.		BRASS-LINED.	
								Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.19 gal.	1 1/4 in. pipe	1 1/4 in. pipe	1/2 in.	60 ft.	Foxy	\$15.00	Landifi	\$17.50
2	2 1/2 "	7 "	.29 "	1 1/4 "	1 1/4 "	1/2 "	60 "	Frame	15.50	Landols	18.00
4	3 "	7 "	.43 "	1 1/2 "	1 1/4 "	1/2 "	60 "	Fray	19.00	Landubs	22.50
6	3 1/2 "	7 "	.58 "	1 1/2 "	1 1/2 "	5/8 "	45 "	Freak	22.00	Leabac	26.50
8	4 "	7 "	.76 "	2 "	2 "	3/4 "	45 "	Fritted	38.00	Leabid	43.00

\*Depth of wells in which Cylinders may be operated, or total lift and force from water to point of discharge, Pump not more than 25 feet above water.

# GOULDS "PACIFIC" WELL FORCE PUMP.

85

FOR HAND AND WIND MILL.




FIG. 674

Fig. 674 represents our "Pacific" Well Force Pump on base, for hand or wind mill use. The Pumps have been upon the market for some years and are preferred above all others in certain localities. They are made in the very best manner and combine strength with graceful proportions. All are made with brass cased rods, brass stuffing box and valve seats, and provided with new style compression cock spout. Pump cylinder may be emptied of water by raising lever and tripping valve.

All Brass Pumps furnished to order.

Fig. 601 represents our "Pacific" Well Force Pump with brackets, mounted on plank, for hand or wind mill use.

It is a strong and efficient Pump, having a brass cased rod and brass stuffing box and valve seats. Provided with new style compression cock spout. Pump cylinder may be emptied of water by raising lever and tripping valve.

All brass Pumps furnished to order. Furnished without plank at a reduction of 50 cents list.




FIG. 601

FIG. 674. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		IRON.		BRASS-LINED.		BRASS CYLINDER.	
					Top of Air Chamber.	Spout.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	6½ in.	.14 gal.	1¼ in. pipe	1¼ in.	1 in. hose.	Robe	\$14.50	Granfuf	\$17.00	Robin	\$20.00
4	3 " "	6½ " "	.20 " "	1¼ " "	1¼ " "	1 " "	Roded	16.50	Granfylo	19.00	Roely	21.50
6	3½ " "	6½ " "	.27 " "	1½ " "	1½ " "	1 " "	Rollat	24.00	Graga	27.50	Romp	32.00
8	4 " "	6½ " "	.35 " "	2 " "	1½ " "	1 " "	Roofed	25.50	Grangis	30.50	Rooki	38.50

FIG. 601. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		IRON.		BRASS-LINED.		BRASS CYLINDER.	
					Top of Air Chamber.	Spout.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	6½ in.	.14 gal.	1¼ in. pipe	1¼ in.	1 in. hose	Life	\$14.50	Grangoa	\$17.00	Lifted	\$20 00
4	3 " "	6½ " "	.20 " "	1¼ " "	1¼ " "	1 " "	Limb	16.50	Grangub	19.00	Limel	21.50
6	3½ " "	6½ " "	.27 " "	1½ " "	1½ " "	1 " "	Liner	24.00	Granhab	27.50	Linked	32.00
8	4 " "	6½ " "	.35 " "	2 " "	1½ " "	1 " "	Lion	25.50	Granhij	30.50	Lisped	38.50

# 86 GOULDS "ATLANTIC" DOUBLE-ACTING FORCE PUMP.

FOR HAND, WIND MILL OR OTHER POWER.




FIG. 1216

Fig. 1216 shows our new "Atlantic" Double-Acting Force Pump with lever and cock spout. Valves are brass, leather-faced and accessible by removing valve box cover. The Piston is double cup leather packed. Pump is strong, compact and of neat design, capable of throwing solid stream to a great height. Discharge may be made at top of air chamber if so desired. Drip plug is provided for emptying Pump in cold weather. Suction and discharge is fitted for iron pipe as specified. Nose of cock screwed for hose coupling.

Fig. 1217 shows our new "Atlantic" Double-Acting Force Pump mounted on plank. It may be operated by hand or connected to Wind Mill or other power as occasion requires. Its construction is essential with that of Fig. 1216, described above and the same remarks will apply to both, Prices include plank.




FIG. 1217

Furnished without plank at 50 cents less list.

FIG. 1216. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Cap per Rev.	Suction.	Discharges.		*Lift and Force.	IRON.		BRASS-LINED.	
					Top of Air Chamber.	Cock Spout.		Cipher.	Price.	Cipher.	Price.
4	3 in.	{ 6 in. Hand } 8 " Mill }	.49	1½ in.	1½ in. pipe	1 in. hose	75	Gageul	\$30.00	Galler	\$33.50
6	3½ "		.67	2 "	2 "	1¼ "	50	Gageva	37.50	Gallest	42.50
8	4 "		.87	2 "	2 "	1¼ "	50	Gagfly	45.00	Gallic	50.00

FIG. 1217. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Cap per Rev.	Suction.	Discharges.		*Lift and Force.	IRON.		BRASS-LINED.	
					Top of Air Chamber.	Cock Spout.		Cipher.	Price.	Cipher.	Price.
4	3 in.	{ 6 in. Hand } 8 " Mill }	.49	1½ in.	1½ in. pipe	1 in. hose	75	Gallida	\$30.00	Gavale	\$33.50
6	3½ "		.67	2 "	2 "	1 "	50	Gall'o	37.50	Gavame	42.50
8	4 "		.87	2 "	2 "	1 "	50	Gavab	45.00	Gavana	50.00

\* Total lift and force from water to point of discharge, Pump not more than 25 feet above water.



# GOULDS "ATLANTIC" DOUBLE-ACTING FORCE PUMPS. 87

FOR MANUAL, WIND MILL OR OTHER POWER.

Figs. 1211 and 1212 represent a new style of Double-Acting Force Pumps, every detail of which has been carefully considered in the design. We offer them with iron or brass-lined cylinder. The valves are brass, leather-faced and have brass seats which, combined, make the best construction. Valves are accessible by removing valve box cover. The Piston is packed with double cup leathers. The action of these Pumps is easy, the discharge uniform and constant, making them very effective and durable.

Fig. 1211 has long wood lever for hand use but can be arranged for power by attaching special forked rod which is furnished with any size Pump at \$1.50 extra list.

Fig. 1212 is the same Pump which we build for power, only arranged with pitman and stub end for welding to connecting rod. We supply special forked rod with this Pump at an extra list of \$1.50.




FIG. 1211




FIG. 1212

FIG. 1211. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
4	3 in.	10 in. for 8 in. stroke mill.	.49 gal.	1½ in. pipe	1½ in. pipe	75 ft.	Frecob	\$40.00	Frecody	\$43.50
6	3½ in.	10 " 8 " "	.67 "	2 " "	2 " "	50 "	Fusuba	50.00	Fusuef	55.00
8	4 "	10 " 8 " "	.87 "	2 " "	2 " "	50 "	Fusudu	60.00	Fusufo	65.00

FIG. 1212. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED CYLINDER.	
							Cipher.	Price.	Cipher.	Price.
4	3 in.	10 in. for 8 in. stroke mill.	.49 gal.	1½ in. pipe	1½ in. pipe	75 ft.	Fusugas	\$40.00	Fusujag	\$43.50
6	3½ in.	10 " 8 " "	.67 "	2 " "	2 " "	50 "	Fusugib	50.00	Gagest	55.00
8	4 "	10 " 8 " "	.87 "	2 " "	2 " "	50 "	Fusuho	60.00	Gageta	65.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

# "STAR" DOUBLE ACTING RAILROAD FORCE PUMPS.

FOR HAND OR MACHINE POWER.




FIG. 338

Figs. 338 and 339 represent our famous "Star" Double-Acting Railroad Force Pumps, specially designed for the use of distilleries, mills, railroad companies, etc. Briefly described: The Pump is exceptionally heavy and strong in casting, the plunger rod and solid-cross head are of bronze, while the valves (four in number) with their seats, are of the same metal, and grouped under valve cover in front. These valves are of a new type, calculated to develop greatest efficiency, and rubber faced, rendering them perfectly tight and relieving Pump of all pounding.

Fig. 338 is designed to be worked by wood levers, but can be arranged for power as well by substituting special Strap Rod for regular straps, at \$5.00 extra list.

Fig. 339 is the same Pump, which we build in larger sizes, with stub end for welding to connecting rod, driven by any power, as steam or wind, working head, counter shaft, walking beam, etc., or with Forked Rod, at \$5.00 extra list.




FIG. 339.

Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED CYL.	
						Cipher.	Price.	Cipher.	Price.
3 in.	8 in. for 6 in. stroke mill.	.49 gal.	1½ in. pipe.	1½ in. pipe.	75 ft.	Ebon	\$65.00	Edge	\$72.00
4 "	8 " 6 " "	.87 "	2 "	2 "	75 "	Echo	75.00	Edict	82.00
5 "	8 " 6 " "	1.36 "	2½ "	2½ "	75 "	Eddy	90.00	Edify	97.00
6 "	8 " 6 " "	1.96 "	3 "	3 "	75 "	Edend	120.00	Edited	130.00

FIG. 339. SIZES, PRICES, ETC.

Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED CYL.	
						Cipher.	Price.	Cipher.	Price.
3 in.	10 in. for 8 in. stroke mill.	.49 gal.	1½ in. pipe.	1½ in. pipe.	100 ft.	Educt	\$65.00	Elder	\$72.00
3 "	14 " 12 " "	.73 "	1½ "	1½ "	100 "	Eject	78.00	Ella	90.00
4 "	10 " 8 " "	.87 "	2 "	2 "	100 "	Eel	75.00	Elect	82.00
4 "	12 " 10 " "	1.09 "	2 "	2 "	100 "	Eidly	95.00	Elking	105.00
4 "	14 " 12 " "	1.31 "	2 "	2 "	100 "	Ekela	101.00	Elms	115.00
5 "	10 " 8 " "	1.36 "	2½ "	2½ "	100 "	Egg	90.00	Elfed	97.00
5 "	14 " 12 " "	2.04 "	2½ "	2½ "	100 "	Eland	120.00	Elogy	135.00
5 "	17 " 15 " "	2.55 "	2½ "	2½ "	100 "	Elate	135.00	Elong	150.00
5 "	20 " 18 " "	3.06 "	2½ "	2½ "	100 "	Elapse	170.00	Elastic	180.00
6 "	10 " 8 " "	1.96 "	3 "	3 "	100 "	Eider	120.00	Elite	130.00
6 "	16 " 14 " "	3.43 "	3 "	3 "	100 "	Elbow	175.00	Elope	190.00
6 "	20 " 18 " "	4.41 "	3 "	3 "	100 "	Eldate	225.00	Elsen	250.00
7 "	14 " 12 " "	4.00 "	4 "	4 "	75 "	Elderly	260.00	Eldern	285.00
7 "	16 " 14 " "	4.66 "	4 "	4 "	75 "	Elding	275.00	Eldorad	300.00
7 "	20 " 18 " "	6.00 "	4 "	4 "	75 "	Elapsot	300.00	Elapsut	330.00
8 "	14 " 12 " "	5.22 "	5 "	5 "	75 "	Electio	300.00	Electro	330.00
8 "	17 " 15 " "	6.53 "	5 "	5 "	75 "	Electri	340.00	Electiv	375.00
8 "	20 " 18 " "	7.82 "	5 "	5 "	75 "	Elapsub	375.00	Elapsyd	415.00

\*Total lift and force from supply to point of delivery. Pump not more than 25 feet above water.



# GOULDS WIND MILL IRRIGATION CYLINDER.

89

Fig. 1064 is largely used with Wind Mills and other power to raise water in large quantities for irrigation or drainage. Double hinged valve in plunger affords ample water way. Lower valve is of same type. We offer in Regular Brass-Lined and Special Brass-Lined, the latter having an extra heavy lining and plunger with brass follower 3 inches long, extra heavy brass valve weights and brass cross bar and bolts. Unless otherwise ordered we fit both suction and discharge for wrought-iron pipe as per table, but when especially ordered can fit top for spiral riveted pipe of same diameter as cylinder and through which the plunger can be withdrawn.

FIG. 1064. SIZES, PRICES, ETC.

Diameter and Stroke.	Capacity per Stroke.	Suction and Discharge.	Wood Rod.	*Lift and Force.	REGULAR BRASS-LINED.		SPECIAL BRASS-LINED.	
					Cipher.	Price.	Cipher.	Price.
6 x 15 in.	1.84 gal.	3 in. pipe	2 in.	100 ft.	Numgo	\$26.00	Iteno	\$40.00
7 x 15 "	2.49 "	4 "	2 "	100 "	Numhen	31.00	Ilenode	50.00
8 x 15 "	3.26 "	4 "	2 "	75 "	Ondlaw	37.50	Numfyx	60.00
10 x 15 "	5.10 "	5 "	2½ "	50 "	Ondleo	52.50	Paiperl	90.00
12 x 15 "	7.35 "	6 "	3 "	50 "	Ondlom	75.00	Paipida	120.00

\*Depth of Wells in which Cylinders may be operated or total lift and force from surface of water.




FIG. 1064

## GOULDS WIND MILL IRRIGATION PUMPS.

Figs. 1043 and 1043½ have special application for pumping water from shallow wells or creeks, for irrigating, etc. They are self-contained, have Brass-Lined Cylinder and leather-faced valves, readily accessible. If half-hose coupling for Fig. 1043½ is ordered, extra charge is made, otherwise both Pumps have pipe thread at suction as per table. Forked rod coupling is furnished without extra charge.

FIGS. 1043 AND 1043½. SIZES, PRICES, ETC.

Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Lift.	FIG. 1043.		FIG. 1043½.	
					Cipher.	Brass Lined.	Cipher.	Brass Lined.
6 in.	12 in.	1½ gals.	3-in. pipe	20 ft.	Bringer	\$31.00	Broach	\$32.50
8½ "	12 "	3 "	4 "	20 "	Baldpat	40.00	Broaden	42.50
10 "	12 "	4 "	5 "	20 "	Painga	55.00	Paipa	60.00
12 "	12 "	6 "	6 "	20 "	Painhat	75.00	Paipap	80.00




FIG. 1043




FIG. 1043½





Our illustration shows a very common application of our Fig. 1121, Combined Triplex Pump and Horse Power, in operation, filling road sprinkler wagon. This apparatus may be used wherever water is within suction distance, 15 to 20 feet below surface of ground, for water supply, irrigation, etc.

The line of Pumps and Horse Powers will be found between pages 91 and 97.

# GOULDS TRIPLEX POWER PUMP.

91

FOR ELEVATIONS UP TO 50 FEET OR EQUIVALENT PRESSURE.

Fig. 1010 is a new type of Triplex Power Pump for such light service as required for irrigating land, watering stock, filling tanks, etc. It is fitted with pulley to be *driven by belt connection from gas, gasoline, petroleum engine, or other motive power.*

The valves are rubber faced, with bronze seats; the plungers are inside-packed and have water seals; substantial connecting rods and crank shaft with ample bearings. Crank shaft is extended at both ends, so that pulley can be used at either end, or pulleys may be mounted at both ends.

It has but few working parts and they are readily accessible for inspection and care. Altogether it is a most excellent, serviceable Pump and meets with a large demand from the agricultural districts.




FIG. 1010

FIG. 1010. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Rev. of Crank Shaft.	Capacity per Hour at 40 Revolutions per Minute.	Suction.	Discharge.	Pulley.	Cipher.	Brass- Lined Cylinders.
Diameter.	Stroke.							
4 in.	8 in.	1.3 gals.	3,120 gals.	3½ in. pipe	3 in. pipe	20 x 4 in.	Riceba	\$120.00
5 "	10 "	2.5 "	6,000 "	4 "	4 "	30 x 5 "	Boycott	200.00
6 "	12 "	4.4 "	10,560 "	5 "	5 "	36 x 6 "	Boyhood	300.00



# 92 GOULDS COMBINED TRIPLEX PUMP AND HORSE POWER.

FOR ELEVATIONS TO 50 FEET OR EQUIVALENT PRESSURE.




FIG. 1121.

Fig. 1121 is a modification of our Fig. 1010 (page 91), Triplex Pump with horse power gear surrounding and direct connected to pump crank shaft. The advantages of the Triplex type Pump was never more clearly demonstrated than when operated by horse power. The operation of this Pump is uniform and smooth, entirely free from that jar and hitch in other Pumps, which is so trying to the animal. Pump is regularly supplied with double sweep, to which one or two horses may be attached. It is regularly geared 14 to 1. Animal will make three to four circuits per minute, giving pump crank shaft a speed of 40 to 50 revolutions per minute. This outfit is especially adapted for farm or country pumping, and offers advantages over wind power in that it is always ready for use and can be transported if necessary.

FIG. 1121. SIZE, CAPACITY, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Capacity per Hour at 40 Revolutions per Minute.	Suction.	Discharge.	Cipher.	Brass-Lined Cylinders.
Diameter.	Stroke.						
4	8	1.3 gals.	3120 gals.	3½ in. pipe	3 in. pipe	Wooraly	\$200.00



FOR ONE OR TWO HORSES.

The illustration shows a very powerful Double-Geared Iron Horse Power for one or two horses, with covered internal master gear, two babbitted 1½-in. journal boxes, driver's seat, pole and all necessary details.

This Horse Power is geared about 14 to 1. The usual travel of horse or other animal is three to four circuits per minute, giving the Tumbling Shaft a speed of from 40 to 50 revolutions per minute. By providing extra length wrought-iron Tumbling-Shaft, Plummer Blocks and Driving Pulley at end (which we list below), this Power may be employed for driving our Fig. 1010, Triplex Irrigating Pump (illustrated on page 91) or other Power Pump. Of course it has a wide range of application for other duties where horse power can be employed.

Horse Power alone weighs about 550 pounds. Sweeps about 60 pounds each. Ten feet Shafting with Face Plate, etc., 200 pounds.




FIG. 914

FIG. 914. PRICES, ETC.

Iron Horse Power, with one pole — for one horse.....	(Weir) .....	\$90.00
Iron Horse Power, with two poles — for two horses.....	(Weirda).....	93.00
With 10 feet 2 Inch Wrought-Iron Tumbling Shaft and Face Plate at end, for 6, 8 and 10 inch stroke, extra.....		10.00
With 10 feet 2 inch Wrought-Iron Tumbling Shaft and 30 x 6 Driving Pulley at end, and 2 Plummer Blocks, extra.....		20.00
2 inch Wrought-Iron Tumbling Shaft, per foot, extra.....		.75
Air Chamber with Tee for 3 inch pipe, extra.....		7.50
Heavy Balance Wheel, 36 x 4½ inch, extra.....		12.00
Plummer Blocks, extra.....		3.00

# GOULDS IRON HORSE POWER.

FOR ONE OR TWO HORSES.




FIG. 597

The cut shows a very simple, though thoroughly constructed One-Horse or Pony Gear for operating any kind of agricultural machinery, as feed cutters, corn mills, etc. We furnish it complete, as shown in cut, with universal joint and stub end to weld to horizontal shaft, and hardwood pole ten feet long. The animal will ordinarily make from three to four circuits per minute, giving the tumbling shaft a speed of 20 to 25 revolutions.

Fig. 597½ represents a larger form of our Fig. 597, described, and can be driven by one or two horses.

SIZES, PRICES, ETC.

	Geared.	Size Frame.	Cipher.	Price.
Fig. 597, One-horse.....	6½ to 1	38 x 12 in., 10 in. high	Miry	\$55.00
Fig. 597½, Two-horse.....	6 to 1	48 x 32 " 13 "	Missed	120.00


When pole is not furnished a reasonable reduction will be made.

## GOULDS HORSE GEAR PUMPING APPARATUS.

FOR ONE OR TWO HORSES.

Fig. 884 consists of Horse Gear amply strong for one horse; two-throw wrought-iron crank shaft, plummer blocks for mounting on timbers placed on top of well, slings, guides and rods for connecting to Fig. 527½, Double Barrel Pump, page 96. The apparatus is very simple, requires but little attention. From three to four circuits a minute are ordinarily made, giving the tumbling shaft a speed of 20 to 25 revolutions per minute. We give prices below and also upon extra tumbling shaft, plummer blocks and universal coupling. Arranged in this manner, animal tracks between well and gear. A track with radius of ten feet is recommended. Price includes one pole.

Fig. 885, Horse Gear Pumping Apparatus, is practically the same as our Fig 884 described, but about twice as heavy and powerful, and designed to be operated by two horses. Price includes one pole. When furnished with single throw crank deduct \$10.00 list.



SIZES, PRICES, ETC.

	Stroke.	Geared.	*Will Operate.	Cipher.	Price.
Fig. 884, One-horse Gear..	10 in.	6½ to 1	{ 2½ in. double cyl., 85 ft. }	Wayfare	\$95.00
Fig. 885, Two-horse Gear..	10 "	6 to 1	{ 3½ " " 80 " }	Wayfet	160.00
			{ 6 " " 30 " }		

Extra Hardwood Pole..... \$3.00    Universal Coupling..... \$10.00  
2-inch Tumbling Shaft, per foot..... .75    Plummer Blocks..... 3.00

\*Smaller Cylinders in proportionately deeper, and larger Cylinders in shallower wells.

FIG. 885

FOR ONE OR TWO HORSES.




FIG. 894

This consists of horse gear amply strong for two horses; 10 feet of shafting with plummer blocks and couplings, two-throw wrought-iron crank shaft, plummer blocks for mounting on timbers placed on top of well, slings, guides and rods for connecting to pump rods below. The apparatus is very simple, requires but little attention and will work satisfactorily. A track with radius of 10 feet is recommended, the animal tracking between well and gear with this outfit. An animal makes three to four circuits per minute, giving tumbling shaft a speed of 20 to 25 revolutions. Power of donkey or pony one-half that of horse. We recommend our Fig. 527½ (given on next page), for use with this horse gear.

FIG. 894. SIZES, PRICES, ETC.

	Stroke.	Geared.	* Will Operate.	Cipher.	Price.
One Horse Gear.....	10 in.	6 to 1	{ 2½ in. Double Cylinder, 85 ft. {	Bondmaid	\$120.00
			{ 3 " " " " 55 " }		
Two Horse Gear.....	10 "	6 to 1	{ 3½ " " " " 80 " }	Bondman	170.00
			{ 6 " " " " 30 " }		

\*Smaller Cylinders in proportionately deeper, and larger Cylinders in shallower Wells.



# GOULDS SINGLE AND DOUBLE-BARREL PUMPS.

FOR DEEP WELLS.




FIG. 526 1/2



FIG. 515

Fig. 526 1/2 represents our Single-Barrel Deep Well Pump, with air chamber in iron or with brass cylinders, as ordered, with doors at top and bottom, allowing free access to all valves. This Pump may be operated by any of our pumping apparatuses, pages 100 to 103, or with our Horse Gears with single throw crank, Figs. 884, 885 and 894, pages 94 and 95. A check or foot valve should be placed at extremity of suction pipe. We fit with harp connection and stub for welding to connecting rod.

Fig. 527 1/2 represents our superior Double-Barrel Deep Well Pump, in iron or with brass cylinders, as ordered, with doors at top and bottom for access to all valves.

They are also built with brass stuffing boxes, buckets, rods, etc., and fitted for welding connecting rods to stub with bow, as shown in cut, or pin and socket stub, as preferred. These Double-Barrel Pumps are specially designed to be operated by our Horse Gears, pages 94 and 95, for irrigating service, etc.

Pumps may be worked at 30 to 40 revolutions per minute, according to depth of well.

SIZES, PRICES ETC.




FIG. 527 1/2

Fig.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction and Discharge.	*Lift and Force.	Well Rod.	IRON BARREL.		BRASS BARREL.	
							Cipher.	Price.	Cipher.	Price.
526 1/2	2 1/2 in.	10 in.	.21 gal.	1 1/2 in. pipe	200 ft.	3/8 in.	Jawad	\$42.00	Jibbo	\$44.50
"	3 "	10 "	.31 "	1 1/2 "	200 "	7/8 "	Jayel	44.00	Jigar	49.50
"	3 1/2 "	10 "	.42 "	2 "	150 "	7/8 "	J-erba	49.50	Jobba	57.00
"	4 "	10 "	.54 "	2 "	150 "	7/8 "	Jerko	62.00	Jog	71.00
"	5 "	10 "	.85 "	2 1/2 "	100 "	7/8 "	Jestlu	84.50	John	103.00
"	6 "	10 "	1.22 "	3 "	100 "	7/8 "	Jetam	101.25	Join	129.00
527 1/2	2 1/2 "	10 "	.42 "	1 1/2 "	200 "	7/8 "	Joke	58.00	July	71.00
"	3 "	10 "	.60 "	2 "	200 "	7/8 "	Jolt	64.00	Jump	81.00
"	3 1/2 "	10 "	.84 "	2 1/2 "	150 "	7/8 "	Jots	74.00	June	93.00
"	4 "	10 "	1.08 "	2 1/2 "	150 "	7/8 "	Joves	85.00	Junks	108.00
"	5 "	10 "	1.70 "	3 "	100 "	7/8 "	Joy	120.00	Jury	175.00
"	6 "	10 "	2.44 "	3 1/2 "	100 "	7/8 "	Jug	160.00	Just	235.00

\*Total lift and force from water to point of discharge, Pump not more than 25 feet above water.

## GOULDS ROD COUPLINGS AND GUIDES.

FIG. 515. WELL ROD JOINT AND BRASS BUSH.

FIG. 516. SINGLE AND DOUBLE ROLLER GUIDES FOR PISTON RODS.




FIG. 516

Size Rod, In.	5/8	3/4	7/8	1
Cipher.....	Getterst	Gilding	Gimmel	Girlish
Price.....	\$1.20	\$1.38	\$1.75	\$2.45

For Rod.....	5/8 OR 3/4 IN.	7/8 IN.	1 IN.	1 1/4
	Cipher Price	Cipher Price	Cipher Price	Cipher Price
Sing. Roller	Vesta \$1.25	Vergont \$1.50	Venum \$2.45	Leabjoy \$3.00
Doub. Roller	Versing 2.25			

FOR HORSE POWER.

Fig. 720 represents Fig. 885, our Two-Horse Gear, and Fig. 527½, Double-Barrel Pump, arranged for well pumping. The Pump is fully described on page 96; Horse Gear on page 94. As illustrated in cut, Pump should be attached to coping or planks laid across the well and a check valve should be placed in the lower end of suction pipe. Roller guides should be located about every 12 feet on supports for the rods to work through. We furnish this pumping apparatus complete with the exception of wrought-iron connecting pipes, rods and roller guides. These we supply according to depth of well at extra price, and will be found listed on pages 96 and 299.

Our table gives full information.

FIG 720. SIZES, PRICES, ETC.

Dia. Cyls.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	*Lift and Force.	IRON CYLINDER.	
						Cipher.	Price.
2½ in.	10 in.	.43 gals.	1½ in. pipe.	1½ in. pipe.	150 ft.	Dinjjig	\$218.00
3 "	10 "	.61 "	2 "	2 "	110 "	Dipbak	224.00
3½ "	10 "	.83 "	2½ "	2½ "	80 "	Dipbell	234.00
4 "	10 "	1.09 "	2½ "	2½ "	60 "	Dipbig	245.00
5 "	10 "	1.70 "	3 "	3 "	40 "	Driped	280.00
6 "	10 "	2.45 "	3½ "	3½ "	26 "	Drlpig	320.00

\* Total lift and force from supply to point of delivery, Pump not more than 20 feet above water.].




FIG. 720




## DEEP WELL PUMPING.



In some localities deep wells are depended upon for the entire supply of water; in others, deep well furnishes the only available supply of pure water.

Our illustration shows Chenoa, Ill., Deep Well Pumping Plant, operated by Gasoline Engine. This installation is a type of many power pumping plants employed to supply water to towns, cities, etc.

Our Differential Power Working Heads and Cylinders, given on pages 104 to 112 offer a wide range of capacity. We refer to our tables given in connection with each Pump, showing working depth and capacity for which they are adapted, etc.







# 98-A GOULDS HAND AND POWER PUMPING APPARATUS.



FIG. 1314

WITH PULLEY FLY WHEEL.

Fig. 1314 consists of a heavy working head, with cast-iron bed plate and column, and a Deep Well Cylinder with air chamber having hand hold plates at top and bottom which allow free access to all valves.

Fig. 1313 is a heavier and taller working head and geared 3 to 1. If so ordered, this working head can be furnished direct connected and with face plate (as shown in Fig. 1314.) The cylinder is the same as supplied with Fig. 1314.

We regularly fit as below with iron cylinder, but can supply with brass-lined or all brass cylinder at extra price.

Connecting pipe, rods and guides furnished at market rates.



FIG 1313

FIG. 1314. SIZES, PRICES, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Well Rod.	Pulley Fly-Wheel.	*Lift and Force.	Cipher.	Price.
2½ in.	6 in.	.128 gal.	1½ in. pipe.	{ 1¼ in. pipe and 1 in. hose. }	5⁄8 in.	36 x 4½ in.	75 ft.	Varjac	\$83.00
3 " "	6 " "	.184 " "	1½ " "		5⁄8 " "	36 x 4½ " "	60 " "	Varjed	85.00
3½ " "	6 " "	.25 " "	2 " "		5⁄8 " "	36 x 4½ " "	45 " "	Varjfx	90.50
4 " "	6 " "	.326 " "	2 " "		5⁄8 " "	36 x 4½ " "	35 " "	Vargos	103.00

FIG. 1313. SIZES, PRICES, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Well Rod.	Pulley Fly-Wheel.	*Lift and Force.	Cipher.	Price.
2½ in.	6 in.	.128 gal.	1½ in. pipe.	{ 1¼ in. pipe and 1 in. hose. }	5⁄8 in.	36 x 4½ in.	125 ft.	Vargha	\$107.00
3 " "	6 " "	.184 " "	1½ " "		5⁄8 " "	36 x 4½ " "	100 " "	Varghel	109.00
3½ " "	6 " "	.25 " "	2 " "		5⁄8 " "	36 x 4½ " "	60 " "	Vargibs	114.50
4 " "	6 " "	.326 " "	2 " "		5⁄8 " "	36 x 4½ " "	45 " "	Vargkob	127.00

\*Depth of Wells to which Pumping Apparatus may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS HAND AND POWER PUMPING APPARATUS.

99

WITH TIGHT AND LOOSE PULLEYS

This apparatus consists of iron bed with vertical column, which supports shaft with tight and loose pulleys, crank handle and face plate, these operating pitman and connecting rod (working through usual stuffing box), suitable for welding to plunger rod of pump cylinder in well. This can be worked by either manual or other power supplied from steam, gas or petroleum engine, if belt speed is not too high. Can tap suction for 1½-inch or 2-inch pipe, but always as below, unless otherwise ordered.

FIG. 872. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	Pulleys, Each.	* Lift and Force.	Cipher.	Price.
4, 5 or 6 in.	1½ in. pipe	1¼ in. pipe	¾ in.	15 x 3 in.	{ 2½ in. cyl., 50 ft. } 3 " 40 "	Waxlight	\$30.00

Cylinders, like Figs. 1230, 1231, pages 62 and 63, or Figs. 514½, 1192, pages 82 and 83, are required with this Pumping Apparatus, and *cost extra*.

\*Depth of wells to which Pumping Apparatus may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 872

## GOULDS COMBINATION PUMPING HEAD.

FOR DEEP WELLS.

(Patent Applied For.)

Fig. 1280 illustrates a new Well Pump Head that we have recently designed. In this construction we offer a combination of hand, wind mill or belted Deep Well Head. We furnish a self-contained machine and do away with the cumbersome walking-beam, generally used when power is employed to operate a hand pump. Connecting rods can be easily disconnected, and so change from hand to power or wind mill at will. Gas, gasoline, steam, electricity or wind power may be applied to this head.

FIG. 1280. SIZES, PRICES, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	Gearing.	Pulleys, T. & L.	* Lift and Force.	Cipher.	Price.
Adjustable 6, 8, 10 in.	1¼, 1½ or 2 in.	1¼ in. pipe or 1 in. hose	7-16 or 1 in. Wood Rod	5 to 1	20 x 3 in.	{ 2 in. cyl., 200 ft. } 2½ " 125 " 3 " 100 "	Maltyeb	\$50.00

\*Depth of wells to which Pump Standard may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

Cylinders, like Figs. 1230 and 1231, pages 62 and 63, are required with this Pump Standard, and *cost extra*.




FIG. 1280



# GOULDS MANUAL PUMPING APPARATUS.

WITH HEAVY FLY-WHEEL AND WINCH HANDLE.

This apparatus consists of heavy cast-iron bed plate and column supporting wrought-iron shaft with round rim fly-wheel affixed, face plate, steel wrist pin, pitman, guided connecting rod passing through stuffing box in bed plate and thence inside pipe connecting with pump cylinder below. It is strongly bolted together and offers a very effective and simple apparatus for raising water from wells. As shown, water is discharged through spout, but by substituting a flange for spout it can be piped to convey the water to a distance.




FIG. 547

FIG. 547. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	Fly-Wheel.	*Lift and Force.	Cipher.	Price.
4, 5 or 6 in.	1½ in. pipe	{ 1¼ in. pipe and 1 in. hose. }	⅝ in.	36 in.	{ 2½ in. cyl., 75 ft. 3 " 60 " }	Lamp	\$39.00
Same as above with air chamber.....						Leabjud	42.00
Same as above with air chamber and cock spout.....						Leabki	44.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, or Figs. 514½, 1192, pages 82 and 83, are required with this Pumping Apparatus and *cost extra*.

\*Depth of wells to which Pumping Apparatus may be adapted by placing Cylinder within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

## MANUAL AND POWER PUMPING APPARATUS.

WITH PULLEY FLY-WHEEL.

Fig. 547½ is the same in all respects as Fig. 547, but with flat rim fly-wheel to be worked by manual power, or belt transmission from any of the numerous and well known gas or steam engines, under proper speed conditions. By substituting a flange for spout, pipe may be connected to convey water wherever desired.




FIG 547½

FIG. 547½. SIZE, PRICE, ETC.

Stroke.	Suction.	Discharge.	Well Rod.	Pulley Fly-Wheel.	*Lift and Force.	Cipher.	Price.
5, 6 or 7 in.	1½ in. pipe	{ 1¼ in. pipe and 1 in. hose. }	⅝ in.	36 x 4½ in.	{ 2½ in. cyl., 75 ft. 3 " 60 " }	Lane	\$41.00
Same as above with air chamber.....						Leablow	44.00
Same as above with air chamber and cock spout.....						Leabma	46.00

Cylinders like Figs. 1230, 1231, pages 62 and 63, or Figs. 514½, 1192, pages 82 and 83, are required with this Pumping Apparatus and *cost extra*.

\*Depth of wells to which Pumping Apparatus may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.

# GOULDS POWER PUMPING APPARATUS.

101

WITH TIGHT AND LOOSE PULLEYS.

Fig. 589 represents our Pumping Apparatus for power only. The pinion shaft is made extra heavy and long enough to carry tight and loose pulleys, the size of which can be changed to meet any special requirements. An out-board bearing is not essential for the ordinary range of service, but in some cases it may be advantageous. Gear and pinion are all best steel with machine-cut teeth. Gas, steam, oil or electric power may be employed to operate these pumps.

FIG. 589. SIZES, PRICES, ETC.

Stroke.	Suction.	Well Rod.	Geared.	Pulleys Each.	*Lift and Force.	Cipher.	Price.
6 in.	1½ in. pipe.	5⁄8 in.	3 to 1	20 x 3 in.	$\left\{ \begin{array}{l} 2\frac{1}{2} \text{ in. Cylinder, 125 feet.} \\ 3 \text{ " " 100 " } \\ 3\frac{1}{2} \text{ " " 60 " } \end{array} \right\}$	Warping	\$68.00
Same as above with air chamber.....					$\left\{ \begin{array}{l} 4 \text{ " " 45 " } \\ 4\frac{1}{2} \text{ " " 30 " } \end{array} \right\}$	Warplume	71.00
Same as above with air chamber and cock spout.....						Warproof	73.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, or Figs. 514½ and 1192, pages 82 and 83, are required for this Pumping Apparatus and *cost extra*.

\* Depth of Wells to which Pumping Apparatus may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 589.

# GOULDS MANUAL AND POWER PUMPING APPARATUS.

WITH GEAR AND PINION.

Figs. 888 shows our Manual and Power Pumping Apparatus with gear and pinion, and cock spout with air chamber on same. The main gear and pinion are made of best steel with machine-cut teeth, well fitted, bright finished, and work with minimum friction. Water can be forced upward through top of air chamber or drawn through the spout.

FIG. 888. SIZE, PRICE, ETC.

Stroke.	Suction Fitted for.	Well Rod.	Geared.	Pulley Fly-Wheel.	*Lift and Force.	Cipher.	Price.
6 in.	1½ in. pipe.	5⁄8 in.	3 to 1	36 x 4½ in.	$\left\{ \begin{array}{l} 2\frac{1}{2} \text{ in. Cylinder, 125 feet.} \\ 3 \text{ " " 100 " } \\ 3\frac{1}{2} \text{ " " 60 " } \\ 4 \text{ " " 45 " } \\ 4\frac{1}{2} \text{ " " 30 " } \end{array} \right\}$	Vexil	\$70.00
Same as above with air chamber, no cock.....						Leabnug	68.00
Same as above without air chamber or cock spout.....						Lenado	65.00

Cylinders like Figs. 1230 and 1231, pages 62 and 63, or Figs. 514½, 1192, pages 82 and 83, are required for this Pumping Apparatus and *cost extra*.

\* Depth of Wells to which Pumping Apparatus may be adapted by placing Cylinders within 15 or 20 feet of water, or total lift and force from supply to point of delivery.




FIG. 888.



# GOULDS OVERHEAD COUNTER SHAFT.

FOR OPERATING POWER PUMPS.

Fig. 711 represents a light Counter Shaft, consisting of hangers, tight and loose pulleys, face plate, wrist pin and stub rod for driving any of our smaller Power Pumps, such as Fig. 279, page 129, or Cylinders, pages 62 to 69.

Can change sizes of pulleys enumerated in our tables to meet requirements, at proportionate prices.




FIG. 711

FIG. 711 SIZES, PRICES, ETC.

No.	Stroke.	Drop of Hanger.	Pulleys, Each.	*Will Operate.	Cipher.	Price.
1	{ 6 in. } { 8 " }	12 in.	16 x 3½ in.	{ 4 in. cyl., 55 ft. } { 5 " 25 " }	Syrup	\$30.00
2	{ 6 " } { 8 " }	12 "	18 x 4 "	{ 4 " 70 " } { 5 " 50 " }	Sythe	35.00
3	{ 6 " } { 8 " } { 10 " }	12 "	22 x 5 "	{ 4 " 100 " } { 5 " 75 " } { 6 " 25 " }	Table	45.00

\*Smaller Cylinders proportionately deeper.

# GOULDS OVERHEAD GEARED COUNTER SHAFT.

Fig. 650½ represents our Overhead Geared Counter Shaft with plummer blocks, tight and loose pulleys, face plate with pin for varying stroke, connecting rod for driving Power Pumps such as Figs. 714, 514½, 526½, 279, 1212, or Cylinders as shown on pages 62 to 69, etc. We make this Counter Shaft in the shorter strokes only, but can fully recommend for duty specified in our table below. Gears are machine cut. Prices do not include wood frame.




FIG. 650½

FIG. 650½. SIZES, PRICES, ETC.

No.	Stroke.	Diameter Large Gear.	Diameter Small Gear.	Face of Gears.	Pulleys, Each.	Will Operate.	Cipher.	Price.
1	10 in.	12 in.	4 in.	2½ in.	14 x 4 in.	4 in. cyl., 90 ft.	Beater	\$50.00
1A	12, 14 or 16 in.	12 "	4 "	2½ "	14 x 4 "	4 " cyl. 60 "	Casem	60.00



Fig. 650 represents our Overhead Geared Counter Shaft, mounted on heavy oak frame, with wrought-iron stay rods, ready for putting in place. Counter Shaft has machine-cut spur and pinion gears, plummer blocks, tight and loose pulleys, face plate with pin for varying stroke and stub connecting rod.

This Counter Shaft is very powerful and well made, and can be relied upon for satisfaction during a long period of most exacting service. Upper engraving shows Counter Shaft attached to ceiling; lower engraving as placed over open well. For *Pumps* to be operated by Counter Shaft we recommend:




FIG. 650

Figs. 514½, 339, 526½, 279, 1212 (See index for pages).

For *Cylinders* we refer to:

Figs. 1230, 1064, 1135, 904 — especially the two latter.

For *Working-Heads* to use in combination with above *Cylinders* for forcing water we recommend:

Figs, 978, 979, 446, 1127.




FIG 650

FIG. 650. SIZES, PRICES, ETC.

No.	Stroke.	Dia. Large Gear.	Dia. Small Gear.	Face of Gears.	Pulleys, Each.	* Will Operate.	Cipher.	Price.
2	10 in.	22 in.	7¼ in.	3½ in.	22 x 5½ in.	{ 2¼ in. cyl., 300 ft. 3¼ " 200 " 4¾ " 150 " 5¾ " 75 "	Beef	\$125.00
2A	12, 16 or 18 in.	22 "	7¾ "	3½ "	22 x 5½ "		Cason	140.00
2B	20, 22 or 24 "	22 "	7¾ "	3½ "	22 x 5½ "		Casort	150.00
2C	26, 28 or 30 "	22 "	7¾ "	3½ "	22 x 5½ "		Chestad	160.00

\* Working Heads are practically strong enough to operate any suitable Pumps to such depth as they are adapted; this is told in connection with Pumps to which we refer.

## GOULDS DIFFERENTIAL POWER WORKING HEAD.

*FOR OPERATING SINGLE-ACTING DEEP WELL CYLINDER.*




FIG. 971 A. 24" STROKE




FIG. 971 C. 24" STROKE



# GOULDS DIFFERENTIAL POWER WORKING HEAD.

105

FOR OPERATING SINGLE-ACTING DEEP WELL CYLINDERS.

Fig. 971, 16-inch and Fig. 971 A, 24-inch Stroke Power Working Heads, have substantial bed-plate, to which the discharge piece and frame are bolted. The differential plunger effects a constant flow and smooth running. The crank pin bearing has strap head with adjustable bronze box. The gear and pinion are machine cut. Tight and loose pulleys are regularly supplied for belt drive from any source of power.

Fig. 971 B, 24-inch Stroke, is the same as Fig. 971 A, 24-inch Stroke, except that it carries heavier gearing, adapting it for deeper wells.

Fig. 971 C, 24-inch Stroke, has double gears, with extended pinion shaft, carrying tight and loose pulleys and supported by outboard bearing. Connecting rod is forged steel with bronze marine head. This construction adapts Working Head for operating Cylinders in very deep wells, as shown in our tables.

Fig. 904, Brass Deep Well Cylinder, is designed to be used with this type of Working Head. Description Fig. 904 on page 68; Wood Rod, Couplings, etc., page 70.

Complete catalogue of Power Working Heads sent upon request.

FIG. 971. SINGLE-ACTING WORKING HEAD. SIZES, ETC.

Stroke.	MAXIMUM SIZE OF PIPE.		Geared.	Pulleys. Tight and Loose.	Cipher.
	Connecting.	Discharge.			
16 in.	8 in.	4 in.	5 to 1	30 x 6 in.	Writ
24 " A	8 "	5 "	5 to 1	36 x 6 "	Hendafa
24 " B	8 "	5 "	5 to 1	36 x 8 "	Hendago
24 " C	8 "	5 "	5 to 1	48 x 8 "	Hendaho

FIG. 904. SINGLE-ACTING DEEP WELL CYLINDER. SIZES, CAPACITIES, PRICES, ETC.

See pages 68 and 69 for size pipe, wood rod, etc., to use with these Cylinders.

Fig. 904 Diameter and Stroke.	Capacity per Stroke.	Usual Speed and Capacity per Minute.	*DEPTH OF WELL IN WHICH FIG. 971 WILL OPERATE FIG. 904 CYLINDERS.				Cipher.	All-Brass.
			16-In.	24-In., A.	24-In., B.	24-In., C.		
3 1/4 x 16 in.	.57 gals.	30 revs., 17 gals.	450 ft.	450 ft.			Whim	\$48.00
3 1/4 x 24 "	.86 "	25 " 21 "					Whine	52.00
3 1/4 x 16 "	.76 "	30 " 22 "	400 ft.				Zylonkk	70.00
3 3/4 x 24 "	1.15 "	25 " 28 "		400 ft.			Whiners	75.00
4 1/4 x 16 "	.98 "	30 " 29 "	350 ft.				Zylonle	90.00
4 1/4 x 24 "	1.47 "	25 " 36 "		350 ft.			Whinny	95.00
4 3/4 x 16 "	1.23 "	30 " 36 "	300 ft.				Zylonm	127.50
4 3/4 x 24 "	1.84 "	25 " 46 "		300 ft.	375 ft.		Whippe	135.00
5 3/4 x 16 "	1.80 "	30 " 53 "	200 ft.				Zylonna	180.00
5 3/4 x 24 "	2.70 "	25 " 67 "		200 ft.	250 ft.	400 ft.	Dufabl	195.00
6 3/4 x 16 "	2.50 "	30 " 74 "	150 ft.				Gra lew	280.00
6 3/4 x 24 "	3.72 "	25 " 92 "		150 ft.	200 ft.	300 ft.	Gratifa	300.00
7 3/4 x 16 "	3.26 "	30 " 97 "	125 ft.				Zylonoc	425.00
7 3/4 x 24 "	4.90 "	25 " 122 "		125 ft.	160 ft.	250 ft.	Willri	450.00
8 3/4 x 16 "	4.16 "	30 " 124 "	100 ft.				Gratijo	685.00
8 3/4 x 24 "	6.20 "	25 " 156 "		100 ft.	125 ft.	200 ft.	Groomug	725.00

\* From surface of water in well to point of delivery.



## GOULDS DIFFERENTIAL POWER WORKING HEAD.

*FOR OPERATING SINGLE-ACTING DEEP WELL CYLINDER.*




FIG. 1191, 24" STROKE.



FIG. 904.

## FOR OPERATING SINGLE-ACTING DEEP WELL CYLINDER.

In Fig. 1191, Differential Working Head, the driving mechanism is located down close to the top of the well and the discharge piece in a pit below.

It is built heavy and strong and it is powerfully geared. The gearing is machine-cut. Tight and loose pulleys. The bearings are all very liberally proportioned. The bed plate is a massive casting in one piece, forming a stable foundation for and preserving true alignment of the driving mechanism.

We offer in 24-inch and 36-inch stroke, adapted for working limits given in our table.

Fig. 904, Single-Acting Deep Well Cylinder, is used with this type of Working Head.

The size of Deep Well Pump to be selected for any well is governed by the quantity of water required, the inside diameter and the depth of the well.

We recommend the use of wood sucker rod with forged couplings.

FIG. 1191. SINGLE-ACTING WORKING HEAD. SIZES, ETC.

Stroke.	MAXIMUM SIZE OF PIPE.		Geared.	Pulleys, Tight and Loose.	Cipher.
	Connecting.	Discharge.			
24 in.	8 in.	4 in.	5 to 1	36 x 6 in.	Wo'dec
36 "	12 "	6 "	6 to 1	48 x 12 "	Maulfa

FIG. 904. SINGLE-ACTING DEEP WELL CYLINDER. SIZES, CAPACITIES, PRICES, ETC.

See pages 68 and 69 for size pipe, wood rod, etc., to use with these Cylinders.

Fig. 904 Diameter and Stroke.	Capacity per Stroke.	Usual Speed and Capacity per Minute.	*Depth of well in which Fig. 904 Cylin- der can be operated by Fig. 1191.		Cipher.	All Brass.
			24-in. Stroke.	36-in. Stroke.		
3 $\frac{1}{4}$ x 24	.86 gals.	25 revs.— 21 gals.	450 ft.	.....	Whine	\$52.00
3 $\frac{3}{4}$ x 24	1.14 "	25 " 28 "	400 "	.....	Whiners	75.00
4 $\frac{1}{4}$ x 24	1.47 "	25 " 36 "	350 "	.....	Whinny	95.00
4 $\frac{3}{4}$ x 24	1.84 "	25 " 46 "	300 "	.....	Whippe	135.00
5 $\frac{3}{4}$ x 24	2.69 "	25 " 67 "	200 "	.....	Dufabl	195.00
7 $\frac{3}{4}$ x 24	4.9 "	25 " 122 "	125 "	.....	Willri	450.00
7 $\frac{3}{4}$ x 36	7.34 "	20 " 147 "	.....	550 ft.	Willga	500.00
8 $\frac{3}{4}$ x 36	9.36 "	20 " 187 "	.....	475 "	Groomwo	800.00
9 $\frac{1}{2}$ x 36	11.02 "	20 " 220 "	.....	350 "	Mamoz	1,000.00
11 $\frac{1}{2}$ x 36	16.16 "	20 " 323 "	.....	225 "	Mamut	1,250.00

\* Vertical height from surface of water in well to point of delivery.

FOR DEEP WELLS.




FIG. 1087A; 18" STROKE.

The Double-Acting Deep Well Pump delivers more water from a cased well of a given size than the Single-Acting Pump, as there are two pistons constantly working instead of one.

Fig. 1087, Double-Acting Working Head, is mounted on a heavy base plate, which forms a substantial foundation, preserves the accurate alignment of all the working parts, and insures easy running and great durability.

There are two piston rods and two cross-heads. The outer rod is a specially made tube and is driven by the lower crosshead; the inner rod is solid, reciprocating through the outer rod, and driven by the upper crosshead. The two outside connecting rods are attached to crank pins in arms of the gears and to the lower crosshead. The inner connecting rod is attached to the crank of the main shaft, directly opposite the outer crank pins (*i. e.*, 180 degrees apart) and the upper crosshead. There are tight and loose pulleys on the pinion shaft, which is extended and supported by an out-board bearing. Provision is made for drawing back the Working Head, leaving the well clear for inspection and removal of the piston rods and pistons.



FIG. 1088



Fig. 1088, Double-Acting Deep Well Pump, contains the foot valve, and above this are two pistons, which are actuated by separate piston rods driven by the double-acting working head.

The Cylinder, Pistons and Valves are a special design, which insures a maximum delivery of water with the least expenditure of power, the valves being so designed that they provide an unobstructed waterway with the least possible slip.

The Working Head has double gears, machine cut. The connecting rods are forged steel. The crank and crosshead pins have adjustable bronze boxes of the marine type. The pinion and crank shafts run in adjustable babbitt-lined bearings. The crossheads are iron and steel and have adjustable bronze shoes. The piston rods are brass and steel tubing and solid polished steel, with stuffing boxes of bronze.

The pump cylinder is made of seamless brass tubing. The pistons are of bronze and fitted with cup leather packings. The valves in the pistons and the foot valve are of bronze. Great care is taken to secure the joints of the piston rods from all liability of loosening, and a special check device holds the cup leathers in place. All parts are made to standard gauges and are strictly interchangeable.

In our tables below we give safe working limits for several forms of Working Heads.

FIG. 1087. DOUBLE-ACTING WORKING HEAD, SIZES, ETC.




Stroke.	MAXIMUM SIZE OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
	Connecting.	Discharge.			
18 in. A	8 in.	4 in.	6 to 1	36 x 6 in.	Wryafi
18 " B	10 "	5 "	6 to 1	42 x 10 "	Maulgu
18 " C	12 "	6 "	6 to 1	48 x 12 "	Maulhy

FIG. 1088. DOUBLE-ACTING DEEP WELL PUMP. SIZES, CAPACITIES, ETC.

Fig. 1088. Dia. and Stroke.	Capacity One Rev. of Crank Shaft.	Usual Speed and Capacity per Minute.	*DEPTH OF WELL HEAD WILL OPERATE CYLINDERS.			Connecting Pipe.	Maximum Outside Diameter.	Cipher.
			18 In. A.	18 In. B.	18 In. C.			
3 $\frac{3}{4}$ x 18 in.	1.52 gals.	25 revs., 43 gals.	500 ft.	.....	.....	4 in.	5 $\frac{1}{8}$ in.	Wryail
4 $\frac{3}{4}$ x 18 "	2.56 "	25 " 69 "	425 "	.....	.....	5 "	6 $\frac{3}{8}$ "	Wryaka
5 $\frac{3}{4}$ x 18 "	4.04 "	25 " 101 "	325 "	600 ft.	.....	6 "	7 $\frac{3}{8}$ "	Wryalm
6 $\frac{3}{4}$ x 18 "	5.56 "	25 " 139 "	200 "	400 "	.....	7 "	8 $\frac{3}{8}$ "	Wryamd
7 $\frac{3}{4}$ x 18 "	7.34 "	25 " 183 "	150 "	275 "	550 ft.	8 "	9 $\frac{3}{8}$ "	Wryane
8 $\frac{3}{4}$ x 18 "	.....	.....	.....	225 "	475 "	9 "	11 "	Mearul
9 $\frac{1}{2}$ x 18 "	.....	.....	.....	175 "	350 "	10 "	12 "	Meshot
11 $\frac{1}{2}$ x 18 "	.....	.....	.....	.....	225 "	12 "	14 "	Meshown

\* Depth of the well from surface of water supply to point of delivery.

## GOULDS TRIPLEX POWER PUMP.

*FOR DEEP OPEN WELLS.**FIG. 1251. DOUBLE ROD GUIDE.**FIG. 1062 SIZE 6¼" X 8"*

Adapted to	Size Rod.	Fig. 1251. Double Roller Guide.	Welding Stub.	Rods and Couplings.
Fig. 1062—5 x 8 in.....	1¼ in.	\$2.00	\$2.50	\$0.65 per ft.
" 1062—6½ x 8 ".....	1½ "	2.25	2.75	.75 "
" 1062—8 x 10 ".....	1¾ "	2.50	3.00	.85 "
" 1262—8½ x 12 ".....	1¾ "	3.00	3.75	1.00 "

# GOULDS TRIPLEX POWER PUMP FOR DEEP OPEN WELLS. 111

FOR ELEVATIONS TO 300 FEET, EQUIVALENT TO 130 POUNDS PRESSURE.

Fig. 1062, Triplex Power Pump, is used in open wells and pits, where the water is too low to be reached by suction from the surface, and in localities where floods are liable to submerge Pumps placed within suction limits in the ordinary stages of the water.

The Frame, which contains the driving parts of the Pump, is on the surface, where attention is easily given. In this construction the cross head guides are cast in the frame, and do not need to be supported or brought into alignment in the well.

The cylinders, plungers and valve chests are built in one self-contained part, which is supported by beams in the well. The connecting rods, guides, etc., vary according to the depth.

In construction, materials and workmanship the Pump is first class. The gearing is machine-cut, bearings are of bronze or babbitt, adjustable, and easily renewed.

Fig. 1262, Triplex Power Pump (not illustrated), is designed for same service as Fig. 1062, above described, for elevations to 350 feet, equivalent to 150 pounds pressure. It is built with single throw crank shaft, operating the centre connecting rod, and having driving gears at each end with wrist pins and two outside connecting rods—cross heads are outside guided. Our tables indicate the working limit. Further details upon request. Brass fitted Pumps built to order.

FIG. 1062. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Sizes of Tension Rods.	Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.				
5 in.	8 in.	2.0 Gals.	35 Revs.— 70 Gals.	3 in.	3 in.	1 1/4 in.	5 to 1	30 x 5 in.	Elbem
6 1/2 "	8 "	3.4 "	35 " —119 "	4 "	4 "	1 1/2 "	5 to 1	30 x 6 "	Elbend
8 "	10 "	6.5 "	35 " —227 "	5 "	5 "	1 3/4 "	5 to 1	42 x 6 "	Elbida

FIG. 1262. SIZE, CAPACITY, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZE OF PIPE.		Size of Tension Rod.	Geared.	Tight and Loose Pulleys.	Cipher
Diameter.	Stroke.			Suction.	Discharge.				
8 1/2 in.	12 in.	8.8 Gals.	35 Revs.—308 Gals.	7 in.	8 in.	1 3/4 in.	5.6 to 1	36 x 12 in.	Mamic



# GOULDS DIFFERENTIAL POWER WORKING HEAD.

FOR OPERATING SINGLE-ACTING DEEP WELL CYLINDER.

Fig. 1030 is a neat, strong, Working Head; serviceable, convenient and easy to keep in running order. The design is similar to Fig. 971, pages 104 and 105. It has tight and loose pulleys, machine-cut gear and pinion, and a differential plunger, which causes the water to flow from the well in a continuous stream.

Fig. 904, Brass Deep Well Pump, is especially designed to be used with this type of Working Head. See pages 68 and 69 for complete description.

Selection of Deep Well Pump will be governed by quantity of water required, bore and depth of well. We recommend the use of wood sucker rod with forged couplings, page 70. Air chamber for discharge of Fig. 1030 furnished at \$7.50 extra list.

FIG. 1030. SINGLE-ACTING WORKING HEAD, SIZE, ETC.

Stroke.	MAXIMUM SIZE OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.	Price.
	Connecting.	Discharge.				
6 in.	4 1/2 in.	3 in.	5 to 1	20 x 3 in.	Veerao	\$90.00
10 "	6 "	3 "	4 to 1	20 x 4 "	Vatful	120.00
14 "	6 "	3 "	5 to 1	26 x 4 "	Vaunted	180.00
16 "	6 "	3 "	5 to 1	26 x 4 "	Vectutd	200.00

FIG. 904. BRASS DEEP WELL PUMP. SIZES, CAPACITIES, ETC.

Fig. 904. Dia. and Stroke.	*Fig. 1030. Will Operate in Wells.	Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.		Top and Bot- tom Connect- ing Pipe.	Maximum Outside Diameter.	Square Wood Sucker Rod.	Cipher.	All Brass.
2 3/4 x 6 in.	200 ft.	.154 gals.	35 revs.,	5.4 gals.	3 in.	3 7/8 in.	1 1/2 in.	Dumpy	\$34.00
2 3/4 x 10 "	275 "	.257 "	35 "	9. "	3 "	3 7/8 in.	1 1/2 in.	Dumpy	34.00
2 3/4 x 14 "	275 "	.359 "	30 "	10.77 "	3 "	3 7/8 in.	1 1/2 in.	Endmoub	36.00
2 3/4 x 16 "	275 "	.411 "	30 "	12.33 "	3 "	3 7/8 in.	1 1/2 in.	Whilom	36.00
3 1/4 x 6 "	150 "	.215 "	35 "	7.5 "	3 1/2 in.	4 1/2 in.	2 "	Dumpyb	45.00
3 1/4 x 10 "	200 "	.359 "	35 "	12.5 "	3 1/2 in.	4 1/2 in.	2 "	Dumpyb	45.00
3 1/4 x 14 "	200 "	.503 "	30 "	15.0 "	3 1/2 in.	4 1/2 in.	2 "	Endmove	48.00
3 1/4 x 16 "	200 "	.574 "	30 "	17.2 "	3 1/2 in.	4 1/2 in.	2 "	Whim	48.00
3 3/4 x 6 "	100 "	.286 "	35 "	10. "	4 "	5 1/2 in.	2 1/4 in.	Dumqeel	67.50
3 3/4 x 10 "	150 "	.478 "	35 "	16.7 "	4 "	5 1/2 in.	2 1/4 in.	Dumqeel	67.50
3 3/4 x 14 "	150 "	.669 "	30 "	20.6 "	4 "	5 1/2 in.	2 1/4 in.	Endmuba	60.00
3 3/4 x 16 "	150 "	.764 "	30 "	22.92 "	4 "	5 1/2 in.	2 1/4 in.	Zylonkk	70.00
4 1/4 x 6 "	75 "	.368 "	85 "	12.8 "	4 1/2 in.	5 3/4 in.	2 1/2 in.	Dumqued	87.50
4 1/4 x 10 "	120 "	.614 "	35 "	21.4 "	4 1/2 in.	5 3/4 in.	2 1/2 in.	Dumqued	87.50
4 1/4 x 14 "	120 "	.859 "	30 "	25.7 "	4 1/2 in.	5 3/4 in.	2 1/2 in.	Endmud	90.00
4 1/4 x 16 "	120 "	.982 "	30 "	29.4 "	4 1/2 in.	5 3/4 in.	2 1/2 in.	Zylonle	90.00
4 3/4 x 6 "	60 "	.46 "	35 "	16.1 "	5 "	6 1/4 in.	3 "	Dumquill	120.00
4 3/4 x 10 "	100 "	7.67 "	35 "	26.8 "	5 "	6 1/4 in.	3 "	Dumquill	120.00
4 3/4 x 14 "	100 "	1.073 "	30 "	32.1 "	5 "	6 1/4 in.	3 "	Endmuck	127.50
4 3/4 x 16 "	100 "	1.227 "	30 "	36.8 "	5 "	6 1/4 in.	3 "	Zylonm	127.50
5 3/4 x 6 "	40 "	.67 "	35 "	23.4 "	6 "	7 1/4 in.	3 1/2 in.	Dubame	172.50
5 3/4 x 10 "	70 "	1.12 "	35 "	39.2 "	6 "	7 1/4 in.	3 1/2 in.	Dubame	172.50
5 3/4 x 14 "	70 "	1.57 "	30 "	47.1 "	6 "	7 1/4 in.	3 1/2 in.	Endnab	180.00
5 3/4 x 16 "	70 "	1.79 "	30 "	53.7 "	6 "	7 1/4 in.	3 1/2 in.	Zylonna	180.00

FIG. 1030. 10"

FIG. 904

\*From surface of water in well to point of delivery.

# DEEP WELL STEAM PUMPING ENGINE.

113

WITH BRASS DISPLACEMENT PLUNGER.

These Engines are adapted for non-flowing, Artesian, tubular, bored, dug or driven wells. They are constructed so as to insure a steady flow of water, whether raised from shallow or deep wells, there being separate adjustments for the upward and downward strokes; therefore a perfect travel of piston is obtained, without regard to the weight of the reciprocating parts.

The Valve Gear governing the operation of the Engine is not connected with the auxiliary piston or valve, and has no upward or downward movement, consequently the weight of the piston and valve rod, to which the tappets are attached, are not dependent upon the action of the steam to govern their relative positions to that of the main piston at different points of the stroke.

The breaking of the pump poles, due to the sudden reversal motion, is avoided in our Deep Well Engines, as the adjustment can be so made that the reversal motion will be slow and easy at either end, thus allowing the Pump to properly fill.

Sight Feed Lubricator, Drain Cocks, Plugs and Spanner Wrench are furnished with each outfit.

FIG. 1057. SIZES, PRICES, ETC.

SIZES AND PRICES.  
COMBINED AIR CHAMBER AND DIS-  
CHARGE CHECK VALVE.

STEAM CYL.		Steam Pipe.	Exhaust Pipe.	STEAM END ONLY.	
Dia.	Stroke.			Cipher.	Price.
5 in.	24 in.	3/4 in.	1 in.	Mobaca	\$225.00
5 "	36 "	3/4 "	1 "	Mobadu	250.00
6 "	24 "	1 "	1 1/4 "	Mobafs	250.00
6 "	36 "	1 "	1 1/4 "	Mobago	300.00
7 "	24 "	1 1/4 "	1 1/2 "	Mobick	300.00
7 "	36 "	1 1/4 "	1 1/2 "	Mobopa	315.00
8 "	24 "	1 1/4 "	1 1/2 "	Moboqu	315.00
8 "	36 "	1 1/4 "	1 1/2 "	Mobuda	325.00
9 "	24 "	1 1/2 "	2 "	Mobuel	325.00
9 "	36 "	1 1/2 "	2 "	Mobufu	350.00
10 "	24 "	1 1/2 "	2 "	Mobugs	350.00
10 "	36 "	1 1/2 "	2 "	Mobuim	375.00
11 "	24 "	2 "	2 1/2 "	Mobujg	415.00
11 "	36 "	2 "	2 1/2 "	Mobuka	450.00
12 "	24 "	2 "	2 1/2 "	Mobulm	450.00
12 "	36 "	2 "	2 1/2 "	Mobumo	500.00
14 "	24 "	2 "	2 1/2 "	Mobund	675.00
14 "	36 "	2 "	2 1/2 "	Moburt	750.00

Size Well.	Size Check Valve.	Price.
3 in. and smaller	2 in.	\$12.00
3 1/2 "	2 1/2 "	14.00
4 "	2 1/2 "	14.00
4 1/2 "	3 "	16.25
5 "	3 "	16.25
6 "	3 1/2 "	21.00
7 "	3 1/2 "	21.00
8 "	4 "	24.50
10 "	5 "	27.00




FIG. 1057


For Cylinders, Rods, Couplings, etc., to use with this Steam Head, see pages 67-70.



## HAND AND HOUSE FORCE PUMPS.



Hand and House Force Pumps have an almost limitless application for pumping water to laundry tubs, kitchen sinks, upper floors for bath rooms, etc. A full line of this class of Pumps will be found between pages 115 and 129.





# GOULDS HOUSE FORCE PUMPS.

115

WITH CHECK VALVE AND REVOLVING FULCRUM

Fig. 390 represents our House Force Pump on base with upper check valve discharge. It has brass-cased piston rod, working through brass gland and attached to lever by links.




FIG. 390

Fig. 391 represents our House Force Pump on plank, with upper check valve discharge. It has brass-cased piston rod, working through brass gland and attached to lever by links. Pump furnished without plank at fifty cents less list. These figures represent a very popular style of Force Pumps for house use over sink, for tank pumping, etc. Below we list with Polished Iron Cylinder, Brass-Lined Cylinder and Brass Body Cylinder. Special Brass Pumps made to order. Pump Cylinder can be emptied of water by raising lever to extreme height, thus tripping valves.

Regular fitting, Iron Pipe. Fitted for lead pipe to order.




FIG. 391

FIG. 390. SIZES, PRICES, ETC.

No.	Diameter. Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	* Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe.	60 ft.	Child	\$9.00	Holejlm	\$11.50	Cart	\$13.50
2	2½ "	6 "	.13 "	1¼ "	1¼ "	60 "	Chind	9.50	Holekad	12.00	Drum	14.00
4	3 "	6 "	.18 "	1½ "	1½ "	60 "	Cited	11.00	Holeklg	13.50	Dry	16.00
6	3½ "	7½ "	.31 "	1½ "	1½ "	40 "	Curdy	17.00	Hoopist	20.50	Cured	24.00
8	4 "	7½ "	.41 "	2 "	1½ "	40 "	Cure	18.00	Hoopltu	23.00	Curfue	30.00

\* Total lift and force from water to point of delivery, Pump not more than 25 feet above water.

FIG. 391. SIZES, PRICES, ETC.

No.	Diameter. Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	* Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe.	1 in. pipe	60 ft.	Chime	\$9.00	Hoopiux	\$11.50	C-se	\$13.50
2	2½ "	6 "	.13 "	1¼ "	1¼ "	60 "	Chippy	9.50	Hoopiva	12.00	Ducat	14.00
4	3 "	6 "	.18 "	1½ "	1½ "	60 "	City	11.00	Hoopiwa	13.50	Duchy	16.00
6	3½ "	7½ "	.31 "	1½ "	1½ "	40 "	Curly	17.00	Hoopja	20.50	Current	24.00
8	4 "	7½ "	.41 "	2 "	1½ "	40 "	Curly	18.00	Hoopjll	23.00	Currier	30.00

\* Total lift and force from water to point of discharge, Pump not more than 25 feet above water.

# GOULDS HOUSE FORCE PUMPS.

WITH AIR CHAMBER AND REVOLVING FULCRUM.

Fig. 392 represents our House Force Pump on base, having upward discharge air chamber and brass cased rod working through brass gland and attached to lever by links.

Fig. 393 represents our House Force Pump on plank, having upward discharge air chamber and brass cased rod working through brass gland and attached to lever by links. Pumps furnished without plank at 50 cents less list.

These are most popular styles of Force Pumps for house use, for tank pumping, etc.

Below we list them made with polished iron cylinder, brass-lined cylinder and brass body cylinder. Special brass Pumps made to order.

Pump cylinder may be emptied of water by raising lever to extreme height, thus tripping valve.

Regular fitting, iron pipe. Fitted for lead pipe to order.



FIG. 392




FIG. 393

FIG. 392. SIZES, PRICES, ETC

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe	75 ft.	Carviol	\$9.50	Hoopjot	\$12.00	Carvkog	\$14.00
2	2½ "	6 "	.13 "	1¼ "	1¼ "	75 "	Chirp	10.00	Hoopjug	12.50	Duck	14.50
4	3 "	6 "	.18 "	1¼ "	1¼ "	75 "	Cavil	12.00	Hourly	14.50	Due	17.00
6	3½ "	7½ "	.31 "	1½ "	1½ "	50 "	Vacancy	19.00	Hourmo	22.50	Vacate	26.00
8	4 "	7½ "	.41 "	2 "	1½ "	50 "	Vacant	20.00	Hournal	25.00	Vacatid	32.00

FIG. 393. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe	75 ft.	Carvman	\$9.50	Houros	\$12.00	Buoma	\$14.00
2	2½ "	6 "	.13 "	1¼ "	1¼ "	75 "	Chop	10.00	Houoto	12.50	Dual	14.50
4	3 "	6 "	.18 "	1¼ "	1¼ "	75 "	Claim	12.00	Houruba	14.50	Duel	17.00
6	3½ "	7½ "	.31 "	1½ "	1½ "	50 "	Vaccary	19.00	Hourve	22.50	Vacuato	26.00
B	4 "	7½ "	.41 "	2 "	1½ "	50 "	Vaccine	20.00	Hutcka	25.00	Vacuaso	32.00

\* Total lift and force from water to point of discharge, Pump not more than 25 feet above water.

# GOULDS HOUSE FORCE PUMPS.

117

WITH AIR CHAMBER, COCK SPOUT AND REVOLVING FULCRUM




FIG. 394

Fig. 394 represents our Hand Force Pump on base with double discharge air chamber and cock.

Fig. 395 represents our Hand Force Pump on plank, with double discharge air chamber and cock spout. Furnished without plank at fifty cents less list.

Figs. 394 and 395 are exceedingly popular Force Pumps for house use over kitchen sinks. By opening or closing the cock. Pump is made to deliver either at the spout or to storage tank above, as desired. Also popular for stable and out-door use. Pump cylinder can be emptied to prevent freezing by raising lever to extreme height, thus tripping the valve.

Below we list these Pumps, made with Polished Iron Cylinders, with Brass-Lined and with Brass Body Cylinder. Special Brass Pumps made to order.

Regular fitting, iron pipe. Fitted for lead pipe to order.



FIG. 395

FIG. 394. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke	Suction.	DISCHARGES.		* Lift and Force.	IRON.		BRASS-LINED.		BRASS-CYL.	
					Top of Air-Chamber.	Nose of Cock.		Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe	1 in. hose	75 ft.	Diggub	\$12.00	Hutckin	\$14.50	Digha	\$16.50
2	2 1/2 "	6 "	.13 "	1 1/4 "	1 1/4 "	1 "	75 "	Drone	12.50	Hutckos	15.00	Duger	17.00
4	3 "	6 "	.18 "	1 1/4 "	1 1/4 "	1 "	75 "	Dross	14.50	Hutckul	17.00	Duke	19.50
6	3 1/2 "	7 1/2 "	.31 "	1 1/2 "	1 1/2 "	1 "	50 "	Cut	21.50	Hutbac	25.00	Cutlas	28.50
8	4 "	7 1/2 "	.41 "	2 "	1 1/2 "	1 "	50 "	Cycle	22.50	Hutbil	27.50	Cygnat	34.50

FIG. 395. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		* Lift and Force.	IRON.		BRASS-LINED.		BRASS CYL.	
					Top of Air-Chamber.	Nose of Cock.		Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe	1 in. hose	75 ft.	Dighim	\$12.00	Hutbims	\$14.50	Dighot	\$16.50
2	2 1/2 "	6 "	.13 "	1 1/4 "	1 1/4 "	1 "	75 "	Drop	12.50	Hutbino	15.00	Duly	17.00
4	3 "	6 "	.18 "	1 1/4 "	1 1/4 "	1 "	75 "	Drove	14.50	Hutbore	17.00	Dumb	19.50
6	3 1/2 "	7 1/2 "	.31 "	1 1/2 "	1 1/2 "	1 "	50 "	Curt	21.50	Hutbud	25.00	Curtail	28.50
8	4 "	7 1/2 "	.41 "	2 "	1 1/2 "	1 "	50 "	Curve	22.50	Hutbwo	27.50	Curved	34.50

\* Total lift and force from water to point of discharge, Pump not more than 25 feet above water.



# GOULDS HOUSE FORCE PUMPS.

WITH DOUBLE DISCHARGE AIR CHAMBER AND REVOLVING FULCRUM.



FIG. 398

Fig. 398 represents our House Force Pump on base, with horizontal discharge air chamber. The brass cased piston rod works through brass gland and is attached to lever by links.

Fig. 399 represents our House Force Pump on plank, with horizontal discharge air chamber. Brass cased piston rod works through brass gland and is attached to lever by links. Furnished without plank at 50 cents less list.

These pumps are extremely popular for house pumping, being often set over kitchen sink. Also for filling house tanks; and in warm climates used out of doors. Pump cylinder can be emptied of water by raising lever to extreme height, thus tripping valve.

Below we list with Polished Iron Cylinder, Brass-Lined Cylinder and Brass Body Cylinder. Special Brass Pumps made to order. Regular fitting, iron pipe. Fitted for lead pipe to order.




FIG. 399

FIG. 398. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. hose	75 ft.	Dighyer	\$10.50	Hutcat	\$13.00	Dinhus	\$15.00
2	2½ "	6 "	.13 "	1¼ "	1 "	75 "	Chuck	11.00	Hutcase	13.50	Dunac	15.50
4	3 "	6 "	.18 "	1¼ "	1 "	75 "	Clamy	13.00	Hutcela	15.50	Dunce	18.00
6	3½ "	7½ "	.31 "	1½ "	1 "	50 "	Vagous	20.00	Idlist	23.50	Vagrant	27.00
8	4 "	7½ "	.41 "	2 "	1 "	50 "	Vagrancy	21.00	Idlite	26.00	Vague	33.00

FIG. 399. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. hose	75 ft.	Dinib	\$10.50	Idlive	\$13.00	Dinite	\$15.00
2	2½ "	6 "	.13 "	1¼ "	1 "	75 "	Churn	11.00	Idljay	13.50	Dupe	15.50
4	3 "	6 "	.18 "	1¼ "	1 "	75 "	Clamper	13.00	Idljibs	15.50	Dusk	18.00
6	3½ "	7½ "	.31 "	1½ "	1 "	50 "	Vailers	20.00	Idljocs	23.50	Vain	27.00
8	4 "	7½ "	.41 "	2 "	1 "	50 "	Vailing	21.00	Idljugs	26.00	Vainly	33.00

\*Total lift and force from water to point of discharge, Pump not more than 25 feet above water.

# GOULDS "UNIVERSE" HAND FORCE PUMP.

119

FOR HOUSE OR DRIVE WELL USE.




FIG. 1168

Fig. 1168 is an easy working, compact and substantial Hand Force Pump, well adapted for house pumping, furnishing water either at spout or through opening at back to storage tank. Also for outdoor use over drive wells, etc. We offer these pumps with oil polished iron cylinder and nickel-plated brass cylinder. Both iron and brass cylinder pumps have brass cased plunger rod, brass gland and revolving bearer attached with through bolts. Brass Cylinder Pump has galvanized plunger. When so ordered, spout is provided with shut-off cap, attached by swivel and chain.

Fig. 1169 differs from Fig. 1168 only in that it carries brass-fitted compression cock spout.

Either pump fitted for lead pipe suction at slight extra charge if so ordered.




FIG 1169

FIG. 1168. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		IRON.		NICKEL-PLATED, BRASS CYLINDER.	
					Spout.	Back Outlet.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	4 in.	.09 gals.	1¼ in. pipe	1 in. hose	1 in. pipe	Maltyot	\$7.50	Vibreck	\$10.00
6	3½ in.	4 in.	.17 "	1½ in. "	1 "	1 "	Maltyis	10.00	Maltyul	12.50

FIG. 1169. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		IRON.		NICKEL-PLATED, BRASS CYLINDER.	
					Spout.	Back Outlet.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	4 in.	.09 gals.	1¼ in. pipe	1 in. hose	1 in. pipe	Mamar	\$10.00	Vibreel	\$12.50
6	3½ in.	4 in.	.17 "	1½ in. "	1 "	1 "	Mamel	12.50	Mamemo	15.00

# GOULDS IMPROVED BRASS HOUSE FORCE PUMP.

ON IRON FRAME WITH REVOLVING LEVER

Fig. 1122 represents our Improved Brass House Force Pump on iron frame with revolving lever. Lever may be moved to any position most convenient to operate the Pump. The change of position involves no removing of nuts and bolts. The Pump is so constructed that by releasing one set screw and unscrewing the guide bushing and cap, the plunger may be drawn out without disturbing the pipe connections. This is claimed as a feature of many Pumps of this kind, but is only true in Goulds Improved House Force Pump.

Fig. 1241 represents the same Pump with air chamber.

We can fit both suction and discharge for either hose or iron pipe if so ordered, but regularly fit as given in our table below.




FIG. 1122




FIG. 1241

FIG. 1122. SIZE, PRICE, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	Cipher.	Brass.
1 13-16 in.	3½ in.	.04 gal.	1 in. lead pipe	1 in. gas pipe	50 ft.	Fustko	\$10.00

FIG. 1241. SIZE, PRICE, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	Cipher.	Brass.
1 13-16 in.	3½ in.	.04 gal.	1 in. lead pipe	¾ in. hose	75 ft.	Maltud	\$14.00

\* Total lift and force from water to point of delivery, Pump not more than 25 feet above water.



# GOULDS HOUSE FORCE PUMP.

121

WITH CRANK SHAFT AND FLY WHEEL.

Fig. 1243 represents a Suction and Force Pump arranged with crank shaft and fly-wheel.

Recognizing the fact that lever pumps are rarely, if ever, worked to their full length of stroke and that many prefer the crank motion, we have been enabled to shorten the stroke and yet to obtain the same results as from a longer stroke lever Pump, operated in the usual manner.

The addition of cock in air chamber permits water being discharged at point of operation as well as at a distance removed.

FIG. 1243. SIZES, PRICES, ETC.

No.	Dia.	Cyl.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		IRON.		BRASS-LINED.	
						Top of Air Chamber.	Nose of Cock.	Cipher.	Price.	Cipher.	Price.
2	2½ in.		2½ in.	.05 gal.	1¼ in. pipe.	1¼ in pipe.	1 in. hose.	Napklo	\$20.50	Naplot	\$23.00
4	3 "		2½ "	.08 "	1¼ "	1¼ "	1 "	Naplig	22.50	Numef	25.00




FIG. 1243

# GOULDS DOUBLE-ACTING HOUSE FORCE PUMP.

WITH CRANK SHAFT AND FLY-WHEEL.

The Pump, represented herewith is but a modification of our new style "Atlantic" Double-Acting Suction and Force Pump, arranged with crank shaft and fly-wheel. Cock in spout permits discharge to be made from top of air chamber to tank above or wherever desired.

The Valves, of a new and improved style, are all grouped in valve box in front and easy of access.

Plugs are provided for emptying Pump of water in cold weather.

FIG. 1242. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Revolution.	Suction.	DISCHARGES.		IRON.		BRASS-LINED.	
					Top of Air Chamber.	Nose of Cock.	Cipher.	Price.	Cipher.	Price.
4	3 in.	2½ in.	.15 gal.	1½ in. pipe.	1½ in. pipe.	1 in. hose.	Napjat	\$38.00	Napkil	\$40.50




FIG. 1242

# GOULDS HOUSE FORCE PUMPS.

MOUNTED ON PLANK, RIGHT OR LEFT HANDED.

Fig. 440 represents our Single-Acting Suction and Force Pump, with brass-cased plunger rod, pitman and guide, mounted on plank, for indoor use, and can be made either right or left handed.

It is generally employed for lifting water from wells or cisterns and forcing it up into more elevated parts of the house for bath-rooms, tanks, etc. Plumbers, wishing to attach copper air chambers, usually select this style. The check valve can be removed and air chamber substituted without extra fitting.

Fig. 441 represents the same Pump with the addition of an air chamber which insures a continuous stream of water and relieves the pipe from the concussion of the water.

Brass Cylinder Pumps have Brass Plungers.

Brass Air Chambers and All-Brass Pumps made to order.

Pumps furnished without planks, \$1.00 less list.




FIG. 440



FIG. 441

FIG. 440. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.09 gal.	1 in. pipe	1 in. pipe	80 ft.	Flit	\$15.00	Lenafx	\$17.50	Dyer	\$20.00
2	2 1/2 "	7 "	.15 "	1 1/4 "	1 1/4 "	60 "	Float	15.50	Lenagy	18.00	Eacher	20.50
3	2 3/4 "	7 "	.18 "	1 1/4 "	1 1/4 "	60 "	Flock	16.00	Lenagzu	19.00	Eady	22.00
4	3 "	7 "	.21 "	1 1/4 "	1 1/4 "	60 "	Flog	16.50	Lenahow	20.00	Eager	23.50
5	3 1/4 "	7 "	.25 "	1 1/2 "	1 1/2 "	40 "	Flopa	20.00	Lenahud	24.00	Eagerly	28.00
6	3 1/2 "	7 "	.29 "	1 1/2 "	1 1/2 "	40 "	Flora	22.00	Lenahyx	26.50	Earing	32.00

FIG. 441. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.09 gal.	1 in. pipe	1 in. pipe	100 ft.	Floss	\$17.00	Lenaid	\$19.50	Earn	\$22.00
2	2 1/2 "	7 "	.15 "	1 1/4 "	1 1/4 "	75 "	Flour	17.50	Lenafu	20.00	Earth	22.50
3	2 3/4 "	7 "	.18 "	1 1/4 "	1 1/4 "	75 "	Flout	18.00	Lenajoe	21.00	Earwig	24.00
4	3 "	7 "	.21 "	1 1/4 "	1 1/4 "	75 "	Flow	18.50	Listmae	22.00	Ease	25.50
5	3 1/4 "	7 "	.25 "	1 1/2 "	1 1/2 "	50 "	Flown	23.00	Listmlc	27.00	Easel	31.00
6	3 1/2 "	7 "	.29 "	1 1/2 "	1 1/2 "	50 "	Fluid	25.00	Listmoq	29.50	Easily	35.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# GOULDS HOUSE FORCE PUMPS.

123

Fig. 442 represents our House Force Pump with air chamber and cock through which water can be drawn at pump. This cock spout can be exchanged for brass tube, cut for iron pipe, at a \$1.50 less list.

Pumps furnished without plank, \$1.00 less list.

Fig. 281 represents a House Force Pump adapted for deep wells or any place where it is desired to operate Pump at some distance above water. The following should be observed in placing these Pumps: At, say, 15 or 20 feet from the bottom of well secure Pump to a timber or plank. At convenient height above locate lever and spout air chamber. Connect the air chamber above with the one below by pipe. Join the stub end attached to the lever to the stub end of the Pump by the necessary length of rod.

When ordered without spout air chamber, a deduction of \$1.00 in list will be made.

Brass Air Chamber and All-Brass Pumps made to order.




FIG. 442




FIG. 281

FIG. 442. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	DISCHARGES.		*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYL.	
					Top of Air Chamber.	Nose of Cock.		Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.09 gal.	1 in. pipe.	1 in. pipe.	1 in. hose.	100 ft.	Fluke	\$19.50	Hipluc	\$22.00	Fog	\$24.50
2	2½ "	7 "	.15 "	1¼ "	1¼ "	1 "	75 "	Flume	20.00	Hipluda	22.50	Foil	25.00
3	2¾ "	7 "	.18 "	1½ "	1½ "	1 "	75 "	Flung	20.50	Hiplufd	23.50	Foiler	26.50
4	3 "	7 "	.21 "	1¾ "	1¾ "	1 "	75 "	Flush	21.00	Hipluga	24.50	Fold	28.00
5	3¼ "	7 "	.25 "	1½ "	1½ "	1 "	50 "	Flute	26.00	Hipluhu	30.00	Folder	34.00
6	3½ "	7 "	.29 "	1½ "	1½ "	1 "	50 "	Flusha	28.00	Himal	32.50	Foliage	38.00

FIG. 281. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.		BRASS CYL.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.09 gal.	1 in. pipe.	1 in. pipe.	75 ft.	Dandy	\$17.00	Himeta	\$19.50	Holeci	\$22.00
2	2½ "	7 "	.15 "	1¼ "	1¼ "	50 "	Dane	17.50	Himevo	20.00	Holedo	22.50
3	2¾ "	7 "	.18 "	1½ "	1½ "	50 "	Danker	18.00	Himfa	21.00	Holefu	24.00
4	3 "	7 "	.21 "	1¾ "	1¾ "	50 "	Darell	18.50	Himfig	22.00	Holega	25.50
5	3¼ "	7 "	.25 "	1½ "	1½ "	35 "	Dared	23.00	Himgal	27.00	Holeho	31.00
6	3½ "	7 "	.29 "	1½ "	1½ "	35 "	Dark	25.00	Holeba	29.50	Holeiku	35.00

\* Total lift and force from supply to point of delivery, Pumps not more than 25 feet above water.



# GOULDS HOUSE FORCE PUMPS.

FOR HAND AND MACHINE POWER.

Fig. 480 represents our House Force Pump, with pitman, guide and guide rod, but with disconnected rod above, adapted for deep wells or any place where it is desired to operate Pump at some distance above water.

The cylinder can be placed at the bottom of well or cistern, or within, say, fifteen or twenty feet (suction distance) of water. At convenient height above locate lever and join the stub end attached to the lever to the stub end of the Pump by connecting rod

Brass Pumps made to order.

Fig. 714 represents our Single-Acting Force Pump without lever, bearer and cock, but with the pitman and guide arranged for power. Counter shafts, Figs. 711, 650, 650½, pages 102 and 103, may be employed to operate.

Brass Pumps made to order.

Pumps furnished without planks, \$1.00 less list.




FIG. 480




FIG. 714

FIG. 480. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke	Suction.	Discharge.	* Lift and Force.	IRON.		BRASS-LINED.		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.09 gal.	1 in. pipe	1 in. pipe	80 ft.	Grass	\$14.00	Hencipa	\$16.50	Hewjost	\$19.00
2	2½ in.	7 "	.15 "	1¼ in. pipe	1¼ in. pipe	60 "	Grate	14.50	Hewioc	17.00	Hewjuga	19.50
3	2¾ in.	7 "	.18 "	1½ in. pipe	1½ in. pipe	60 "	Gray	15.00	Hewips	18.00	Highac	21.00
4	3 in.	7 "	.21 "	1¾ in. pipe	1¾ in. pipe	60 "	Graze	15.50	Hewirt	19.00	Highil	22.50
5	3¼ in.	7 "	.25 "	1½ in. pipe	1½ in. pipe	40 "	Greet	19.00	Hewisa	23.00	Highob	27.00
6	3½ in.	7 "	.29 "	1½ in. pipe	1½ in. pipe	40 "	Grew	21.00	Hewjon	25.50	Highud	31.00

FIG. 714. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	* Lift and Force.	IRON.		BRASS-LINED		BRASS CYLINDER.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	7 in.	.15 gal.	1¼ in. pipe	1¼ in. pipe	75 ft.	Textok	\$17.00	Highso	\$19.50	Warry	\$22.00
3	2¾ in.	7 "	.18 "	1½ in. pipe	1½ in. pipe	75 "	Thaw	17.50	Hiplid	20.50	Warsong	23.50
4	3 in.	7 "	.21 "	1¾ in. pipe	1¾ in. pipe	75 "	Thorn	18.50	Hiplifa	22.00	Warsunk	25.50
5	3¼ in.	7 "	.25 "	1½ in. pipe	1½ in. pipe	50 "	Throb	23.00	Hiploe	27.00	Wart	31.00
6	3½ in.	7 "	.29 "	1½ in. pipe	1½ in. pipe	50 "	Tick	25.00	Hiploma	29.50	Warted	35.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

# GOULDS HOUSE FORCE PUMPS.

125

*MOUNTED ON PLANK, WITH CRANK AND BALANCE WHEEL.*




FIG. 712

Fig. 712 shows our Single-Acting House Force Pump, with check valve, mounted on plank, with crank shaft and balance wheel, which will be found a welcome substitute for the ordinary lever where any considerable quantity of water is to be raised.

Fig. 713 is the same pump arranged with air chamber instead of check valve, and we recommend this form where water is to be lifted any distance above pump.

Cock added to air chamber at \$2.50 extra list.

We can also furnish our Double-Acting Pumps, like Figs. 271 and 273, page 126, mounted in the same way, if desired. We give lists on both kinds of pumps below.

In ordering, always state whether you want a Single or Double-Acting Pump.

Pumps furnished without planks, \$1.00 less list.

Brass-Lined, Brass Cylinder or Brass Pumps made to order at proportionate prices.




FIG. 713

FIG. 712. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Suction.	Discharge.	*Lift and Force.	SINGLE-ACTING PUMP.			DOUBLE-ACTING PUMP.		
						Capacity per Stroke.	Cipher.	Iron.	Capacity per Rev.	Cipher.	Iron.
2	2½ in.	7 in.	1¼ in. pipe	1¼ in. pipe	80 ft.	.15 gal.	Tabor	\$27.00	.30 gal.	Talon	\$29.00
3	2¾ in.	7 "	1¼ "	1¼ "	60 "	.18 "	Tack	29.00	.36 "	Tame	33.00
4	3 "	7 "	1¼ "	1¼ "	60 "	.21 "	Tagar	32.00	.43 "	Tank	36.50
5	3¼ in.	7 "	1½ "	1½ "	40 "	.25 "	Tail	35.00			
6	3½ in.	7 "	1½ or 2 "	1½ or 2 "	40 "	.29 "	Tally	39.00	.58 "	Tansy	43.00

FIG. 713. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Suction.	Discharge.	*Lift and Force.	SINGLE-ACTING PUMP.			DOUBLE-ACTING PUMP.		
						Capacity per Stroke.	Cipher.	Iron.	Capacity per Rev.	Cipher.	Iron.
2	2½ in.	7 in.	1¼ in. pipe	1¼ in. pipe	100 ft.	.15 gal.	Tareat	29.00	.30 gal.	Teamo	\$31.50
3	2¾ in.	7 "	1¼ "	1¼ "	75 "	.18 "	Tartes	31.00	.36 "	Tearap	35.50
4	3 "	7 "	1¼ "	1¼ "	75 "	.21 "	Task	34.50	.43 "	Tenor	38.50
5	3¼ in.	7 "	1½ "	1½ "	50 "	.25 "	Taxdet	38.00			
6	3½ in.	7 "	2 "	2 "	50 "	.29 "	Teaba	42.00	.58 "	Tentap	46.00

\* Total lift and force from supply to point of delivery, Pumps not more than 25 feet above water.



# DOUBLE-ACTING HOUSE FORCE PUMPS.

MOUNTED ON PLANK. RIGHT OR LEFT HANDED.

Fig. 271 represents one of our well-known Double-Acting Force Pumps, mounted on plank, with check valve for house use. In explanation of a Double-Acting Pump would say that they lift and force water with both the upward and downward motions of the lever, giving double the quantity of water that a Single-Acting Pump of equal size would.

Fig. 273 represents one of our well-known Double-Acting Suction and Force Pumps, mounted on plank, with air chamber and cock spout. Can be arranged either right or left handed, and discharge may be made through top of air chamber or from spout.

Can furnish with plain air chamber for single or double discharge, or with check valve instead, at a reduction in price.

Pumps fitted for hot water with metallic valves at extra charge. Brass Cylinder and Brass Pumps made to order. Pumps furnished without planks, \$1.00 less list.




FIG. 271

No.	Dia. Cyl.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	IRON.		BRASS-LINED.	
						Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.19 gal.	1 1/4 in. pipe	1 1/4 in. pipe	Clump	\$16.50	Muncud	\$19.00
1	2 1/4 "	7 "	.24 "	1 1/4 "	1 1/4 "	Coach	16.50	Muncyx	19.00
2	2 1/2 "	7 "	.30 "	1 1/4 "	1 1/4 "	Coast	17.00	Mundar	19.50
3	2 3/4 "	7 "	.36 "	1 1/4 "	1 1/4 "	Coated	19.00	Mundask	22.00
4	3 "	7 "	.43 "	1 1/2 "	1 1/4 "	Coax	21.00	Mundem	24.50
6	3 1/2 "	8 "	.67 "	1 1/2 "	1 1/2 "	Codex	25.00	Mustama	29.50
8	4 "	8 "	.87 "	2 "	2 "	Coiled	37.00	Mustet	42.00
10	4 1/2 "	8 "	1.10 "	2 1/2 "	2 1/2 "	Coin	50.00	Mustevo	55.00

FIG. 271. SIZES, PRICES, ETC.




FIG. 273

FIG. 273. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	DISCHARGES FITTED.		*Lift and Force.	IRON.		BRASS-LINED.	
					Top of Air Chamber.	Nose of Cock.		Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.19 gal.	1 1/4 in. pipe	1 1/4 in. pipe	1 in. hose	100 ft.	Verdict	\$21.00	Mustib	\$23.50
1	2 1/4 "	7 "	.24 "	1 1/4 "	1 1/4 "	1 "	75 "	Verdigr	21.00	Musticl	23.50
2	2 1/2 "	7 "	.30 "	1 1/4 "	1 1/4 "	1 "	75 "	Verditer	21.50	Mustjaw	24.00
3	2 3/4 "	7 "	.36 "	1 1/4 "	1 1/4 "	1 "	75 "	Verdure	23.50	Mustjib	26.50
4	3 "	7 "	.43 "	1 1/2 "	1 1/4 "	1 "	75 "	Verecun	25.50	Napid	29.00
6	3 1/2 "	8 "	.67 "	1 1/2 "	1 1/2 "	1 "	50 "	Verge	31.00	Napiff	35.50
8	4 "	8 "	.87 "	2 "	2 "	1 "	50 "	Vergers	45.00	Napigs	50.00
10	4 1/2 "	8 "	1.10 "	2 1/2 "	2 1/2 "	1 "	40 "	Verging	58.00	Napiho	63.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# GOULDS HOUSE FORCE PUMPS.

127

FOR HAND AND POWER.




FIG. 449

Fig. 449 represents our Single-Acting Force Pump, on plank, with crank shaft, balance wheel and winch handle adapted for two to four men. When so ordered we can supply with 24-inch diameter, 3-inch face pulley balance wheel for belt, at \$1.00 extra list.

Fig. 450 represents our Double-Acting Force Pump with crank shaft, balance wheel and winch handles, adapted for two to four men. When so ordered, we can supply with 24-inch diameter, 3½-inch face pulley balance wheel for belt, at \$1.00 extra list or with 36 x 4-inch, at \$2.50 extra list.

Suction and discharge always fitted for wrought-iron pipe, although we can fit for lead pipe if so ordered.

Can also fit these and other Pumps of this class with metallic valves throughout for hot or corrosive liquids. Brass pumps made to order. We deduct \$1.00 from list given below when planks are not furnished.

FIG. 449. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	IRON.		BRASS-LINED.	
						Cipher.	Price.	Cipher.	Price.
0	2 in.	7 in.	.09 gal.	1¼ in. pipe	1¼ in. pipe	Frith	\$37.00	Moonki	\$39.50
2	2½ "	7 "	.15 "	1¼ "	1¼ "	Friz	39.00	Moonlat	41.50
3	2¾ "	7 "	.18 "	1¼ "	1¼ "	Frock	39.50	Mostol	42.50
4	3 "	7 "	.21 "	1¼ "	1¼ "	Frog	40.00	Mostyi	43.50
5	3¼ "	7 "	.25 "	1½ "	1½ "	Fromer	44.00	Motija	48.00
6	3½ "	7 "	.29 "	1½ "	1½ or 2 "	Front	48.00	Motiks	52.50



FIG. 450

FIG. 450. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Rev.	Suction.	Discharge.	Balance Wheel.	*Lift and Force.	IRON.		BRASS-LINED.	
								Cipher.	Price.	Cipher.	Price.
2	2½ in.	7 in.	.30 gal.	1¼ in. pipe	1¼ in. pipe	24 in.	75 ft.	Full	\$40.00	Muncjo	\$42.50
3	2¾ "	7 "	.36 "	1¼ "	1¼ "	24 "	75 "	Fume	42.00	Muncku	45.00
4	3 "	7 "	.43 "	1½ "	1¼ "	24 "	75 "	Funab	45.00	Muncia	48.50
6	3½ "	7½ "	.62 "	1½ "	1½ "	36 "	50 "	Fund	55.00	Muncme	59.50
8	4 "	7½ "	.82 "	2 "	2 "	36 "	50 "	Fur	65.00	Muncny	70.00
10	4½ "	7½ "	1.03 "	2½ "	2½ "	36 "	40 "	Fursa	80.00	Muncob	85.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

# GOULDS DOUBLE-ACTING HOUSE FORCE PUMPS.

*MOUNTED ON PLANK AND FITTED WITH COCK-SPOUT.*

Fig. 1233 represents our new Double-Acting House Force Pump, mounted on long plank, and provided with pitman and guide Valves are brass, leather-faced, and being grouped in valve chest are easily accessible by removing front plate. Piston is double cup-leather packed. Cock-spout is provided, thus affording necessary means of closing spout discharge when desiring to pump through discharge at top of air chamber to tank or elsewhere. Pumps furnished without cock spout, \$2.00 less list, without plank, \$1.00 less list.

Fig. 1234 represents the same Pump, mounted on heavy plank, with crank shaft, stub end, gib and key, plummer blocks, winch handle and fly-wheel, arranged for two to four men and capable of lifting or forcing large quantities of water. Pumps furnished without cock spout, \$2.00 less list, without plank, \$1.00 less list.

Fig. 1234, with 36 x 4 inch heavy pulley for belt substituted for either fly-wheel or handle at \$2.50 extra list.




FIG. 1233




FIG. 1234

FIG. 1233. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	† Suction Fitted for.	DISCHARGES FITTED.		* Lift and Force.	IRON.		BRASS-LINED.	
					Top of Air Chamber.	Cock Spout.		Cipher.	Price.	Cipher.	Price.
4	3 in.	6 in.	.37 gal.	1½ in. pipe	1½ in. pipe	1 in. hose	75 ft.	Meshub	\$30.00	Meshxur	\$33.50
6	3½ "	6 "	.50 "	2 "	2 "	1 "	50 "	Meshvu	37.50	Mesleen	42.50
8	4 "	6 "	.65 "	2 "	2 "	1 "	50 "	Meshwy	45.00	Mesleft	50.00

FIG. 1234. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	† Suction Fitted For.	DISCHARGES FITTED.		* Lift and Force.	IRON.		BRASS-LINED.	
					Top of Air Chamber.	Cock Spout.		Cipher.	Price.	Cipher.	Price.
4	3 in.	6 in.	.37 gal.	1½ in. pipe	1½ in. pipe	1 in. hose	75 ft.	Moawa	\$45.00	Moonhat	\$48.50
6	3½ "	6 "	.50 "	2 "	2 "	1 "	50 "	Moonel	55.00	Moonill	60.00
8	4 "	6 "	.65 "	2 "	2 "	1 "	50 "	Moongis	65.00	Moonja	70.00

† Suction and discharge can be fitted differently, but always sent as listed unless otherwise ordered.

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# GOULDS FORCE PUMP ON PLANK.

129

FOR HAND OR POWER.

Fig. 278 gives a good representation of a new pattern of Iron Force Pump, mounted on plank, for hand use. It is extra strong and heavy, fitted with leather valves and packings, and has no equal for forcing water into railroad station tanks, tubs in distilleries, breweries, etc., where one man's power is to be exerted.

Fig. 279 differs but slightly in construction from Pump described above, having the pitman forged with a stub end for connecting to face plate above.

For pumping hot liquids we fit them with metallic valves and packings at extra charge.

Brass Pumps made to order.

We deduct \$1.00 from list when ordered without plank.




FIG. 278




FIG. 279

FIG. 278. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.	
							Cipher.	Price.	Cipher.	Price.
8	4 in.	8 in.	.43 gal.	2 in. pipe	2 in. pipe	75 ft.	Cynic	\$30.00	Rawfel	\$35.00
12	5 "	10 "	.85 "	2½ "	2½ "	75 "	Czar	40.00	Rawfib	47.50
16	6 "	10 "	1.22 "	3 "	3 "	50 "	Dah	55.00	Reeffe	65.00

FIG. 279. SIZES, PRICES, ETC.


No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.	
							Cipher.	Price.	Cipher.	Price.
8	4 in.	8 in.	.43 gal.	2 in. pipe	2 in. pipe	75 ft.	Daily	\$30.00	Reeffo	\$35.00
12	5 "	10 "	.85 "	2½ "	2½ "	75 "	Daisy	40.00	Reefhe	47.50
16	6 "	10 "	1.22 "	3 "	3 "	50 "	Dairy	55.00	Reefhif	65.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.




# PIPING DIAGRAMS OF GOULDS WATER LIFTERS.

————— PIPES SHOWN IN FULL LINE CONTAIN COLD WATER. —————  
 PIPES SHOWN IN LIGHT LINE CONTAIN HOT WATER.



PUMPING SOFT WATER DIRECT TO FIXTURES  
WITHOUT USE OF STORAGE TANK.



PUMPING SOFT WATER TO TANK AND USING  
EXHAUST WATER.

Above engravings show two of the most economical plans for piping Water Lifters. These can be modified or elaborated to suit requirements. When pumping to tank without desiring to use exhaust water, Automatic Shut-off Valve is not required, and exhaust is piped into sewer.

# GOULDS "NEW DUPLEX" BRONZE WATER LIFTER.

131

FOR DIRECT SYSTEM OR TANK PUMPING.

Fig. 1250, "New Duplex" Bronze Water Lifter, is a hydraulic pumping engine operated by city water pressure, for automatically pumping rain water to storage tank or direct to fixtures, or increasing city water pressure for high buildings.


Tables on following page show the results which can be attained at either service, also the pumping capacity of machines.

For pumping direct to fixtures (no storage tank), always use "New Duplex" with *Automatic Shut-off Valve*, which shuts off the city water from the machine when plumbing fixtures are closed. When a fixture is opened, and thereby pressure on pump discharge relieved, the Automatic Shut-off opens and machine starts. When at rest there is no pressure on machine; all strain is relieved, and all "creeping" and wasting of water avoided. Only by this controlling principle can direct pumping be *satisfactory*.

Exhaust city water, after performing its function as power in pumping soft water to tank, can be used in kitchen or closets, and thereby an actual economy in city water consumption effected. For this plan, connect Automatic Shut-off to exhaust.

See piping diagram on previous page.

Automatic  
Shut-off Valve.



(Patent applied for.)




FIG. 1250

FIG. 1250. SIZES, PRICES, ETC.


No.	DIAMETER OF CYLINDER.		Stroke.	PIPE CONNECTIONS.				FIG. 1250, WITHOUT AUTO- MATIC SHUT-OFF.		FIG. 1250, WITH AUTOMATIC SHUT-OFF.	
	Power.	Pump.		Power Cylinders.		Pump Cylinders.		Cipher.	Price.	Cipher.	Price.
				*Supply.	Exhaust.	Suction.	Discharge.				
0	2 in.	1½ in.	3 in.	½ in. pipe.	¾ in. pipe.	¾ in. pipe.	½ in. pipe.	Rusefat	\$40.00	Rusegun	\$45.00
1	2½ "	1½ "	3 "	¾ "	¾ "	¾ "	½ "	Rusefel	40.00	Rusegyl	45.00
3	2 "	2 "	3 "	¾ "	¾ "	¾ "	¾ "	Rusefir	42.50	Ruseham	47.50
4	2½ "	2 "	3 "	¾ "	¾ "	¾ "	¾ "	Rusego	45.00	Rusehen	50.00

\* If more than 10 feet of this pipe is required, a size larger than given in table should be used to avoid friction loss and consequent reduction of pressure.

# GOULDS DUPLEX WATER LIFTER.

A PUMP OPERATED BY WATER PRESSURE.

Automatic  
Shut-off Valve.



(Patent applied for.)




FIG. 935

Fig. 935, Duplex Water Lifter, is built in larger sizes and differs somewhat in design and details of construction from the "New Duplex," shown on page 131. It can be used to supply tanks, or, by the addition of automatic *shut-off* valve, can be used to pump direct to fixtures. The cylinder is brass-lined and all valves and working parts are brass.

Furnished with fibrous or metallic packed pistons, for hot water or acids, to order.

Table of pumping power and capacity on following page,

FIG. 935. SIZES, PRICES, ETC.

No.	DIAMETER OF CYLINDERS.		Stroke.	SIZES OF PIPE CONNECTIONS.				WITHOUT AUTOMATIC SHUT-OFF.		WITH AUTOMATIC SHUT-OFF.	
	Power.	Pump.		Power Cylinders.		Pump Cylinder.		Cipher.	Price.	Cipher.	Price.
				Supply.	Exhaust.	Suction.	Delivery.				
10	3 in.	2 in.	4 in.	1¼ in.	1½ in.	1¼ in.	1¼ in.	Worsepr	\$70.00	Ridejg	\$80.00
11	3 “	2½ “	4 “	1¼ “	1½ “	1½ “	1¼ “	Wrassid	75.00	Rideki	85.00
12	3 “	3 “	4 “	1½ “	1½ “	1½ “	1¼ “	Wrather	80.00	Ridels	90.00



# PUMPING POWER AND CAPACITY OF WATER LIFTERS. 133

FIG. 1250. "NEW DUPLEX."

Diameter Power Cylinders.....	2 in.	2½ in.	2 in.	2½ in.	2 in.	2½ in.	2 in.	2½ in.	2 in.	2½ in.	2 in.	2½ in.
Diameter Pump Cylinders.....	1½ "	1½ "	2 "	2 "	1½ "	1½ "	2 "	2 "	1½ "	1½ "	2 "	2 "
Gallons Pumped per Hour at 30 Revolutions per Minute.....	165	165	295	295	165	165	295	295	165	165	295	295
Gallons Exhausted per Hour at 30 Revolutions per Minute.....	295	455	295	455	295	455	295	455	295	455	295	455
<b>CITY WATER PRESSURE.</b>	Exhausting Freely Will Pump Cistern Water to Elevations as Given Below.				Elevating Exhaust Water 15 Feet Will Pump Cistern Water to Elevations as Given Below.				Exhausting Freely Will Pump City Water to Elevations as Given Below.			
15 lbs.....	35 ft.	55 ft.				30 ft.			70 ft.	110 ft.	40 ft.	60 ft.
20 ".....	50 "	75 "		40 ft.	30 ft.	45 "		25 ft.	100 "	150 "	50 "	80 "
25 ".....	60 "	90 "	30 ft.	50 "	40 "	65 "	25 ft.	35 "	120 "		60 "	100 "
30 ".....	70 "	110 "	40 "	60 "	50 "	80 "	30 "	45 "	140 "		80 "	120 "
35 ".....	80 "	130 "	45 "	70 "	65 "	100 "	35 "	55 "			90 "	140 "
40 ".....	95 "		55 "	80 "	75 "	120 "	45 "	65 "			110 "	
45 ".....	105 "		60 "	90 "	90 "		50 "	75 "			120 "	
50 ".....			65 "	100 "	100 "		55 "	85 "			140 "	
60 ".....							70 "	105 "				
70 ".....							85 "	125 "				
80 ".....							95 "					

FIG. 935. DUPLEX WATER LIFTER.

Diameter Power Cylinders.....	3 in.	3 in.	3 in.	3 in.	3 in.	3 in.	3 in.	3 in.	3 in.	3 in.
Diameter Pump Cylinders.....	2 "	2½ "	3 "	2 "	2½ "	3 "	2 "	2½ "	3 "	3 "
Gallons Pumped per hour at 30 Revolutions per Minute.....	390	610	880	390	610	880	390	610	880	880
Gallons Exhausted per Hour at 30 Revolutions per Minute.....	880	880	880	880	880	880	880	880	880	880
<b>CITY WATER PRESSURE.</b>	Exhausting Freely will Pump Cistern Water to Elevations as Given Below.			Elevating Exhaust Water 15 Feet Will Pump Cistern Water to Elevations as Given Below.			Exhausting Freely Will Pump City Water to Elevations as Given Below.			
15 lbs.....	45 ft.	30 ft.		25 ft.			90 ft.	60 ft.	40 ft.	
20 ".....	60 "	40 "		40 "	25 ft.		120 "	80 "	50 "	
25 ".....	75 "	50 "	35 ft.	55 "	35 "	25 ft.		100 "	70 "	
30 ".....	90 "	60 "	40 "	70 "	45 "	30 "		120 "	80 "	
35 ".....	105 "	70 "	45 "	85 "	55 "	35 "			90 "	
40 ".....		80 "	55 "	100 "	65 "	45 "			110 "	
45 ".....		90 "	60 "		75 "	50 "			120 "	
50 ".....		100 "	70 "		85 "	55 "			135 "	
60 ".....			80 "		105 "	70 "				
70 ".....			95 "			85 "				
80 ".....			110 "			95 "				

For Piping Diagrams, see page 130.



*HYDRAULIC RAM IN OPERATION SEE PAGES 135 TO 137.*



*FOR SUPPLYING DWELLINGS, HOTELS, FACTORIES, RAILROAD STATIONS STOCK  
YARDS, ETC., WITH RUNNING WATER.*

**THE HYDRAULIC RAM AS WE BUILD IT** to-day represents the most efficient and automatic labor-saving device known for raising water any distance where a sufficient supply and head are attainable, and the slight expense for first outlay and maintenance considered render them most desirable for supplying running water in any quantity. With an experience of 35 years in their manufacture, and a practical knowledge of the requirements necessary for their successful operation, we are able to offer the most efficient Ram in the market. Our castings are all heavy in pattern and of proportionate strength. The air chambers are larger than those of any other Ram, thus relieving it of all undue strain and aiding its working, while the valve stem and case (made of the best bronze metal) are of a new and improved design, calculated to develop the greatest possible efficiency. Reference to our engravings will show in a measure how these Rams have been strengthened in all parts, while we can still further increase their efficiency by substituting a new and improved style of brass poppet or spring valve in place of the ordinary leather one in the air chamber, thus rendering them metallic fitted throughout. The conditions and requirements under which rams are operated are so varied that we have thought best to treat these under separate heads.

**HEAD OR FALL OF DRIVE PIPE.**—Rams will work successfully where the spring or brook is only three feet higher than the Ram; yet, as the height or head increases, the more powerful the Ram operates, and its ability to force water to greater elevation and distance correspondingly strengthened. The best results will be secured where the head of fall is proportioned to work. See table, etc.

**SIZE AND LENGTH OF DRIVE PIPE.**—Size of drive pipes has been determined for each size of Ram, after years of experiment and practical use. Do not change it. Practical experience and experiments have proven that the best results are obtained where there is ample, though not excessive, length as well as fall to the drive pipe, for the weight of this volume of water is an important auxiliary in forcing water into the air chamber and through the delivery pipe. We recommend drive pipes to be 50 to 75 feet in length, though in very heavy lifts this may be advantageously increased to 125 feet.

Friction of water in pipes will prevent good results if the Ram with a small drive pipe be placed too far from the water supply; the larger the drive pipe, the longer it can be successfully made.

**WATER FURNISHED RAM.**—The quantity of water furnished a Ram, or amount requisite to operate it, is determined by the size and fall of head of drive pipe. Where the supply water is limited there is no simpler or better plan of determining this quantity than to measure in pails or barrels the number of gallons which can be led in pipes from the spring or brook per minute or in any given length of time.

**WATER RAISED AND WASTED.**—The relative height of the spring or supply above the Ram, and the elevation to which it is required to raise, determine the relative proportion between the water raised and wasted — the quantity raised varying according to the height it is conveyed with a given fall; also, the distance the water has to be conducted, and consequent length of pipes, have some influence on the quantity delivered at the point of discharge, as the more extended pipes through which the water has to be forced by the Ram, the more friction there is to overcome. See table, etc.



**DIRECTIONS FOR PLACING RAMS AND PIPES**—Do not use smaller discharge pipes than given in our tables, and where length be great it is advisable to increase size. Turns or bends in either drive or discharge pipe should be avoided, if possible. Where obliged to set the Ram with elbows in pipes, make these elbows as large as may be, so as to place as little obstruction to the free and easy flow of water as possible. Same considerations recommend the use of full way gate valves where required.

Ram should always be secured to heavy timbers or masonry and not left dependent merely upon pipe connections. This is important, as there is a constant concussion and strain upon the Ram, and it should be set on foundation as we recommend. Care should be taken to place a suitable strainer over the drive pipe to exclude all rubbish which might choke the pipes or Ram.

In the use of water from deep springs, it is sometimes difficult to keep an adequate supply of air in the air chamber. This can be avoided by drilling a very small hole in the side of the drive pipe near the Ram and inserting a little snifting valve, which is supplied with each Ram.

**BATTERIES OF RAMS**—We have frequent inquiries for Rams of greater capacity than we build, and to meet this demand offer a combination or battery of any number of Rams playing into a single discharge pipe, which possesses some advantages over the largest Rams which it might be practical or profitable to make.

At the same time, as above stated, these combinations offer certain advantages over Single Rams, for as each Ram receives its water through a separate drive pipe, the strain is not so great on pipe or Rams as if but one Ram were used, and then, too, in the event of accidents at any time the supply is not suspended, for each of the Rams acts independently of the others.

*TABLE OF PROPORTIONATE HEAD OF FALL GIVING HIGHEST EFFICIENCY IN  
OPERATION OF HYDRAULIC RAMS.*

To deliver Water to Height of	Place Ram under	Conducted through	*Any size Ram may be operated under these conditions and will afford the following approximate delivery :
20 Feet above Ram.	3 Feet Head of Fall.	† 30 Feet of Drive Pipe.	{ No. 2 require 2 to 3 gals. per min. and del. 10 to 15 gals. per hr.
30 " " " "	4 " " " "	30 " " " "	{ " 3 " 2 to 4 " " " 10 to 20 " "
40 " " " "	5 " " " "	40 " " " "	{ " 4 " 3 to 7 " " " 15 to 35 " "
50 " " " "	7 " " " "	50 " " " "	{ " 5 " 6 to 12 " " " 30 to 60 " "
60 " " " "	8 " " " "	60 " " " "	{ " 6 " 11 to 20 " " " 65 to 100 " "
80 " " " "	10 " " " "	80 " " " "	{ " 7 " 18 to 35 " " " 90 to 175 " "
100 " " " "	14 " " " "	100 " " " "	{ " 8 " 30 to 60 " " " 150 to 300 " "
120 " " " "	17 " " " "	125 " " " "	

† Where necessary head of fall cannot be had in length of drive pipe given, the same results can be secured by conveying water any distance necessary and placing an open stand pipe in line of drive pipe at point 50 to 75 feet (as required) from Ram.

\*It is assumed that the smaller Rams will not be selected for extreme high lift, as the friction loss of water in a small drive and discharge pipe renders their use impracticable.

Larger length of drive pipe may be used on larger Rams.

Where water supply will permit, always select Ram of ample size for requirements.

# GOULDS IMPROVED HYDRAULIC RAMS.

137

FIG. 345. SIZES, PRICES, ETC.




FIG. 345

Size.	Supply per Minute to Operate Ram.	Length of Drive Pipe, Feet.	PIPES.		Cipher.	*PRICE. Leather Valve.
			Drive.	Discharge.		
No. 2	1 to 2 gals.	50 to 75	$3\frac{1}{4}$ in.	$1\frac{1}{2}$ in.	Evade	\$9.00
" 3	2 to 4 "	50 to 75	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	Evan	11.00
" 4	3 to 7 "	50 to 100	$1\frac{1}{4}$ "	$3\frac{1}{4}$ "	Event	14.00

FIG. 345½. SIZES, PRICES, ETC.

Size.	Supply per Minute to Operate Ram.	Length of Drive Pipe, Feet.	PIPES.		Cipher.	*PRICE. With Leather Valve.
			Drive.	Discharge.		
No. 5	6 to 10 gals.	50 to 150	2 in.	1 in.	Exabub	\$22.00
" 6	11 to 25 "	50 to 200	$2\frac{1}{2}$ in.	$1\frac{1}{4}$ in.	Fabida	40.00
" 7	20 to 40 "	50 to 200	3 "	$1\frac{1}{2}$ in.	Fabief	75.00
" 8	25 to 75 "	50 to 200	4 "	2 "	Fabift	125.00

\*Leather Valve under Air Chamber.




FIG 345½

FIG. 346½. SINGLE RAM. SIZES, PRICES, ETC.

Size.	Supply per Minute to Operate Ram.	Length of Drive Pipe, Feet.	PIPES.		Cipher.	PRICE. Brass Spring Valve.
			Drive.	Discharge.		
No. 6	11 to 25 gals.	50 to 200	$2\frac{1}{2}$ in.	$1\frac{1}{4}$ in.	Exabuck	\$45.00
" 7	20 to 40 "	50 to 200	3 "	$1\frac{1}{2}$ in.	Exabude	80.00
" 8	25 to 75 "	50 to 200	4 "	2 "	Exacat	130.00

FIG. 346. DOUBLE RAM. SIZES, PRICES, ETC.

Size.	Supply per Minute to Operate Ram.	Length of Drive Pipe, Feet.	PIPES.		Cipher.	PRICE. †Brass Spring Valve.
			Drive.	Discharge.		
No. 6	22 to 50 gals.	50 to 200	$2\frac{1}{2}$ in.	$1\frac{1}{2}$ in.	Exalt	\$90.00
" 7	40 to 80 "	50 to 200	3 "	2 "	Excel	160.00
" 8	50 to 150 "	50 to 200	4 "	$2\frac{1}{2}$ in.	Exert	260.00

†Brass Spring Valve under Air Chamber.




FIG. 346½





FIG. 346

Fig. 345 can be fitted for wrought-iron or lead pipe, as ordered ; Fig. 345½ for wrought-iron pipe only.





### Double-Acting Force Pumps

of "Alert" and "Challenge" types have a general use for raising water in residences, on boats, around wharves, etc.

"Deluge" and Diaphragm Lift Pumps are used almost exclusively on vessels as illustrated.

See pages 139 to 147.



# GOULDS "ALERT" DOUBLE-ACTING FORCE PUMP.

139

WITH IRON OR BRASS-LINED CYLINDER.

The "Alert" Double-Acting Force Pump is similar to the "Challenge," which we were first to build and popularize, but, instead of the expensive composition valves and valve seats, this Pump has leather valves.

The valves are all grouped together under the air chamber and can be readily exposed to view by unscrewing the bolts at side. Suction and discharge openings are on opposite sides of cylinder.

We always fit suction and discharge for sizes of iron pipe named below, but can fit them for lead pipe or hose, if so ordered, at extra charge for Nos. 2 and 4 of \$2.00, and Nos. 6 and 8 of \$2.50.

FIG. 747. SIZES, PRICES, ETC.

No.	Dia. Cal.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.	
							Cipher.	Price.	Cipher.	Price.
2	2½ in.	5 in.	.21 gal.	1¼ in. pipe	1 in. pipe	75 ft.	Vareb	\$16.00	Basebal	\$18.50
4	3 " "	5 " "	.31 " "	1¼ " "	1 " "	75 " "	Varech	18.00	Baseboa	21.00
6	3½ " "	5 " "	.42 " "	1½ " "	1¼ " "	50 " "	Vivesu	20.00	Baselar	23.50
8	4 " "	5 " "	.54 " "	1½ " "	1¼ " "	50 " "	Vivid	24.00	Baseles	28.00




FIG. 747

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

# GOULDS "ALBANY" DOUBLE-ACTING FORCE PUMP.

WITH BRASS VALVES AND SEATS.

Fig. 1255, like our "Alert" and "Challenge" Pumps, has long vertical lever. Works easily. Is largely used for filling tanks. Valves are brass, on brass seats, and are located at ends of cylinder, easy of access. Cylinders either iron or brass-lined, as ordered. Piston rod brass-cased. Piston has two cupped leathers. Ample air chamber is provided.

FIG. 1255 SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	IRON.		BRASS-LINED.	
							Cipher.	Price.	Cipher.	Price.
4	3 in.	5 in.	.31 gal.	1¼ in. pipe	1 in. pipe	75 ft.	Paipops	\$18.00	Paigem	\$21.00
8	4 " "	5 " "	.54 " "	1½ " "	1¼ " "	50 " "	Paipug	24.00	Paigid	28.00
12	5 " "	5 " "	.85 " "	2 " "	2¼ " "	50 " "	Paigal	30.00	Panifo	35.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.




FIG. 1255

# 140 "ROCKER" DUPLEX DOUBLE-ACTING FORCE PUMPS.

WITH BRACKETS AND DETACHABLE STANDARDS.





FIG. 1213



Sectional View.




FIG. 1214

Figs. 1213 and 1214, "Rocker" Force Pumps, have a general application for all purposes where a Hand Force Pump may be employed. They are provided with two double-acting pistons, each fitted with double cup leathers, working in brass-lined cylinders. The suction and discharge valves and valve seats are brass, and are accessible without disturbing pipe connections. Lever is long, of malleable iron and may be operated in a vertical or horizontal position. The working parts of the Pump are so nicely arranged that the slightest movement of the lever causes the water to flow at once. Suction and discharge regularly fitted for iron pipe. Fitted for hose or lead pipe to order at extra price. For pumping wines, acids or hot water, Pumps should be specially fitted. This we do to order. Fig 1213 has Brackets for attaching to wall or plank. Fig. 1214 has Brackets, also detachable legs or standards.

FIGS. 1213 AND 1214. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Capacity per Revolution.	Approximate Capacity per Minute.	Suction and Discharge.	*Lift and Force.	FIG. 1213.		FIG. 1214.	
						Cipher.	Brass-Lined Cylinder.	Cipher.	Brass-Lined Cylinder.
2	2½ in.	.21 gals.	10 to 16 gals.	1 in. pipe	175 ft.	Metobe	\$25.00	Moawed	\$27.25
4	3 in.	.33 "	18 to 24 "	1¼ "	175 "	Metock	28.00	Moawig	30.50
6	3½ "	.60 "	33 to 40 "	1½ "	150 "	Metuma	31.00	Moawon	33.75
8	4 "	.82 "	40 to 48 "	2 "	150 "	Metund	37.00	Moawub	40.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# "ROCKER" DUPLEX DOUBLE-ACTING FORCE PUMPS. 141

MOUNTED ON STANDARDS, WITH OR WITHOUT AIR CHAMBER.





FIG. 1215



Sectional View.




FIG. 1219

General description of "Rocker" Force Pumps and their construction is given on preceding page. Pumps with legs or standards also have brackets by which they can be attached to wall or plank.

Fig. 1215 has air chamber and cock spout. So arranged, these Pumps provide for water being drawn at spout or forced above to tank. Suction and top of air chamber regularly fitted for iron pipe. Fitted for lead pipe or hose to order.

Fig. 1219 is same as Fig. 1214, on preceding page, with addition of suction and discharge elbows and iron couplings. Iron pipe of same size can be attached to end of elbow by removing hose coupling.

FIG. 1215. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Capacity per Revolution.	Approximate Capacity per Minute.	Suction.	DISCHARGES.		*Lift and Force.	Cipher.	Brass Lined Cylinder.
					Top of Air Chamber.	Nose of Cock.			
2	2½ in.	.21 gals.	10 to 16 gals.	1 in. pipe	1 in. pipe	1 in. hose.	175 ft.	Mobuso	\$28.50
4	3 "	.33 "	18 to 24 "	1¼ "	1¼ "	1 "	175 "	Mobvab	32.00
6	3½ "	.60 "	33 to 40 "	1½ "	1½ "	1 "	150 "	Mobvit	35.00
8	4 "	.82 "	40 to 48 "	2 "	2 "	1 "	150 "	Mobvox	42.00

FIG. 1219. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Capacity per Revolution.	Approx. Capacity per Minute.	Suction and Discharge.	*Lift and Force.	Cipher.	Brass Lined Cylinder.
2	2½ in.	.21 gals.	10 to 16 gals.	1 in. hose	175 ft.	Moonfat	\$31.00
4	3 "	.33 "	18 to 24 "	1¼ "	175 "	Moonfem	35.00
6	3½ "	.60 "	33 to 40 "	1½ "	150 "	Moongal	39.00
8	4 "	.82 "	40 to 48 "	2 "	150 "	Moonget	45.00

\*Total lift and force from water to point of discharge, Pump not more than 25 feet above water.



# 142 GOULDS "CHALLENGE" DOUBLE-ACTING FORCE PUMPS.

WITH BRASS VALVES.

Fig. 470 represents our "Challenge" Double-Acting Force Pump of great compactness and power, for use on shipboard, wharves, around factories, mills, warehouses, etc., and in residences for tank pumping. On all




FIG. 470

"Challenge" Pumps piston rods are brass-cased, valves and valve seats of brass, cylinders either brass-lined or brass, therefore working parts are non-corrosive. On ships "Challenge" Pump performs the three-fold purpose of filling boilers when cold, washing down decks, and satisfy government inspection as to fire protection.

In mines these Pumps are almost invaluable, as they are unaffected by mine water and will force to great elevation.

Fig. 562 represents our "Challenge" Double-Acting Force Pump, described above, in a larger form, and arranged with double levers. This Pump has only one stuffing box, so that it is less liable to leak than with two, and in case of such an accident one set of valves would be in readiness at all events, and thus arranged can be operated, too, with much less friction and labor.

For use on ship wharves, about factories, mills, mines, warehouses, etc., it is capable of inestimable service. We regularly fit iron pipe. Fitted for hose to order. Pumps furnished with fibrous or metallic-packed pistons to order.




FIG. 562

FIG. 470. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	* Lift and Force.	BRASS-LINED CYL.		BRASS CYLINDER.		† BRASS.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	4½ in.	.19 gal.	1¼ in. hose	1 in. hose	150 ft.	Grande	\$27.00	Rawems	\$55.00	Grantee	\$75.00
4	3 "	4½ "	.28 "	1¼ "	1 "	150 "	Grapery	28.00	Rawenb	55.00	Gratad	75.00
8	4 "	4½ "	.49 "	1½ "	1¼ "	100 "	Grab	30.00	Raweol	60.00	Loned	90.00
12	5 "	5 "	.85 "	2 "	1½ "	100 "	Grace	40.00	Rawepa	90.00	Longsa	150.00
16	6 "	5 "	1.22 "	2½ "	2 "	100 "	Vareibj	50.00	Rawfat	120.00	Vareick	185.00

FIG. 562. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	* Lift and Force.	BRASS-LINED CYL.		BRASS CYLINDER.		† BRASS.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
8	4 in.	4½ in.	.49 gal.	1½ in. hose	1¼ in. hose	125 ft.	Vareidz	\$35.00	Rawejx	\$65.00	Vareien	\$100.00
12	5 "	5 "	.85 "	2 "	1½ "	125 "	Leader	45.00	Rawekl	95.00	Looky	155.00
16	6 "	5 "	1.22 "	2½ "	2 "	125 "	Leaflet	55.00	Rawell	125.00	Looma	195.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

† Brass Pumps are made entirely of brass, except levers, links and bolts.

# "MONITOR" D. A. SUCTION AND FORCE PUMP COMBINED. 143

WITH BRASS-LINED CYLINDER AND METAL VALVES

The cut exhibits our Double-Acting "Monitor" Suction Pump, for elevating large quantities of water from the holds of vessels, or from wells, cisterns, reservoirs, etc. It is essentially a Brass Pump, as the cylinder is lined with that metal, while the piston, piston rod, valves and their seats are made of the best composition metal. By the addition of a very few and inexpensive appliances, this Pump can be converted into a very powerful engine, with a capacity of forcing a good-sized stream of water a long distance, thus combining in one machine, and at a little more cost, a Lifting and Force Pump when required. On shipboard this Pump can be set as Bilge Pumps usually are, with the iron suction pipe extending into the hold, and by very simple changes a Force Pump can be had for extinguishing fires, washing decks, etc. One Pump, therefore, performs the functions of two, and we guarantee that in either capacity it will give all the satisfaction that either of two Pumps would, designed specially for only one purpose.

Under the air chamber, which is easily detached, lie the upper valves, while by unscrewing the four nuts that secure the bed plate to the cylinder, the cylinder can be raised, and the lower valves are exposed. The position of the Pump or the pipes have, therefore, in no way to be disturbed should the valves become clogged and require examination. We can most heartily commend this Pump to our friends. Fitted for hose, unless otherwise ordered, but we can fit for iron pipe if so desired. Pumps furnished with fibrous or metallic packed piston to order.




FIG. 581.

FIG. 581. SUCTION AND BILGE PUMP. SIZE, PRICE, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	Cipher.	Brass-Lined.
16	6 in.	5 in.	1.22 gal.	2½ in. hose	Melt	\$55.00

FIG. 582. COMBINED FORCE PUMP. SIZE, PRICE, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	*Lift and Force.	Cipher.	Brass-Lined.
16	6 in.	5 in.	1.22 gal.	2½ in. hose	2 in. hose	125 ft.	Mend	\$60.00

\*Total lift and force from supply to point of delivery.



# 144 GOULDS "CHALLENGE" DOUBLE-ACTING FORCE PUMP.

WITH PITMAN FOR MACHINE POWER.

Fig. 604 represents our "Challenge" Double-Acting Force Pump, mounted on plank, with pitman, guide and guide rod for attaching to face plate and crank pin by means of connecting rod. May be operated by Figs 597 or 597½, Horse Powers (page 94), or other machine power. They can be run up to a maximum of 40 to 50 revolutions per minute, though 30 would be better. Both suction and discharge fitted for gas pipe, unless otherwise ordered.

Pump furnished with fibrous or metallic packed piston to order.




FIG. 604

FIG. 604. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	BRASS-LINED.		BRASS CYL.	
						Cipher.	Price.	Cipher.	Price.
2	2½ in.	4½ in.	.19 gal.	1¼ in. pipe	1 in. pipe	Molec	\$30.00	Reper	\$58.00
4	3 "	4½ "	.28 "	1¼ "	1 "	Molty	31.00	Repesu	58.00
8	4 "	4½ "	.49 "	1½ "	1¼ "	Monkish	33.00	Rideck	63.00
12	5 "	5 "	.85 "	2 "	1½ "	Moody	45.00	Rideds	95.00
16	6 "	5 "	1.22 "	2½ "	2 "	Moon	55.00	Rideer	125.00




FIG. 773

## GOULDS BRASS TWO-CYLINDER FORCE PUMP.

WITH DETACHABLE IRON LEVER.

Fig. 773 represents our Two-Cylinder Force Pump with brass cylinders, check valve, rods and stuffing boxes, making it practically a brass Pump. This Pump has two vertical working pistons actuated by one lever, having the full effect of a double-acting Pump.

The suction and discharge are fitted for lead or iron pipe, as ordered.

FIG. 773. SIZES, PRICES, ETC.

No.	Diameter Cylinders.	Stroke.	Capacity per Rev.	Suction.	Discharge.	*Lift and Force.	Cipher.	Brass.
0	2 in.	4 in.	.11 gal.	1¼ in. pipe	1 in. pipe	150 ft.	Vendor	\$30.00
2	2½ "	4 "	.17 "	1¼ "	1¼ "	125 "	Vendue	35.00
4	3 "	4 "	.24 "	1½ "	1¼ "	100 "	Veneer	45.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# GOULDS "THRESHER" DOUBLE-ACTING FORCE PUMP. 145

FOR FILLING THRESHER TANKS AND GENERAL USE.

Fig. 1145 is perhaps better than any other Pump adapted to the requirements of Threshermen. Easy of operation and of great capacity, it saves much time and labor in filling tank wagons. Being a Force Pump, it is used to fill the boiler when cold. Its construction is most simple and all parts are easily removable. Caps over discharge valves are so constructed that they can be unscrewed by any stick or rod. Valves are all metal, leather-faced. Solid piston is packed with double crimped leathers. Piston rod of polished steel works through Brass stuffing-box. Water ways are large and direct. Capacity of Pump is one to two barrels a minute, depending upon rapidity of operation. Aside from service suggested above, it is much used by contractors, etc. With each Pump is included Strainer, Hose Coupling and one pair Suction Hose Bands.




FIG. 1145. SIZE, PRICE, ETC.




FIG. 1145

Fig. 1145.	Dia. Cyl.	Stroke.	Capacity per Rev.	+ Suction.	+ Discharge.	*Lift and Force.	Cipher.	Price.
Pump with Strainer, Hose Couplings and Clamps.....	5 in.	5 in.	.85 gal.	2 in. hose	1 in. hose	50 ft.	Gushab	\$18.00
OUTFIT A.....	{ Fig. 1145, Thresher Tank Pump, with 15 feet 2-inch spiral wire suction hose, 12½ feet 1-inch 3-ply discharge hose, couplings, suction basket and nozzle, all complete.....						Gushik	40.00
OUTFIT B.....	{ Fig. 1145, Thresher Tank Pump, with 20 feet 2-inch spiral wire suction hose, 12½ feet 1-inch 3-ply rubber discharge hose, couplings, suction basket and nozzle, all complete.....						Gushod	45.00
OUTFIT C.....	{ Fig. 1145, Thresher Tank Pump, with 25 feet 2-inch spiral wire suction hose, 12½ feet 1-inch 3-ply discharge hose, couplings, suction basket and nozzle, all complete.....						Gushum	50.00
OUTFIT D.....	{ Fig. 1145, Thresher Tank Pump, with 25 feet 2 inch spiral wire suction hose, 25 feet 3-inch 1-ply discharge hose, couplings, suction basket and nozzle, all complete.....						Gushva	54.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.

† When specially ordered we can fit suction for 2-inch pipe and discharge for 1½-inch iron pipe, with out extra charge.

# GOULDS "NEW DELUGE" SUCTION PUMP.

WITH BRASS-LINED CYLINDER AND REMOVABLE VALVES.




FIG. 829

Fig. 829 represents our improved "New Deluge" Pump, which is designed for shallow or small vessels of not more than 15 to 20 feet depth of hold; for contractors who wish to pump large quantities of water from excavations, etc.; for irrigation or any other purpose where a compact and capacious Pump is desired.

The cylinder is lined with brass, the valves rubber-faced and the lever socket made at such an angle that the bent wrought-iron lever when put in one side up is right for ordinary pumping, and by simply changing it to the other side up it becomes a vertical lever. This lever may also be worked from three different points, as shown by lugs in our cut.

The Pump has large valves accessible and removable by hand from above, while to the bottom of the base is bolted a flange which may be cut for any size pipe ordered, or changed for other sizes if desired.

FIG. 829. SIZES, PRICES, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	Cipher.	Brass Lined.
6 in.	4 in.	.49 gal.	2½ in. pipe	20 ft.	Wakend	\$23.00
8½ in.	6 in.	1.47 "	3 in. pipe	20 "	Waking	30.00

Can furnish 8½-inch by 6-inch Iron (not brass lined) Pump fitted 4-inch pipe, with special foot valve for pumping asphaltum, at \$50.00 list.

# GOULDS "NEW DELUGE" SUCTION PUMP.

WITH BRASS-LINED CYLINDER AND REMOVABLE VALVES.




FIG. 836

Fig 836 represents our "New Deluge" Pump described above, arranged with elevated base to be used above deck or foundation where it is desired to use hose suction or more convenient to make pipe connections in this manner. The suction flange is fitted for sizes of wrought-iron pipe given below, unless otherwise ordered, or can be cut hose gauge to take our regular suction half hose coupling, which is furnished at extra price.

FIG. 836. SIZES, PRICES, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	Cipher.	Brass Lined.
6 in.	4 in.	.49 gal.	2½ in. pipe	20 ft.	Weaken	\$24.00
8½ in.	6 in.	1.47 "	3 in. pipe	20 "	Weakeos	31.00



# GOULDS NEW DIAPHRAGM SUCTION PUMP.

147

WITH BOTTOM SUCTION FOR PIPE.

Fig. 1222 represents the most approved design of Diaphragm Pump. Lever is reversible and can be used at back of the Pump, or on either side. Lower valve is of metal, rubber faced, easy of access and readily removable. Waterways are large and easy. Diaphragm is made of *best quality* rubber. Pump combines simplicity with strength. In these Pumps the diaphragm takes the place of the plunger. They are particularly adapted for pumping water containing mud, sand, gravel, sewage, coal, chips or any semi-fluid matter. Pumps with bottom suction are used in places where they can remain stationary, as on vessels, barges, dredges, wharves, etc. We regularly fit as in our table below.




FIG. 1222

FIG. 1222. SIZES, PRICES, ETC.

No.	Suction.	Approximate Capacity.	Cipher.	Price.
2	2½ in. iron pipe	1800 gallons per hour	Tokeot	\$17.50
3	3 in. "	3500 "	Todeka	20.00

# GOULDS NEW DIAPHRAGM SUCTION PUMP.

WITH SIDE SUCTION FOR HOSE OR PIPE.

Fig. 1223, New Diaphragm Pump, is similiar in general construction to Fig. 1222, described above, differing only in that it has side suction, and therefore a different kind of suction valve. This valve is brass, rubber-faced, resting upon an inclined seat, thus affording smallest obstruction to passage of any matter. Unless otherwise ordered, suction is cut 3-inch pipe thread, which is also the thread now generally used on hose couplings of that size. We can cut to any special hose gauge, if ordered. Suction hose and couplings furnished at market prices. Special brass hose couplings, suction hose and strainers furnished at market prices when ordered.




FIG. 1223

FIG. 1223. SIZES, PRICES, ETC.

No.	Suction.	Approximate Capacity.	Cipher.	Price.
2	2½ in. hose or iron pipe	1800 gallons per hour	Tokepy	\$21.50
3	3 in. "	3500 "	Todels	24.00




# GOULDS ODORLESS DIAPHRAGM FORCE PUMP.

*WITH LARGE AIR CHAMBER AND REVERSIBLE LEVERS.*


Fig. 1161 illustrates our improved Odorless Diaphragm Force Pump, specially designed for pumping out sewers, cesspools, vaults, etc., or moving any semi-liquid matter which an ordinary Pump could not successfully handle. In this Pump a rubber diaphragm with special valve acts as plunger. Bronze valve seat and cover incase the inclined rubber-faced suction valve, offering least obstruction to passage of matter. The levers are wrought-iron and reversible. The stroke is short and operates easily. Pump has convenient hand-hole for getting at interior without removing air-chamber. Suction and discharge regularly fitted for iron-pipe, but can cut to any special hose gauge. We can furnish hose and couplings to order.

*FIG 1161. SIZE, PRICE, ETC.*

Diameter Diaphragm.	Stroke.	Capacity per Stroke	Suction.	Discharge.	Cipher.	Price.
13 in.	2½ in.	1.47 gals.	3 in. pipe	3 in. pipe	Zutad	\$45.00



*FIG. 1161*



*FIG 1162*

## TWO-CYLINDER SUCTION PUMP.

*WITH FOLDING LEVERS.*

The cut represents our new Two-Cylinder Suction or Contractors' Pump. This Pump has large capacity, and for pumping out pits, mines, quarries, etc., will render most excellent service. These pumps can be mounted on a truck with wheels and drag handle, when so ordered, at a small additional expense. The levers can be folded into a small space, as shown in illustration. The suction is always fitted for iron pipe unless ordered to the contrary, although can be arranged for suction hose when so specified.

*FIG. 1162. SIZE, PRICE, ETC.*

Dia. Cyls.	Stroke.	Capacity per Stroke.	Suction.	Cipher.	Price.
12 in.	8 in.	7.83 gals.	6 in. pipe	Tickist	\$140.00

# GOULDS SHIP'S MAIN AND BILGE PUMP.

149

WITH WOOD LEVERS.

The cut represents our improved Ship's Main and Bilge Pump, for use upon shipboard, in mines and upon plantations for irrigation. It has a reversible top, heavy strong bed-plate, poppet valves of new design ; the suction pipe is attached to the vacuum chamber above the valves, so that they are always submerged ; the plungers are always made of brass, with large water-ways. We also furnish two and three-way cocks, at extra list price. See under Fig. 579.

FIG. 578. SIZES, PRICES, ETC.

Diameter Cylinders.	Stroke.	Capacity per Rev.	Suction.	Lift.	IRON CYLINDERS.		BRASS-LINED CYLINDERS.	
					Cipher.	Price.	Cipher.	Price.
5½ in.	6½ in.	1.34 gal.	3 in. pipe	25 ft.	Lestal	\$55.00	Lidda	\$75.00
5½ "	8 "	1.64 "	3 "	25 "	Letada	60.00	Lien	80.00
6 "	8 "	1.96 "	3 "	25 "	Levy	70.00	Maw	90.00




FIG. 578

# GOULDS SHIP'S MAIN AND BILGE PUMP.

WITH WROUGHT-IRON EXTENSION LEVERS.

Fig. 579 represents our improved Ship's Main and Bilge Pump, fully described above, arranged with wrought-iron extension levers, so that a large force of men can be employed in operating it. We also furnish two and three-turn brass cocks with elbows, where a suction pipe is wanted for each side of the keelson.

FIG. 579. SIZES, PRICES, ETC.

Diameter Cylinder.	Stroke.	Capacity per Rev.	Suction.	Lift.	IRON CYLINDERS.		BRASS-LINED CYLINDERS.	
					Cipher.	Price.	Cipher.	Price.
5½ in.	6½ in.	1.34 gal.	3 in. pipe	25 ft.	Maya	\$60.00	Meada	\$80.00
5½ "	8 "	1.64 "	3 "	25 "	Mazed	65.00	Meal	85.00
6 "	8 "	1.96 "	3 "	25 "	Mazy	75.00	Meaned	95.00
8 "	8 "	3.48 "	4 "	25 "	Mazera	115.00	Meant	140.00




FIG. 579

Brass 2-way cock, with 2 elbows for 2 suction pipes..... \$18.00 net  
 Brass 3-way cock, with 2 elbows for 3 suction pipes..... 20.00 net



# GOULDS TWO-CYLINDER FORCE PUMPS.

WITH WOOD OR WROUGHT LEVERS.




FIG. 518

Fig. 518 is a powerful Two-Cylinder Force Pump, which is double-acting in operation, simple and compact in build, all parts being readily accessible, and can be operated by wood levers or power, as desired. The suction is always fitted for wrought-iron pipe, and the discharge for hose, unless otherwise ordered; can fit both ends for wrought-iron pipe, or both ends for hose, if ordered.

Fig 520 represents our Two-Cylinder Suction and Force Pump described above, arranged with extension levers. When these levers are put in place, they afford room for many men to work, and render this pump a most powerful engine for forcing water on fires, or supplying it for many uses about factories, ware-houses, wharves, etc.




FIG. 520

FIG. 518. SIZES, PRICES, ETC

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	*Lift and Force.	IRON CYLINDERS.		BRASS-LINED CYLINDERS.		BRASS CYLINDERS.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
4	3 in.	6½ in.	.40 gal.	1½ in. pipe	1¼ in. hose	100 ft.	Hoax	\$35.00	Holt	\$42.00	Hoot	\$55.00
6	3½ "	6½ "	.54 "	2 "	1½ "	75 "	Hock	40.00	Home	50.00	Hops	63.00
8	4 "	8 "	.87 "	2½ "	2 "	75 "	Hod	45.00	Honel	55.00	Hopel	75.00
10	4½ "	8 "	1.10 "	2½ "	2 "	75 "	Hoe	52.50	Hood	67.50	Hose	87.50
12	5 "	8 "	1.36 "	2½ "	2 "	75 "	Hold	60.00	Hoofit	75.00	Hostal	100.00
16	6 "	8 "	1.96 "	4 "	2½ "	50 "	Hole	85.00	Hoopla	105.00	Hour	135.00

FIG. 520. SIZES, PRICES, ETC

No.	Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	*Lift and Force.	IRON CYLINDERS.		BRASS-LINED CYLINDERS.		BRASS CYLINDERS.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
4	3 in.	6½ in.	.40 gal.	1½ in. pipe	1¼ in. hose	100 ft.	Visitab	\$45.00	Visne	\$52.00	Vitalize	\$65.00
6	3½ "	6½ "	.54 "	2 "	1½ "	75 "	Visitan	50.00	Visor	60.00	Vitality	73.00
8	4 "	8 "	.87 "	2½ "	2 "	75 "	Visited	55.00	Vista	65.00	Vitals	85.00
10	4½ "	8 "	1.10 "	2½ "	2 "	75 "	Visitfy	62.50	Visual	77 50	Vitiate	97.50
12	5 "	8 "	1.36 "	2½ "	2 "	75 "	Visitor	70.00	Vital	85.00	Vitious	110.00
16	6 "	7 "	1.96 "	4 "	2½ "	50 "	Visive	95.00	Vitalit	115.00	Vitreos	145.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water.



# GOULDS TWO-CYLINDER FORCE PUMPS.

151

WITH WOOD LEVERS OR FOLDING BRAKES.

Fig. 283 exhibits a new Two-Cylinder Force Pump, with wood levers, etc., and may be worked by hand or machinery, while Fig. 284 is the same Pump with folding brakes, which are large enough to admit four or six men working upon them. Pumps are made with brass-cased piston rods, brass plungers, valves and stuffing boxes.

The valve at the bottom of the Cylinder is double and improved in its construction, and can be readily tripped or opened by pressing down the lever until it strikes the top of the air chamber.

The Pump is simple in its construction, not liable to get out of order, and by the directness of its action and consequent freedom from friction is a most efficient and powerful Pump.




FIG. 283




FIG. 284

FIG. 283. SIZES, PRICES, ETC.

No.	Diameter Cylinders.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	*Lift and Force.	IRON CYLINDERS.		BRASS-LINED CYL.		BRASS CYLINDERS.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	6 in.	.26 gal.	2 in. pipe	1¼ in. hose	125 ft.	Dazed	\$38.00	Polmegs	\$45.00	Debar	\$58.00
4	3 in.	6 in.	.37 "	2 in. pipe	1¼ in. hose	125 "	Dazzle	40.00	Polmeho	47.00	Debase	60.00
6	3½ in.	6 in.	.50 "	2½ in. pipe	1¼ in. hose	100 "	Deafa	47.00	Polmeja	57.00	Debit	70.00
8	4 in.	6 in.	.65 "	2½ in. pipe	1½ in. hose	100 "	Deale	55.00	Polmeks	65.00	Debta	85.00
10	4½ in.	6 in.	.83 "	3 in. pipe	2 in. hose	100 "	Deam	65.00	Polmelb	80.00	Debut	100.00
12	5 in.	8 in.	1.36 "	4 in. pipe	3 in. hose	75 "	Balse	75.00	Polmem	90.00	Benec	115.00
16	6 in.	8 in.	1.96 "	4 in. pipe	3 in. hose	75 "	Dear	100.00	Polmeno	120.00	Decay	150.00

FIG. 284. SIZES, PRICES, ETC.

No.	Diameter Cylinders.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	*Lift and Force.	IRON CYLINDERS.		BRASS-LINED CYL.		BRASS CYLINDERS.	
							Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	6 in.	.26 gal.	2 in. pipe	1¼ in. hose	125 ft.	Deck	\$53.00	Polmeop	\$60.00	Deep	\$73.00
4	3 in.	6 in.	.37 "	2 in. pipe	1¼ in. hose	125 "	Decker	55.00	Polmeou	62.00	Deeply	75.00
6	3½ in.	6 in.	.50 "	2½ in. pipe	1¼ in. hose	100 "	Decoyed	62.00	Polmics	72.00	Deera	85.00
8	4 in.	6 in.	.65 "	2½ in. pipe	1½ in. hose	100 "	Decry	70.00	Polmld	80.00	Defer	100.00
10	4½ in.	6 in.	.83 "	3 in. pipe	2 in. hose	100 "	Deedo	80.00	Polmifu	95.00	Defix	115.00
12	5 in.	8 in.	1.36 "	4 in. pipe	3 in. hose	75 "	Belted	90.00	Primmo	105.00	Blown	130.00
16	6 in.	8 in.	1.96 "	4 in. pipe	3 in. hose	75 "	Deema	120.00	Primnu	140.00	Deftly	170.00

\*Total lift and force from supply to point of delivery, Pumps not more than 25 feet above water.

## 152 GOULDS HAND AND POWER ROTARY FORCE PUMP.

Probably in no class of manufacture is the axiom, "The best is the cheapest," better exemplified than in that of Hand and Power Rotary Force Pumps.


Having been extensively engaged for the past 35 years in the manufacture and sale of these Pumps, we have profited by our experience, and feel justified, by the unsolicited testimony of our patrons and our constantly increasing sales in saying we are to-day making the largest and best line of these goods in the market. A Rotary Pump must be made with the utmost care and accuracy, or it is worthless — and it is these points of excellence, accomplished by our skilled labor and improved machinery, that have earned the enviable reputation of the "Goulds Rotary."

These Pumps will lift water as far as any piston Pump and give a constant uniform discharge.


When wanted for pumping hot liquids it is necessary that we should be advised of it, as we put in a metallic valve in that case. Bronze Pumps should always be used in distilleries, malt houses, etc.

The whole inside working and principle of our Pumps are obvious from the illustrations given below, in which Fig. 299 represents the cams used in our smaller Hand Pumps, and Fig. 300 those in our large Power Pumps.

*VIEW OF GOULDS ROTARY PUMPS WITH CASE COVER REMOVED.*



*FIG. 299*



*FIG. 300*

The peculiar formation of these revolving cams or pistons was acquired after long experimenting and successful practice, and has demonstrated them to be of such a shape as to produce the very minimum of friction and wear with the greatest results.

The cases which receive these cams are engine lathe turned and bored and so perfectly true and smooth that the cams when in operation create almost a perfect vacuum and will "pick up" water quicker, for a long distance, and hold it better than any other Pump. The cams are not rough castings, "sand ground," as those in some inferior Pumps, but are carefully and accurately planed to mesh into each other and fit their case perfectly.

It is also a point worth noting that if a little good oil be put into the case of our Pumps before and after using at first, or simply pump air with this oil a few times, the cams become as hard upon the surface as fine tempered steel, and are almost unaffected by constant use afterwards.

Drip plugs are provided for draining Pumps in cold weather. To do this, turn the cams backward a single revolution to release all water.



# GOULDS ROTARY FORCE PUMPS.

153

WITH BALANCE WHEEL FOR HAND POWER.

Fig. 297 represents one of our celebrated Hand Rotary Force Pumps. They are adapted for every place or purpose where a Lift and Force Pump can be used, and will pump from a well or cistern, or can be moved to any place where water is within suction distance and instantly operated.

Fig. 297½ Hand Rotary Pump is made in larger sizes than Fig. 297, and has higher base and larger balance wheel. The cam shaft is long enough to put another fly-wheel on, so that four men can work if necessary. Brass plugs are provided at top and bottom of case for letting out the water in cold weather. After taking out the plugs reverse the cams two or three times around so as to get the water down from the top. We would advise the use of a check valve at end of suction pipe, as it keeps the pipe always filled and renders the Pump ready for use with a single revolution. Constructive view of Rotary Pump is given on preceding page 152. By the addition of metallic lower valve, hot liquids can be handled as well as cold. Hot liquid must always flow to the Pump, as the vapors prevent any Pump from making a vacuum and thereby "sucking" the liquid.

For wine or liquor a Bronze Pump should always be used, as it is unaffected by the action of acids. *Our Rotary Pumps are known in every country of the world as the very best made, and always give satisfaction.*




FIG. 297




FIG. 297½

FIG. 297. SIZES, PRICES, ETC

No.	Capacity per Minute 100 Revs.	Suction.	DISCHARGES.		Diameter Balance Wheel.	*Lift and Force.	IRON.		BRONZE CASE AND CAMS.		† BRONZE.	
			End of Spout.	Top of Spout.			Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1¼ in. pipe	1 in. hose	1 in. pipe	14½ in.	60 ft.	Ditty	\$19.00	Dizzy	\$41.00	Primnyx	\$51.00
2	13 "	1¼ "	1 "	1 "	14½ "	60 "	Dive	22.00	Dock	46.00	Primob	56.00
3	17 "	1½ "	1¼ "	1¼ "	14½ "	60 "	Divan	26.00	Dodge	51.00	Primocs	63.00

FIG. 297½. SIZES, PRICES, ETC.

No.	Capacity per Minute 100 Revs.	Suction.	DISCHARGES.		Diameter Balance Wheel.	*Lift and Force.	IRON.		BRONZE CASE AND CAMS.		† BRONZE.	
			End of Spout.	Top of Spout.			Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1¼ in. pipe	1 in. hose	1 in. pipe	20 in.	60 ft.	Doer	\$20.00	Doled	\$42.00	Primodl	\$52.00
2	13 "	1¼ "	1 "	1 "	20 "	60 "	Doif	23.00	Domel	47.00	Primof	57.00
3	17 "	1½ "	1¼ "	1¼ "	20 "	60 "	Doggel	27.00	Donad	52.00	Primoga	64.00
4	27 "	1½ "	1½ "	1½ "	20 "	60 "	Dogma	35.00	Done	65.00	Primul	87.00
4A	27 "	1½ "	1½ "	1½ "	36 "	60 "	Dogskin	39.00	Doit	69.00	Primums	91.00
5	36 "	2 "	2 "	2 "	20 "	60 "	Doing	40.00	Doom	75.00	Primve	105.00
5A	36 "	2 "	2 "	2 "	36 "	60 "	Doily	44.00	Dolce	79.00	Primvit	109.00
6	45 "	2½ "	2½ "	2½ "	36 "	60 "	Voidues	50.00	Voiture	100.00	Primvo	140.00

\* Total lift and force from supply to point of delivery, Pump not more than 15 to 20 feet above water.

† "Bronze" Pumps have all parts coming in contact with the liquid of Bronze.



# GOULDS ROTARY FORCE PUMPS.

Fig. 821 represents our Hand Rotary Force Pump arranged with side suction for hose or lead pipe. Unlike other Rotary Pumps, which are tapped for wrought-iron pipe, that must pass up through bottom of standard or base, this one is conveniently arranged for hose suction at side. Many reasons will suggest themselves of the practical utility and convenience of this feature, as the suction hose may be dropped in any position readily, and as readily removed to another for immediate use.




FIG. 821

Fig. 819 represents our Rotary Force Pump with outside bearing and pulley fly-wheel for power use. This Pump may be used for any of the many services of Rotaries—for pumping hot or cold water, wines, liquors, etc., and is specially arranged for power use at a moderate expense. These Pumps are admirably adapted for use with high-speed gas, kerosene, or other engines, as the height of outside bearing admits the use of a very large pulley to compensate for speed of engine.

Always fitted for wrought-iron suction pipe.

Constructive view is shown on page 152.

By the addition of a metallic lower valve any of our Rotary Pumps will handle hot liquids. Hot liquid must always flow to the Pump, as rising vapors prevent any Pump from forming a vacuum and thereby “sucking” the liquid. For handling wines, liquors or any acid substances, bronze Pumps should be used.




FIG. 819.

FIG. 821. SIZES, PRICES, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	DISCHARGES.		Diameter Balance Wheel.	*Lift and Force.	IRON.		BRONZE CASE AND CAMS.	
			End of Spout.	Top of Spout.			Cipher.	Price.	Cipher.	Price.
1	10 gals.	1 1/4 in. pipe	1 in. hose	1 in. pipe	14 1/2 in.	60 ft.	Watest	\$20.00	Wateyf	\$42.00
2	13 "	1 1/4 "	1 "	1 "	14 1/2 "	60 "	Wateta	23.00	Watfat	47.00
3	17 "	1 1/2 "	1 1/4 "	1 1/4 "	14 1/2 "	60 "	Wateub	27.25	Watfeg	52.25
4	27 "	1 1/2 "	1 1/2 "	1 1/2 "	20 "	60 "	Watevs	36.25	Watgan	66.25
5	36 "	2 "	2 "	2 "	20 "	60 "	Watewd	41.75	Watges	76.75
6	45 "	2 1/2 "	2 1/2 "	2 1/2 "	36 "	60 "	Watexr	51.75	Wathot	101.75

FIG. 819 SIZES, PRICES, ETC.

No.	Capacity per Min., 100 Revs.	Suction.	DISCHARGES.			Pulley.	*Lift and Force.	IRON.		BRONZE CASE AND CAMS.		†BRONZE.	
			End of Spout.	Top of Spout.				Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1¼ in. pipe	1 in. hose	1 in. pipe	12 x 3 in.	60 ft.	Vaguene	\$25.00	Vahepa	\$47.00	Primwu	\$57.00	
2	13 "	1¼ "	1 "	1 "	12 x 3 "	60 "	Vahab	28.00	Vaheqt	52.00	Prinap	62.00	
3	17 "	1½ "	1¼ "	1¼ "	15 x 3 "	60 "	Vahela	32.00	Vaherls	57.00	Prinate	69 00	
4	27 "	1½ "	1½ "	1½ "	16 x 4 "	60 "	Vahemy	45.00	Vahesm	75.00	Prineb	97.00	
5	36 "	2 "	2 "	2 "	20 x 4 "	60 "	Vaheni	50.00	Vaheta	85.00	Prineco	115.00	
6	45 "	2½ "	2½ "	2½ "	24 x 4 "	60 "	Vaheop	60.00	Vaheub	110.00	Prineds	150.00	

\* Total lift and force from supply to point of delivery, Pump not more than 20 feet above water.

† “Bronze” Pumps have all parts coming in contact with the liquid of bronze.

# GOULDS ROTARY FORCE PUMPS.

155

## FOR HAND PUMPING.




FIG. 464

Fig. 464 shows our Hand Rotary Pumps, arranged with an improvement for holding the suction pipe of the Pump rigid in the bung of a barrel. The holder is a tapering sleeve in two halves, and can be used in barrels having any size of bung, from 1½ to 4 inches in diameter. A suction pipe of three feet in length is furnished with each Pump as well as a hose coupling. With this apparatus, fluids of any character or consistency can be pumped from a barrel, tierce or hogshead, and forced into a reservoir or receptacle at a distance removed.

The prices given below include suction pipe, hose coupling, hook and holder.

Fig. 665 shows one of our celebrated Hand Rotary Force Pumps, arranged on a flat base or plate, 7 x 10 inches, with a cast-iron hub projecting four or five inches below it.




FIG. 665

We always fit both suction and discharge for hose coupling unless otherwise ordered, but can fit them also for gas pipe if so advised. Constructive view and description of our celebrated Rotary Pump is given on page 152. For handling wine, liquor or any acid substances, Bronze Pumps should be used.

FIG. 464. SIZES, PRICES, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	DISCHARGES.			IRON.		BRONZE CASE AND CAMS		† BRONZE.	
			End of Spout.	Top of Spout.		Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1 in. pipe	1 in. hose	1 in. pipe		Girth	\$17.00	Glade	\$39.00	Prineet	\$49.00
2	13 "	1 "	1 "	1 "		Gist	20.00	Glared	44.00	Prinfu	54.00
3	17 "	1 ¼ "	1 ¼ "	1 ¼ "		Give	24.00	Glass	49.00	Pringas	61.00

FIG. 665. SIZES, PRICES, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	DISCHARGES.			Dia. Balance Wheel.	IRON.		BRONZE CASE AND CAMS.		† BRONZE.	
			End of Spout.	Top of Spout.			Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1 ¼ in. pipe	1 in. hose	1 in. pipe		14 ½ in.	Louck	\$19 50	Lung	\$41.50	Pringet	\$51.00
2	13 "	1 ¼ "	1 "	1 "		14 ½ "	Luff	22.50	Lured	46.50	Prubo	56.00
3	17 "	1 ½ "	1 ¼ "	1 ¼ "		14 ½ "	Luke	26.75	Lush	51.75	Prubum	64.00
4	27 "	1 ½ "	1 ½ "	1 ½ "		20 "	Lull	36.50	Lute	67.00	Prudat	89.00
5	36 "	2 "	2 "	2 "		20 "	Lump	42.00	Mace	77.50	Prudet	107.00

† "Bronze" Pumps have all parts coming in contact with the liquid of Bronze.



## GOULDS SPECIAL ROTARY FORCE PUMP.

WITH BRACKET FOR ATTACHING TO MACHINES.




FIG. 944

Fig. 944 is a special pattern Rotary Force Pump, designed to pump small quantities of oil to pipe-cutting and threading machines, bolt cutters, etc., or return this oil to reservoir from which supply is taken to machines. They are simple in construction, the principal mechanism being a pair of gears, which run together in a tight case.

Pump has bracket for fastening to machines and shaft long enough to receive pulley.

While Pump will specially recommend itself to machine builders, manufacturers of bolts, screws, etc., yet it may be employed for any service where a small compact Force Pump is required.

FIG. 944. SIZE, PRICE, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	Discharge.	* Lift and Force.	IRON.		† BRONZE.	
					Cipher.	Price.	Cipher.	Price.
0	1 gal.	½ in. pipe	½ in. pipe	100 ft.	Awning	\$15.00	Calmed	\$25.00

\* Total lift and force from supply to point of delivery, Pump not more than 20 feet above liquid.

† Bronze Pump is made entirely of bronze.

## GOULDS SPECIAL ROTARY FORCE PUMP.

ON FRAME WITH SINGLE PULLEY.

Fig. 1239 is designed especially to supply the increasing demand for a small and inexpensive Rotary Force Pump. It is simple in construction, the principal mechanism being a pair of gears, which run together in a tight case. It is provided with a substantial base with bearing for shaft cast thereon. Bearings are babbitted, suction is at side; single tight pulley provides power connection. It may be put to any ordinary uses where a small Force Pump can be employed.

Pump furnished with tight and loose pulley to order.




FIG. 1239

FIG. 1239. SIZE, PRICE, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	Discharge.	Pulley.	* Lift and Force.	IRON.		† BRONZE.	
						Cipher.	Price.	Cipher.	Price.
2	5 gals.	1 in. pipe	1 in. pipe	10 x 2½	100 ft.	Reefji	\$25.00	Reefjod	\$55.00

\* Total lift and force from supply to point of delivery, Pump not more than 20 feet above liquid.

† Bronze Pump has all parts coming in contact with the liquid bronze.



# GOULDS POWER ROTARY FORCE PUMPS.

157

ON FRAME WITH TIGHT AND LOOSE PULLEYS.

Fig. 1185½ accurately represents our Rotary Force Pump on heavy cast-iron frame, with tight and loose pulleys for power. Its internal construction is described on page 152. Beyond the pulleys is a strong bearing with Babbitt-lined boxes in which the driving shaft runs. The shaft is also made long enough to take a balance

wheel beyond the bearing, but this wheel is only furnished at extra price. This Pump will be found serviceable for furnishing considerable volume to elevations not exceeding 60 feet. They are largely used in creameries, breweries, wine cellars, oil refineries, etc. Fig. 1281, Power Rotary Force Pump, is the same as Fig. 1185½ described above but without spout piece, the top of case being tapped for iron pipe as per sizes given in table below. These are largely used for pumping to tanks.

By the addition of a metallic lower valve any of our Rotary Pumps will handle hot liquids. Hot liquids should always flow to the Pump, as rising vapors prevent any Pump from forming a vacuum, and thereby "sucking" the liquid. For handling acid substances Bronze Pumps should be used.




FIG. 1185½




FIG. 1281

FIG. 1185½. SIZES, PRICES, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	DISCHARGES.		Pulleys, Each.	*Lift and Force.	IRON.		BRONZE CASE AND CAMS.		†BRONZE.	
			End of Spout.	Top of Spout.			Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1¼ in. pipe	1 in. hose	1 in. pipe	8 x 2½ in.	60 ft.	Tubeul	\$27.00	Tubfat	\$49.00	Pulpac	\$60.00
2	13 "	1¼ "	1 "	1 "	8 x 2½ "	60 "	Tubevy	32.00	Tubfel	56.00	Pulpet	65.00
3	17 "	1½ "	1¼ "	1¼ "	8 x 2½ "	60 "	Tubewd	38.00	Tubfig	63.00	Pulpig	75.00
4	27 "	2 "	1½ "	1½ "	12 x 3½ "	60 "	Dotad	48.00	Douse	78.00	Pulpod	100.00
5	36 "	2 "	2 "	2 "	12 x 3½ "	60 "	Doteb	54.00	Dove	90.00	Pulpun	120.00
6	45 "	2½ "	2½ "	2½ "	24 x 4 "	60 "	Weigky	80.00	Wheezin	135.00	Pulpyx	175.00

FIG. 1281. SIZES, PRICES, ETC.

No.	Capacity per Minute, 100 Revs.	Suction.	Discharge.	Pulleys, Each.	*Lift and Force.	IRON.		BRONZE CASE AND CAMS.		†BRONZE.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	10 gals.	1¼ in. pipe	1¼ in. pipe	8 x 2½ in.	60 ft.	Puntum	\$26.00	Punsis	\$48.00	Quire	\$58.00
2	13 "	1¼ "	1¼ "	8 x 2½ "	60 "	Puntvo	31.00	Pusjit	55.00	Rabidmu	63.00
3	17 "	1½ "	1½ "	8 x 2½ "	60 "	Puntwi	37.00	Puskax	62.00	Rabidno	73.00
4	27 "	2 "	2 "	12 x 3½ "	60 "	Puntwut	46.00	Puskem	76.00	Rabidot	96.00
5	36 "	2 "	2 "	12 x 3½ "	60 "	Punsab	52.00	Puslit	88.00	Rabidug	116.00
6	45 "	2½ "	2½ "	24 x 4 "	60 "	Punsel	77.50	Quihot	132.50	Rabifa	170.00

\*Total lift and force from supply to point of delivery, Pump not more than 20 feet above water.

†Bronze Pumps have all parts coming in contact with the liquid of bronze.

# GOULDS SEMI-ROTARY "CLOCK" FORCE PUMP.

DOUBLE-ACTING, WITH REMOVABLE LEVER.

Fig. 965 represents our Semi-Rotary "Clock" Force Pump, arranged with removable malleable lever.

Working parts of Pump comprise brass double wing, oscillating piston with brass valves on each side of wing, encased in cylinder. The lever is attached to shaft or piston rod and the waterway of each set of valves is separated from the other in the suction-valve box. These Pumps are practically metallic fitted, and having no leather packing, may be employed in pumping hot liquids, oil, wine, etc.

In our brass-fitted Pumps all working parts are brass, except cylinder case and cover; in brass Pumps, all working parts are made of this metal.




FIG. 965

FIG. 965. SIZES, PRICES, ETC.

No.	Approximate Capacity per Minute.	Suction.	Discharge.	* Lift and Force.	BRONZE-FITTED.		BRONZE.	
					Cipher.	Price.	Cipher.	Price.
1	4 gals.	$\frac{1}{2}$ in. pipe	$\frac{1}{2}$ in. pipe	150 ft.	Wordym	\$8.00	Worldly	\$16.00
2	5 "	$\frac{3}{4}$ "	$\frac{3}{4}$ "	150 "	Worec	9.50	Worm	20.00
3	6 "	1 "	1 "	125 "	Work	11.00	Wormal	27.50
4	9 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	125 "	Worker	13.00	Wormy	35.00
5	13 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	100 "	Workin	16.00	Wornl	42.50
6	19 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	100 "	World	20.00	Wornie	50.00
8	26 "	2 "	2 "	90 "	Vahev	27.50	Valency	70.00
9	36 "	$2\frac{1}{2}$ "	$2\frac{1}{2}$ "	80 "	Vahewx	40.00	Vareda	90.00

\* Total lift and force from supply to point of delivery, Pump not more than 15 to 20 feet above water.

# GOULDS SEMI-ROTARY "CLOCK" FORCE PUMP.

DOUBLE-ACTING. ON BASE.

Fig. 982 represents our celebrated Semi-Rotary "Clock" Pump, arranged on a base or standard. This base is detachable, and the Pump can either be used with the base, or can be bolted to a plank or the side of wall, as desired. These Pumps are practically metallic fitted, and may be employed for pumping hot liquids, oil, etc. Suction and discharge always fitted for wrought-iron pipe unless otherwise ordered. When fitted for lead pipe or hose an extra charge will be made.

FIG. 982. SIZES, PRICES, ETC.




FIG. 982

No.	Capacity per Minute.	Suction.	Discharge.	* Lift and Force.	BRONZE FITTED.		BRONZE.	
					Cipher.	Price.	Cipher.	Price.
1	4 gals.	$\frac{1}{2}$ in. pipe	$\frac{1}{2}$ in. pipe	150 ft.	Wronga	\$9.00	Zylop	\$17.00
2	5 "	$\frac{3}{4}$ "	$\frac{3}{4}$ "	150 "	Wronger	10.50	Zylopel	21.00
3	6 "	1 "	1 "	125 "	Wrongfu	12.00	Zylops	28.50
4	9 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	125 "	Wrongly	14.00	Zyloppd	36.00
5	13 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	100 "	Wrongne	17.00	Zylora	44.00
6	19 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	100 "	Wrongou	21.00	Zylored	52.50
8	26 "	2 "	2 "	90 "	Vareef	30.00	Varegat	72.50
9	36 "	$2\frac{1}{2}$ "	$2\frac{1}{2}$ "	80 "	Vareful	42.50	Varehes	92.50

\* Total lift and force from supply to point of delivery, Pump not more than 15 to 20 feet above water.



## DOUBLE-ACTING. ON BRACKETS OR BASE.

Fig. 1149 represents our Semi-Rotary "Clock" Force Pump, arranged with removable malleable lever, and elbows for hose connections.

In construction it is the same as Fig. 965, described on page 158.

Fig. 995 represents our "Clock" Pump, mounted on iron standard, with air chamber and cock spout. So arranged, these pumps may be used for drawing water at the spout, or for forcing the water above the Pump to tanks, bath-rooms, etc. Having metal valves, they may be employed for pumping hot liquids, oil, etc. Suction and discharge always fitted for wrought-iron pipe unless otherwise ordered. When fitted for lead pipe or hose an extra charge will be made.




FIG 1149.




FIG. 995.

FIG 1149. SIZES, PRICES, ETC.

No.	Approximate Capacity per Minute.	Suction.	Discharge.	*Lift and Force.	BRONZE-FITTED.		BRONZE.	
					Cipher.	Price.	Cipher.	Price.
1	4 gals.	$\frac{1}{2}$ in. pipe	$\frac{1}{2}$ in. pipe	150 ft.	Gulfab	\$ 9.00	Hailap	\$17.00
2	5 "	$\frac{3}{4}$ "	$\frac{3}{4}$ "	150 "	Gulface	10.75	Haillet	22.50
3	6 "	1 "	1 "	125 "	Gulfib	12.50	Hailik	29.00
4	9 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	125 "	Gulfog	15.00	Hailod	37.00
5	13 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	100 "	Gulfus	18.50	Hailus	45.00
6	19 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	100 "	Gelfyx	23.00	Haims	53.00

FIG. 995. SIZES, PRICES, ETC.

No.	Approximate Capacity per Minute.	Suction.	Discharge.	*Lift and Force.	BRONZE-FITTED.		BRONZE.	
					Cipher.	Price.	Cipher.	Price.
1	4 gals.	$\frac{1}{2}$ in. pipe	$\frac{1}{2}$ in. pipe	150 ft.	Zutela	\$11.00	Zutelop	\$19.00
2	5 "	$\frac{3}{4}$ "	$\frac{3}{4}$ "	150 "	Zuteled	12.50	Zutelny	23.00
3	6 "	1 "	1 "	125 "	Zylonp	14.00	Zyma	30.50
4	9 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	125 "	Zylonti	16.00	Zym	38.00
5	13 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	100 "	Zyloo	19.00	Zymad	46.00
6	19 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	100 "	Zyloosd	24.00	Zymeg	56.00
8	26 "	2 "	2 "	90 "	Vareef	35.00	Varegat	77.50
9	36 "	$2\frac{1}{2}$ "	$2\frac{1}{2}$ "	80 "	Vareful	47.50	Varehes	97.50


\*Total lift and force from supply to point of delivery, Pump not more than 15 to 20 feet above water.





## GOULDS POWER ROTARY FIRE PUMPS.

These Pumps are unexcelled for fire protection for factories, ware-houses, etc. They occupy little space, are moderate in cost and will afford effective fire protection. The method of driving, connections, etc., are details covered by local conditions and requirements. We refer to pages 162 to 167.



# GOULDS POWER ROTARY PUMP.

161

A Pump of this type has remarkably great capacity, considering its dimensions, and its capacity increases or decreases in proportion to increase or decrease of speed. It handles liquids of any kind, hot or cold, thick or thin. For fire protection, pumping for manufacturing and other purposes, our Rotary Pump possesses a long established reputation for durability, good workmanship and general excellence.

When the Pump is used intermittently, it should be freed of water when stopped and some oil introduced at the priming plug. Turning the Pump a few times will effectively spread the oil over the cams and the case and thus corrosion will be prevented.

Following table of Effective Fire Streams is condensed from paper by John R. Freeman, C. E., read before the New England Water Works Association :

TABLE OF EFFECTIVE FIRE STREAMS.

USING 100 FEET OF 2½-INCH ORDINARY BEST QUALITY RUBBER-LINED HOSE BETWEEN NOZZLE AND HYDRANT, OR PUMP.

Smooth Nozzle, Size.....	¾-Inch.						⅞-Inch.						1-Inch.					
Pressure at Hydrant, lbs.....	32	43	54	65	75	86	34	46	57	69	80	91	37	50	62	75	87	100
Pressure at Nozzle, lbs.....	30	40	50	60	70	80	30	40	50	60	70	80	30	40	50	60	70	80
Pressure lost in 100 ft., 2½-in. hose, lbs.....	2	3	4	5	5	6	4	6	7	9	10	11	7	10	12	15	17	20
*Vertical Height, feet Effective Stream.....	48	60	67	72	76	79	49	62	71	77	81	85	51	64	73	79	85	89
*Horizontal Distance, feet, Effective Stream.....	37	44	50	54	58	62	42	49	55	61	66	70	47	55	61	67	72	76
Gals. Discharged per minute.....	90	104	116	127	137	147	123	142	159	174	188	201	161	186	208	228	246	263

Smooth Nozzle, Size.....	1⅛-Inch.						1¼-Inch.						1½-Inch.					
Pressure at Hydrant, lbs.....	42	56	70	84	98	112	49	65	81	97	113	129	58	77	96	116	135	154
Pressure at Nozzle, lbs.....	30	40	50	60	70	80	30	40	50	60	70	80	30	40	50	60	70	80
Pressure lost in 100 ft., 2½-in. hose, lbs.....	12	16	20	24	28	32	9	25	31	37	43	49	28	37	46	56	65	74
Vertical Height of Effective Stream, feet.....	52	65	75	83	88	92	53	67	77	85	91	95	55	69	79	87	92	97
Horizontal Dis. of Effective Stream, feet.....	50	59	66	72	77	81	54	63	70	76	81	85	56	66	73	79	84	88
Gals. Discharged per minute.....	206	238	266	291	314	336	256	296	331	363	392	419	315	363	406	445	480	514

Two hundred and fifty gallons per minute is a good standard fire stream with 80 pounds pressure at the hydrant.

\*Spray or drops will go from 22 per cent. to 56 per cent. higher, and from 120 per cent. to 150 per cent. farther horizontally, but figures given in table are for "Effective" fire streams that will make a black mark where they hit.



# GOULDS POWER ROTARY FORCE PUMP.

WITH TIGHT AND LOOSE PULLEYS FOR BELT.




FIG. 301. NO. 5

Fig. 301, Power Rotary Force Pump, is designed for water supply, tank service, circulating liquids of any kind, pumping, oil, etc. It has tight and loose pulleys. Sizes No. 1, 2 and 3 have shaft extended to carry the pulleys, which will be placed at either end of the Pump, as ordered. Nos. 4, 5 and 6 have pulleys mounted on short piece of shaft and connected to cam shaft by flange coupling, which may be attached at either end of Pump. All sizes have out-board bearing for pulleys. Pulleys are regularly attached, as shown in illustration. Cut and description on page 152 show the construction of these celebrated Rotary Pumps. Outside of case are two heavy sets of cut gears connecting the cam shafts. Nos. 1, 2 and 3 have two discharge openings fitted with interchangeable flanges, one tapped for pipe of size given in table, the other fitted for hose coupling and furnished with cap. (Size hose given in

table.) Nos. 4, 5 and 6 have three discharge openings, two being fitted as above and the third with blank flange. We list Nos. 3, 4, 5 and 6 with air chamber under Fig. 896, page 164.

FIG. 301. SIZES, PRICES, ETC.

No.	Capacity One Rev.	† Speed and Capacity per Minute, varying with Kind of Work and Pressure.		Suction.	Discharges.		Pulleys, Each.	IRON.		BRONZE CASE AND CAMS.		* BRONZE.	
								Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
1	1/4 gal.	100 to 250 revs.,	25 to 60 gals.	2 in. pipe	1 1/2 in. pipe and 1 1/2 in. hose	12 x 3 1/2 in.	Dowdy		\$115.00	Dozad	\$155.00	Rabkul	\$185.00
2	1/2 "	100 to 200 "	50 to 100 "	2 1/2 "	2 " " 2 "	16 x 4 "	Down		130.00	Dozer	195.00	Rablee	245.00
3	1 "	100 to 175 "	100 to 175 "	3 "	2 1/2 " " 2 1/2 "	18 x 5 "	Dowry		185.00	Dozy	305.00	Rablig	405.00
4	1 2/3 "	100 to 150 "	165 to 250 "	5 "	4 " " 2 1/2 "	24 x 6 "	Wealth		275.00	Weanac	475.00	Raptom	650.00
5	2 1/2 "	75 to 125 "	185 to 310 "	6 "	5 " " 2 1/2 "	30 x 8 "	Wean		350.00	Weanel	600.00	Raptore	900.00
6	4 1/2 "	60 to 100 "	270 to 450 "	8 "	6 " " 2 1/2 "	36 x 10 "	Bandage		550.00	Basal	950.00	Raptub	1450.00

† Speeds given are a fair rate for continuous running; can be doubled for occasional service. Pumps are strong enough to force against about 100 pounds pressure.

\* "Bronze" Pumps have all parts coming in contact with the liquid of bronze.



ON FRAME, WITH COUPLINGS ON EACH END OF DRIVING SHAFT.

This cut represents another of our Power Rotary Force Pumps as we build them in the larger sizes, mounted on frame, with two heavy sets cut gears and coupling on each end of driving shaft for power connection.

On page 152 is given constructive view of these celebrated Rotary Pumps, together with description. Nos. 1, 2 and 3 have two discharge openings, fitted with interchangeable flanges; one tapped for pipe of size given in table, the other fitted for hose coupling and furnished with cap (size hose given in table).

Nos. 4, 5 and 6 have three discharge openings; two being fitted as above and the third with blank flange.

We list Nos. 3, 4, 5 and 6 with air chamber under Fig. 302 $\frac{1}{2}$  on page 165.




FIG. 302

FIG. 302. SIZES, PRICES, ETC.

No.	Capacity one Revolu- tion.	†Speed and Capacity per Minute.	Suction.	Discharges.	IRON.		BRONZE CASE AND CAMS.		* Bronze.		
					Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	
1	¼ gal.	100 to 250 revs.,	25 to 60 gals.	2 in. pipe	1½ in. pipe and 1½ in. hose	Draft	\$100.00	Weaning	\$140.00	Raptulo	\$170.00
2	½ "	100 to 200 "	50 to 100 "	2½ "	2 " "	Drag	115.00	Weapon	180.00	Raptums	230.00
3	1 "	100 to 175 "	100 to 175 "	3 "	2½ " "	Drain	170.00	Wear	290.00	Raptunt	390.00
4	1⅔ "	100 to 150 "	165 to 250 "	5 "	4 " "	Drake	250.00	Wearda	450.00	Raptva	625.00
5	2½ "	75 to 125 "	185 to 310 "	6 "	5 " "	Dram	325.00	Wearer	575.00	Raptvex	875.00
6	4½ "	60 to 100 "	270 to 450 "	8 "	6 " "	Dripom	525.00	Wearfu	925.00	Raptvil	1425.00

† Speeds given are a fair rate for continuous running; can be doubled for occasional service. Pumps are strong enough to force against about 100 pounds pressure.

\* "Bronze" Pumps have all parts coming in contact with the liquid of bronze.

# GOULDS POWER ROTARY FIRE PUMP.




FIG. 896

lets will be fitted otherwise to order. See page 152 for construction view and description.

See our remarks under Fig. 302½ (page 165) concerning water relief valve to be used with this pump.

See "Table of Effective Fire Stream," page 161.

FIG. 896. SIZES, PRICES, ETC.

Size.	Capacity, one Revolution.	Speed and Capacity per Minute, for Good Fire Service.		Suction.	Discharges.	Single Pulley.	IRON.		BRONZE CASE AND CAMS.	
							Cipher.	Price.	Cipher.	Price.
No. 3	1 gal.	350 to 400 revs..	350 to 400 gals.	3 in. pipe	2½ in. hose and 2½ in. pipe	22 x 12 in.	Weald	\$200.00	Raptvov	\$320.00
" 4	1½ "	300 to 350 "	500 to 580 "	5 "	2½ " " 4 "	24 x 14 "	Wealden	290.00	Raptvud	490.00
" 5	2½ "	250 to 300 "	625 to 750 "	6 "	2½ " " 5 "	30 x 15 "	Wealdis	375.00	Raptvyw	625 00
" 6	4½ "	200 to 250 "	900 to 1125 "	8 "	2½ " " 6 "	36 x 16 "	Wealar	600.00	Raptwax	1000.00

See pages 299 to 307 for Prices, Pipe, Hose, Couplings, Play Pipes, etc.



WITH COUPLING FOR DRIVING SHAFT.

Fig. 302½ is a powerful Fire Pump, durable and simple, having only two moving parts in the case (or cylinder.) The method of driving shown in Fig. 895, page 166, is excellent.

On page 152 is constructive view and description of these celebrated Rotary Pumps. The suction is regularly fitted for wrought-iron pipe. It will be fitted for cast-iron pipe or hose when so ordered. There are five discharge openings on all Pumps. One has flange cut for 2½-inch hose coupling and furnished with cap. Another has flange tapped for iron pipe of size stated in table below; the other outlets are provided with blank flanges. All five flanges are interchangeable. These outlets will be fitted otherwise to order.

An automatic relief valve should be attached close to the Pump. Either the spring or lever style may be used. General preference is for the spring valve. We are prepared to furnish both at market rates.

Valves for the several sizes should be: For No. 3 Pump, 2½-inch; No. 4 Pump, 3-inch; No. 5 Pump, 3½-inch; No. 6 Pump, 4-inch.

See "Table of Effective Fire Streams," page 161.




FIG. 302½

FIG. 302½. SIZES, PRICES, ETC


No.	Capacity One Rev.	Speed and Capacity per Minute for Good Fire Service.	Suction.	Discharges.	IRON.		BRONZE CASE AND CAMS.	
					Cipher.	Price.	Cipher.	Price.
3	1 gai.	350 to 400 revs., 350 to 400 gals.	3 in. pipe	2½ in. hose and 2½ in. pipe	Dregs	\$175.00	Rabims	\$295.00
4	1½ "	300 to 350 " 500 to 580 "	5 "	2½ " " 4 "	Dress	260.00	Rabjoe	460.00
5	2½ "	250 to 300 " 625 to 750 "	6 "	2½ " " 5 "	Drift	335.00	Rabjud	585.00
6	4½ "	200 to 250 " 900 to 1125 "	8 "	2½ " " 6 "	Bearish	535.00	Rabkoo	935.00

See pages 299 to 307 for Prices, Pipe, Hose, Couplings, Play Pipes, etc.



# GOULDS POWER ROTARY FIRE PUMP.

*WITH FRICTIONAL GEARING.*



*FIG. 895*

Fig. 895, Power Rotary Fire Pump, is arranged with frictional gearing. It is a method of driving acceptable to the Fire Underwriters, and is generally specified by them. Friction gears are a special form of pulley with faces cut to V-shaped grooves accurately fitted to mesh together. They have great traction or transmitting power, and with but relatively little thrust on the bearings.

Rotary Fire Pumps are more commonly found in mills having water power, yet the Rotary Pump is often placed in mills and factories having steam power only. We have in our own works a 1,000-gallon Rotary Fire Pump coupled to a steam engine. This equipment is satisfactory to and has been accepted by the Associated Factory Mutual Insurance Companies.

Prices upon complete outfit with any method of driving will be quoted upon application. The following data is necessary: Quantity of water required per minute; elevation above the Pump to highest point to be covered by fire stream; distance from Pump to remotest points to be protected; diameter and speed of the shaft available for driving the Pump; a sketch showing where the Pump is to be placed, the driving shaft and immediate surroundings.

We refer to previous pages for further description and to page 161 for information about Fire Streams, etc.

# GOULDS ROTARY ELECTRIC PUMP.

167

WITH BASE AND INTERMEDIATE GEARING.

Fig. 303 is our Rotary Pump arranged with base and gearing to be driven by an electric motor.

This combination forms a pumping equipment which is light, compact, portable and of great capacity. It is serviceable for mining, irrigation, fire protection and in manufacturing plants for a wide variety of pumping.

Price will include the Pump, the motor base and the gearing necessary to connect the Pump and motor, but does not include the motor.

We will furnish electric motors of any make and type, completing the equipment, sending it out ready for pipe and wire connections, if so ordered.




FIG. 303, No. 3

FIG. 303. SIZES, CAPACITIES, ETC.

Size.	Capacity one Revolution.	Usual Speed and Capacity per Minute.	Suction.	Discharge.	Geared.	IRON.		BRONZE CASE AND CAMS.	
						Cipher.	Price.	Cipher.	Price.
No. 1	.25 gal.	250 revs.— 62 gals.	2 in.	1½ in.	As Required by the Electric Motor.	Zymo	\$235.00	Zymn	\$275.00
" 2	.50 "	200 " 100 "	2½ "	2 "		Zymols	275.00	Zymrd	340.00
" 3	1. " "	175 " 175 "	3 "	2½ "		Zymose	345.00	Zymso	465.00
" 4	1.6 "	150 " 240 "	5 "	4 "		Zymot	500.00	Zylo	700.00
" 5	2.5 "	125 " 312 "	" "	5 "		Zymome	625.00	Zylobs	875.00
" 6	4. " "	100 " 400 "	8 "	6 "		Zymfur	975.00	Zylocl	1375.00

Prices upon application.



# GOULDS CENTRIFUGAL PUMPS.

Centrifugal Pumps have been built for years, but they have mostly been of a very crude and inefficient type. The Pumps we build have been gradually improved until now they are in point of capacity, efficiency and workmanship the best on the market. This class of Pumps is intended for elevating large quantities of water under comparatively low heads, and they will show a greater economy than any other type of Pump. They are extremely simple. The only moving parts being the runner and shaft, there is practically nothing to wear out, and they will last, therefore, for years without any expenditure whatever in repairs.

Many builders of Centrifugal Pumps state a capacity for each Pump which can only be obtained with an enormous expenditure of power and very high speed. In the following tables we only give the economical capacity of our Pumps; that is, the capacity at which they will take the least amount of power. By running them at a higher speed a greater capacity can be obtained, but, at the same time, the efficiency is reduced so that the power required to operate them will be greater than if a larger size Pump were used. The table of revolutions per minute given below is accurate, and if the Pumps are run according to the speeds there given, the discharge will be that given in the tables.

Centrifugal Pumps are used very extensively for irrigation and drainage, sewage pumping, dry docks, paper and pulp mills, tanneries, dyers, distillers, starch factories, excavations, etc., and they are especially to be recommended as no solid matter in suspension will prevent their operation, because, as they have no valves whatever, there is nothing to clog up or become foul.

Pump No. Diameter Discharge Opening.	Economical Capacity per Minute.	Horse-Power Required for Each Foot Elevation.	REVOLUTIONS PER MINUTE AT WHICH PUMPS SHOULD BE RUN TO DELIVER "ECONOMICAL CAPACITY" TO DIFFERENT ELEVATIONS.									Pump No. Diameter Discharge Opening.
			5 feet.	10 feet.	15 feet.	20 feet.	25 feet.	30 feet.	35 feet.	40 feet.	50 feet.	
Inches.												Inches.
1½	70 gals.	.035	428	604	739	854	955	1,045	1,131	1,208	1,351	1½
1¾	90 "	.046	348	491	601	695	777	850	920	982	1,099	1¾
2	120 "	.06	302	426	522	603	674	737	798	852	953	2
2½	185 "	.09	302	426	522	603	674	737	798	852	953	2½
3	260 "	.13	302	426	522	603	674	737	798	852	953	3
4	470 "	.22	285	402	493	569	637	697	754	805	901	4
5	735 "	.37	256	362	443	512	572	626	678	724	810	5
6	1,050 "	.53	214	302	368	427	478	523	566	604	675	6
8	2,000 "	1.01	183	259	317	366	409	448	485	517	579	8
10	3,000 "	1.52	168	238	291	336	376	411	445	475	532	10
12	4,200 "	2.12	133	188	230	266	298	326	352	376	421	12
15	7,000 "	3.53	105	148	181	209	234	256	277	295	331	15
*15	7,000 "	3.53	151	213	261	301	337	369	399	426	477	15*
18	10,000 "	5.00	105	148	181	209	234	256	277	295	331	18
*18	10,000 "	5.00	151	213	261	301	337	369	399	426	477	18*
20	12,000 "	6.00	144	202	245	285	321	348	376	400	448	20

\* Refers to low-lift Pumps.

Above table gives *correct* speed of our Pumps as employed under usual conditions of pumping. If water must be forced through a number of bends and elbows, or a great length of piping the above speed must be somewhat increased.

Use large pipes and easy bends wherever practicable, as they save power. We can furnish elbows and piping of any size.



# GOULDS VERTICAL CENTRIFUGAL PUMPS.

169

## SUBMERGED AND SUCTION TYPES.




FIG. 694  
SUBMERGED TYPE.

Fig. 694 shows our Vertical Pump which is intended to be submerged in the liquid to be pumped. This is probably the simplest type of pump in the market and is easily placed in position. Being entirely covered by water it requires no apparatus for priming. It is always ready to start as soon as power is applied. This Pump is used considerably by contractors in excavations and coffer-dam work, and also in some instances for pumping out dry docks. We are prepared to furnish extra shafting, bearings and pipe. In ordering shafting give distance from foundation on which the pump sets to center of pulley.

Fig. 693 shows our Vertical Suction Pump. This Pump is to be placed above the water from which it is drawing. This Pump is mainly used for pumping from driven wells or in any place where it is not desirable to submerge the pump, but where the situation nevertheless will not allow the use of a horizontal pump.




FIG. 693  
SUCTION TYPE.

## FIGS. 694 AND 693. SIZES, PRICES, ETC.

Pump No. Diameter Discharge Opening. Inches.	Economical Capacity per Minute.	Diameter and Face of Pulley in Inches.	Floor Space Re- quired in Inches.	Distance from Bottom of Pump to Center of Coupling.	Coupling Bored for Connect- ing Shaft, Diameter.	FIG. 694. SUBMERGED TYPE, WITH ELBOW, ONE PAIR COUPLINGS, PUL- LEY AND ONE BEARING.				FIG. 693. SUC. TYPE, WITH ELBOW, ONE PAIR COUP'S, PUL. AND ONE BEARING.		Pump No. Diameter of Discharge Opening. Inches.
						IRON.		BRASS.		IRON.		
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	
1 <sup>1</sup> / <sub>2</sub>	70 gals.	5 x 6	17 x 21	2 ft. 9 in.	1 in.	Zymek	\$40.00	Bill	\$70.00	Reefky	\$44.00	1 <sup>1</sup> / <sub>2</sub>
1 <sup>3</sup> / <sub>4</sub>	90 "	6 x 6	21 x 29	3 " 0 "	1 "	Pant	50.00	Peak	90.00	Reeflu	55.00	1 <sup>3</sup> / <sub>4</sub>
2	120 "	7 x 8	23 x 30	3 " 4 "	1 <sup>1</sup> / <sub>8</sub> "	Pare	65.00	Peal	110.00	Reefmor	72.00	2
2 <sup>1</sup> / <sub>2</sub>	185 "	7 x 8	24 x 30	3 " 4 "	1 <sup>1</sup> / <sub>8</sub> "	Wander	80.00	Wang	135.00	Reefnir	88.00	2 <sup>1</sup> / <sub>2</sub>
3	260 "	7 x 8	25 x 32	3 " 6 "	1 <sup>1</sup> / <sub>8</sub> "	Park	95.00	Peat	150.00	Reefnud	105.00	3
4	470 "	8 x 10	29 x 39	4 " 0 "	1 <sup>7</sup> / <sub>8</sub> "	Part	110.00	Peck	240.00	Reefoj	122.00	4
5	735 "	10 x 10	34 x 45	4 " 7 "	1 <sup>1</sup> / <sub>8</sub> "	Zymel	140.00	Bind	315.00	Reefju	155.00	5
6	1,050 "	12 x 12	37 x 48	4 " 7 "	1 <sup>1</sup> / <sub>8</sub> "	Pass	170.00	Peek	360.00	Reefqut	190.00	6
8	2,000 "	18 x 12	45 x 56	5 " 5 "	2 "	Past	265.00	.....	.....	Reegas	295.00	8
10	3,000 "	20 x 12	51 x 68	5 " 5 "	2 "	Pate	330.00	.....	.....	Reeget	365.00	10
12	4,200 "	24 x 14	63 x 72	6 " 0 "	2 <sup>3</sup> / <sub>8</sub> "	Path	420.00	.....	.....	Reegim	475.00	12
15	7,000 "	30 x 16	77 x 102	6 " 6 "	3 <sup>1</sup> / <sub>4</sub> "	Pave	600.00	.....	.....	Reegog	665.00	15
15*	7,000 "	30 x 15	60 x 71	6 " 6 "	3 <sup>1</sup> / <sub>4</sub> "	Regeab	480.00	.....	.....	Reegum	530.00	*15
18	10,000 "	36 x 18	98 x 126	7 " 0 "	3 <sup>3</sup> / <sub>4</sub> "	Pawn	950.00	.....	.....	Reegvo	1050.00	18
18*	10,000 "	30 x 16	66 x 78	6 " 6 "	3 <sup>1</sup> / <sub>4</sub> "	Regeel	850.00	.....	.....	Reegvus	940.00	*18
20	12,000 "	36 x 20	73 x 92	4 " 6 "	4 "	Regeff	1200.00	.....	.....	Reegwe	1325.00	20

\* Refers to Low Lift Pumps.

For table of revolutions and power required to lift water to different heights, see table page 163.

## GOULDS HORIZONTAL CENTRIFUGAL PUMPS.




FIG 695 WITHOUT PRIMER.




FIG. 696, WITH PRIMER.

Fig. 695 shows our improved Horizontal Pump without suction primer. This pump as a machine is perfect. It is strong and solid. It has a large diameter shaft running in long bearings lined with best babbitt metal. The pulley is large, the hub bearing is of special design fitted with proper packing gland. Oil boxes are large and have covers to keep out dust and dirt. All parts are accurately machine fitted.

Fig. 696 shows our Standard Horizontal Pump with suction primer attached. The small force pump on the extreme left is only used for charging the main pump. Before starting, this small force pump is worked by hand until the main pump is filled so that the water spurts from the pet-cock on top of the pump shell. This shows that the pump is completely filled and therefore is ready to start. The primer will keep the pump primed and makes foot valves unnecessary.

## FIGS. 695 AND 696. SIZES, CAPACITIES, PRICES, ETC.

No. Pump. Diameter of Dis- charge. Inches.	Size Pipe Flange on Suction.	Economical Capacity per Minute.	Diameter and Face of Pulley in Inches.	Floor Space Re- quired in Inches. With- out Primer.	FIG. 695. WITHOUT PRIMER.			FIG. 696. WITH PRIMER.		
					Iron. Cipher.	Brass Fitted. Price.	Brass. Price.	Iron Cipher.	Brass Fitted. Price.	Brass Price.
1 1/4	2 in.	70 gals.	6 x 6	17 x 31	Bung	\$45.00	\$57.00	Cabined	\$55.00	\$67.00
1 3/4	2 "	90 "	7 x 8	21 x 32	Mane	60.00	75.00	Oval	70.00	85.00
2	3 "	120 "	8 x 8	23 x 37	Many	75.00	93.00	Oven	90.00	108.00
2 1/2	3 "	185 "	8 x 8	24 x 38	Wanting	90.00	112.00	Wapiti	105.00	127.00
3	4 "	260 "	8 x 8	25 x 39	Mar	110.00	135.00	Over	130.00	155.00
4	5 "	470 "	10 x 10	29 x 41	Mare	130.00	170.00	Oxen	155.00	195.00
5	6 "	735 "	12 x 12	34 x 54	Broadcast	165.00	225.00	Bugler	195.00	255.00
6	8 "	1,050 "	15 x 12	37 x 55	Mark	200.00	290.00	Oyer	240.00	330.00
8	10 "	2,000 "	20 x 12	45 x 64	Marl	310.00	440.00	Pace	375.00	505.00
10	12 "	3,000 "	24 x 12	51 x 69	Mars	395.00	560.00	Pack	470.00	635.00
12	15 "	4,200 "	30 x 14	63 x 71	Mart	500.00	775.00			
15	18 "	7,000 "	40 x 15	77 x 80	Mash	850.00				
15*	18 "	7,000 "	30 x 16	60 x 68	Regegs	710.00				
18	20 "	10,000 "	40 x 15	93 x 103	Regeho	1,300.00				
18*	20 "	10,000 "	30 x 16	66 x 72	Regfat	1,150.00				
20	22 "	12,000 "	36 x 20	73 x 83	Regfen	1,540.00				

\*Refers to Low Lift Pumps.

Cipher is given for iron pump only. When Brass-Fitted Pump is wanted add to cipher the word "Brass-Fitted." When Brass is wanted add the word "Brass."

For table of revolutions and power required to elevate water to different heights, see table page 168. For priming pumps larger than 10-inch we recommend flap valve or foot valve with Steam Ejector. See page 173.



Fig. 1257, Special Double-Action Centrifugal Pump (right and left hand combined), is made especially to meet the wants of a high grade pump in paper mills, where service in handling not only water but pulp is especially severe. The cut gives a good idea of the extreme strength and heavy proportions of this pump. One of its special features is that the same pump can readily be made into either right or left hand by simply swiveling the discharge piece around. The bearings are of a special type and are removable without disturbing shaft, pulley, belt, or in fact any part of the pump. The pump is designed to give the very best efficiency and is capable of continuous operation even if the discharge pipe is closed, keeping the water under pressure until required.




FIG. 1257, DOUBLE-ACTION.  
RIGHT AND LEFT HAND COMBINED PUMP.

FIG. 1257 SIZES, CAPACITIES, PRICES, ETC.

Pump No. Diameter Discharge Opening. Inches.	Capacity per Minute.	SPEED NECESSARY TO DELIVER THIS CAPACITY TO DIFFERENT ELEVATIONS.													Dia. and Face Pulley in Inches.	Floor Space Re- quired in Inches.	IRON.	
		Revolutions per Minute.															Cipher.	Price.
		10 ft.	15 ft.	20 ft.	25 ft.	30 ft.	35 ft.	40 ft.	50 ft.	60 ft.	70 ft.	80 ft.	90 ft.	100 ft.				
4	500 gals.	284	348	402	450	492	532	568	622	681	735	786	834	880	16 x 10	45 <sup>1</sup> / <sub>2</sub> x 33 <sup>1</sup> / <sub>2</sub>	Remab	\$150.00
6	1,000 "	241	295	341	382	417	452	482	527	577	623	666	706	747	20 x 12	55 <sup>1</sup> / <sub>2</sub> x 41 <sup>3</sup> / <sub>4</sub>	Remace	250.00
8	1,800 "	198	244	281	314	344	372	397	434	476	514	550	583	615	24 x 15	68 x 51 <sup>1</sup> / <sub>2</sub>	Remadl	400.00

NOTE: Pump, when run at speeds given in above table and with pipes two sizes larger than opening in pump, will require the least power. By increasing the speed a greater discharge can be obtained, for a given lift, but with a loss of power. Due consideration must be taken of the length of pipe and number of elbows forced through.



## GOULDS SAND AND DREDGING PUMP.




FIG. 1181  
SAND AND DREDGING PUMP.

Fig. 1181 shows our Sand and Dredging Pump. The Pump shell is made in one casting and is very heavy, especially in the part that receives the greatest wear. A removable disk is fitted to the suction side of Pump, which can be readily removed, and as this opening is larger than the piston, this can be withdrawn without disturbing the Pump shell or any other part. The pistons have removable liners. It is heavily ribbed inside and has a large surface on the bottom. The bearing pedestals are very strong and heavy, so as to prevent any vibration.

We can furnish any of our Dredging Pumps with engines, single or compound, directly connected, and will, upon application, make special estimates for same.

FIG. 1181. SIZES, CAPACITIES, PRICES, ETC.

Pump No. Diameter Discharge Opening. Inches.	Diameter Suction.	CUBIC YARDS MATERIAL PER HOUR. Per Cent. of Solids.			Horse Power Required for Each 10 Feet Elevation.	Floor Space Required. Inches.	Will Pass Solids, Diameter. Inches.	IRON PUMP, WITH SUCTION AND DISCHARGE ELBOWS, FLAP VALVE AND EJECTOR.	
		10 Per Cent.	15 Per Cent.	20 Per Cent.				Cipher.	Price.
4	4 in.	14 yds.	21 yds.	28 yds.	4	40 x 31	2	Remaeh	\$210.00
6	6 "	30 "	45 "	60 "	8	68 x 40	4 $\frac{1}{2}$	Remafg	300.00
8	8 "	60 "	90 "	120 "	15	72 x 48	6	Remago	475.00
10	10 "	90 "	135 "	180 "	25	94 x 54	8	Remahi	600.00
12	12 "	125 "	190 "	250 "	30	114 x 66	10	Repemo	850.00
15	15 "	210 "	315 "	420 "	50	154 x 78	10	Rebens	1775.00
18	18 "	300 "	450 "	600 "	70	160 x 80	10	Repeol	2000.00

# GOULDS CENTRIFUGAL PUMP FITTINGS.

173

Ejectors are used for priming or charging Centrifugal Pumps where steam can be obtained. A Flap Valve or Foot Valve, as shown below, or Gate Valve, see page 298, is used in connection with Ejector.

Ejector.




SIZES, PRICES, ETC.

Number and Size Centrifugal Pumps.....	1½ and 1¾	2 and 2½	3	4	5 and 6	8 and 10	12 and 15	18	22
Number of Ejector .....	1	1	2	3	4	5	6	7	8
Diameter of Steam Pipe....	¾ in.	¾ in.	½ in.	¾ in.	1 in.	1 in.	1¼ in.	1¼ in.	2 in.
Diameter of Delivery and Suction Pipe.....	½ in.	½ in.	¾ in.	1 in.	1¼ in.	1½ in.	2 in.	2½ in.	3 in.
Price of Ejector and Valves for Connecting .....	\$8	\$8	\$12	\$15	\$25	\$30	\$35	\$45	\$55


Flap Valve.




Foot Valve.



Long Radius Elbow, Plain.



Long Radius Swivel Elbow.



Flap Valve is used on end of discharge pipe to prevent air from entering when using Ejector. (If Gate Valve is preferred, see page 298.)

Foot Valve is used on end of suction pipe to hold column of water and keep pump primed. Iron Foot Valves only furnished with strainer when ordered.

Long Radius Plain Cast Iron Elbow is very desirable for use on Centrifugal Pump, as it does not impede the flow of water as does a short turn.

Long Radius Swivel Elbow performs the same office as the Plain one described above, but is often found more convenient.

FLAP VALVES AND FOOT VALVES. SIZES, PRICES, ETC.

For Centrifugal Pump No.....	1½	1¾	2	2½	3	4	5	6	8	10	12	15	18	22
Flap Valve, Flanged.....	\$5	\$6	\$8	\$9	\$9	\$13	\$19	\$22	\$28	\$36	\$44	\$60	\$88	\$150
Foot Valve, Iron, Flanged.....	5	6	7	8	9	12	15	20	30	40	50	75	110	150
" " Brass " .....	8	9	12	15	18	25	30	40						

LONG RADIUS PLAIN AND SWIVEL ELBOWS. SIZES, PRICES, ETC.

Size.	1½-inch	1¾-inch	2-inch	2½-inch	3-inch	4-inch	5-inch	6-inch	8-inch	10-inch	12-inch	14-inch	15-inch	18-inch	20-inch	22-inch
Plain Iron Elbow .....	\$1.00	\$1.2	\$1.50	\$1.75	\$2.50	\$3.50	\$4.00	\$5.00	\$10.00	\$15.00	\$17.50	\$22.00	\$25.00	\$30.00	\$38.00	\$50.00
Swivel Iron Elbow .....	1.25	1.60	1.90	2.10	3.15	4.40	5.00	6.25	12.50	19.00	22.00	27.00	31.50	37.50	47.50	62.00



# GOULDS "ALERT" DOUBLE-ACTING POWER PUMP.

FOR ELEVATIONS TO FIFTY FEET OR EQUIVALENT PRESSURE.




FIG. 785 $\frac{1}{2}$

Fig. 785 $\frac{1}{2}$  is a Light Service Tank Pump. It has a substantial bed plate, machine cut gear and pinion, pulley to be driven by belt (tight and loose pulleys and out-board bearing at extra price), leather valves, brass-cased piston rod, cup leather packed piston. Suction and discharge connections on either side of pump tapped for standard wrought-iron pipe. Fitted for hose at extra price.

FIG. 785 $\frac{1}{2}$ . SIZES, PRICES, ETC.

PISTON.		Capacity 1 Rev. of Crank Shaft.	Suc. Pipe.	Dis- charge Pipe.	IRON.		BRASS-LINED.	
Dia.	Stroke.				Geared Pulley.		Cipher	Price.
3 in.	5 in.	.31 gal.	1 $\frac{1}{4}$ in.	1 in.	4 to 1	20 x 3 in.	Zoon	\$55.00
3 $\frac{1}{2}$ "	5 "	.42 "	1 $\frac{1}{2}$ "	1 $\frac{1}{4}$ "	4 to 1	20 x 3 "	Zope	60.00
4 "	5 "	.54 "	1 $\frac{1}{2}$ "	1 $\frac{1}{4}$ "	4 to 1	20 x 3 "	Zoril	70.00
							Regebs	\$58.50
							Regeck	65.00
							Regedu	75.00

## DOUBLE-ACTING POWER PUMP.

FOR ELEVATION TO TWENTY-FIVE FEET OR EQUIVALENT PRESSURE

Fig. 1004, Power Double-Acting Suction and Force Pump, is mounted on bed plate, has tight and loose pulleys, brass-lined cylinder, brass valves and valve seats. The discharge valves are accessible through ports or hand holes closed with plugs, or the suction valves below may be reached by removing either cylinder head. The solid piston is double crimped packed. Brass-cased piston rod works through brass stuffing box. Pump is designed only for working against very low head or pressure and should be run not above 20 to 25 R. P. M. Has special application as Circulating Pump, also for pumping oil from tank cars.

FIG. 1004. SIZE, PRICE, ETC.

PISTON.		Capacity one Rev. of Crank Shaft.	Suction.	Discharge.	Pulleys, Each.	Cipher.	Brass- Lined.
Dia.	Stroke.						
5 in.	5 in.	.86 gal.	2 in. pipe	2 in. pipe	20 x 4 in.	Baldrib	\$75.00




FIG. 1004



# GOULDS "CHALLENGE" DOUBLE-ACTING POWER PUMP. 175

FOR ELEVATIONS TO 75 FEET OR EQUIVALENT PRESSURE.




FIG 824½. SIZE 6" X 5"




FIG. 824½. SIZE 7" X 6"

Fig. 824½, "Challenge" Double-Acting Power Pump, is adapted for light work, such as filling tanks, circulating brine, maintaining vacuum, etc. A substantial bed-plate extends the whole length of the Pump, affording a rigid support and permanent alignment for the working parts and cylinder. All Pumps have machine-cut gears, tight and loose pulleys, babbitted bearing, sight-feed oil cups; piston, cupped-leather packed; brass valve seats, brass glands and brass-cased piston rod. Two and one-half-inch, three and four-inch Pumps have brass valves ground to seats. Five, six, seven and eight-inch Pumps have rubber discs valves. Fibrous or metallic-spring packed pistons to order, at extra price.

Above is given detail of our *standard construction*. When so ordered, we modify their construction to suit particular requirements.


FIG. 824½. SIZES, CAPACITIES, ETC.

PISTON.		Capacity One Rev. of Crank Shaft.	Usual Speed and Capacity per Minute.		Suction.	Dis.	Geared	Tight and Loose Pulleys.	BRASS-LINED CYLINDER.		BRASS CYLINDER.		*ALL BRASS.	
Dia.	Stroke.								Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2½ in.	4½ in.	.20 gals.	30 to 40 revs.,	6.0 to 8.0 gals.	1¼ in. pipe	1 in. pipe	4 to 1	20 x 3 in.	Zoste	\$85.00	Ridema	\$115.00	Rigust	\$150.00
3 "	4½ "	.27 "	30 to 40 "	8.1 to 10.8 "	1¼ "	1¼ "	4 to 1	20 x 3 "	Zostera	90.00	Riguls	120.00	Rigute	155.00
4 "	4½ "	.50 "	30 to 40 "	15.0 to 20.0 "	1½ "	1¼ "	4 to 1	20 x 3 "	Zouave	95.00	Rigumd	130.00	Riguvo	170.00
5 "	5 "	.85 "	30 to 40 "	25.5 to 34.0 "	2 "	1½ "	3 to 1	20 x 4 "	Zound	125.00	Rigunl	175.00	Rihads	260.00
6 "	5 "	1.22 "	30 to 40 "	36.6 to 48.8 "	2½ "	2 "	3 to 1	20 x 4 "	Zuche	150.00	Riguop	220.00	Rineml	320.00
7 "	6 "	2.00 "	30 to 40 "	60.0 to 80.0 "	3 "	3 "	4 to 1	24 x 4 "	Zynat	250.00	Rigupa	425.00	Rintal	550.00
8 "	6 "	2.60 "	30 to 40 "	78.0 to 104.0 "	4 "	4 "	4 to 1	24 x 4 "	Zyned	300.00	Rigurl	500.00	Rintet	650.00

\* All-brass Pumps have all parts of brass, except the bed-plate and driving parts.

## GOULDS HORIZONTAL TANK PUMP.

*FOR ELEVATIONS TO 75 FEET, EQUIVALENT TO 32 POUNDS PRESSURE.*



*FIG. 1114, SIZE 12" X 16"*

# GOULDS HORIZONTAL TANK PUMP.

177

*FOR ELEVATIONS TO 75 FEET, EQUIVALENT TO 32 POUNDS PRESSURE.*




Fig. 1114 is a Horizontal Pump for light service. It has one cylinder with a double-acting piston, and is intended for pumping water to tanks, circulating brine, or other fluids, irrigation, etc.

The cylinder is fitted with removable bronze lining. The piston is packed with fibrous packing. The piston rod is of steel. The crosshead runs in adjustable guides. The crank and crosshead pins have adjustable bronze boxes. The gearing is machine-cut. Tight and loose pulleys. Slight-feed oil cups. Suction pipe may be connected at either side of the cylinder.

*FIG. 1114 SIZES, CAPACITIES, ETC*

PISTONS.		SIZES OF PIPE.						
Diameter	Stroke.	Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
				Suction.	Discharge.			
8 in.	10 in.	4.25 gals.	30 revs., 127 gals.	5 in.	5 in.	4 to 1	30 x 5 in.	Treadl
10 "	10 "	6.5 "	30 " 195 "	7 "	6 "	4 to 1	30 x 6 "	Treaef
10 "	14 "	9.5 "	30 " 285 "	8 "	6 "	4 to 1	36 x 6 "	Treaba
12 "	16 "	15.4 "	30 " 462 "	10 "	8 "	4 to 1	42 x 6 "	Treact
14 "	18 "	24. "	30 " 720 "	12 "	10 "	4 to 1	48 x 8 "	Trevob





GOULDS TRIPLEX POWER PUMPS IN MILLS AND FACTORIES.

Gould's Triplex Power Pump, by its continuous action of parts, produces a constant flow of fluids and develops highest efficiency. Efficiency is the ratio between the effective, or useful, work and the total work put into a machine. The effective, or theoretical, work of a Pump lifting water is the quantity of water lifted to a certain height. When the rate of doing this work of pumping is considered it is measured in horse power. The actual horse power consumed in pumping water includes, not only the delivery of a certain quantity to a given height, but also the power required to overcome its inertia, viz.: to start it from a state of rest and to stop it; its friction in passing through the pipes and the Pump; and the inertia and friction of the working parts of the Pump.

While it is impracticable to build a Pump that will produce perfectly uniform action upon the water, the work wasted in this particular by the Triplex is only about one-third of that wasted in the best designed duplex or four-plunger Pumps; and in this respect the single Pumps are unworthy of comparison.

Among pumping devices depending upon steam are:

Injectors and Inspirators, using about.....	100	lbs.	Coal	per	H.	P.	Hour.
Pulsometers, using about.....	67	"	"	"	"	"	"
Small steam pumps using about.....	25	"	"	"	"	"	"
Larger steam pumps, compounded, using about.....	13	"	"	"	"	"	"

The Power Pump participates in the economy of the Steam Engine, using from  $1\frac{1}{2}$  pounds of coal to five or six pounds per H. P. per hour.

Electrically operated Power Pumps are frequently employed under such conditions that the cost, aside from their convenience, is much in their favor.

The operating of Power Pumps by Gas or Gasoline Engines is rapidly coming into use, and at very low cost for fuel, and with expense for attendance reduced to a minimum.

We manufacture in quantities on the interchangeable plan. We use only high-grade materials and a modern shop equipment. Our Pumps are of handsome design, correctly proportioned, and exceptionally well built. All parts are accurately interchangeable and wearing parts are adjustable or easily renewed.



# GOULDS TRIPLEX POWER PUMP FOR LIGHT SERVICE.

FOR ELEVATIONS TO 100 FEET, EQUIVALENT TO 43 POUNDS PRESSURE.




FIG. 957. SIZE 7" X 8"

Fig. 957, Triplex Power Pump, single acting, is designed and built especially for pumping water to tanks or reservoirs, directly into pipe systems, and for circulating fluids of any kind.

It is a special type of our Standard Triplex construction, having a large valve area, outside-packed plungers with water seal, bronze-lined crank boxes, machine-cut gear and pinion. It has tight and loose pulleys for belt drive from line shaft, or from gas or steam engine, or by electric motor.

Our regular construction: Iron plungers, cylinders and glands, with rubber disc valves for cold water. These parts made of other materials to order, adapting the Pump to a wide variety of service.

Prices upon application.

FIG. 957. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
4 in.	6 in.	1.0 ga s.	45 revs., 45 gals.	2 in.	2 in.	5 to 1	20 x 3	Wraivj
5 "	8 "	2.0 "	45 " 90 "	3 "	3 "	5 to 1	26 x 4	WraiwI
7 "	8 "	4. "	45 " 180 "	5 "	5 "	5 to 1	30 x 5	WritheS
8 "	10 "	6.5 "	40 " 260 "	6 "	5 "	5 to 1	36 x 6	Writin
8 "	12 "	7.8 "	40 " 312 "	6 "	5 "	5 to 1	36 x 6	Wroken

For Power Tables see page 203.

Methods of driving from electric motor, etc., see pages 188, 189.



# GOULDS TRIPLEX POWER PUMP FOR GENERAL SERVICE. 181

FOR ELEVATIONS TO 300 FEET, EQUIVALENT TO 130 POUNDS PRESSURE.

Fig. 924 is the Pioneer Triplex Power Pump, single-acting, for general service, such as Water Supply, Hydraulic Pressure, Boiler Feeding, etc. It is compact, self-contained, well-built, and requires no special foundation. It has proven reliable and durable, and is the accepted pump for a wide variety of service.

The valves have rubber discs with bronze trimmings and seats, all easily accessible. The plungers are outside-packed and have water seal. Each connecting rod has bronze bushed bearing in plunger and adjustable bronze bearing at crank. The crank shaft is in one piece and runs in large babbitted bearings. The gear and pinion are machine cut. Tight and loose pulleys. Sight-feed oil cups.

Our regular construction is : Iron cylinders, glands, plungers, and rubber disc valves for hot or cold water, as ordered. Bronze plungers, bronze-lined cylinders and glands at extra price. State whether hot or cold water is to be pumped. Prices upon application.




FIG. 924. 6½" x 8"

FIG. 924. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity one Revolution of Crank Shaft.	*Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
1¼ in.	2 in.	0.03 gal.	50 Revs.. 12 gals.	1½ in.	1½ in.	5 to 1	15 x 3 in.	Wench
1¾ in.	2½ in.	0.07 "		1½ "	1½ "	5 to 1	15 x 3 "	Wend
2 "	3 "	0.12 "		2 "	2 "	5 to 1	20 x 3 "	Wenel
2½ in.	4 "	0.25 "		2 "	2 "	5 to 1	20 x 3 "	Wenta
3 "	4 "	0.36 "	45 " 18 "	3 "	3 "	5 to 1	26 x 4 "	Wereba
4 "	4 "	0.65 "	45 " 29 "	3 "	3 "	5 to 1	30 x 5 "	Werste
4 "	6 "	1.0 "	45 " 45 "	4 "	4 "	5 to 1	30 x 6 "	Wooring
5 "	6 "	1.5 "	45 " 67 "	5 "	5 "	5 to 1	36 x 6 "	Werte
5 "	8 "	2.0 "	40 " 80 "	5 "	5 "	5 to 1	42 x 6 "	Zylode
6½ in.	8 "	3.4 "	40 " 136 "	6 "	6 "	5 to 1	42 x 8 "	Zylom
8 "	8 "	5.2 "	40 " 208 "					
8 "	10 "	6.5 "	40 " 260 "					
9 "	10 "	8.2 "	40 " 328 "					

We build these sizes in Fig. 1009 type only, see page 183.

\* Speed and Capacity for boiler feeding, see page 185. Power Table, see page, 203.  
Methods of driving from Electric Motors, etc., see pages 188, 189.

# 182 GOULDS TRIPLEX POWER PUMP FOR GENERAL SERVICE.

FOR ELEVATIONS TO 250 FEET, EQUIVALENT TO 110 POUNDS PRESSURE.




FIG. 1140. SIZE 6" X 8"

Fig. 1140, Triplex Power Pump, has three single-acting plungers, with crossheads and guides, which sustain the side thrust of the connecting rods, permitting the plungers to reciprocate through the packings, without lateral thrust. By this means the wear of the plungers, glands and packings is reduced to a minimum and the crosshead bearings are accessible. Connecting rod and crank shaft bearings are bronze-lined and adjustable for wear. Crosshead bearings are bronze bushed. Gearing is machine cut. Our regular construction provides for tight and loose pulleys and sight feed oil cups. Suction pipe connections are provided at both ends of the valve chest. There is one discharge connection located centrally on the discharge side. Pump is designed for general service, water supply, hydraulic pressure, etc., etc.

Prices upon application.

FIG. 1140. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
4 in.	6 in.	1.0 gals.	45 revs., 45 gals.	2 in.	2 in.	5 to 1	20 x 3 in.	Tobeul
5 "	8 "	2.0 "	45 " 90 "	3 "	3 "	5 to 1	30 x 5 "	Tobey
6 "	8 "	2.9 "	45 " 130 "	4 "	4 "	5 to 1	30 x 6 "	Tobewx
7 "	8 "	4.0 "	45 " 180 "	4 "	4 "	5 to 1	30 x 6 "	Tobid
8 "	10 "	6.5 "	40 " 260 "	5 "	5 "	5 to 1	36 x 6 "	Tobick

For Power Tables, see page 203.

Methods of driving from Electric Motor, etc., see pages 188, 189.



# GOULDS TRIPLEX POWER PUMP FOR GENERAL SERVICE. 183

FOR ELEVATIONS TO 350 FEET, EQUIVALENT TO 150 POUNDS PRESSURE.

Fig. 1009, Triplex Power Pump, has three single-acting plungers, with crossheads and guides which sustain the side thrust of the connecting rods, permitting the plungers to reciprocate through the packings without lateral thrust.

The crank shaft is in one piece and runs in bearings lined with best anti-friction metal. The connecting rod heads are provided with bronze boxes, made in halves, with strap-ends. The crosshead pins have bronze-lined boxes and the crossheads have bronze shoes, all adjustable for taking up wear. Machine-cut gear and pinion; tight and loose pulleys, and sight-feed oilers. Pump is recommended for boiler feeding, hydraulic pressure and general water supply.

Our regular construction is: Sizes,  $1\frac{1}{4} \times 2$  to  $2 \times 3$ , inclusive; iron cylinders, bronze plungers and glands. Larger sizes; iron cylinders, plungers and glands, and rubber disc valves for hot or cold water, as ordered. Bronze plungers, bronze-lined cylinders and glands at extra price.

Data regarding boiler feeding on page 185.

Prices upon application.





FIG. 1009. 6" x 8"

FIG. 1009. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	*Usual Speed and Capacity per Minute.		SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.				Suction.	Discharge.			
$1\frac{1}{4}$ in.	2 in.	0.03 gals.	60 revs.,	1.8 gals.	$\frac{3}{4}$ in.	$\frac{3}{4}$ in.	5 to 1	$12 \times 1\frac{1}{2}$ in.	Crag
$1\frac{3}{4}$ "	$2\frac{1}{2}$ "	0.07 "	60 "	4.2 "	1 "	1 "	5 to 1	$12 \times 2\frac{1}{2}$ "	Craggy
2 "	3 "	0.12 "	50 "	6 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	5 to 1	$12 \times 2\frac{1}{2}$ "	Crachom
$2\frac{1}{2}$ "	4 "	0.25 "	50 "	12 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	5 to 1	$15 \times 3$ "	Cragify
$3\frac{1}{2}$ "	4 "	0.5 "	50 "	25 "	2 "	2 "	5 to 1	$15 \times 3$ "	Craftul
4 "	6 "	1.0 "	45 "	45 "	2 "	2 "	5 to 1	$20 \times 3$ "	Crajum
5 "	6 "	1.5 "	45 "	67 "	3 "	3 "	5 to 1	$26 \times 4$ "	Crajyx
5 "	8 "	2.0 "	40 "	80 "	3 "	3 "	5 to 1	$30 \times 5$ "	Crakal
6 "	8 "	2.93 "	40 "	117 "	4 "	4 "	5 to 1	$30 \times 6$ "	Cusick
7 "	8 "	4.0 "	40 "	160 "	4 "	4 "	5 to 1	$36 \times 6$ "	Cusjoe
8 "	10 "	6.5 "	40 "	260 "	5 "	5 "	5 to 1	$42 \times 6$ "	Cuskus

Speed and Capacity for Boiler Feeding, see page 185. Power Table, see page 203.  
Methods of driving from Electric Motors, etc., pages 188, 189.





*A MODERN POWER HOUSE, WITH GOULDS TRIPLEX POWER BOILER FEED PUMP.*

See Fig. 1157, page 186, and Fig. 1009, page 183.

# GOULDS TRIPLEX POWER PUMPS FOR BOILER FEEDING. 185

ESTIMATE TABLE SHOWING QUANTITY FEED WATER REQUIRED FOR BOILERS, AND SIZE SINGLE-ACTING TRIPLEX PUMP FOR DELIVERING THIS QUANTITY.

Table is based on 30 pounds feed water per horse power per hour, which is the standard adopted by the American Society of Mechanical Engineers, and is the generally accepted commercial standard by boilermakers and users.

Size Boiler.	Quantity Feed Water Required.	Valves and Connections.	* Size Triplex Pump.
50 H. P.	3 gals. minute	1 in.	2 x 3 in.
100 "	6 " "	1 "	2½ x 4 "
200 "	12 " "	1¼ "	3½ x 4 "
250 "	15 " "	1¼ "	3½ x 4 "
300 "	18 " "	1¼ "	4 x 6 "
400 "	24 " "	1¼ "	4 x 6 "
500 "	30 " "	1½ "	5 x 6 "
600 "	36 " "	1½ "	5 x 6 "
800 "	48 " "	1½ "	5 x 8 "
1,000 "	60 " "	1½ "	5 x 8 "
1,200 "	72 " "	2 "	6 x 8 "
1,500 "	90 " "	2½ "	7 x 8 "
1,800 "	108 " "	2½ "	7 x 8 "
2,200 "	132 " "	2½ "	7 x 10 "
3,000 "	180 " "	2½ "	8 x 10 "
3,500 "	210 " "	2½ "	8 x 10 "
4,500 "	270 " "	3 "	8½ x 12 "
6,000 "	360 " "	4 "	10 x 12 "




PLATE "E"

\*Based upon a moderate speed of 25 R. P. M. of Pump Crank Shaft.

Pumps fitted as above, with by-pass and water relief, to order.



# 186 GOULDS TRIPLEX HIGH-PRESSURE BOILER-FEED PUMP.

FOR PRESSURE TO 200 POUNDS, EQUIVALENT TO 460 FEET ELEVATION.




FIG. 1157 SIZE 6" X 8"

Compound Engines and High Pressure Boilers are rapidly coming into use. We are supplying Power Boiler Feed Pumps for pressures up to and exceeding 200 pounds per square inch.

Fig. 1157, for High Pressure Boiler Feeding and other heavy pumping, has distinctive features especially adapting it to hard service. Outside connected plungers with cross-heads and guides, connecting rods with strap ends and phosphor bronze boxes, heavy bearings, extra weight and stiffness throughout.

Our regular construction provides cylinders, plungers, and glands of iron, and valves for cold or hot water. We furnish plungers, etc., of phosphor bronze, when so ordered, at extra price.

Correspondents should carefully specify the work to be done, stating the kind and volume of fluid to be pumped, the pressure at the pump, and other conditions.

Prices upon application.

FIG. 1157. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	*Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
1½ in.	3 in.	.07 gal.	40 revs., 2.8 gals.	1¼ in.	1¼ in.	5 to 1	12 x 2½ in.	Rusehis
2 " "	4 " "	.16 " "	35 " 5.7 " "	1½ " "	1½ " "	5 to 1	15 x 3 " "	Saploa
3 " "	4 " "	.36 " "	35 " 12 " "	2 " "	2 " "	5 to 1	15 x 3 " "	Sapluer
3½ " "	6 " "	0.74 " "	30 " 22 " "	2 " "	2 " "	5 to 1	20 x 3 " "	Tobem
4 " "	8 " "	1.3 " "	30 " 39 " "	2½ " "	2½ " "	5 to 1	30 x 5 " "	Tobens
5 " "	8 " "	2.0 " "	30 " 60 " "	3 " "	3 " "	5 to 1	30 x 6 " "	Tobepo
6 " "	8 " "	2.9 " "	30 " 87 " "	4 " "	4 " "	5 to 1	36 x 6 " "	Toberd
7 " "	10 " "	5.0 " "	30 " 150 " "	5 " "	5 " "	5 to 1	42 x 6 " "	Tobest

\*Speed and capacity for boiler feeding, see page 185. Power Table, see page 203.

Methods of driving from Electric Motors, etc., see pages 188, 189.



# GOULDS TRIPLEX POWER PRESSURE PUMP.

187

Fig. 997, Triplex Power Pressure Pump, is for use with filter presses, hydraulic presses and cranes, in oil refineries, on pipe lines, and for other service where the pressure exceeds the ordinary 100 to 200 pounds per square inch. It is vertical and self-contained. The plungers are single-acting, outside guided and connected, outside packed, and driven by a powerfully geared three-throw crank shaft.

Size No. M and smaller have Bronze Cylinders and Glands. The steel plungers are fitted with cup leather or fibrous packing according to intended service. The crossheads are of the cylindrical type and run in bored guides.

Size No. 1 and larger (type illustrated) have Bronze-Lined Cylinders and Glands with Steel Plungers. The crossheads have bronze shoes and run in bored guides. Air chambers are furnished only on sizes, D, E, G and H.

All sizes have metal valves, bronze main bearings for the crank shafts, bronze crank pin and crosshead pin boxes, machine-cut gearing tight and loose pulleys, and sight-feed oil cups. Special construction, including Bronze Plungers, to order. Prices upon application.





FIG. 997. No. F, SIZE 3" x 8"


FIG. 997. SIZES, CAPACITIES, ETC.

No.	PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.		Limit Pressure per Square Inch.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
	Diameter.	Stroke.					Suction.	Discharge.			
A	1 in.	4 in.	.04 gals.	40 revs.,	1.6 gals.	1500 lbs.	1 1/4 in.	1 in.	5 to 1	15 x 3 in.	Riteho
K	1 1/4 "	4 "	.06 "	40 "	2.4 "	900 "	1 1/4 "	1 "	5 to 1	15 x 3 "	Riteil
B	1 3/4 "	6 "	.03 "	40 "	1.2 "	5000 "	1 "	3/4 "	7 to 1	26 x 4 "	Ritejm
L	1 1/4 "	6 "	.09 "	40 "	3.6 "	1800 "	1 1/4 "	1 "	7 to 1	26 x 4 "	Riteka
M	1 1/2 "	6 "	.13 "	40 "	5.2 "	1200 "	1 1/4 "	1 "	7 to 1	26 x 4 "	Ridefu
S	2 1/4 "	6 "	.30 "	40 "	12.0 "	1500 "	2 "	1 1/2 "	5 to 1	30 x 5 "	Ridegsl
N	3 "	6 "	.55 "	40 "	22.0 "	650 "	2 "	2 "	5 to 1	30 x 5 "	Ridehm
P	4 "	6 "	1. "	40 "	40.0 "	350 "	2 "	2 "	5 to 1	30 x 5 "	Rideis
R	5 "	6 "	1.53 "	40 "	61.0 "	240 "	3 "	3 "	5 to 1	30 x 5 "	Roatila
C	2 1/4 "	8 "	.41 "	40 "	16.4 "	1500 "	3 "	2 "	5 to 1	36 x 6 1/2 "	Roatat
D	4 1/2 "	8 "	1.65 "	40 "	66.0 "	400 "	3 "	3 "	5 to 1	36 x 6 1/2 "	Roatem
E	6 1/2 "	8 "	3.44 "	40 "	137.0 "	200 "	4 "	4 "	5 to 1	36 x 6 1/2 "	Roatfo
F	3 "	8 "	.73 "	40 "	29.2 "	1500 "	3 "	2 "	5 to 1	42 x 6 1/2 "	Roatget
G	4 1/2 "	8 "	1.65 "	40 "	66.0 "	600 "	3 "	3 "	5 to 1	42 x 6 1/2 "	Roatgof
H	6 1/2 "	8 "	3.44 "	40 "	137.0 "	300 "	4 "	4 "	5 to 1	42 x 6 1/2 "	Roathad

For Power Tables see page 203. Methods of driving from electric motors, etc., pages 188, 189.



Standard Construction. Tight and Loose Pulleys for Belt from Counter Shaft or Engine.



FORM "B" (Cipher, Form B.)

With Rawhide Pinion and Single Pulley for Belt from Electric Motor.


Outline engravings on this and following page are intended to represent a general type of Triplex Power Pump with changes in form of driving connections which can be applied (with some small modifications) to any of our Pumps.

Standard construction tight and loose pulleys. Under this form we catalogue our several types as Figs. 924, 1009, etc., and refer to previous pages for details

Form "B," with rawhide pinion and single pulley for belt drive from electric or other high speed motor. This form of belt drive is practically noiseless and wherever space will permit, and dampness does not prohibit, we recommend it. Always specify dimensions and speed of motor pulley and required number of gallons per minute.


Form "C," intermediate gearing, rawhide motor pinion and bed plate for geared connections to electric motor. We cannot recommend as perfectly noiseless, or for this reason adapted for house use. In damp places, where noise is no objection, or in places where economy of space is a first requisite we recommend. Orders should be accompanied by detail motor drawings. State required number of gallons per minute. In Figs. 957 and 924, types motors are usually placed behind pumps, instead of at end as shown. In largest sizes of pumps bed plates are sometimes dispensed with.





FORM "C" (Cipher, Form C.)

Intermediate Gearing, Rawhide Motor Pinion and Bed Plate for Geared Connection to Electric Motor.



FORM "D" (Cipher, Form D.)

Friction Clutch for Direct Connection to Engine Shaft. With or Without Bed Plate.

Form "D," for friction clutch connection to engine shaft; a very satisfactory connection to steam, gas and gasoline engines where speed conditions will allow. Always specify speed of engine shaft and required number of gallons per minute. Can be furnished with or without bed plate.

Any of these forms of driving connections may be applied to following figures to which we refer :


Fig. 957.	Triplex Power Pump	.....	page 180
Fig. 924.	" " "	.....	" 181
Fig. 1140.	" " "	.....	" 182
Fig. 1009.	" " "	.....	" 183
Fig. 1157.	" " "	.....	" 186
Fig. 997.	" " "	.....	" 187

Prices upon application.

In telegraphing, place cipher representing desired Form immediately after cipher standing for type and size Pump selected.



## WATER WORKS PUMPING.




One of the most convenient and economical methods of pumping for village water works, irrigation, railroad tanks, etc., is by the use of our Triplex Power Pump, driven by gas or gasoline engine. The equipment is so simple, so easily managed, so quickly started and stopped, and runs for such long intervals without attention, that cost for labor is reduced to a minimum, or entirely eliminated.

Gas and gasoline are cheaper than coal for power in small units, and are less bulky and expensive to handle.

We are annually installing a considerable number of pumping plants with gas or gasoline engines for village water works, etc., in all cases with gratifying success. We shall be pleased to correspond with parties who contemplate purchasing pumps for this line of work.





We can supply Triplex Pumps, complete and ready for erecting, with any type of gas or gasoline engine, or the Pump, friction clutch, and sub-base without Engine, or the Pump alone, as purchasers prefer. The size of Pump and type of engine are factors in making the combination. For pumps of the smaller sizes, cast iron sub-base is desirable, as it affords a rigid and permanent alignment of the Pump and Engine. By its use, expense for other foundation is slight. Arrangement generally used is that shown in illustration. Friction clutch between Pump and Engine allows starting of engine without load. Triplex Power Pumps, pages 180 to 199, are adapted for this service.

## GOULDS SINGLE-ACTING TRIPLEX POWER PUMP.

*FOR ELEVATIONS TO 300 FEET, EQUIVALENT TO 130 POUNDS PRESSURE.*




FIG. 1227 SIZE 8 $\frac{1}{2}$ " X 12".



# GOULDS SINGLE-ACTING TRIPLEX POWER PUMP.

193

*FOR ELEVATIONS TO 300 FEET, EQUIVALENT TO 130 POUNDS PRESSURE.*

Fig. 1227, illustrated on preceding page, shows our new type of Single-Acting Triplex Power Pump. It is designed for a wide variety of service, including Water Supply, Hydraulic Elevator Work, Water Works, etc. The base forms a rigid foundation for the working parts of the Pump, and contains the suction chamber. The valves are contained in the cylinder casting, doing away with outside valve boxes and making a most compact and accessible Pump. It has three single-acting plungers, outside packed and outside guided and connected.

The crossheads have bronze shoes, adjustable for taking up the wear. Each connecting rod, at the crank, has a bronze box with strap and taper attachment, and, at the crosshead pin, a bronze bearing, adjustable for wear. The valve area is ample for fast running and full capacity.

Power for driving is applied to pulley on the pinion shaft, extended at one end, and supported by outboard bearing.

Regular construction is machine-cut gearing, iron plungers, cylinders and glands, rubber disc valves, sight feed oilers, but can supply with bronze plungers, bronze-lined glands at extra price, when so ordered.

The discharge pipe connection may be made at either end of the Pump. The suction pipe connection at either side of the Pump.

The suction pipe connection can be made at the opposite end from the discharge pipe, if so ordered.

Prices upon application.

*FIG. 1227. SIZES, CAPACITIES, ETC*

PLUNGERS.		Capacity, One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	For Elevations to	SIZES OF PIPE.		Geared.	Pulley.	Cipher.
Diameter.	Stroke.				Suction.	Discharge.			
8½ in.	12 in.	8.8 gals.	40 revs., 352 gals.	300 ft.	7 in.	6 in.	5.6 to 1	36 x 12 in.	Wellvet

For Power Table, see page 203.

Methods of driving from Electric Motors, etc., pages 200, 201.

# GOULDS SINGLE-ACTING TRIPLEX POWER PUMP.

*FOR ELEVATIONS TO 350 FEET, EQUIVALENT TO 150 POUNDS PRESSURE.*




FIG. 920. SIZE 10" X 12"

# GOULDS SINGLE-ACTING TRIPLEX POWER PUMP.

195

Fig. 920, Single-Acting Triplex Power Pump, is of the vertical type, and requires little floor space in proportion to its capacity. Power for driving is applied to pulley or gear on the pinion shaft, either centrally, between the housings, or this shaft is extended at either end. For electric or other high speed motive power, intermediate gearing and auxiliary shaft are used and can be supplied. See pages 200, 201.

The design and construction of this Pump embody all the features conducive to high efficiency, durability and strength. It has three single-acting plungers, outside packed and outside guided and connected. The crossheads have bronze shoes. Each connecting rod has strap-head with bronze box at crank and bronze bearing of the marine type at crosshead. The valve area is ample for fast running and large delivery. Each group of suction and discharge valves is conveniently accessible through hand-holes.

Regular construction is machine-cut gearing, iron plungers, cylinders and glands, rubber disc valves, sight feed oilers, but can supply with bronze plungers, bronze-lined glands at extra price, when so ordered.

As this Pump is applied to such a variety of work, we solicit the opportunity to send detailed information to intending purchasers. Prices upon application.

FIG. 920. SIZES, CAPACITIES, ETC.

No.	PLUNGERS.		Capacity One Revolution of Crank Shaft.	† Usual Speed and Capacity per Minute.		For Elevations To	SIZES OF PIPE.		Geared.	* Pulleys.	Cipher.
	Diameter.	Stroke.					Suction.	Discharge.			
A	6 in.	12 in.	4.4 gals.	40 revs..	176 gals.	750 ft.	6 in.	5 in.	5.6 to 1	30 x 12 in.	Wagael
B	7 "	12 "	6. "	40 "	240 "	500 "	6 "	5 "	5.6 to 1	30 x 12 "	Wagaft
C	8½ "	12 "	8.8 "	40 "	352 "	350 "	7 "	6 "	5.6 to 1	30 x 12 "	Clecob
D	5 "	12 "	3.06 "	40 "	122 "	1,500 "	5 "	4 "	5.6 to 1	32 x 12 "	Wagags
E	5½ "	12 "	3.7 "	40 "	148 "	1,300 "	5 "	4 "	5.6 to 1	32 x 12 "	Wagaho
F	6 "	12 "	4.4 "	40 "	176 "	1,000 "	6 "	5 "	5.6 to 1	32 x 12 "	Wagaic
G	7 "	12 "	6 "	40 "	240 "	800 "	6 "	5 "	5.6 to 1	32 x 12 "	Wagaju
H	8 "	12 "	7.8 "	40 "	312 "	600 "	7 "	6 "	5.6 to 1	32 x 12 "	Wageba
I	9 "	12 "	9.9 "	40 "	396 "	500 "	7 "	6 "	5.6 to 1	32 x 12 "	Wageck
J	10 "	12 "	12.2 "	40 "	488 "	350 "	8 "	7 "	5.6 to 1	32 x 12 "	Woooven
K	11 "	12 "	14.8 "	40 "	592 "	300 "	10 "	8 "	5.6 to 1	32 x 12 "	Clubka
L	12 "	12 "	17.6 "	40 "	704 "	250 "	10 "	8 "	5.6 to 1	32 x 12 "	Clubkih

\*Largest pulley that can be placed between pinions and shaft. If speed conditions require larger pulley the pinion shaft may be extended and supported by outboard bearing. See pages 200, 201.

†Speed and capacity for boiler feeding, see page 185. For Power Tables see page 203.



## GOULDS DOUBLE-ACTING TRIPLEX POWER PUMP.

*FOR ELEVATIONS TO 350 FEET, EQUIVALENT TO 150 POUNDS PRESSURE.*




FIG. 1095 7" x 8".

# GOULDS DOUBLE-ACTING TRIPLEX POWER PUMP.

197

*FOR ELEVATIONS TO 350 FEET, EQUIVALENT TO 150 POUNDS PRESSURE.*

Fig. 1095, Double-Acting Triplex Power Pump, is designed for water works, hydraulic elevator service, water supply for manufacturing purposes, etc.

It has three double-acting pistons, and, therefore, nearly twice the displacement of a single-acting Triplex Pump of the same diameter and stroke. It combines large capacity with minimum floor space.

In design, materials and workmanship, the Pump is of the highest grade. The valves and other working parts are liberally proportioned and easily accessible. It has adjustable bearings, crossheads and guides, double gearing, removable bronze cylinder linings, and packed pistons. Our standard arrangement is shown in the illustration. Smaller sizes vary somewhat in detail. Pipe connections may be made at either end of the Pump.

Power for driving is applied to pulley or gearing on the pinion shaft, either centrally, between the housings, or this shaft can be extended at either end to order. For electric or other high speed motive power, intermediate gearing and auxiliary shaft are used. See pages 200, 201 for these different methods of driving.

As this Pump is applied to such a variety of work, we solicit the opportunity to send detailed information to intending purchasers.

Prices upon application.

*FIG 1095. SIZES, CAPACITIES, ETC.*

PLUNGERS.		Capacity per Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.		SIZES OF PIPE.		Geared.	*Pulley.	Cipher.
Diameter.	Stroke.				Suction.	Discharge.			
3 in.	6 in.	1. gal.	60 revs.,	60 gals.	2½ in.	2½ in.	6 to 1	15 x 4 in.	Waxips
4 "	6 "	1.9 "	60 "	114 "	2½ "	2½ "	6 to 1	15 x 4 "	Waxigt
5 "	8 "	3.9 "	40 "	156 "	5½ "	5 "	5.5 to 1	20 x 8 "	Waxirf
6 "	8 "	5.6 "	40 "	224 "	6 "	6 "	5.5 to 1	22 x 10 "	Waxix
7 "	8 "	7.7 "	40 "	308 "	6 "	6 "	5.5 to 1	22 x 10 "	Waxjak
7 "	10 "	9.8 "	40 "	392 "	7 "	6 "	5.3 to 1	26 x 10 "	Waxiob
8 "	10 "	12.7 "	40 "	508 "	8 "	7 "	5.3 to 1	26 x 10 "	Waxiwd
8 "	12 "	15.3 "	40 "	612 "	8 "	7 "	5.6 to 1	30 x 12 "	Waxish
9 "	12 "	19.4 "	40 "	776 "	8 "	7 "	5.6 to 1	30 x 12 "	Waxito
10 "	12 "	23.8 "	40 "	952 "	10 "	8 "	5.7 to 1	32 x 18 "	Waxiun
11 "	14 "	33.6 "	40 "	1344 "	12 "	10 "	5.5 to 1	36 x 20 "	Waysvo
12 "	14 "	40.3 "	40 "	1610 "	12 "	10 "	5.5 to 1	36 x 20 "	Wayswd

\* Largest pulley that can be placed between pinions and crank shaft. If speed conditions or power require larger pulley, the pinion shaft may be extended and supported by outboard bearing. See pages 200, 201.

For Power Table, see page 203.



# GOULDS DOUBLE-ACTING TRIPLEX POWER PUMP. FOR LIGHT SERVICE.

*FOR ELEVATIONS TO 100 FEET, EQUIVALENT TO 43 POUNDS PRESSURE.*




FIG. 1177. SIZE 9" X 12"



# GOULDS DOUBLE-ACTING TRIPLEX POWER PUMP.

199

*FOR ELEVATIONS TO 100 FEET, EQUIVALENT TO 43 POUNDS PRESSURE.*

Fig. 1177, Vertical Triplex Type, has double-acting pistons. Valve chests are on one side of the Pump, and each chest contains two sets of suction and discharge valves. Base casting forms a substantial foundation for working parts of Pump. Power for driving is applied to pulley on the pinion shaft, either centrally between the main bearings, or, when so specified, this shaft is extended beyond the bearing at either end of the Pump and an outboard bearing provided. For electric or other high speed motive power intermediate gearing and auxiliary shaft are used. See pages 200 and 201 for these different methods of driving. The double gearing is machine cut; steel crank shaft carrying a gear at each end beyond the bearing. Connecting rods are of the marine type, made from forged steel and finished all over. Crossheads have bronze shoes and adjustable for taking up wear. Cylinders have removable bronze linings. Pistons are made with followers and fitted with fibrous packing. Pipe connections are at both ends of the Pump for connection to suction and discharge pipes as most convenient. All bearings provided with glass oil cups. Our illustration shows our standard construction. Prices upon application.


*FIG. 1177. SIZES, CAPACITIES, ETC.*

PISTONS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Single Pulley.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
7 in.	8 in.	7.7 gals.	40 revs.. 308 gals.	7 in.	6 in.	5.6 to 1	18 x 8 in.	Repepr
8 "	10 "	12.7 "	40 " 508 "	8 "	7 "	5 to 1	30 x 7 <sup>1</sup> / <sub>2</sub> "	Weaknit
9 "	12 "	19.4 "	40 " 776 "	8 "	8 "	5.7 to 1	30 x 8 "	Weaknop
11 "	12 "	29.1 "	40 " 1164 "	10 "	10 "	5.3 to 1	30 x 8 <sup>1</sup> / <sub>2</sub> "	Weaknug
12 "	14 "	40.5 "	40 " 1620 "	12 "	10 "	5.6 to 1	30 x 12 "	Weakof

For Power Table, see page 203.

Methods of driving from Electric Motors, etc., pages 200, 201.

## 200 DRIVING CONNECTIONS FOR TRIPLEX POWER PUMPS.



FORM "E" (Cipher, Form E.)

Outline engraving represents one of our Double-Acting Triplex Power Pumps with extended pinion shaft, supported by out-board bearing and carrying driving pulley for belt, where speed connections require larger diameter than can be placed between bearings back of Pump. Always specify dimensions and speed of motor pulley and required number of gallons per minute. Can be applied to any of the following Triplex Power Pumps:

Fig. 1227. Single-Acting Triplex Pump.....page 193


Fig. 920. Single-Acting Triplex Pump..... " 195

Fig. 1095. Double-Acting Triplex Pump.....page 197

Fig. 1177. Double-Acting Triplex Pump ..... " 199

Prices upon application.

In telegraphing, place cipher, representing desired Form, immediately after cipher standing for type and size Pump selected.



FORM "I" (Cipher, Form I.)

Outline engraving shows one of our Double-Acting Triplex Power Pumps, with auxiliary shaft, gearing and coupling for connection to electric or other high-speed motor. Always specify speed of motor shaft and required number of gallons per minute. Can be applied to any of the following Triplex Power Pumps:

Fig. 1227, Single-Acting Triplex Pump .....	page 193
Fig. 920, Single-Acting Triplex Pump.....	page 195
Fig. 1095, Double-Acting Triplex Pump .....	page 197
Fig. 1177, Double-Acting Triplex Pump .....	page 199

Prices upon application. In telegraphing, place cipher, representing desired Form, immediately after cipher standing for type and size Pump selected.



# 202 STRAINERS, FOOT VALVES, CHECK VALVES, FITTINGS.

Fig. 964, Suction Pipe Strainer, protects the Pump from foreign matter which might enter valves. It is made with a wire basket, which is easily removed for cleaning.




FIG. 964

FIG. 964. SIZES, PRICES, ETC.

Size, inches	$\frac{3}{4}$	*1	* $1\frac{1}{4}$	* $1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Price.	\$2.25	2.50	3.00	4.00	6.00	8.00	12.00

\* Screwed ends.

FIG. 36. WROUGHT-IRON STRAINER.





FIG. 36

Dia. Suction Pipe...	3	4	5	6	7	8	9	10	12
Flange Joint.....	\$4.25	6.65	8.00	9.75	11.45	14.90	20.60	23.00	28.60

## PRESSURE AND VACUUM CHAMBERS.

A—Diameter Flange, in.....	7	7	9	9	11 $\frac{1}{2}$
K—Diameter Chamber, in.....	10	10 $\frac{1}{2}$	13 $\frac{1}{2}$	14 $\frac{3}{4}$	17 $\frac{1}{2}$
H—Height, in.....	32	35	35	48 $\frac{1}{2}$	47 $\frac{1}{2}$
Price.....	\$7.50	9.00	16.00	30.00	40.00



## VERTICAL CHECK VALVES.


Iron body with bronze mountings. Gates rubber faced. Tested at 300 pounds water pressure per square inch. Test guaranteed.

Size, inches.....	2	$2\frac{1}{2}$	3	4	5	6	7	8	10	12
Screwed Ends.....	\$7.50	8.00	12.70	16.50	22.50	29.00	32.50	37.00	92.50	123.00
Flanged Ends.....	\$8.00	8.50	12.70	16.50	22.00	28.00	31.50	36.50	92.50	123.00
Hub or Bell Ends	\$8.00	8.50	12.70	16.50	22.00	30.00	35.00	39.00	94.50	125.00

## VERTICAL FOOT VALVES.


Iron body with bronze mountings. Gates rubber faced. Copper screen. Tested at 200 pounds water pressure per square inch. Test guaranteed.

Sizes, inches...	2	$2\frac{1}{2}$	3	4	5	6	7	8	10	12
Screwed Ends ...	\$11.50	12.00	16.25	20.00	26.25	33.00	38.50	44.75	82.00	113.00
Flanged Ends.....	\$11.75	12.25	16.25	20.00	25.75	32.50	38.00	43.50	82.00	112.00
Hub or Bell Ends	.....	.....	.....	.....	.....	33.25	39.00	46.50	83.00	113.00
If without Screen deduct from list	.....	.....	.....	4.50	5.25	6.25	7.00	8.00	7.00	10.00



VERTICAL  
CHECK VALVES

8-inch and under have single valve.  
Larger sizes have nest of valves.



VERTICAL  
FOOT VALVES

8-inch and under have single valve  
and copper basket screen.  
Larger sizes have nest of valves and  
copper plate screen.

For other fittings, supplies, etc., see pages  
72—Foot Valves, Suction Pipe Strainers, etc.  
293—Pulleys, Cut-off Couplings, etc.  
299—Wrought-Iron Pipe and Fittings.  
295—Spiral Riveted Pipe and Fittings.  
294—Cast-iron Pipe and Fittings.  
296, 297—Water Relief Valves, Gauges, Rev. Counters, etc.  
298—Gate Valves, Check Valves, etc.

# TABLE OF POWER REQUIRED TO OPERATE GOULDS 203 TRIPLEX POWER PUMPS.

The estimates given in the table are made with a liberal allowance of power. The power for other capacities and heights is, approximately, in proportion to that tabulated. Closer estimates will be given upon application. By "head" is meant the vertical distance from surface of water supply to point of delivery. One foot head is equivalent to .43 pounds pressure. The head is increased by the friction of the water in the pipes and elbows.



## GENERAL SERVICE PUMPS.

## HIGH SERVICE PRESSURE PUMPS.

Diameter and Stroke of Pump.		Capacity at 40 Revs. per Min. of Crank Shaft.	100 Feet Head or 43 Pounds Pressure.	200 Feet Head or 87 Pounds Pressure.	300 Feet Head or 130 Pounds Pressure.	Diameter and Stroke of Pump.		Capacity at 40 Revs. per Min. of Crank Shaft.	400 Feet Head or 173 Pounds Pressure.	600 Feet Head or 260 Pounds Pressure.	900 Feet Head or 300 Pounds Pressure.
Single Acting	1 1/4 x 2 in.	1 gals.	.24 H. P.	.32 H. P.	.40 H. P.	Single Acting	5 x 6 in.	61 gals.	8.1 H. P.		
	1 3/4 x 2 1/2 "	3 "	.35 "	.50 "	.65 "		4 1/2 x 8 "	66 "	10.1 "	13.7 H. P.	18.5 H. P.
	2 x 3 "	5 "	.50 "	.80 "	1. "		5 1/2 x 8 "	98 "	15. "	20.4 "	27.6 "
	2 1/2 x 4 "	10 "	.85 "	1.25 "	1.7 "		6 x 8 "	116 "	16.6 "	23.2 "	
	3 x 4 "	14 "	.90 "	1.6 "	2.25 "		6 1/2 x 8 "	136 "	19.4 "	27.2 "	
	3 1/2 x 4 "	20 "	1.11 "	1.81 "	2.5 "		7 x 8 "	160 "	21.3 "		
	4 x 4 "	26 "	1.25 "	2. "	3. "		5 x 12 "	122 "	20.3 "	28.1 "	38.1 "
	4 x 6 "	40 "	2. "	3. "	4.5 "		5 1/2 x 12 "	148 "	22.8 "	32.6 "	46.2 "
	5 x 6 "	60 "	3. "	4.5 "	6. "		6 x 12 "	176 "	25.8 "	36.6 "	52.8 "
	5 x 8 "	80 "	4. "	5.5 "	8.25 "	Double Acting	7 x 12 "	240 "	33.3 "	48. "	
	6 x 8 "	117 "	4.8 "	7.8 "	11.7 "		8 x 12 "	312 "	43.3 "	58.5 "	
	6 1/2 x 8 "	136 "	5.5 "	9. "	13.5 "		9 x 12 "	396 "	52.8 "		
	7 x 8 "	160 "	6.1 "	10.7 "	16. "		5 1/4 x 16 "	360 "	55.3 "	77.1 "	110.9 "
	7 x 10 "	200 "	7.5 "	13. "	20. "		5 3/4 x 16 "	432 "	66.4 "	92.5 "	130. "
	8 x 8 "	208 "	8. "	13.5 "	21. "		6 1/2 x 16 "	552 "	78.8 "	113.4 "	155.2 "
	8 x 10 "	260 "	10.5 "	18.25 "	26. "		7 1/2 x 16 "	720 "	100. "	144. "	
	8 x 12 "	312 "	12.0 "	22. "	30. "		8 1/2 x 16 "	940 "	125.3 "		
	9 x 10 "	328 "	12.5 "	23. "	31.5 "						
	8 1/2 x 12 "	352 "	14.5 "	23.5 "	33. "						
	10 x 12 "	488 "	19. "	33. "	46. "						
	11 x 12 "	592 "	23. "	40.5 "	56. "						
	12 x 12 "	704 "	28. "	47.5 "	68. "						
Double Acting	5 x 8 "	156 "	6.5 "	10.4 "	14.6 "						
	6 x 8 "	224 "	9. "	15. "	21. "						
	7 x 8 "	308 "	11.8 "	20.5 "	28.8 "						
	7 x 10 "	392 "	15. "	26.1 "	36.7 "						
	8 x 10 "	508 "	19.5 "	34.1 "	47.6 "						
	8 x 12 "	612 "	24. "	41.6 "	58.5 "						
	9 x 12 "	776 "	29.8 "	51.7 "	72.7 "						
	10 x 12 "	952 "	36.6 "	63.4 "	89.2 "						
	11 x 12 "	1164 "	44.7 "	77.6 "	109.1 "						
	11 x 14 "	1344 "	51.7 "	89.6 "	126. "						
	12 x 14 "	1610 "	61.8 "	107.2 "	150.7 "						



## TRIPLEX ELECTRIC POWER PUMPS.



Triplex Electric Power Pumps are largely used in dwellings, hotels, etc., to afford an independent supply of soft water; also for operating hydraulic elevators, etc. They are free from odor, dust or ashes; give out no heat and afford no chance of explosion. Automatic controls provided for special service. The larger forms of these Pumps offer many advantages for service in mills, factories, for water works, etc. The subject is one of detail and will be treated upon application.

See pages 205 to 213.



# GOULDS TRIPLEX ELECTRIC PUMP, BELT CONNECTED. 204-A

FOR ELEVATIONS TO 350 FEET, EQUIVALENT TO 150 POUNDS PRESSURE.

Fig. 932 represents our Triplex Electric Pump, especially adapted for general water supply in hotels, residences, etc. It is well-built, carefully finished and of high-grade throughout.

It is largely used also in connection with hydraulic elevators, and when so ordered, can be fitted with automatic controlling device adapted to the service for which the pump is to be employed

Driving pulley on Pump will be furnished of required size at extra charge. Electric motor of approved type and size will be furnished at favorable prices.

The Pump is identical in design and construction with Fig. 1009. (See page 183, also Form B, page 188.) Regular construction in sizes  $1\frac{1}{4}$  x 2 inches to 2 x 3 inches inclusive, iron cylinders, bronze plungers and glands: larger sizes, iron cylinders, plungers and glands, and raw-hide pinions, but the price does not include pulley, because the wide variation in the speed of Motors prevents our establishing a standard of sizes.

Prices upon application.




FIG. 932, 7" x 8"

FIG. 932. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Rev. of Crank Shaft.	Usual Speed and Capacity per Minute.		SIZES OF PIPE.		Geared.	Cipher.
Diameter.	Stroke.				Suction.	Discharge.		
$1\frac{1}{4}$ in.	2 in.	0.03 gal.	60 revs.,	1.8 gals.	$\frac{3}{4}$ in.	$\frac{3}{4}$ in.	5 to 1	Althorn
$1\frac{3}{4}$ "	$2\frac{1}{2}$ "	0.07 "	60 "	4.2 "	1 "	1 "	5 to 1	Although
$2\frac{1}{4}$ "	3 "	0.12 "	50 "	6 "	$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	5 to 1	Altimeter
$2\frac{1}{2}$ "	4 "	0.25 "	50 "	12 "	$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	5 to 1	Altincar
$3\frac{1}{2}$ "	4 "	0.5 "	50 "	25 "	2 "	2 "	5 to 1	Abaction
4 "	6 "	1.0 "	45 "	45 "	2 "	2 "	5 to 1	Alto
5 "	6 "	1.5 "	45 "	67 "	3 "	3 "	5 to 1	Altogeth
5 "	8 "	2.0 "	45 "	90 "	3 "	3 "	5 to 1	Altomet
6 "	8 "	2.9 "	45 "	130 "	4 "	4 "	5 to 1	Binocular
7 "	8 "	4.0 "	45 "	180 "	4 "	4 "	5 to 1	Binominal
8 "	10 "	6.5 "	40 "	260 "	5 "	5 "	5 to 1	Biographer

For Power Table, see page 203.

## GOULDS CENTRIFUGAL ELECTRIC PUMP.

Our Fig. 1258, Horizontal Centrifugal Pump, has suction inlet on each side of the pump case so that an equal amount of water enters on each side of the piston, thus perfectly balancing the same and preventing all end thrust of shaft. Pump is made very strong and heavy, and especially designed for use where the lift is high or suction pipe long, and is capable of passing muddy or gritty water without injury to its parts. Pump shell can be swiveled on to hooded frame, so as to bring the suction and discharge in position suitable

for the work. Shaft bearings each side of pump case are so arranged that they can be removed without disturbing the Pump or pipe connections. Built with electric motor, direct connected, takes up very little space, and is always ready to start. If the motor speed is higher than the Pump speed, the proper speed can be obtained by the use of gearing and still the Pump and motor can be on the same base, making a perfectly self-contained outfit. We give range of sizes, capacity, etc., below. Prices upon application.




FIG. 1258

FIG. 1258. SIZES, CAPACITIES, ETC.

Pump No., Diameter Discharge Opening.	Diameter Suction Opening.	Economical Capacity, per Minute.	Cipher.
1 $\frac{1}{2}$ inch	2 inch	70 gal.	Sceneno
1 $\frac{3}{4}$ "	2 "	90 "	Sceneop
2 "	2 $\frac{1}{2}$ "	120 "	Scenept
2 $\frac{1}{2}$ "	3 "	185 "	Scenequt
3 "	4 "	260 "	Scenero
4 "	5 "	470 "	Scorop
5 "	6 "	735 "	Scoroqa
6 "	7 "	1,050 "	Scororo
8 "	9 "	2,000 "	Scorpa
10 "	11 "	3,000 "	Scorpeg
12 "	13 "	4,200 "	Scorpiil

# GOULDS TRIPLEX ELECTRIC HOUSE PUMP.

205

WITH BELT CONNECTION BETWEEN PUMP AND MOTOR

Fig. 1220 represents our Complete Triplex Electric House Pump, including both Pump and Motor, mounted on iron bed plate and connected by belt running over idler. It runs smoothly and noiselessly, is of neat, compact design, simple and easy to take care of, and, where electric current is available, completely solves the problem of water supply.

Largely used in New York City when pressure of city water is insufficient to reach upper floors. Rendered entirely automatic by use of switch, which cuts out or throws in the electric current as water in tank rises or falls. Either an open tank in upper part of the building or a compression tank in the basement can be used. Our prices are for complete outfit, as shown in cut, motor included.

We will furnish without motor, also without bed plate, if so desired.

Automatic switches furnished at moderate prices.

Prices upon application.





FIG. 1220. SIZE 2" X 3"

FIG 1220. SIZES, CAPACITIES, ETC.


PLUNGER.		Capacity per Hour.	SIZES OF PIPE.		FOR ELEVATIONS UP TO 100 FEET.		FOR ELEVATIONS FROM 100 TO 200 FEET.	
Diameter.	Stroke.		Suction.	Discharge	Size of Motor.	Cipher.	Size of Motor.	Cipher.
1 3/4 in.	2 1/2 in.	200 gals.	1 in.	1 in.	1/2 H. P.	Panger	1/2 H. P.	Painheg
2 "	3 "	350 "	1 1/4 "	1 1/4 "	1 1/2 "	Paingib	1 "	Painhit
2 1/2 "	4 "	600 "	1 1/2 "	1 1/2 "	1 "	Paingor	1 "	Painita
3 1/2 "	4 "	1200 "	2 "	2 "	1 "	Paingul	2 "	Painivo



# AUTOMATIC SWITCHES FOR ELECTRIC PUMPING.



TYPE "A"



TYPE "D"

Type "A," illustrated, single pole, maximum volts, 300; maximum amperes, 20; low tension, direct current, automatic switch, adapted for starting series wound motors of one horse-power or less.

Type "B," not illustrated, same as Type "A," only double pole. Can also be used with small, alternating, polyphase motors of not over five horse-power and not over 300 volts.

Type "C," not illustrated, double pole, maximum volts, 600; maximum amperes, 15. Can be used for small, series, direct current motors of 600 volts or less, and of not over one horse-power. Can also be used with polyphase, alternating current motors of not over five horse-power and not over 600 volts.

Type "D," illustrated, automatic, double pole, automatic motor starter, with magnetic release, designed for direct current, shunt, series or compound wound motors of one-half to 25 horse-power.

Alternating current, polyphase motors of over five horse-power require starters of special designs, which vary according to conditions.

In writing always give size of motor and whether shunt, series or compound. For series or compound wound motors state resistance of series coil.

Prices on automatic switches and motor starters upon application.

Floats, chain, pulleys, etc., are not included and only furnished when ordered and at extra price.

# GOULDS AUTOMATIC REGULATOR AND BY-PASS.

207

FOR USE WHEN THE PUMP RUNS CONTINUOUSLY




PLATE "F"


Plate "F," shows Automatic Regulator and By-Pass attached to the Pump in the usual manner. The discharge pressure on the Pump is controlled by the pressure in the compression tank. The regulator is adjusted to open the By-Pass Valve, whenever the limit pressure is reached, and the By-Pass is kept open, until the pressure begins to drop, as the elevator is started. The By-Pass then closes and the Pump discharges into the tank, until the limit pressure is again reached.

Prices will be quoted for the parts shown in full-line engraving.

## GOULDS AUTOMATIC REGULATOR AND BY-PASS FOR ELEVATOR PUMPS.

To be used with Single-Acting Pumps.	Valves and Connections.	Cipher.	To be used with Double-Acting Pumps.	Valves and Connections	Cipher.
5 x 6 and 5 x 8	1½ in.	Goldjag	7 x 8 and 7 x 10	3 in.	Goldkof
6 x 8 and 6½ x 8	2 "	Goldjom	8 x 10, 8 x 12, 9 x 12 and 10 x 12	4 "	Goldkur
7 x 8, 8 x 8 and 8 x 10	2½ "	Goldjust	11 x 14 and 12 x 14	5 "	Goldkys
9 x 10 and 8½ x 12	3 "	Goldkam			
10 x 12, 11 x 12 and 12 x 12	4 "	Goldkil			

## GOULDS HORIZONTAL TRIPLEX MINE PUMP.

*FOR HEAVY PRESSURE.**FIG. 1218. SIZE 7" X 8"*



## FOR HEAVY PRESSURE.

Fig. 1218, Horizontal Single-Acting Triplex Mine Pump, is especially adapted for mine work, there being no piece in the Pump but that can be lowered into a mine shaft  $3\frac{1}{2}$  feet x 6 feet.

It has single-acting plungers, outside guided and outside packed. The crank shaft is of steel, the gear is made in halves and has machine cut teeth. Power is transmitted directly from pinion on the motor shaft to the gear on the crank shaft, consequently speed of motor must not exceed 400 revolutions per minute. Bed plate is extended for motor.

Suction and discharge headers are arranged to allow piping from either side. The valves are conveniently located in separate chambers and are easily accessible. A spring alleviator is used, instead of the usual form of air chamber.

The regular construction is with iron plungers, cylinders and glands. These parts can be furnished: plungers of bronze, glands and cylinders bronze lined, at extra price, when so ordered.

Prices upon application.

FIG. 1218. SIZES, CAPACITIES, ETC.

PLUNGERS.		SIZES OF PIPE.						
Diameter.	Stroke.	Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	For Elevations to	Suction.		Gearing.	Cipher.
						Discharge.		
5½ in.	8 in.	2.46 gals.	50 revs., 123 gals.	880 ft.	5 in.	4 in.	8 to 1	Roatimo
6 "	8 "	2.9 "	50 " 145 "	750 "	5 "	4 "	8 to 1	Roatinu
6½ "	8 "	3.4 "	50 " 170 "	640 "	6 "	5 "	8 to 1	Roatlob
7 "	8 "	4. "	50 " 200 "	550 "	6 "	5 "	8 to 1	Roatus

For Power Tables see page 203.

210 HORIZONTAL DOUBLE-ACTING TRIPLEX MINE PUMP.

*FOR HEAVY PRESSURE.*




FIG. 1221. SIZE 5 $\frac{3}{4}$ " X 16"

# GOULDS HORIZONTAL DOUBLE-ACTING MINE PUMP. 211

## FOR HEAVY PRESSURE.

Fig. 1221, Horizontal Double-Acting Triplex Power Pump, illustrated on opposite page, has capacity ranging from 940 to 360 gallons per minute against elevations from 500 to 1400 feet, equivalent to from 216 to 600 pounds pressure. Power for driving may be applied at either side. For electric or other high-speed motor power, intermediate gearing and auxiliary shaft are used and can be supplied at extra price.

It is double-acting, each plunger being outside-packed and the two plungers for each cylinder connected by outside rods. Crank shaft is of steel and driven by double gears and pinions with machine-cut teeth. All bearings are large and adjustable for wear.

Suction and discharge valves are located in separate chambers or boxes and can be readily examined. The suction and discharge pipes can be connected at either side of the Pump. A spring alleviator is provided for equalizing the flow and taking any shock which may occur.

For Mine Pump or other service, where economy in installation and maintenance is desired, this Pump is especially recommended.

The regular construction is with iron plungers, cylinders and glands, but these parts can be furnished; plungers of bronze, glands and cylinders bronze-lined, at extra price, when so ordered.

Prices upon application.

FIG. 1221. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	For Elevations to	SIZES OF PIPE.		Geared.	Cipher.
Diameter.	Stroke.				Suction.	Discharge.		
5¼ in.	16 in.	9. gals.	40 revs., 360 gals.	1400 ft.	7 in.	6 in.	6 to 1	Roative
5¾ " "	16 " "	10.8 " "	40 " 432 "	1150 "	8 " "	7 " "	6 to 1	Rusebb
6½ " "	16 " "	13.8 " "	40 " 552 "	900 "	8 " "	7 " "	6 to 1	Ruseck
7½ " "	16 " "	18. " "	40 " 720 "	700 "	10 " "	8 " "	6 to 1	Rusedr
8½ " "	16 " "	23.5 " "	40 " 940 "	500 "	12 " "	10 " "	6 to 1	Rusedsa

For Power Table, see page 203.



# 212 GOULDS HORIZONTAL TRIPLEX ELECTRIC MINE PUMP.

FOR ELEVATIONS TO 300 FEET, EQUIVALENT TO 130 POUNDS PRESSURE.




FIG. 966. SIZE 6½" X 8"

Fig. 966 is the original and approved Horizontal, Electric Mine Pump. Our experience in mine Pumping has enabled us to embody all the essentials in this Pump which insure convenience, reliability and compactness.

It is mounted on an iron truck, which cannot be affected by moisture and which always maintains the accurate alignment of the Pump and Motor; insuring easy running and exceptional durability.

A distinctive feature of our Mine Pumps appears from the fact that they do not require an attendant, because they cannot "run away" when the water is pumped out. Occasional oiling is all that is necessary.

The materials, construction and workmanship are of the best, the gearing is machine-cut, the bearings are

of bronze or babbitt and adjustable or easily renewed, the valves are quickly accessible.

Our regular construction is: Phosphor bronze plungers, lined cylinders and glands; but can supply, when so ordered, with iron working parts at some saving in cost. Price includes the Pump complete, the iron truck with wheels, the gearing necessary to connect the Motor, but it does not include the Motor. We are prepared to furnish Motors of any make and type at current prices.

Correspondents should advise us of the width of the track, height of roof, also furnish working drawing of Motor and advise speed and gallons to be pumped per minute.

Prices upon application.

FIG. 966. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Crank and Pinion Shafts Geared.	Cipher. Bronze Fitted.	Cipher, Iron.
Diameter.	Stroke.			Suction.	Discharge.			
5 in.	8 in.	2.0 gals.	40 revs., 80 gals.	3 in.	3 in.	5 to 1	Briefer	Blunder
6½ "	8 "	3 4 "	40 " 136 "	4 "	4 "	5 to 1	Baldeft	Blunderbus
8 "	8 "	5.2 "	40 " 208 "	5 "	4 "	5 to 1	Brimful	Blundering

For Power Table, see page 203.

*FOR ELEVATIONS TO 300 FEET, EQUIVALENT TO 130 POUNDS PRESSURE.*


Fig. 1237, Electric Mine Sinking Pump, is compact in form and not liable to damage from moisture or hard usage. A special type of water-proof motor is used, which is enclosed in tight casing and will work as well under water as out and cannot be "drowned" by a sudden inrush of water in the mine. The Pump is of the duplex double-acting type, with outside packed plungers. Although the working parts are almost entirely concealed, they are readily accessible for examination or repairs.

The sizes, given in the following table, may be modified as desired for special capacities or greater lifts.

Prices on Pumps and Motors upon application.


*FIG. 1237. SIZES, CAPACITIES, ETC.*

PLUNGERS.		Capacity One Rev. of Crank Shaft.	Capacity per Minute at Ordinary Speed.	SIZES OF PIPE.		Size Motor Re- quired.	Dimensions Over All.	Cipher.
Dia.	Stroke			Suc.	Dis.			
4½ in.	6 in.	1.6 gals.	96 gals.	4 in.	3 in.	15 H. P.	30 x 40 x 108 ins.	Ruseegs
6 "	6 "	2.9 "	174 "	5 "	4 "	25 "	34 x 45 x 114 "	Ruseehi



*FIG. 1237. SIZE 4½" X 6"*






Engraving shows Hydraulic Grinders in Pulp Mill.

Goulds Triplex Pumps are used for maintaining pressure on these grinders; see following pages.





Engraving shows the widest Fourdrinier in the World—162 inches. The stuff for this machine is pumped by a Goulds Triplex Stuff Pump, size 10" x 10".

See following pages.

# GOULDS TRIPLEX POWER SUCTION PUMP.

FOR PAPER MACHINE SUCTION BOXES.




FIG. 947. SIZE 7" X 8"

Fig. 947, Triplex Suction Pump, is of the vertical type and has three single-acting bronze plungers, operated by three-throw crank shaft. The cylinders and glands are bronze-lined. Water seal around the plungers, which admits of loosely adjusted packing, and insures great durability and easy running. Large valve area; all valves quickly accessible. Crank shaft complete in one piece and runs in babbitted bearings. The connecting rods have bronze bushed bearings in plungers and strap head crank bearings with phosphor-bronze boxes. Sight-feed oilers. Suction connection at either end of the Pump; discharge on the other side. Pump may be placed in any position relative to the paper machine.

When inquiring about Suction Pumps please state width of paper machine, number of suction boxes, range of speeds, kind of stock used, weight of paper made, general working conditions.

Prices upon application.

FIG. 947. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Speed of Crank Shaft per Minute.	Suction.	Discharge.	Pulley.	Cipher.
Diameter.	Stroke.						
7 in.	8 in.	4 gals.	40 to 60 revs.	4 in. pipe	4 in. pipe	36 x 6 in.	Wraith
8 "	10 "	6.5 "	40 to 60 "	6 "	5 "	48 x 8 "	Repelled
8 "	12 "	7.8 "	40 to 60 "	6 "	5 "	48 x 8 "	Repelling



FOR PAPER MACHINE SUCTION BOXES.




FIG. 956. SIZE 7" X 8"

Fig. 956, Triplex Suction Pump, is of the vertical type, and has three single-acting bronze plungers, operated by three-throw crank shaft. The cylinders and glands are bronze-lined. Water seal around the plungers, which admits of loosely adjusted packing, and insures great durability and easy running. Large valve area; all valves quickly accessible. Crank shaft complete in one piece and runs in babbitted bearings. Machine-cut gearing. The connecting rods have bronze bushed bearings in plungers and strap head crank bearings with phosphor-bronze boxes. Sight-feed oilers. Suction connection at either end of the Pump; discharge on the other side. Pump may be placed in any position relative to the paper machine.

When inquiring about Suction Pumps please state—

Width of paper machine, number of suction boxes.

Range of speeds.

Kind of stock used, weights of paper made.

General Working Conditions.


Prices upon application.

FIG. 956. SIZES, CAPACITIES, ETC.

PLUNGERS.				SIZES OF PIPE.				
Diameter.	Stroke.	Capacity One Rev. of Crank Shaft.	Usual Speed per Minute.	Suction.	Discharge.	Geared.	Pulley.	Cipher.
7 in.	8 in.	4. gals.	50 revs.	4 in.	4 in.	4 to 1	30 x 5 in.	Wrangle
8 "	10 "	6.5 "	50 "	6 "	5 "	5 to 1	36 x 6 "	Wrap
8 "	12 "	7.8 "	50 "	6 "	5 "	5 to 1	36 x 6 "	Wrapper



## GOULDS HORIZONTAL VACUUM PUMP.

*FIG. 1022. SIZE 14" X 10"*

# GOULDS HORIZONTAL VACUUM PUMP.

219

Fig. 1022 is a high grade, efficient and reliable pump for vacuum work. It is horizontal, single-cylinder, with double-acting piston.

The cylinder has a bronze lining, arranged to equalize the wear and to provide true alignment. This can be speedily removed by a millwright, with an ordinary wrench. The piston is of bronze, fitted with fibrous packing. The piston rod is of Tobin bronze and with bronze stuffing boxes. Large valve area. Valves quickly accessible. Crossheads and guides have adjustment for taking up wear. Connecting rod is in one piece, with strap ends and with phosphor bronze boxes. Crank shaft of steel. Discharge connections at rear side of cylinder. Suction at both front and top. Sight feed oilers

It is used with surface condensers in connection with steam engines, with evaporators and for other service where high vacuum is to be maintained. Please state the quantity of water condensed per minute or hour, or the speed of engines, size of cylinders and terminal pressure.

This Pump is also used in many of the newest paper mills, in connection with suction boxes with high-speed paper machines on news, and performs this exacting and important service (the essential of fast running) in a reliable and satisfactory manner. It is used with these machines, running manila, book, fine writings, etc. Please state width of paper machines, number of suction boxes on the wire and on the felt, and whether one Pump is intended for the wire or felt boxes, or for both.

Prices upon application.

FIG. 1022. SIZES, CAPACITIES, ETC.

PISTON.		Displacement One Revolution of Crank Shaft.	Speed of Crank Shaft per Minute.	SIZES OF PIPE.		Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.		
8 in.	10 in.	4.3 gals.	40 to 60 revs.	4 in.	4 in.	48 x 4 in.	Acnodal
10 "	10 "	6.8 "	40 to 60 "	4 "	4 "	48 x 5 "	Acnode
12 "	10 "	9.6 "	30 to 50 "	5 "	5 "	48 x 6½ "	Abactor
14 "	10 "	13.2 "	30 to 50 "	6 "	6 "	48 x 8½ "	Abacus
14 "	14 "	18.6 "	30 to 40 "	6 "	6 "	48 x 10½ "	Bunol
16 "	16 "	27.8 "	25 to 35 "	8 "	8 "	60 x 10½ "	Buntel

## GOULDS HORIZONTAL VACUUM PUMP.


*FIG 1049 SIZE 16" X 16"*



Fig. 1049, Geared Horizontal Vacuum Pump, has cylinder with bronze lining, arranged to equalize the wear and provide true alignment. This can be speedily removed by a millwright with an ordinary wrench. The piston is of bronze, fitted with fibrous packing. The piston rod is of Tobin bronze. Bronze stuffing boxes. Large valve area. Valves quickly accessible. Machine cut gears. Crosshead and guides have adjustment for taking up wear. Connecting rod is in one piece, with strap ends and with phosphor bronze boxes. Crank shaft of steel. Discharge connections are at rear side of cylinder. Suction at both front and top. Sight feed oilers. Pump may be used with surface condensers in connection with steam engines or for other service where high vacuum is to be maintained. State quantity of water condensed per minute or hour. Where used with paper machines, state width of machine, number of suction boxes on the wire and on the felt, whether one Pump is needed for the wire or felt boxes, or for both. We recommend our Fig. 1049, Geared Pump, where operated from fast running driving shafts.

Prices upon application.

FIG. 1049. SIZES, CAPACITIES, ETC.

PISTON.		Displacement One Revolution of Crank Shaft.	Speed of Crank Shaft per Minute.	SIZES OF PIPE.		Geared.	Pulley.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
8 in.	10 in.	4.3 gals.	40 to 60 revs.	4 in.	4 in.	4 to 1	30 x 4 in.	Dreba
12 "	10 "	9.6 "	30 to 50 "	5 "	5 "	4 to 1	30 x 5 "	Drebef
14 "	10 "	13.2 "	30 to 50 "	6 "	6 "	4 to 1	30 x 5 "	Drebegl
14 "	14 "	18.6 "	30 to 40 "	6 "	6 "	4 to 1	36 x 6 "	Curyme
16 "	16 "	27.8 "	25 to 35 "	8 "	8 "	4 to 1	36 x 6 "	Cusab
18 "	18 "	39.5 "	25 to 35 "	10 "	8 "	4 to 1	42 x 8 "	Repeql

## GOULDS VERTICAL TRIPLEX VACUUM PUMP.

(Patented Nov. 8, 1898.)




FIG. 1124. SIZE 14" X 12"

# GOULDS VERTICAL TRIPLEX VACUUM PUMP.

223

(Patented Nov. 8, 1898.)

Fig. 1124 is a Vertical, Triplex, Single-Acting Vacuum Pump, of a design never before presented for this work. It is vastly superior to what is embodied in any other Vertical Pump known to the trade. In building a Pump of such a progressive and distinctive type we are holding to our faith in a class of purchasers who want only the very best and who appreciate good machinery.

For paper mill work the constantly increasing speed of paper machines and the greater widths emphasize the fact that SUCTION is a prime consideration for safe running at fast speeds, involving the use of more suction boxes and pumps of great capacity and suction power. To meet these requirements we have brought out a complete new line of Triplex Vacuum Pumps, of ample capacity for the widest and fastest machines. We invite correspondence, and full information as to design, materials and construction will be furnished and performance of service will be guaranteed.

It is used with surface condensers in connection with steam engines, with evaporators and for other service where high vacuum is to be maintained.

Please state the quantity of water condensed per minute or hour, or speed of engines, size of cylinders, and terminal pressure.

Prices upon application.

FIG. 1124. SIZES, CAPACITIES, ETC.

PISTONS.		Displacement One Revolution of Crank Shaft.	Speed of Crank Shaft per Minute.	SIZES OF PIPE.		Geared.	Pulley.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
14 in.	12 in.	23.9 gals.	30 to 40 revs.	8 in.	6 in.	5.3 to 1	30 x 7 in.	Wrecla
16 "	12 "	31.3 "	30 to 40 "	10 "	8 "	5.3 to 1	30 x 8½ "	Wrecmo
18 "	12 "	39.6 "	30 to 40 "	12 "	10 "	5.3 to 1	30 x 9 "	Wrecny






FIG 1136. SIZE 15" X 12"

# GOULDS DOUBLE-ACTING TRIPLEX VACUUM PUMP. 225

Fig. 1136, Triplex Double-Acting Vacuum Pump, is a new type for use with Surface Condensers, Evaporators, etc., and for Paper Machine Suction Boxes.

It is a strong, substantial, well built Pump. It has machine-cut gearing. The driving pulley is on the pinion shaft, between the pinions, or at either end of Pump, the pinion shaft being extended and provided with an outboard bearing. The bearings are of bronze and are adjustable for taking up wear. The cylinders are bronze lined. Pistons, piston rods and stuffing boxes are all bronze. Suction and discharge pipe connections may be made at either end of the Pump.

In steam power plants, for use in connection with Surface Condensers, we should be advised of the speed, size of cylinders and other data regarding the Engine, and for Condenser work generally the conditions should be carefully stated.

In paper mills, for use in connection with paper machine suction boxes, it is a very effective, reliable Pump. It may be divided between boxes on the wire and the felt, using one cylinder for the felt suction boxes and the remaining two cylinders for the wire, or *vice versa*, according to requirements.

Prices upon application.

FIG. 1136. SIZES, CAPACITIES, ETC.

PISTONS.		Displacement One Revolution of Crank Shaft.	Speed of Crank Shaft per Minute.	SIZES OF PIPE.		Geared.	Pulley.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
12 in.	12 in.	35 gals.	30 to 40 revs.	8 in.	8 in.	5.3 to 1	30 x 8	Zitfa
15 "	12 "	55 "	30 to 40 "	10 "	10 "	5.3 to 1	30 x 8	Zitgel

For Power Table, see page 203.

# GOULDS TRIPLEX POWER STUFF PUMP.

*FOR ELEVATIONS TO 100 FEET, EQUIVALENT TO 43 POUNDS PRESSURE.*




FIG. 1105. SIZE 8" X 10"



# GOULDS TRIPLEX POWER STUFF PUMP. FOR PULP AND PAPER MILLS.

227

*FOR ELEVATIONS TO 100 FEET. EQUIVALENT TO 43 POUNDS PRESSURE.*

Fig. 1105, Triplex Stuff Pump, is a modern design, the result of our own experience and many valuable suggestions by expert paper makers.

It is self-contained, compact, rigid. Valves quickly accessible. Easily kept in perfect working condition. Suction and discharge pipe connections at both ends. The passages through the Pump have the full, rounded, easy curves which prevent lodgment of air or stuff and consequent formation of slugs.

The valves are bronze balls finished true and balanced. Valve seats are bronze and of the "flanged-in" type, removable by unbolting the valve chests. The valve weight and lift, opening through seat, and flow of stuff bear a certain relation to diameter and stroke of plunger, which insures reliable and effective delivery, details of prime importance which are carefully embodied in this Pump.

The mechanical construction and workmanship are of the best. The plungers are bronze. The bearings are of liberal size. The gear and pinion are machine-cut. The driving pulley and gearing are proportioned for a correct, sure drive from the rather fast running shafting now used in modern mills.

Prices upon application.


*FIG. 1105. SIZES, CAPACITIES, ETC.*

PLUNGERS.		Capacity One Rev. of Crank Shaft.	Dry Paper in 24 Hours at Moderate Speeds.	SIZES OF PIPE.		Geared.	Pulley.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
6 in.	10 in.	3.6 gal.	13 to 18 tons.	5 in.	5 in.	4 to 1	20 x 6 in.	Waxkfs
7 "	10 "	5.0 "	18 to 24 "	5 "	5 "	4 to 1	24 x 7 "	Waxkge
8 "	10 "	6.5 "	25 to 32 "	6 "	6 "	4 to 1	24 x 7 "	Waxkho

For Power Table, see page 203.

228 GOULDS TRIPLEX STUFF PUMP. HEAVY PATTERN.

*FOR ELEVATIONS TO 125 FEET, EQUIVALENT TO 54 POUNDS PRESSURE.*



*FIG. 1128. SIZE 9" X 12"*

# GOULDS TRIPLEX STUFF PUMP. HEAVY PATTERN. 229

## FOR PULP AND PAPER MILLS.

*FOR ELEVATIONS TO 125 FEET, EQUIVALENT TO 54 POUNDS PRESSURE.*

The enormous quantity of stuff required by the big, fast paper machines and the transferring of ground wood and sulphite to the machine rooms involve the use of Stuff Pumps of large capacity and constructed in the best possible manner.

Our Fig. 1128, Triplex Stuff Pump, is designed with a thorough knowledge of modern pulp and paper mills. It is a Pump, complete with respect to design, excellence of materials, accuracy of workmanship and ample and properly distributed weight. It is distinctive in possessing the *substance* as well as the form of a high-class Pump, being built with bronze bearings with adjustments, and with other refinements of mechanical details not yet embodied in other Pumps offered for this work. The suction enters horizontally at the center of side opposite the vertical discharge shown in engraving.

It is intended to be as near absolute perfection and reliability as superior knowledge and skill can make it, and thus eliminate the vexatious and expensive delays incidental to the use of inferior Pumps.

We solicit correspondence regarding Pumps of this type, and shall be pleased to supply detailed specifications and other information in response to inquiries.

Prices upon application.

*FIG. 1128. SIZES, CAPACITIES, ETC.*

PLUNGERS.		Capacity one Revolution of Crank Shaft.	Dry Paper in 24 Hours, Moderate Speeds.	SIZES OF PIPE.		Geared.	Pulley.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
8 in.	10 in.	6.5 gals.	25 to 33 tons.	7 in.	7 in.	5 to 1	30 x 6½ in.	Wraixm
8 "	12 "	7.8 "	30 to 40 "	7 "	7 "	5 to 1	30 x 6½ "	Wrathijos
9 "	12 "	9.9 "	38 to 50 "	8 "	8 "	5.3 to 1	30 x 8½ "	Wrathop
10 "	12 "	12.2 "	50 to 60 "	10 "	10 "	5.3 to 1	30 x 10 "	Wrathus
12 "	12 "	17.6 "	60 to 80 "	10 "	10 "	5.3 to 1	30 x 10 "	Wrecoen

For Power Table, see page 203.



# GOULDS TRIPLEX POWER STUFF PUMP.

FOR PAPER AND PULP MILLS.




FIG. 959. SIZE 7" X 8"

Fig. 969, Triplex Power Stuff Pump, is self-contained and needs but a firm floor for a foundation. The valves are bronze balls with lift and weight as required, and with bronze seats. All quickly accessible.

The cylinders and glands are of great length and bronze-lined. The plungers are of phosphor bronze and have water seal, which aids the packings and insures easy running. All passages are shaped to scour clear, avoiding the formation of "slugs." Each connecting rod has bronze bushed bearing in plunger, and strap head crank bearing at crank with phosphor-bronze box. The crank shaft is in one piece and runs in large babbitt-lined bearings. Sight-feed oilers are provided. The gear and pinion are machine cut.

The pipe flanges are regularly threaded for standard wrought-iron pipe; prepared for copper pipe connections to order. The working strength is ample for all ordinary stuff pumping. Pumps for extra heavy work to order. Pumps without gears can be furnished, but geared pumps drive better and are easier on belts. When inquiring about Stuff Pumps, please state what the service will be.

Prices upon application.

FIG. 969. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	†Speed per Minute and Capacity in 24 Hours, Varying With Kind of Paper.		Suction.	Discharge.	Geared.	Pulley.	Cipher.
Diameter.	Stroke.								
4 in.	4 in.	.65 gal.	25 to 40 revs.,	1.7 to 3 tons	3 in. pipe	3 in. pipe	5 to 1	20 x 3 in.	Clubbed
4 "	6 "	1. "	25 to 40 "	3 to 5 "	3 "	3 "	5 to 1	20 x 3 "	Wrasse
5 "	8 "	2. "	20 to 36 "	5 to 9 "	4 "	4 "	4 to 1	20 x 4 "	Wrathy
7 "	8 "	4. "	20 to 36 "	10 to 18 "	5 "	5 "	4 to 1	30 x 5 "	Wraw
8 "	10 "	6.5 "	20 to 30 "	16 to 24 "	6 "	6 "	5 to 1	36 x 6 "	Rifely

† This means the actual finished product of the Paper Machine. At stated speeds the Pump delivers sufficient stuff to make these amounts besides ample return.

For Power Table, see page 203.

# GOULDS TRIPLEX POWER PUMP, FOR SEMI-FLUIDS.

231

FOR ELEVATIONS TO 100 FEET, EQUIVALENT  
TO 43 POUNDS PRESSURE.

Fig. 1017, Triplex Power Pump, is designed to pump sewage, tan liquor, oils, chemicals, heavy solutions, mud, tar, soap, etc.

It is regularly fitted with iron plungers, cylinders and glands, ball valves, tight and loose pulleys. This construction will be modified, to order, and the Pump will be fitted with bronze plungers, bronze-lined cylinders and glands, etc., at extra price.

It has a wide variety of applications, and we earnestly desire correspondents to state carefully the conditions under which the Pump is to operate, and what is required of it.

Prices upon application.




FIG. 1017 SIZE 7" x 8"

FIG. 1017. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
4 in.	4 in.	0.65 gals.	45 revs., 29 gals.	3 in.	3 in.	5 to 1	20 x 3 in.	Surgent
4 "	6 "	1. "	45 " 44 "	3 "	3 "	5 to 1	20 x 3 "	Surgeon
5 "	6 "	1.5 "	40 " 60 "	4 "	4 "	4 to 1	20 x 4 "	Swack
5 "	8 "	2. "	40 " 80 "	4 "	4 "	4 to 1	20 x 4 "	Swiss
7 "	8 "	4. "	40 " 160 "	5 "	5 "	4 to 1	30 x 5 "	Switch
8 "	10 "	6.5 "	40 " 260 "	6 "	6 "	5 to 1	36 x 6 "	Tilting
8 "	12 "	7.8 "	40 " 312 "	6 "	6 "	5 to 1	36 x 6 "	Tinted

For Power Table, see page 203.

# GOULDS TRIPLEX POWER AMMONIA PUMP.

(Patents Applied For.)




Fig. 1195, Triplex Power Ammonia Pump, is constructed for pumping aqua ammonia in connection with refrigerating machinery, for cold storage, ice-making plants, etc.

Practical experience in using Aqua Ammonia Pumps has led us to radical changes in design and construction. This new type fully eliminates even the possibility of leakage and embodies other improvements of equally great merit.

It is a Triplex Pump, running steadily, receiving and delivering aqua ammonia regularly, and does this work uniformly at all times, without being watched and adjusted, and thereby increases the refrigerating capacity of the plants. The joints and connections of the many coils and piping are thus spared the shock and vexatious leakages incidental to the use of other types of ammonia pumps.

It is substantial, well-built and occupies but small floor space. The connecting rods have strap heads and phosphor bronze boxes. The crank shaft is steel and runs in bronze bearings. These Pumps are built of material wholly unaffected by ammoniacal liquid and are proportioned to sustain the exacting and continuous service of refrigerating plants. The limit pressure is 250 pounds.

Prices upon application.

FIG. 1195. SIZE 3½" X 8"

FIG. 1195. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
1⅞ in.	6 in.	49.6 cu. in., .21 gals.	35 revs., 7.35 gals.	1¼ in.	1 in.	5 to 1	20 x 3 in.	Zynfo
2½ " "	6 " "	88 " .31 " "	35 " 10.85 " "	1½ " "	1¼ " "	5 to 1	24 x 3 " "	Zvngt
3½ " "	8 " "	231 " 1.0 " "	35 " 35. " "	2 " "	2 " "	5 to 1	30 x 4 " "	Zynho
5 " "	8 " "	470 " 2.04 " "	35 " 71.4 " "	3 " "	3 " "	5 to 1	30 x 6 " "	Zymtvf

For Power Table, see page 203.



# GOULDS TRIPLEX POWER BRINE PUMP.

233

*FOR ELEVATIONS TO 100 FEET, EQUIVALENT  
TO 43 POUNDS PRESSURE.*

Fig. 1059, Triplex Power Pump, is designed to circulate Brine in refrigerating and cold-storage plants, etc. It is of neat and compact design, well built and reliable. The gearing is machine-cut; tight and loose pulleys; crank shaft in one piece. The 7 x 8 inch and smaller have rods with crank bearings like Fig. 1140, page 182, and bushed bearings in plungers; large valve area.

These Pumps are regularly fitted for pumping solutions of chloride of calcium as a refrigerating medium, with iron plungers, cylinders, glands and rubber disc valves. These parts will be made of bronze to order, at extra price, if the Pump is to circulate solutions of common salt or other fluids destructive to iron. Always describe requirements as fully as possible.

Prices upon application.





FIG. 1059. SIZE 8" X 12"

FIG. 1059. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Usual Speed and Capacity per Minute.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
4 in.	6 in.	1. gal.	45 revs., 45 gals.	2 in.	2 in.	5 to 1	20 x 3 in.	Boxhaul
5 "	8 "	2. "	45 " 90 "	3 "	3 "	5 to 1	26 x 4 "	Boxing
7 "	8 "	4. "	45 " 180 "	5 "	5 "	4 to 1	30 x 5 "	Boxiron
8 "	10 "	6.5 "	40 " 260 "	6 "	5 "	5 to 1	36 x 6 "	Boxkeep
8 "	12 "	7.8 "	40 " 312 "	6 "	5 "	5 to 1	36 x 6 "	Boxthor

For Power Table, see page 203.

GOULDS SEPARATE TRIPLEX POWER PUMP.



FOR ELEVATIONS TO 100 FEET, EQUIVALENT TO  
43 POUNDS PRESSURE.

Fig. 1072 is a Pump comprising three separate Pumps, each with its independent suction and discharge pipe connections, and driven by one crank shaft. This combination saves space and power and admits of pumping several fluids at once. It is used in gas and chemical works, refineries, etc., for pumping ammonia water, tar, semi-fluids, etc.

It is regularly fitted with ball valves, iron plungers, cylinders and glands. Tight and loose pulleys, machine-cut gearing, and valves, as required for the specified service. The general design and construction are clearly indicated by the illustration.

Prices upon application.

FIG. 1072. SIZE 7" X 8"

FIG. 1072. SIZES, CAPACITIES, ETC.

PLUNGERS.		Capacity of Each Plunger per Rev.	Usual Speed and Capacity per Minute of Each Plunger.	SIZES OF PIPE.		Geared.	Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.			Suction.	Discharge.			
4 in.	4 in.	.22 gals.	40 revs., 8.8 gals.	2 in.	2 in.	5 to 1	20 x 3 in.	Woolmo
4 "	6 "	.33 "	40 " 13.2 "	2 "	2 "	5 to 1	20 x 3 "	Woolnd
5 "	6 "	.51 "	40 " 20.4 "	3 "	3 "	5 to 1	20 x 4 "	Woolog
5 "	8 "	.68 "	40 " 27.2 "	4 "	4 "	4 to 1	20 x 4 "	Woolpa
7 "	8 "	1.33 "	40 " 53.2 "	5 "	5 "	4 to 1	30 x 5 "	Woolqt

For Power Table, see page 203.

FOR VARIABLE DELIVERY.

Fig. 1034 is a modification of our standard Triplex Pressure Pump, Fig. 997, page 187. Instead of having three plungers, identical in size and working power, one plunger is of larger diameter and greater displacement than the others. When used with a press or other hydraulic machine, the initial movement of the ram is made more rapidly by the combined delivery of the three plungers, until a certain pressure is reached, then an automatic device cuts out the larger plunger and the operation is continued by the smaller plungers to the desired pressure. The pressure on the larger plunger should not exceed 25 per cent. of the maximum pressure exerted by the Pump.

Hydraulic Pressure Pumps of this form are particularly serviceable for Baling Presses, Testing Machines, etc., in mills and factories.

In making inquiries or orders, state fully the services required of the Pump.

Prices upon application.




FIG. 1034. SIZE  $\frac{3}{4}$ " AND  $1\frac{1}{2}$ " X 6"

FIG. 1034. SIZE, CAPACITY, ETC.

PLUNGERS.		Capacity One Revolution of Crank Shaft.	Speed and Capacity per Minute, Varying with Kind of Work and Pressure.	Limit Pres- sure per Square Inch.	SIZES OF PIPE.		Tight and Loose Pulleys.	Cipher.
Diameter.	Stroke.				Suction.	Discharge.		
$\frac{3}{4}$ in.	6 in.	15.8 cu. in.	25 to 50 revs.	5,000 lbs.	1 in.	$\frac{3}{4}$ in.	$26 \times 4$ in.	Turf
and		or					geared	
$1\frac{1}{2}$ in.		0.068 gals.	1.7 to 3.4 gals.				7 to 1	

For Power Table, see page 203.



# GOULDS VERTICAL POWER FORCE PUMPS.

WITH CRANK SHAFT, FOR EITHER HAND OR POWER

Fig. 1204 represents our new Vertical Power Force Pump, or, as it is often called, "Covered Crank Pump." Cut of Fig. 1204 gives sectional view, showing arrangement of plunger and valve in the standard, making a complete pump for drawing water from cisterns, shallow wells and streams, where the vertical suction lift is not over twenty-five feet. The Pump, as we now build it, having crank-shaft with bearing on each side of crank, possesses many advantages over the earlier types, and we believe its compact form and low price will commend it for almost innumerable uses. When so ordered, we can furnish with crosshead or guide (in place of plunger and lower valve), thus adapting it for operating a cylinder (see pages 62 and 63) in wells where water stands more than twenty-five feet below the Pump. Pump, thus arranged with cross-head, furnished at price of regular pump, but the deep well cylinder costs extra. Fig. 1205 differs from Fig. 1204, described above, only in that it has tight and loose pulleys. This Pump is largely used in creameries and milk stations, wherever it is desired to force liquids to elevations of fifty feet or less. Arrangement of plunger and valve is as shown in sectional view of Fig. 1204. Can be made for deep wells, same as Fig. 1204, and same remarks apply.




FIG. 1204




FIG. 1205

FIG. 1204. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Pulleys, Each.	*Lift and Force.	Cipher.	Price.
4	3 in.	6 in.	.18 gal.	1 1/4 in. pipe	1 1/4 in. pipe	15 x 3 in.	50 ft.	Waretu	\$27.00
6	3 1/2 in.	6 in.	.25 "	1 1/2 in. "	1 1/2 in. "	15 x 3 "	50 "	Wareul	30.00

FIG. 1205. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Pulleys, Each.	*Lift and Force.	Cipher.	Price.
4	3 in.	6 in.	.18 gal.	1 1/4 in. pipe	1 1/4 in. pipe	15 x 3 in.	50 ft.	Warevz	\$32.00
6	3 1/2 in.	6 in.	.25 "	1 1/2 in. "	1 1/2 in. "	15 x 3 "	50 "	Warewy	35.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water. Hot water must flow to Pump.

WITH BRASS-FITTED GLOBE CHECK VALVE.

Fig. 289 represents a Hand Boiler Feed Pump on plank, for feeding cold boilers or those under moderate steam pressure, as 40 to 60 pounds. It is also well adapted for supplying feed water to boilers employed for making steam for heating only, etc.

The Pumps are supplied with brass-fitted globe check valve on discharge, preventing water from returning to Pump. They have brass plunger and lower valve, adapting them for pumping hot as well as cold water. Where Pumps must handle hot water, we always advise placing them under flooded suction.

These Pumps are heavy and substantial in build, having revolving bearer, brass gland and brass-cased piston rod, and must not be confused with cheaper Pumps of this class.

Fig. 495 is built on same lines as Fig. 289, described above, except that it is a Base Pump. It is designed for the same range of duty.




FIG. 289




FIG. 495

FIG. 289. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	Equivalent Pressure.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe	120 ft.	51 lbs.	Digit	\$12.00
2	2½ "	6 "	.13 "	1¼ "	1¼ "	90 "	38 "	Dikes	14.00
4	3 "	6 "	.18 "	1¼ "	1¼ "	60 "	25 "	Dimal	16.00

FIG. 495. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	*Lift and Force.	Equivalent Pressure.	Cipher.	Price.
0	2 in.	6 in.	.08 gal.	1 in. pipe	1 in. pipe	120 ft.	51 lbs.	Headek	\$12.00
2	2½ "	6 "	.13 "	1¼ "	1¼ "	90 "	38 "	Healed	14.00
4	3 "	6 "	.18 "	1¼ "	1¼ "	60 "	25 "	Heaps	16.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water. Hot water must flow to Pump.

## GOULDS PLUNGER BOILER FEED PUMP.

WITH COLUMN AND SINGLE PULLEY FOR HAND OR MACHINE POWER.




FIG. 482

Fig. 482 represents our Power Boiler Feed Pump on bed plate, with column, crank shaft and face plate, with single pulley, for hand or machine power. Capable of handling hot water as well as cold.

Pump has general application for feeding cold boilers or those under moderate steam pressure. Has special bronze check valves and outside-packed plunger.

We always recommend shortest possible suction pipe with Boiler Feed Pump, as it lessens the danger of losing its priming.

FIG. 482. SIZES, PRICES, ETC.

No.	Dia. of Cyl.	Stroke.	Capacity per Min., 60 Strokes.	Suction.	Discharge.	*Lift and Force.	Equiva- lent Pressure.	Pulley.	Cipher.	Price.
0	2 in.	3 in.	2.45 gal.	1 in. pipe	1 in. pipe	120 ft.	60 lbs.	16 x 3 in.	Gull	\$35.00
2	2½ "	3 "	3.82 "	1 "	1 "	90 "	45 "	18 x 4 "	Gullyx	37.50
4	3 "	3 "	5.51 "	1¼ "	1¼ "	60 "	30 "	20 x 4 "	Gulps	40.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water. Hot water must flow to Pump.

## GOULDS PLUNGER BOILER FEED PUMP.

WITH COLUMN AND TWO PULLEYS, FOR HAND OR MACHINE POWER.




FIG. 484

Fig. 484 represents improved pattern of Power Boiler Feed Pump with crank shaft, face plate, tight and loose pulleys, for hand or machine power. On the end of driving shaft opposite the face plate is a heavy iron crank with wrought-iron handle for working Pump when necessary.

Pumps may be employed for feeding steam boilers under moderate pressure, or any other service within limits cited in our table below.

Has special bronze check valves and outside-packed plunger and is capable of handling hot water.

FIG. 484. SIZES, PRICES, ETC.

No.	Dia. of Cyl.	Stroke.	Capacity per Min., 60 Strokes.	Suction.	Discharge.	*Lift and Force.	Equiva- lent Pressure.	Pulley.	Cipher.	Price.
0	2 in.	3½ in.	2.45 gal.	1 in. pipe	1 in. pipe	120 ft.	60 lbs.	16 x 3 in.	Hairs	\$40.00
2	2½ "	3½ "	3.82 "	1 "	1 "	90 "	45 "	16 x 3 "	Haily	42.50
4	3 "	3½ "	5.51 "	1¼ "	1¼ "	60 "	30 "	16 x 3 "	Halfs	45.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water. Hot water must flow to Pump.



# GOULDS PLUNGER BOILER FEED PUMP.

239

WITH STUB END FOR MACHINE POWER.

Fig. 292 represents our Power Boiler Feed Pump for supplying steam boilers with water against any pressure. The globe check valves are made of separate castings, faced off and bolted on the body of Pump, thus making a tight-packed joint. The valve seats are made of best bronze and screwed into the iron castings, and can therefore be removed when worn out and new ones inserted. The valve itself is also of bronze. The stuffing-box, top of piston and stub end are finished bright and polished.

FIG. 292. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Minute, 60 Strokes.	Suction.	Discharge.	*Lift and Force.	Equiv. Pressure.	Cipher.	Price.
00	1½ in.	9 in.	4.13 gal.	1 in. pipe	1 in. pipe	250 ft.	107 lbs.	Dimed	\$30.00
0	2 in.	9 "	7.35 "	1¼ "	1¼ "	250 "	107 "	Dimal	35.00
2	2½ "	9 "	11.47 "	1½ "	1½ "	250 "	107 "	Dine	40.00
4	3 "	9 "	16.52 "	1½ "	1½ "	250 "	107 "	Dingy	50.00

\*Total lift and force from supply to point of delivery, Pump not more than 25 feet above water. Hot water must flow to Pump.

See notes on Feed Water for Boilers, page 185.




FIG 292

# GOULDS PLUNGER BOILER FEED PUMP.

WITH STUB END FOR MACHINE POWER.

Fig. 485 represents Power Boiler Feed Pump with trunk plunger, which we offer in several sizes given below. Suction and discharge brass check valves are screwed into opposite sides of cylinder. This cheap yet serviceable Pump has general application for feeding steam boilers under moderate pressure, or for any limit duty indicated in our tables.

FIG. 485. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Minute, 60 Strokes.	Suction.	Discharge.	*Lift and Force.	Equiv. Pressure.	Cipher.	Price.
2	1¼ in.	6 in.	1.27 gal.	¾ in. pipe	¾ in. pipe	150 ft.	64 lbs.	Halls	\$10.00
3	1½ "	6 "	1.84 "	1 "	1 "	150 "	64 "	Halor	15.00
4	1½ "	3 "	1.37 "	¾ "	¾ "	150 "	64 "	Halt	14.00
5	2 "	3 "	2.45 "	1 "	1 "	120 "	51 "	Hames	18.00
6	2½ "	3 "	3.82 "	1 "	1 "	90 "	38 "	Hands	22.00
7	3 "	3 "	5.50 "	1¼ "	1¼ "	60 "	25 "	Hank	27.00
8	2 "	6 "	3.26 "	1½ "	1½ "	120 "	51 "	Hard	22.00
9	2½ "	6 "	5.10 "	1½ "	1½ "	90 "	38 "	Hares	30.00
10	3 "	6 "	7.35 "	1½ "	1½ "	120 "	51 "	Harks	40.00

\*Total lift and force from supply to point of delivery, Pump not more than 20 feet above water. Hot water must flow to Pump.

See notes on Feed Water for Boilers, page 185.




FIG. 485

# “ROYAL” STEAM BOILER FEED PUMP.

The “Royal” Steam Boiler Feed Pump has many points of merit in its arrangement, construction and proportions not found in any other pumps.

The main or frame casting, with supporting arm, is all in one piece, so that the shaft revolves in perfectly rigid bearings, while the eccentric connection works in a vertical line, without any lateral pressure on the valve rod to heave and pull the steam chest, cramp the rod and create friction. The cylinder heads have ground surfaces; the space between cylinder and chest is tapped on either side for the exhaust steam pipe, and the brass globe check valves are each designated “suction” or “discharge” for convenience, and can be connected on either side of Pump if necessary. If water is to be raised by suction, put a foot valve and strainer on end of suction pipe and make all joints tight.

Engineers all say that the GOULD “ROYAL” is the most substantial, best proportioned and modern in its general construction and arrangement of parts, of any of the large number of Single-Acting Boiler Feed Pumps, and always give it the preference over all others.

With each Pump we furnish Throttle Valve, Oil Cup and Let-Off Plugs.

The table below will give a full description of capacity, prices, etc., of these Pumps.




FIG. 687

FIG. 687. SIZES, PRICES, ETC.

No.	Diameter Steam Cylinder.	Diameter Water Plunger.	Stroke.	Steam.	Exhaust.	Suction and Discharge.	Rev. per Minute.	Capacity per Minute.	* Lift and Force.	Equiv. Pres- sure.	Cipher.	Price.
1	3 in.	1 $\frac{3}{8}$ in.	3 in.	$\frac{3}{8}$ in. pipe	$\frac{3}{4}$ in. pipe	1 in. pipe	100	1.93 gal.	200 ft.	100 lbs.	Sagot	\$44.00
2	3 $\frac{1}{2}$ "	1 $\frac{3}{4}$ "	3 "	$\frac{1}{2}$ "	$\frac{3}{4}$ "	1 "	100	3.12 "	200 "	100 "	Sailor	55.00
3	4 "	2 $\frac{1}{4}$ "	4 "	$\frac{3}{4}$ "	1 "	1 $\frac{1}{4}$ "	90	6.20 "	200 "	100 "	Sakels	70.00
4	4 $\frac{1}{2}$ "	2 $\frac{3}{4}$ "	4 "	$\frac{3}{4}$ "	1 "	1 $\frac{1}{2}$ "	85	8.75 "	200 "	100 "	Salad	82.50
5	5 "	3 $\frac{1}{2}$ "	4 "	$\frac{3}{4}$ "	1 $\frac{1}{4}$ "	1 $\frac{1}{2}$ "	80	13.33 "	200 "	100 "	Saleso	110.00
6	6 "	4 "	5 "	1 "	1 $\frac{1}{2}$ "	2 "	75	21.75 "	200 "	100 "	Salty	154.00

\* Total lift and force from supply to point of delivery, Pump not more than 25 feet above water. Hot water must flow to Pump.

Pumps with brass-lined cylinder and brass-cased plunger add to list No. 1, \$8.00; No. 2, \$10.00; No. 3, \$12.50; No. 4, \$16.00; No. 5, \$21.00; No. 6, \$30.00.

# GOULDS HYDRAULIC PRESSURE OR TEST PUMP.

241

*FOR TESTING BOILERS, PIPES, ETC.*

Fig. 867 represents a new Hydraulic Pressure or Test Pump, of compact build and of commensurate strength for work for which it is designed.

It has a revolving top, admitting its being worked in any position, and a sectional lever, which can be changed to give greatest leverage. The suction and discharge valves (flanged and bolted to cylinder) are of a new and improved type, with brass valve seats, poppets and caps. The Pump should be placed within short suction distance of water, or on a level with it, and will be found invaluable to the boilermaker, or user, for testing the condition of boilers, vessels, etc., for cleaning out pipes, etc.




FIG. 867

FIG. 867. SIZES, PRICES, ETC.

No.	Diameter Ram.	Stroke.	Suction and Dis.	Working Pressure.	Cipher.	Price.
0	$\frac{3}{4}$ in.	5 in.	1 in. pipe	700 lbs.	Webbed	\$18.50
1	1 " "	5 "	1 "	550 "	Webbery	19.00
2	$1\frac{1}{4}$ "	5 "	1 "	400 "	Webby	19.50
3	$1\frac{1}{2}$ "	5 "	1 "	200 "	Wedah	20.00

Can furnish with strong wood barrow, with cast-iron tank underneath, at \$10.00 extra list.

# GOULDS HIGH SERVICE PRESSURE OR TEST PUMP.

*FOR TESTING BOILERS, TANKS, ETC.*

Fig. 941 is designed to supply the demand for a Test Pump, capable of generating any desired pressure up to 6,000 pounds per square inch. The body or cylinder, as well as ram, is of steel, the valves of best gun metal and the lever forged from wrought-iron. In short, we have sacrificed nothing that would contribute to the strength and efficiency of this Pump, and the results have vindicated our policy. Our table of dimensions, given below, further illustrates the compactness and power of our Pump.




FIG. 941

FIG. 941. SIZE, PRICE, ETC.

Diameter Ram.	Stroke.	Suc. and Dis.	Working Pressure.	Cipher.	Price.
$\frac{1}{2}$ in.	2 in.	$\frac{1}{4}$ in. pipe	6000 lbs.	Wetish	\$30.00



# GOULDS SODA WATER PRESSURE PUMP.

FOR HAND OR POWER USE.

Fig. 1086, Soda Water Pressure Pump, has frame cylinder support and plunger rod guide cast in one piece, this form of construction insuring proper alignment of the working parts.

The frame supports shaft, with connecting rod, and carries on one end tight and loose pulleys, and on other balance wheel with handle.

Pump has bronze cylinder, plunger and valves.

It may also be used for boiler testing or any pumping service where the pressure does not exceed 200 lbs.




FIG. 1086

FIG. 1086. SIZE, PRICE, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Working Pressure.	Balance Wheel.	Pulleys.	Cipher.	Price.
1½ in.	6 in.	.05 gal.	¾ in. pipe	¾ in. pipe	200 lbs.	36 x 3½ in.	20 x 3 in.	Rudehi	\$100.00

# GOULDS SODA WATER PRESSURE PUMP.

Fig. 1083, Soda Water Pressure Pump, is simple in construction, all the parts being readily accessible. The base, lever socket, link and lever are made of iron. The plunger, cylinder and valves are of bronze. In addition to pumping water into soda water tanks, this pump may be used for boiler testing, or any service up to the limits of its working pressure, 200 lbs.




FIG. 1083

FIG. 1083. SIZES, PRICES, ETC.

Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Working Pressure.	Cipher.	Price.
1 in.	5 in.	.02 gal.	½ in. pipe	½ in. pipe	200 lbs.	Rudefa	\$20.00
1¼ in.	5 in.	.03 gal.	½ in. pipe	½ in. pipe	200 "	Rudegg	22.50

# GOULDS HYDRAULIC TEST PUMP.

243

WITH CAST-IRON TANK.




FIG. 789

Fig. 789 illustrates our new Gun Metal Test Pump, for testing boilers, tanks, pipes, etc., to one thousand pounds pressure on the square inch, if necessary. As the cistern only holds about two gallons of water, the thing to be tested should first be filled by other means and the tester then applied to supply the balance and work up the pressure.

Everything is made first-class in all respects. Weight about forty pounds.

FIG. 789. SIZE, PRICE, ETC.

Complete as shown, with  $\frac{7}{8}$ -inch piston and delivery pipe screwed for  $\frac{1}{2}$ -inch gas pipe coupling. (Wedder)..... \$30.00

This price does not include Test Gauge, which will be supplied of any desired size or style at lowest market rates.

## PLUMBERS' BRASS FORCE PUMPS.

In Fig. 1035 we show our new Plumbers' Brass Force Pump, which, we believe, will meet the requirements and approval of the Trade. For removing obstructions in waste or water pipes, Pump is placed in vessel of water and pipe to be cleared connected to Pump by hose. For this purpose we furnish three feet of hose and conical tip, that may readily be connected to any ordinary sized pipe.

Pump is very compact and may easily be carried in sack of plumbers' tools, etc.

FIG. 1035. SIZE, PRICE, ETC.

1-inch Diameter Cylinder, 16-inch Stroke (Baldwin)..... \$7.00




FIG 1035

## PLUMBERS' BRASS FORCE PUMP.

Fig. 322 represents our Plumbers' Force Pump for removing obstructions in waste and water pipes. All working parts are brass. Discharge is furnished with brass check valve and fitted with hose coupling. In operating this Pump, a hose is connected to pipes to be cleared and Pump is set in vessel of water.

FIG. 322. SIZE, PRICE, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Stroke.	Discharge.	Cipher.	Price.
0	2 in.	5 in.	.07 gal.	$\frac{3}{4}$ in. hose	Dusty	\$7.00




FIG. 322



## GAS COMPANIES' AND PLUMBERS' DRIP PUMP.




FIG. 323

Fig. 323, illustrated in cut, is our Plumbers' and Gas Companies' Drip Pump, for extracting the water from gas drips. These Pumps have brass cylinders, brass plunger, valve and plunger rod, glands, etc. Suction is regularly fitted for wrought-iron pipe, unless otherwise ordered.

FIG. 323. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Cipher.	Price.
0	2 in.	9 in.	.12 gal.	3/4 in. pipe	Dutch	\$12.00
2	2 1/2 in.	9 in.	.19 "	3/4 in. pipe	Chesteg	16.00

## GOULDS "MAGIC" HAM-CURING PUMP.

ALL WORKING PARTS BRASS.

Fig. 922 represents our "Magic" Ham-Curing Pump. All working parts are brass, including double-crimp packed plunger, brass valves and seats. We furnish with this Pump 3 feet of 1/2-inch rubber suction and discharge hose and nickel-plated needle point. This is a well proportioned Pump, with a powerful leverage. The office of the Pump is to thoroughly impregnate the ham with a suitable preparation or pickle, thus curing it more quickly and better, in any season, than by the old process. We can furnish interested parties recipes for pickle.

FIG. 922. SIZE, PRICE, ETC.

No.	Diameter Cylinder.	Stroke.	Suction.	Discharge.	Cipher.	Price.
0	2 in.	5 in.	1/2 in. hose	1/2 in. hose	Wevill	\$15.00




FIG. 922

## GOULDS SPECIAL LIFT AND FORCE OIL PUMP.

FOR PUMPING KEROSENE AND OTHER OILS.

Fig. 1120 shows our Special Oil Pump for pumping kerosene, etc. It is so arranged that the lever may be operated by the left hand, leaving the right hand free to control the measuring tank, gauges, etc. This Pump is very strong and durable. The spout is reversible, so that the liquid may be discharged at either right or left of the Pump. This change is made by simply removing the lever and turning the spout either way.

FIG. 1120. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Stroke.	Suction.	Lift.	Cipher.	Price.
1	2 1/4 in.	6 in.	.10 gal.	1 in. pipe	25 ft.	Fustjub	\$5.00
4	3 in.	6 in.	.18 "	1 1/4 in. pipe	25 "	Fustkub	5.50




FIG. 1120



# GOULDS GAS FITTERS' PROVING PUMP.

245

WITH SPRING OR MERCURY GAUGE.

Fig. 1065 shows our Gas Fitters' Proving Pump, with Spring Gauge. It affords the best known means of testing pipes. We price below Pump only, also complete with Spring or Mercury Gauge and Hose, as shown in engraving, if wanted.

FIG. 1065. SIZE, PRICE, ETC.

No.	Diameter Cylinder.	Stroke.	Displacement per Stroke.	Discharge.	Cipher.	Brass Pump Only.
0	2 in.	10 in.	31 cu. in.	$\frac{3}{4}$ in. hose	Dabcer	\$12.00

Pump with Spring Gauge (or Mercury Gauge as ordered), Ether Cup, Cock and Hose Complete.....	\$25.00
Spring Gauge.....	5.00
Mercury Gauge.....	5.00
Ether Cup and Cock.....	7.50
Hose per foot.....	.25




FIG. 1065

## GOULDS DOUBLE-ACTING GAS OR AIR PUMP.

FOR GAS OR OIL WELLS.

Fig. 1130, Double-Acting Gas or Air Pump, is designed for use in gas and oil regions, for relieving the back pressure from oil wells or supplying boilers with gas from non-flowing wells.

Cylinder is cast iron with iron piston, metallic spring packed. The suction valves, placed upon one side of Pump and discharge valves upon opposite side, are bronze, leather faced, and easy of access. Pump is furnished, complete, with forked coupling and yoke for wood rod of walking beam.

FIG. 1130. SIZE, PRICE, ETC.

Diameter Cylinder.	Stroke.	Displacement Free Air per Revolution.	Suction.	Discharge.	Cipher.	Price.
14 in.	20 in.	6152 cubic in.	2 in. pipe	2 in. pipe	Waltab	\$125.00




FIG. 1130

# GOULDS BRASS PRESSURE OR VACUUM PUMP.

*MOUNTED ON PLANK, WITH WROUGHT-IRON LEVER.*




FIG. 1203

Fig. 1203 represents a Brass Air or Vacuum Pump of proper construction for forcing air or gas into barrels, casks or other vessels. In this manner the most destructive acids, such as nitric, sulphuric, etc., may be raised by air pressure without coming in contact with Pump, or in fact anything except conveying pipes. Pump has metallic spring packed plunger, and is so constructed that air or gas may be pumped with minimum loss. It may be used as a pressure or as a vacuum pump, as desired. Inlet and outlet are at the bottom. The uses of an Air Pump are so various, that we prefer to know for what it is to be employed, quantity of air desired, etc.

FIG. 1203. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Displacement per Stroke.	Inlet.	Outlet.	Maximum Pressure.	Cipher.	Price.
0 000	2 in. 1½ "	6 in. 10 "	22 cubic in. 17 "	⅜ in. pipe ¼ "	⅜ in. pipe ¼ "	150 lbs. 250 "	Glasson Glassub	\$15.00 30.00

# GOULDS BRASS PRESSURE OR VACUUM PUMP.

*MOUNTED ON PLANK, WITH CRANK SHAFT AND FLY-WHEEL.*

Fig. 1209 is substantially the same as Fig. 1203, described above, and adapted for the same purposes. Where any amount of pressure is required, it will be generated much easier with the aid of Crank Shaft or Fly-Wheel than with lever.

We might also say this style of Pump is extensively used for pumping air into beer casks and raising it without aid of other appliances.

FIG. 1209. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Displacement per Stroke.	Inlet.	Outlet.	Maximum Pressure.	Cipher.	Price.
0 000	2 in. 1½ "	6 in. 7 "	22 cubic in. 17 "	⅜ in. pipe ¼ "	⅜ in. pipe ¼ "	150 lbs. 250 "	Waraho Waraid	\$28.00 43.00




FIG. 1209

FOR HAND OR MACHINE POWER.



FIG. 605




FIG. 1096




FIG. 772

Air Pumps, shown above, are equally adapted for pumping against pressure or creating vacuum. When ordering, state for which purpose desired. Pumps are made with inside valves, thereby reducing clearances to a minimum.

Fig. 605 is arranged with stub end for power connection. Fig. 772 is similar to Fig. 605, but arranged for hand pumping. Fig. 1096 is hand pump, somewhat lighter and cheaper.

FIG. 605. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Displacement Free Air per Stroke.	Inlet.	Outlet.	Working Pressure.	Cipher.	Price.
16	6 in.	12 in.	339 cubic in.	1 1/4 in. pipe	1 1/4 in. pipe	75 lbs.	Moore	\$35.00
24	8 "	12 "	600 " "	1 1/2 " "	1 1/2 " "	75 "	Clubo	45.00

FIG. 1096. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Displacement Free Air per Stroke.	Inlet.	Outlet.	Working Pressure.	Cipher.	Price.
16	6 in.	10 in.	280 cubic in.	1 1/4 in. pipe	1 1/4 in. pipe	30 lbs.	Gruhal	\$30.00
24	8 "	10 "	500 " "	1 1/2 " "	1 1/2 " "	30 "	Gruhed	40.00

FIG. 772. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Displacement Free Air per Stroke.	Inlet.	Outlet.	Working Pressure.	Cipher.	Price.
16	6 in.	12 in.	339 cubic in.	1 1/4 in. pipe	1 1/4 in. pipe	50 lbs.	Viary	\$40.00
24	8 "	12 "	600 " "	1 1/2 " "	1 1/2 " "	50 "	Dashed	50.00



# POWER AIR PRESSURE OR VACUUM PUMP.

WITH CRANK SHAFT AND PULLEYS.




FIG 1029

Fig. 1029 represents our Air Pressure or Vacuum Pump, with crank shaft, pitman and guide, arranged with tight and loose pulleys for power. Air is received into cylinder through inlet opening in base on the up stroke of piston, and forced out through discharge opening in base on the downward stroke of piston.

These Pumps have a general application for forcing air into receivers, to agitate liquids, and are also used in connection with the dry-pipe sprinkler system in mills and factories. It may also be used for any purpose where a vacuum is required. Maximum speed is 100 R. P. M.

FIG. 1029. SIZE, PRICE, ETC.

PLUNGER.		Displacement Free Air per Rev. of Crank Shaft.	Maximum Pressure.	Inlet and Outlet.	Tight and Loose Pulleys.	Cipher.	Price.
Diameter.	Stroke.						
6 in.	8 in.	226 cubic in.	30 lbs.	1¼ in. pipe	24 x 4 in.	Banjo	\$80.00

# POWER AIR PRESSURE OR VACUUM PUMP.

WITH WATER-JACKET, CRANK SHAFT AND PULLEYS.




FIG. 1190

Fig. 1190 shows one of our water-jacketed Air Pressure Pumps arranged with tight and loose pulleys for power. By means of the water-jacket, cold water may be circulated around the cylinder, preventing it from heating when working under heavy, constant pressure. The tight or driving pulley is made extra heavy and acts as a fly-wheel, producing uniform action of parts. Piston is metal, ring packed. This Pump is well adapted for high, continuous pressure and from its construction and capacity has a varied range of service. It may be used equally as well for a Vacuum Pump as an Air Compressor. It should always be specified for what purpose it is intended. May be operated at 125 revolutions per minute and 125 pounds pressure.

FIG. 1190. SIZE, PRICE, ETC.

Dia.	Stroke.	Dis. Free Air per Rev. Crank Shaft.	Suction.	Discharge.	Water Jacket Inlet and Outlet.	Tight and Loose Pulleys.	Cipher.	Price.
3 in.	8 in.	56 cu. in.	1 in. pipe	¾ in. pipe	½ in. pipe	24 x 4 in.	Flushun	\$100.00

# GOULDS AIR PRESSURE AND VACUUM PUMP.

249

WITH LARGE FLY-WHEEL AND WINCH HANDLE FOR HAND  
OR POWER USE.

Fig. 1176 shows an Air Pump of considerable capacity. It is provided with heavy balance wheel for hand or belt drive, making its operation easy and uniform. Wheel has two handle bosses, by which the leverage can be varied according to the pressure required. The valves, which are contained within its base, are of brass. Piston is metal, ring packed, so constructed as to automatically take up the wear. Pump is built strong and substantial in every way. Clearances are reduced to a minimum, and it will be found a most effective and satisfactory Pump when used as pressure Pump. Suction is fitted for pipe and Pump will be found equally effective for creating vacuum.

FIG. 1176. SIZE, PRICE, ETC.

Diameter.	Stroke.	Displacement Free Air per Rev. Crank Shaft.	Maximum Speed.	Maximum Pressure.	Suction and Discharge.	Pulley.	Cipher.	Price.
3 in.	4 in.	28 cubic in.	150 R. P. M.	100 lbs.	½ in. pipe	30 x 3 in.	Flushyx	\$55.00




FIG. 1176

# GOULDS AIR PRESSURE AND VACUUM PUMP.

WITH WATER-JACKETED CYLINDER, CRANK SHAFT  
AND PULLEYS.

Fig. 1193, Air Pump, is modelled on same lines as Fig. 1176, described above, with the addition of water jacket around cylinder and tight and loose pulleys for power. The driving pulley is made extra heavy and serves as a fly-wheel. The water jacket allows a free circulation of cold water around cylinder, keeping it cool and adapting the Pump for continuous, heavy service. Valves are of brass; plunger is metal, ring packed.

When so ordered, we will supply, in place of regular 15 x 3-inch tight and loose pulleys, a 30 x 3-inch balance wheel for either hand or belt drive, and suitable for running from high speed electric motors, etc., at \$2.50 extra net.

FIG. 1193. SIZE, PRICE, ETC.

Diameter.	Stroke.	Displacement Free Air per Rev. Crank Shaft.	Maximum Speed.	Maximum Pressure.	Suction and Discharge.	Water-Jacket Inlet and Outlet.	Pulleys.	Cipher.	Price.
3 in.	4 in.	28 cubic in.	150 R. P. M.	125 lbs.	½ in. pipe	½ in. pipe	15 x 3 in.	Flushwo	\$65.00




FIG. 1193



# GOULDS "LIGHTNING" AIR PRESSURE PUMP.

FOR HAND USE.



FIG. 1196

Fig. 1196, "Lightning" Air Pressure Pump, is a modification of our original design, with cylinder and base cast in one solid piece. This construction gives additional strength and absolute assurance against leaky joints. Our form of compound lever affords easy, rapid working, with most effective application of power. We have made a special study to reduce clearances to a minimum, and believe succeeded beyond any other pump in the market. Capacities, prices, etc., as below.

FIG. 1196. SIZE, PRICE, ETC.

Dia. Cyl.	Stroke.	Displacement per Stroke.	Discharge.	Working Pressure.	Cipher.	Price.
3 in.	4 in.	28 cubic in.	$\frac{1}{8}$ -in. hose	50 lbs.	Stilt	\$6.00

$3\frac{1}{2}$ -inch Brass Case Pressure Gauge and Cock.....\$3.50  
 $\frac{1}{8}$ -inch C. I. Rubber Tubing, per foot......10

# GOULDS "NEW LIGHTNING" AIR PRESSURE PUMP.

FOR HAND USE.



FIG. 1210

Fig. 1210, "New Lightning" Air Pressure Pump, is an improved type of our Pumps of this class. The essential features are increased capacity, found in the larger diameter and longer stroke, improved form of piston and valves with reduced clearances; also more powerful leverage. The practically perfect cylinder can only be had in the cast body, finished to accurate size. Ours is in one piece with base, to obviate possibility of leakage at this point. The piston and valves are finished with a view of obtaining the highest efficiency. The compound lever is of new form, permitting best possible application of power and rendering the work comparatively easy.

We offer as a strictly high class Pump, designed to meet the demand for the best.

FIG. 1210. SIZE, PRICE, ETC.

Dia. Cyl.	Stroke.	Displacement per Stroke.	Discharge.	Working Pressure.	Cipher.	Price.
$3\frac{3}{4}$ in.	$5\frac{1}{2}$ in.	45.6 cubic in.	3-16 in. hose	100 lbs.	Twiddle	\$10.00



SPRING  
AND SUMMER  
SPRAYING.

Illustrating  
Several Outfits,  
in Operation.





## GOULDS PORTABLE BRASS FORCE PUMPS.



FIG. 561 1/2

Fig. 561 1/2 represents our "Premier" Brass Bucket Pump, arranged with suction and discharge hose and Spray Nozzle. With this Nozzle a solid stream may be thrown, or a fine spray. Pump has brass cylinder, plunger and rod. Pump is particularly adapted for washing windows and wagons, spraying flowers in conservatories, gardens, etc. Its weight is only eight pounds.

FIG. 561 1/2. PRICE.

With 2 1/2 feet 3/4-inch suction and 3 feet 3/4-inch discharge hose, Spray Nozzle and Strainer.....(Velveub) \$7.50

Fig. 1129, "Bordeaux" Brass Garden and Spray Pump, is especially designed for spraying in gardens and greenhouses. The Pump is double-acting in effect, has gutta percha ball valves, proof against the action of acids and oils. Foot piece is malleable iron. The pump end of discharge hose is wire wound, adding largely to its durability. Our "Seneca" nozzle is furnished with Pump. Pump has no suction hose, but is set in pail or bucket with foot-rest outside.

FIG. 1129. PRICE.

With 3 feet 3/8-inch discharge hose and Spray Nozzle.....(Wathug) \$6.00

Fig. 1068 represents a Brass Spray Pump, Fig. 1129, fitted into a galvanized iron bucket, and thus arranged will be found very convenient for carrying about. Capacity of bucket is between 5 and 6 gallons.

FIG. 1068. PRICE.

With 5 feet of 3/8-inch discharge hose and Spray Nozzle.....(Dripus) \$9.00

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.




FIG. 1129



FIG. 1068

# GOULDS "HANDY" KNAPSACK PUMP.

253

FOR VINEYARD, ORCHARD OR FIELD SERVICE.

Fig. 989 represents our Knapsack Spray Pump, made entirely of brass and copper, with ball valves and metal plunger, all of which are easily accessible.

The discharge is at the bottom, and the pump can be entirely drained of the liquid. Any leakage of fluid out of the stuffing-box will drip back into the tank. The change from the right to the left hand is simple, and made by disconnecting the bearer link and bringing it over to the jaw, provided for it on the other side.

An eye on the top and back of knapsack enables one to suspend it steadily, when he wishes to take it off his back. It should be carried on back *with the straps crossed in front*. The reservoir is made of heavy copper, and will hold about five gallons of liquid. Special Agitator, 50 cents extra net.

SIZE, PRICE, ETC.

Fig. 989. "Handy" Knapsack Sprayer, complete as shown in cut, with  $3\frac{1}{2}$  feet of  $\frac{3}{8}$ -inch discharge hose, "Vermorel" Nozzle and Lance for degorger..... (Wrybill) \$15.00

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to use," issued annually and furnished upon application.




FIG. 989

## GOULDS KNAPSACK "KEROWATER."

FOR EMULSIFYING AND SPRAYING KEROSENE AND WATER.

(Patented March 7, 1899.)

Many conditions are encountered, under which our barrel "Kerowater" cannot be advantageously operated, as in greenhouses, work on side hills, etc. For these purposes we have designed our Fig. 1263, Knapsack "Kerowater."

It embodies the same principle as described under Fig. 1187, page 259, and consists of two independent Pumps, operated by a common lever, placed in a galvanized iron tank, with divisions for oil and water. Combined capacity about 5 gallons. Quantity of oil used is controlled by adjustment of a single pin, and may be varied to 5, 10, 15, 20 or 25 per cent. Pump may be operated by either hand, by changing lever to right or left.

FIG. 1263. PRICE, ETC.

Fig. 1263. Knapsack "Kerowater," complete as shown in cut, with 4 feet of  $\frac{3}{4}$ -inch discharge hose, "Seneca" Nozzle and Pipe Extension, 12 inches long..... (Zirdfe) \$12.00




FIG. 1263

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.



# 254 GOULDS "STANDARD" DOUBLE-ACTING SPRAY PUMP.

WITH BRASS-LINED CYLINDER AND BRASS-CASED DIFFERENTIAL PLUNGER

Fig. 905 is a strong Double-Acting Spray Pump, with brass-lined cylinder and brass cased differential plunger, specially adapting it for diffusing poisonous mixtures such as Bordeaux, Paris Green, Copper Sulphate, etc., upon the trees, vines and bushes. The differential plunger forms the air chamber and contributes to sustaining a continuous and uniform discharge at spray nozzles. The base is adapted for either end or side of barrel. Lever is extra long and strong. Pump has two discharges cut for pipe, but when ordered without hose or spray nozzles, we plug one opening and fit the other with brass bushing and half coupling for hose. Also supply brass suction strainer. Prices do not include barrel. Pump fitted with metallic lower valve, \$1.00 Extra net. For Agitator, see Fig. 1079, page 262. For Nozzles, Extensions, Etc., see pages 263 to 266.




FIG. 905

FIG. 905. SIZES, PRICES, ETC.

	No.	Dia. Outer Cyl.	Suction.	Double Discharge.	Cipher.	Brass-Lined.
Pump with Strainer and Hose Coupling.	2	2½ in.	1 in. pipe	½ in. hose and ¾ in. pipe.	Waspfly	\$8.50
	4	3 "	1¼ "	¾ in. hose and 1 in. pipe	Waract	9.50
Outfit A, With One Lead Hose and Nozzle.	Fig. 905. 2½-inch Spray Pump with 2½ feet 1-inch iron suction pipe with brass strainer and one lead of 10 feet, ½-inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzle.					13.00
Outfit AA.	Fig. 905. 3-inch Spray Pump fitted in same manner.					14.00
Outfit B, With Two Leads Hose and Nozzles.	Fig. 905. 2½-inch Spray Pump with 2½ feet 1-inch iron suction pipe with brass strainer and two leads of 10 feet each, ½-inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzles.					16.50
Outfit BB.	Fig. 905. 3-inch Spray Pump fitted in same manner.					17.50

Special Spray Catalogue, "How to Spray, When to Spray, and What Pumps to Use," issued annually and furnished upon application.

# GOULDS "STANDARD" DOUBLE-ACTING SPRAY PUMP. 255

WITH BRASS-LINED CYLINDER, BRASS-CASED DIFFERENTIAL PLUNGER.

Fig. 905½ shows our Double-Acting Spray Pump with base for attaching to either side or top of barrel. This Pump has brass-lined cylinder, brass-cased differential plunger, and is substantially the same as Fig. 905, described on foregoing page, but has an additional air chamber on spout. In spraying old orchards this is a considerable advantage, as the spray can be discharged to topmost branches. Pump has two discharges cut for pipe, but when ordered without hose and nozzles, we plug one opening and fit the other with brass bushing and half coupling for hose. Also supply brass suction strainer. Prices do not include barrel.

Pump fitted with metallic lower valve, \$1.00 extra net.

For agitator, see Fig. 1079, page 262.

For nozzles, extensions, etc., see pages 263 to 266.

FIG. 905½. SIZES, PRICES, ETC.

	No.	Dia. Outer Cyl.	Suction.	Double Discharge.	Cipher.	Brass- Lined.
Pump with Strainer and Hose Coupling.	2	2½ in.	1 in. pipe	½ in. hose and ¾ in. pipe	Zuta	\$9.50
	4	3 "	1¼ "	¾ in. hose and 1 in. pipe	Zymfk	10.50
Outfit A, With One Lead Hose and Nozzle.	Fig. 905½. 2½-inch Spray Pump with 2½ feet 1-inch iron suction pipe with brass strainer and one lead of 10 feet ½-inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzle.					14.00
Outfit AA.	Fig. 905½. 3-inch Spray Pump fitted in same manner. (Zymfls)					15.00
Outfit B, With Two Leads Hose and Nozzles.	Fig. 905½. 2½-Inch Spray Pump with 2½ feet 1-inch iron suction pipe with brass strainer and two leads of 10 feet each, ½-inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzles. (Zuto)					17.50
Outfit BB.	Fig. 905½. 3-inch Spray Pump fitted in same manner. (Zymfma)					18.50




FIG. 905½.

Special Spray Catalogue, "How to Spray, When to Spray, and What Pumps to Use," issued annually and furnished upon application.



# GOULDS "FRUITALL" SPRAY PUMP.

WITH AGITATOR. ALL WORKING PARTS BRASS.



FIG. 1188

Fig. 1188, "Fruitall" Spray Pump, is made on the same general lines as our now famous "Pomona." It is, however made lighter and of smaller capacity. All working parts, including plunger, gland, valves, valve seats, and strainer, are made of brass. Regularly fitted with double wing paddle agitator, same style as used on "Pomona," and which has proven to be the best type. Pump is held in barrel by anchor at bottom and adjustable clamp at top, fitting over end of stave. Not made for side of barrel. When furnished without agitator, deduct \$0.75 from list. We supply barrel, and mount Pump in the same, for \$1.50 extra net. For Nozzles, Extension, etc., see pages 263 to 266.

FIG. 1188. SIZES, PRICES, ETC.

	PLUNGER.		Discharge.	Cipher.	Price.
	Dia.	Stroke.			
Pump With Agitator and Hose Coupling.	2 in.	4 in.	$\frac{1}{2}$ In. hose	Wumac	\$10.00
Outfit A, With One Lead of	Fig. 1188. Spray Pump with agitator and one lead 10 feet, $\frac{1}{2}$ -inch discharge hose, with Hose and Nozzle. "Seneca" or (Vermorel) Spray Nozzle. (Wumbo)				13.00
Outfit B, With Two Leads of	Fig. 1188. Spray Pump with agitator and two leads 10 feet each, $\frac{1}{2}$ -inch discharge hose, Hose and Nozzles with "Seneca" (or Vermorel) Spray Nozzle. (Wullti)				15.50

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.



# GOULDS "POMONA" SPRAY PUMP.

257

WITH AGITATOR. ALL WORKING  
PARTS OF BRONZE.

Fig. 1100, "Pomona" Spray Pump, has won for itself an enviable reputation. We unhesitatingly offer it as the best orchard Spray Pump for mounting in barrel. It has great power and capacity. Briefly stated other points of superiority are:

No leather packings, consequently no hardened and useless valves. All working parts bronze, including plunger, gland, valves, valve seats, etc. Plunger is outside packed. Valves are easily accessible. Air chamber is very large and of steel, free from imperfections of cast iron. Lever long and powerful, with adjustable stroke three, four or five inches. The mechanical agitator, as shown in cut, is operated by the stroke of the handle, so whenever any liquid is pumped it is thoroughly agitated. Pump is held securely by small anchor located at the bottom of barrel and by adjustable clamp plate at the top. Our new plate will admit insertion or withdrawal from the barrel without removing agitator.

Pump projects but little above top of barrel, and is not caught by branches.

We furnish Pumps either for end or side of barrel, but always for end unless otherwise ordered. Pump, less agitator, deduct \$1.00 from list. We supply barrel and mount Pump in same for \$1.50 extra net.

For nozzles, extensions, etc., see pages 263 to 266.




FIG. 1100. AS MOUNTED ON END OF BARREL.

FIG. 1100 SIZES, PRICES, ETC.

	PLUNGER.		Double Discharge.	Cipher.	Price.
	Diameter.	Stroke.			
Pump with Agitator and Hose Coupling.	2½ in.	Adjustable 3, 4 or 5 in.	½ in. hose and ¾ in. pipe	Wullol	\$15.00
Outfit A, with One Lead Discharge Hose and Nozzle.	Fig. 1100. Spray Pump, with agitator and one lead 10 feet, ½-inch discharge hose with "Seneca" or "Vermorel" Spray Nozzle.			Wullpw	18.00
Outfit B, with two Leads Discharge Hose and Nozzles.	Fig. 1100. Spray Pump, with agitator and two leads 10 feet each, ½-inch discharge hose, with "Seneca" or "Vermorel" Spray Nozzle.			Wullre	20.50

Special Spray Catalogue "How to Spray, When to Spray, and What Pumps to Use," issued annually and furnished upon application.

# 258 GOULDS "SENTINEL" DOUBLE-ACTING SPRAY PUMP.

WITH BRASS-LINED CYLINDER, BRASS VALVES, PLUNGER ROD, ETC.

Fig. 963 shows our "Sentinel" Double-Acting Spray Pump, with brass-lined cylinder, brass valves and seats, piston rod, etc., rendering it unaffected by acids, while the extra large air chamber specially adapts it for spraying tall trees. The suction and discharge valves are all grouped in valve chest and are readily accessible by removing air chamber. This Pump supplies the demand for a powerful Spray Pump of sufficient capacity to supply, if necessary, four leads of discharge hose or two leads, each having two, three or four nozzles. In large orchards or groves, such a Pump is a necessity, and our "Sentinel" Pump will be found to answer every requirement. Pump has double suction and discharge openings. Where ordered without hose

or spray nozzles, we plug one suction and fit the other with brass bushing and half coupling for 1¼-inch hose; also fit two discharges with bushings and half couplings for ½-inch hose. Brass "Y's" or Siamese connections, to give two and four leads of hose, extra, as given on page 265. For agitators, nozzles, extensions and fittings, see pages 262 to 266. Regular air chamber is 5 x 21½ inches. When so ordered, we supply with 6 x 30-inch air chamber, in place of our regular one, at \$3.50 additional list.




FIG. 963

FIG. 963 SIZES, PRICES, ETC.

	Dia. Cyl.	Suction.	Double Discharge.	Cipher.	Price.
Pump with Strainer and Hose Couplings.	3 in.	1¼ in. hose	½ in. hose	Woolen	\$28.50
Outfit A.	Fig. 963. "Sentinel" Spray Pump, with 5 feet 1¼-inch rubber suction hose and two leads, 25 feet each, ½-inch discharge hose with "Seneca" (or other) spray nozzles, couplings and hose bands, complete. (Duslap)				\$45.50
Outfit B.	Fig. 963. "Sentinel" Spray Pump, with 5 feet, 1¼-inch rubber suction hose and four leads, 25 feet each, ½-inch discharge hose with "Seneca" (or other) spray nozzles, couplings and hose bands, complete. (Dunled)				\$60.50

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.



# GOULDS "KEROWATER" SPRAY PUMP.

259

FOR EMULSIFYING AND SPRAYING OIL AND WATER

(Patented March 7, 1899.)

Fig. 1187, "Kerowater" Spray Pump, is designed for mechanically mixing and spraying kerosene and water or crude petroleum and water. The oil and water are so thoroughly mixed and blended that the discharge from the nozzle is a milk-like emulsion. Either 5, 10, 15, 20, or 25 per cent. oil can be used.

Construction is simple. As shown by engraving, a galvanized iron tank, containing oil, goes inside of a barrel, containing water. Inside of oil tank is a small Pump, and outside of oil tank is another Pump, similar in design, but larger. Both Pumps are operated by one common lever, and while one draws oil from the oil tank, the other draws water from the surrounding barrel. They both discharge at a common point, where the water and oil are blended.

Percentage of oil is varied by changing a pin in the head of lever, which shortens or lengthens the stroke of oil Pump. Pump is a positive measuring device and delivers exact percentages of oil. Outfit is readily removed from barrel. Oil tank and Pump can be removed and the water Pump used for general spraying with Bordeaux Mixture, etc.

Water Pump is similar to Fig. 1188, page 256, and at 75 cents extra list we can supply Agitator, as there shown.

Notice that prices below include the barrel and double brass shut-off.




FIG. 1187. WITH TWO LEADS OF HOSE.

FIG. 1187. SIZE, PRICES, ETC.

	WATER PLUNGER.		Discharge.	Cipher.	Price.
	Diameter.	Stroke.			
Double Pump Complete. Mounted in Barrel and Fitted with Brass Double Shut-off and Two Half Hose Coup- plings. (No Hose or Nozzles.)	2 in.	4 in.	$\frac{1}{2}$ in. hose	Zymga	\$21.00
Outfit A. With One Lead Hose and Nozzle.	Fig. 1187, "Kerowater," with one lead 10 feet, $\frac{1}{2}$ -inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzle. Mounted in barrel and supplied with double shut-off (Fig. 1186) and extra half hose coupling.			Zymhe	23.75
Outfit B. With Two Leads Hose and Nozzles.	Fig. 1187, "Kerowater," with two leads 10 feet each, $\frac{1}{2}$ -inch discharge hose with "Seneca" (or Vermorel) Spray Nozzle. Mounted in barrel and supplied with double shut-off (Fig. 1186.)			Zymhat	26.50

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.



# GOULDS LARGE "KEROWATER" SPRAY PUMP.

MOUNTED ON TRIPOD.

(Patented March 7, 1899.)




Fig. 1238, "Kerowater" Spray Pump, is designed upon same principals as Fig. 1187, described on previous page, and is offered for the same service : namely, for mechanically mixing and spraying kerosene or crude petroleum and water. It has, however, larger capacity, and will handle larger percentages of oil. Two plungers are operated by a common lever — the one plunger drawing water, the other kerosene, and both delivering at a common point where the water and oil are thoroughly mixed and blended. The emulsion can be made either 15, 25, 40, 50 or 60 per cent. oil, as desired. This is accomplished by setting the pin in the head of lever in the hole marked with the percentage desired. This shortens or lengthens the stroke of the oil pump.

Fig. 1238 is also as good a Pump for handling Bordeaux, or any other spraying liquid, as could be had. For such use one plunger rod can be disconnected, or suction for both pumps taken from one tank.

It is simple in construction, powerful, and of large capacity.

For nozzles, extension pipes, etc., see pages 263 to 266.

FIG. 1238

FIG. 1238. SIZE, PRICE, ETC.

	PLUNGERS.		Discharge.	Cipher.	Price.
	Diameter.	Stroke.			
Pump Mounted on Tripod with Brass Strainer and Barrel Attachment, also Double Discharge Shut-Off and Hose Couplings.	Both 2 in.	Water Plunger, 4 in. Oil Plunger, Variable	For ½ in. hose	Zymhfd	\$22.50
Outfit A,	Fitted with one 10 foot lead of ¾-inch suction hose, with brass strainer and one short lead of special oil hose with barrel attachment; also double discharge shut-off (Fig. 1186), and one 10 foot lead of ½-inch discharge hose with double "Seneca" nozzle and extra half hose coupling.			Zymud	30.00
Outfit B,	Fitted with one 10 foot lead of ¾-inch suction hose, with brass strainer and one short lead of special oil hose with barrel attachment; also double discharge shut-off (Fig. 1186), and two leads 10 foot each ½-inch discharge hose, each with "Seneca" Nozzle.			Zymox	35.00

Special Spray Catalogue, "How to Spray, When to Spray, and What Pumps to Use," issued annually and furnished upon application.

# GOULDS BARREL SPRAY CARTS.

WITH OR WITHOUT SPRAY PUMP.

261




FIG. 1266



FIG. 1012

Fig. 1012, Barrel Spray Cart, is made in most substantial manner. Truck has iron wheels, with  $2\frac{1}{2}$ -inch tires. Truck may be withdrawn from barrel by simply elevating the handles. Outfit will be found very handy and serviceable about orchard and garden. We list with or without Fig. 905 $\frac{1}{2}$ , Spray Pump, fully described on page 255. Fig. 1266 is same Cart, fitted with our Fig. 1100, "Pomona" Spray Pump, fully described on page 257.

## FIG. 1266. OUTFITS AND PRICES.

Outfit A, With One Lead Hose and Nozzle.	Barrel Cart Complete with Fig. 1100. Spray Pump with agitator and one lead 10 feet, $\frac{1}{2}$ -inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzle.	Cipher. Zirdgo	Price. \$31.50
Outfit B, With Two Leads Hose and Nozzles.	Barrel Cart Complete with Fig. 1100. Spray Pump with agitator, and two leads 10 feet, each, $\frac{1}{2}$ -inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzles.	Zirdhy	34.00

## FIG. 1012. OUTFITS AND PRICES.

Barrel Cart Without Pump.	Running Gear Only or Cart with barrel irons; no pump or barrel.	Cipher. Ebbing	Price. \$15.00
Outfit A, With One Lead Hose and Nozzle.	Barrel Cart Complete with Fig. 905 $\frac{1}{2}$ , $2\frac{1}{2}$ -inch Spray Pump with $2\frac{1}{2}$ feet 1 inch iron suction pipe, with brass strainer, and one lead 10 feet, $\frac{1}{2}$ -inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzle.	Edenic	32.00
Outfit AA.	Barrel Cart Complete with Fig. 905 $\frac{1}{2}$ . 3-Inch Spray Pump fitted in same manner.	Edisa	33.00
Outfit B, With Two Leads Hose and Nozzles.	Barrel Cart Complete with Fig. 905 $\frac{1}{2}$ . $2\frac{1}{2}$ -inch Spray Pump with $2\frac{1}{2}$ feet 1 inch iron suction pipe, with brass strainer, and two leads 10 feet each, $\frac{1}{2}$ -inch discharge hose, with "Seneca" (or Vermorel) Spray Nozzles.	Editor	35.50
Outfit BB.	Barrel Cart Complete with Fig. 905 $\frac{1}{2}$ . 3-inch Spray Pump fitted in same manner.	Edisl	36.50

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished on application.



# GOULDS SPRAY PUMP AGITATORS.

FOR USE WITH OUR STANDARD SPRAY PUMPS.

Fig. 1079, Dash Agitator, consists of a clamp, which fastens onto the head of lever of our "Standard" Spray Pumps (Figs. 905 and 905½), and a rod, running through guide on suction pipe, and connected to a brass plate at bottom, which is operated by movement of the lever.




FIG. 1079

Fig. 1079, Dash Agitator with  
Brass Disc..... (Wullmo) \$1.25

Fig. 1102, Independent Revolving Agitator, illustrated on this page, offers advantages over anything yet devised. Power is transmitted through a small pair of bevel gears to a paddle wheel, comprising four arms set at such an angle that, as the wheel revolves, the liquid is carried both around and upwards in the barrel, thus insuring thorough agitation of the entire contents of the barrel. Used in connection with any of our Spray Pumps where barrel or tank is required.




FIG. 1102

Fig. 1102, Goulds Revolving Agitator, Complete (No Barrel).....(Wullny) \$5.00

Special Spray Catalogue "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.



## "VERMOREL" SPRAY NOZZLE, WITH DEGORGER.

Fig. 55, "Vermorel" Spray Nozzle with Degorger, affords a conical discharge, adapting it for close range spraying of vines, trees, etc. The liquid is forced through an eddy chamber and discharge cap. We construct this Nozzle in two sections, making it possible of being taken apart and cleaned. The one-piece nozzle, when plugged, is worthless. It has a stuffing box, which prevents leakage. It is readily cleaned in operation by pulling or pressing the Degorger against limb of tree, or pressing with thumb.




FIG. 55.

Fig. 55, cut for  $\frac{1}{4}$ -inch pipe.....(Zoide) \$1.00

Fig. 55, including hose connection (Fig. 65 or 67, page 265).....(Rabijx) 1.25

## TWO-DISCHARGE "VERMOREL" NOZZLE, WITH DEGORGERS.

Fig. 1103, Two-Discharge "Vermorel" Nozzle, covers twice the surface sprayed by the single nozzle and with equal thoroughness. It has become very popular.




FIG. 1103

## THREE-DISCHARGE "VERMOREL" NOZZLE, WITH DEGORGERS

Fig. 1104 illustrates our Three-Discharge "Vermorel" Nozzle. The advantage of this Nozzle will readily be appreciated where a large amount of spraying is to be done.




FIG. 1104

Fig. 1104, cut for  $\frac{1}{4}$ -inch pipe.....(Zugded) \$2.75

Fig. 1104, including hose connection (Fig. 5 or 67, page 265).....(Rabilm) 3.00

## GOULDS SPRAY NOZZLES.

## "SENECA" SPRAY NOZZLE.




FIG. 81

Fig. 81, "Seneca" Spray Nozzle, gives a very wide spray, covering a great area. By means of a small adjusting screw the discharge can be nicely graduated, as required, and remains fixed, no matter how often the nozzle may be opened or closed. The nozzle may be cleaned by turning plug across the opening. The discharge is fan shaped. With this class of nozzles, the discharge can be instantly shut off, when not required, thus preventing waste of liquid and loss of labor. Recommend for orchard work.

Fig. 81, cut for  $\frac{1}{4}$ -inch pipe.....(Zugbor) \$1.00  
 Fig. 81, including hose connection (Fig. 65 or 67, page 265).....(Rabiges) 1.25

## "MASSON" SPRAY NOZZLE.

Fig 62, "Masson" Spray Nozzle, we offer where extremely fine spray is desired. It may be briefly described as an all-bronze plug cock, constructed to give a fan-shaped discharge at an angle. By simply turning the small "T" handle, the discharge may be graduated from a mist-like spray (consuming only one gallon of liquid in fifteen minutes), to as coarse a spray as may be desired to use. With this class of nozzles, the discharge can be instantly shut off, when not required, thus preventing waste of liquid and loss of labor. It is cleaned by turning plug across the opening.

Fig. 62, cut for  $\frac{1}{4}$ -inch pipe.....(Zufva) \$1.00  
 Fig. 62, including hose connection (Fig. 65 or 67, page 265).....(Rabihe) 1.25




FIG. 62

## "CALLA" SPRAY NOZZLE.

Fig. 69, "Calla" Spray Nozzle, can change from solid stream to fine or coarse spray by adjustment of slide contained in the cap of nozzle. Unless otherwise ordered, Fig. 69 is arranged for wiring into  $\frac{1}{2}$ -inch hose. Can be supplied cut for  $\frac{1}{4}$ -inch pipe, when so ordered.





FIG. 69

Fig. 69 $\frac{1}{2}$  is nozzle same as Fig. 69, except that it is cut to fit  $\frac{1}{2}$  or  $\frac{3}{4}$ -inch male half hose coupling.

Fig. 69.....(Vigonia) \$0.50  
 Fig. 69 $\frac{1}{2}$ .....(Vigonje) .50

FIG. 69 $\frac{1}{2}$ 

## "CYCLONE" SPRAY NOZZLES

Fig. 51, "Cyclone" Spray Nozzle, gives spray similar in form to that of the "Vermorel." Unlike "Vermorel," the "Cyclone" has no "Degorger." Fig. 52, "Pacific Cyclone" differs from Fig. 51 only in that it has end discharge. Both are cut for  $\frac{1}{4}$ -inch pipe; to fit for hose, requires either Fig. 65 or Fig. 67 (page 265), which cost extra.




FIG. 52

Fig. 51, cut for  $\frac{1}{4}$ -inch pipe.....(Zonard) \$0.50  
 Fig. 52, cut for  $\frac{1}{4}$ -inch pipe.....(Zonate) .50




FIG. 51



# GOULDS SPRAY PUMP FITTINGS.

265




Fig. 65, Coupling, has small end cut  $\frac{1}{4}$ -inch pipe thread to fit our spray nozzles, and large end cut to fit  $\frac{1}{2}$  or  $\frac{3}{4}$ -inch male half-hose coupling.

Fig. 65.....(Zornis) \$0.25

FIG. 65

Fig. 85, Brass Stop Cock, is designed to be used with any of our Spray Pumps, to shut off spray quickly and save loss of liquid. It has shank for attaching  $\frac{1}{2}$ -inch discharge hose, and  $\frac{1}{4}$ -inch male pipe thread to attach spray nozzle or extension.

Fig. 85, as above (Zorned) \$0.65




FIG. 85

Fig. 67, Coupling, has one end cut  $\frac{1}{4}$ -inch pipe thread to fit our Spray Nozzles, and other end is turned to wire into  $\frac{1}{2}$ -inch hose (or  $\frac{3}{8}$ -inch if so ordered).




FIG. 67

Fig. 67.....(Zornod) \$0.25

Fig. 1074, Brass "Y," designed so that two nozzles can be used with one lead of hose, is tapped to fit  $\frac{1}{4}$ -inch pipe at butt, which also adapts it to fit our Fig. 65, Coupling, for hose or iron pipe. Any of our various nozzles can be screwed on the branches.



FIG. 1074

Fig. 1074, Brass "Y" .....(Elysign) \$0.50



FIG. 49

Fig. 49, Brass "Y," is cut  $\frac{3}{4}$ -inch male thread on inlet (1-inch if so ordered), and  $\frac{1}{2}$  or  $\frac{3}{4}$ -inch male thread on lateral discharges. Fig. 49 $\frac{1}{2}$ , Brass "Y," is the same in all respects as Fig. 49, described above, except it has female thread on inlet. Lateral discharge same as noted. While it may be employed with any of our Pumps, it is specially designed to be used with Fig. 963, "Sentinel" Spray Pump.

Fig. 49, as above.....(Zonava) \$0.80  
Fig. 49 $\frac{1}{2}$ , as above.....(Zornad) \$0.80



FIG. 49 $\frac{1}{2}$

Fig. 70, Brass Suction Pipe Strainer, is fitted for hose as follows:

Price,  $\frac{3}{4}$  in.....(Rabigan) \$0.50  
Price, 1 in.....(Zonawl) \$0.50  
Price,  $1\frac{1}{4}$  in.....(Zorlun) \$1.00



FIG. 70

Fig. 71, Brass Suction Pipe Strainer, is fitted for wrought iron pipe as follows:

Price, 1 in.....(Zorlyd) \$0.50



FIG. 71




FIG. 1186

Fig. 1186, Brass "Y" Discharge and Shut-Off, is to be used with any of our larger Spray Pumps, where one or two leads of hose are to be employed. Either, or both of the discharges may be opened or closed at will, as shown in the illustration. Butt is threaded to fit pump, lateral discharges threaded to fit  $\frac{1}{2}$ -inch or  $\frac{3}{4}$ -inch hose coupling.

Price.....(Zymfyo) \$2.00

Fig. 1092, Brass Shut-Off Discharge Connection, can be used with any of our Barrel Spray Pumps to control the discharge at the pump. One end is cut to fit the pump, the other threaded for  $\frac{1}{2}$  or  $\frac{3}{4}$ -inch hose coupling.

Price.....(Zymfzm) \$1.50



FIG. 1092

# SPRAY PUMP EXTENSIONS AND ATTACHMENTS.

FOR ORCHARD AND GARDEN USE.




FIG. 1109

Fig. 1109, Extension, consists of 8 feet of  $\frac{1}{4}$ -inch iron or brass pipe, with brass stop cock fitted for  $\frac{1}{2}$ -inch hose. With this arrangement the taller trees may be sprayed and the work among the branches facilitated. Extension is threaded to fit any of our nozzles and may be used in connection with any of our Spray Pumps.

Fig. 1109, Iron pipe, complete with cock.....(Zukvd) \$1.25  
 Fig. 1109, Brass pipe, complete with cock.....(Zukvs) 4.00



FIG. 48

Fig. 48, Bamboo Extension, has 8 feet of iron or brass pipe inside of bamboo, making an easy and pleasant extension to handle. Has stop cock fitted for  $\frac{1}{2}$  or  $\frac{3}{4}$ -inch hose. Other end cut  $\frac{1}{4}$ -inch pipe thread to fit our spray nozzles.

Fig. 48, complete as above, with iron pipe inside.....(Zonals) \$3.00  
 Fig. 48, complete as above, with brass pipe inside.....(Zirdic) 6.00




FIG. 1085

Fig. 1085 is Fig. 1109, Extension Pipe, described above, with Fig. 81, "Seneca" Nozzle.

Fig. 1085, complete with iron extension pipe.....(Zuin) \$2.50  
 Fig. 1085, complete with brass extension pipe.....(Zujk) 5.00




FIG. 1084

Fig. 1084 is Fig. 1109, Extension Pipe, described above, with Brass "Y" and two Fig. 81, "Seneca," Nozzles.

Fig. 1084, complete with iron extension pipe.....(Zuko) \$4.00  
 Fig. 1084, complete with brass extension pipe.....(Zukug) 6.50



FIG. 1131

Fig. 1131, Two-Row Attachment, for spraying potatoes, etc., with a knapsack Pump, has two "Vermorel" nozzles. Total length is 30 inches.

Fig. 1131, as per cut.....(Whelqt) \$3.50



FIG. 1132

The above cut represents an attachment for spraying four rows of potatoes with any of our larger Spray Pumps. It has four "Seneca" Nozzles ("Vermorel" nozzles supplied at same price if so ordered) and connections for hose. Total length nine feet.

Fig. 1132, as per cut.....(Whelro) \$7.00

Special Spray Catalogue, "How to Spray, When to Spray and What Pumps to Use," issued annually and furnished upon application.



Hand, Garden and Fire Engines have a general use in gardens and about lawns for sprinkling. The larger machines have been successfully used for spraying shade trees where smaller pumps are useless. With available water supply, Hand Fire Engines will answer a good purpose for emergency.

This line will be found between pages 268 and 276.



## GOULDS GARDEN OR FIRE ENGINE.




FIG. 304

Fig. 304 represents our Garden Engine, with either wood or iron handles, as ordered. The Pump is placed inside of box, of dimensions suitably large to hold about a barrel of water, and, being on wheels, is easily moved to any place where it is desirable to use it. Pump has brass-cased rod, revolving bearer top and extra long handle, which gives a powerful leverage.

Below we give prices on this Engine, complete as per cut, with three feet of one-inch discharge hose and a discharge pipe.

We can also line box with sheet lead, at extra net charge of \$5.00, or with galvanized iron at an extra net charge of \$3.00, rendering it unaffected by swelling or shrinking of the wood.

FIG. 304. SIZE, PRICES, ETC.

	Dia. Pump Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Cipher.	Price.
With Iron Handles...	3 in.	6 in.	.18 gal.	1½ in.	1 in. hose	Driven	\$26.00
With Wood Handles..	3 "	6 "	.18 "	1½ "	1 "	Drolley	25.00

## GOULDS GARDEN OR FIRE ENGINE, SIDE SUCTION.

Fig. 309 is very similar to Fig. 304, except that Pump is arranged to take suction either from the tank or through suction hose, which can be attached at side of tank, as shown in cut. When suction hose is attached, the cap, removed from outer suction opening, is placed over the suction opening inside the tank. Fitted in this manner, Engine can be moved to any convenient point for draughting water.

Below we give prices on Engine with 3 feet of 1-inch discharge hose and brass discharge pipe. No suction hose is included, but can furnish as ordered at market rates.

We can also line this box with sheet lead at an extra net charge of \$5.00, or with galvanized iron at an extra net charge of \$3.00, rendering it unaffected by swelling or shrinking of the wood.

Longer lengths of hose furnished, if ordered, at extra price. See pages 304 to 307 for lists of Hose, Couplings, etc.

FIG. 309. SIZE, PRICES, ETC.

	Dia. Pump Cyl.	Stroke.	Capacity per Stroke.	Suction.	Discharge.	Cipher.	Price.
With Iron Handles ...	3 in.	6 in.	.18 gal.	1½ in. hose	1 in. hose	Drown	\$29.00
With Wood Handles..	3 "	6 "	.18 "	1½ "	1 "	Drug	28.00




FIG. 309



# GOULDS DOUBLE-ACTING GARDEN OR FIRE ENGINE. 269

*BRASS-LINED CYLINDER, MOUNTED ON WROUGHT-IRON BARROW.*

Fig 630 shows a portable Double-Acting Lift and Force Pump. The cylinder is iron, brass-lined. Four to six men can operate the Engine at one time. It will throw a fine stream through a half-inch nozzle from 80 to 100 feet.

One bolt and nut holds in place a door at either end of base, which can be opened to get at the rubber ball valves.

Below we give price of Engine complete as per cut, with 6 feet 2-inch spiral suction hose and 12 feet 1½-inch discharge hose, brass hose pipe and spreader, hose couplings, suction basket, etc.

Longer lengths of hose can be furnished, if desired, at extra price. See pages 304 to 307 for lists of Hose, Couplings, etc.




FIG. 630

FIG. 630. SIZE, PRICE, ETC.

Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	Cipher.	Brass-Lined With Hose, Etc., as Above.
5 in.	8 in.	1.36 gals.	2 in. hose	1½ in. hose	Racer	\$62.00

# GOULDS DOUBLE-ACTING GARDEN OR FIRE ENGINE.

*BRASS-LINED CYLINDER AND WROUGHT-IRON EXTENSION LEVERS.*

This is the same Engine as described above, except that this is provided with wrought-iron, adjustable arms with wood brakes, on which six to eight men can work, and is consequently capable of performing greater service. Below we give price of Engine complete as per cut, with 6 feet 2-inch spiral suction hose and 12 feet 1½-inch discharge hose, brass hose pipe and spreader, hose couplings, suction baskets, etc.

Longer lengths of hose can be furnished, if desired, at extra price. See pages 304 to 307 for lists of Hose, Couplings, etc.




FIG. 653

FIG. 653. SIZE, PRICE, ETC.

Diameter Cylinder.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	Cipher.	Brass-Lined With Hose, Etc., as Above.
5 in.	8 in.	1.36 gals.	2 in. hose	1½ in. hose	Ravelus	\$64.00

# GOULDS DOUBLE-ACTING GARDEN OR FIRE ENGINE.

WITH WROUGHT-IRON BARROW AND REEL FOR HOSE.




FIG. 1008 $\frac{1}{2}$

Fig. 1008 $\frac{1}{2}$  represents our Double-Acting Garden or Fire Engine, on wrought-iron barrow, with wheels and hose reel. It has brass-lined cylinder and rubber ball valves. Four to six men can operate the Engine to good effect. Hose reel will carry 50 to 75 feet of 1 $\frac{1}{2}$ -inch three-ply rubber hose. We list Engine complete, as per cut, with 6 feet 2-inch spiral suction hose, and 12 feet 1 $\frac{1}{2}$ -inch discharge hose; brass hose pipe, sprinkler, hose coupling and suction basket. Larger lengths of hose can be furnished, if desired, at extra price. See pages 304 to 307 for hose couplings, etc.

FIG. 1008 $\frac{1}{2}$ . SIZES, PRICES, ETC.

Diameter Cylinder	Stroke	Capacity per Rev.	Suction.	Discharge.	Cipher.	Brass-Lined, with Hose, Etc., as Above.
5 in.	8 in.	1.36 gal.	2 in. hose	1 $\frac{1}{2}$ in. hose	Baldrick	\$75.00

## GOULDS UNION HAND FIRE ENGINE.

Fig. 766 represents our Fig. 284, Two-Cylinder Force Pump, mounted upon substantial truck. The tank is made of the best galvanized wrought-iron and sits on a very heavy and strongly bolted wood frame. It can be operated by from two to six men, and will draw from the tank or through suction hose from any other supply. When suction hose is attached, the cap, removed from suction opening outside of the tank, is placed over suction opening inside the tank. The knees are so constructed that they will fold up while being moved, and when in place hold the Engine firmly on the ground when in operation. Below we give price on Engine complete. No suction or discharge hose is included in these prices, but we can furnish same at lowest market rates.

FIG. 766. SIZES, PRICES, ETC.

Dia. Cyl.	Stroke	Capacity per Rev.	Suction.	Discharge.	BRASS-LINED CYLINDER.		BRASS CYLINDER.	
					Cipher.	Price.	Cipher.	Price.
4 in.	6 in.	.65 gal.	2 $\frac{1}{2}$ in. hose	1 $\frac{1}{2}$ in. hose	Vixane	\$110.00	Vixind	\$125.00

See pages 304 to 307 for lists of Hose, Couplings, Discharge Pipes, Strainers, etc.




FIG. 766



# GOULDS "CHALLENGE" DOUBLE-ACTING FORCE PUMP. 271

ON PLATFORM WITH WHEELS.

Fig. 774 represents "Challenge" Double-Acting Force Pump, described on page 142, mounted on platform with wheels for portable use.

The platform brake answers a two-fold purpose, being large enough to admit of the operator standing upon it while working the Pump, and at the same time holding it firm and steady.

Suction and discharge always fitted for hose, unless otherwise ordered.

FIG. 774. SIZES, PRICES, ETC.

No.	Dia. Cyl.	Stroke.	Capacity per Rev.	Suction.	Discharge.	BRASS-LINED.		BRASS.	
						Cipher.	Price.	Cipher.	Price.
2	2 1/2 in.	4 1/2 in.	.19 gal.	1 1/4 in. hose	1 in. hose	Vitrify	\$40.00	Vocalmo	\$87.50
4	3 " "	4 1/2 " "	.28 " "	1 1/4 " "	1 " "	Vitriol	42.50	Vocalny	90.00
8	4 " "	4 1/2 " "	.49 " "	1 1/2 " "	1 1/4 " "	Vituline	45.00	Vocams	105.00




FIG. 774

# GOULDS "BALTIC" HAND FIRE ENGINE.

WITH HEAVY GALVANIZED-IRON TANK AND MALLEABLE-IRON LEVER.

Fig. 1171 shows our "Baltic" Hand Fire Engine equipped ready for use. It is a powerful fire extinguisher, capable of throwing a stream sixty feet horizontally. It has large Air Chamber, Brass Valves and Valve seats. Polished brass cylinder and top. Tank will hold about 42 gallons. It is very easy in action. We supply with six feet of discharge hose and brass hose pipe. Extra lengths of hose and hose couplings furnished as ordered at additional cost.

FIG. 1171. SIZE, PRICE, ETC.

Dia. Cyl.	Stroke.	Capacity per Min.	Discharge.	Approx. Weight.	Cipher.	Brass Cylinder.
3 1/2 in.	8 in.	14 gals.	1 in. hose	185 lbs.	Steak	\$50.00




FIG. 1171

# GOULDS TWO-CYLINDER FORCE PUMP.

WITH FOLDING BRAKES, ON PLATFORM WITH WHEELS.




FIG. 285

Fig. 285 represents our portable Two-Cylinder Force Pump, arranged with folding brakes large enough to admit of six men working upon them. It is a very powerful Pump, and, in case of fire, will be found invaluable.

Pump is made with brass-cased piston rods, brass plungers, valves and stuffing boxes.

The valve at the bottom of the Cylinder is double and improved in its construction, and can be readily tripped or opened by pressing down the lever until it strikes the top of the air chamber.

The Pump is simple in its construction, not liable to get out of order, and by the directness of its action and consequent freedom from friction is a most efficient and powerful Pump.

We make them with Iron Cylinders or with Brass Cylinders, with all the *working portions* of the Pump of the same material.

For Hose, Hose Couplings, Nozzles, etc., see pages 304 to 307.

FIG. 285. SIZES, PRICES, ETC.

No.	Diameter Cylinder.	Stroke.	Capacity per Rev.	Suction.	Discharge.	IRON CYLINDERS.		BRASS-LINED CYLS.		BRASS CYLINDERS.	
						Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
2	2½ in.	6 in.	.26 gal.	2 in. hose.	1¼ in. hose.	Defy	\$68.00	Raptwot	\$75.00	Delaine	\$88.00
4	3 " "	6 "	.37 "	2 " "	1¼ "	Visipl	70.00	Rapwua	77.00	Visit	90.00
6	3½ "	6 "	.50 "	2½ "	1¼ "	Deify	77.00	Rapwyl	87.00	Delf	100.00
8	4 " "	6 "	.65 "	2½ "	1½ "	Deign	85.00	Rapxon	95.00	Dell	115.00
10	4½ "	6 "	.83 "	3 " "	2 " "	Deist	95.00	Rapxul	110.00	Delve	130.00
12	5 " "	6 "	1.02 "	4 " "	3 " "	Daygo	105.00	Rawaya	120.00	Daygul	145.00
16	6 " "	8 "	1.96 "	4 " "	3 " "	Deity	135.00	Raweb	155.00	Demi	185.00



# GOULDS SWAN-NECK VILLAGE FIRE ENGINE.

273

*BRASS CYLINDERS AND FOLDING LEVERS.*




Fig. 1182 is one of our Swan-Neck Portable Fire Engines, arranged to be drawn by hand. It can be turned in its own length. Everything about the Engine is complete and first-class. The Double Brass Cylinder Force Pump used is very powerful. Should any change in the levers or truck be desired to suit any particular locality, we shall always be glad to arrange them to suit the wishes of our correspondents, at lowest possible cost. We build in two sizes. Price does not include hose or fittings. See pages 304 to 307 for these.

Brass "Siamese" double-hose connection, fitting discharge for two leads of hose, furnished when ordered, at \$5.50 extra list.

*FIG. 1182. SIZES, PRICES, ETC.*

No.	Dia. Cyl.	Stroke.	Capacity per Minute.	Suction.	Discharge.	Cipher.	Brass Cylinders.
10	4½ in.	6 in.	34 gals.	2½ in.	1½ in.	Sulky	\$170.00
16	6 "	8 "	78 "	3 "	2 "	Sun	225.00

# GOULDS SWAN-NECK FIRE ENGINE.

WITH HEAVY GALVANIZED TANK. FOLDING LEVERS.




FIG. 1183

Fig. 1183 has powerful Double-Cylinder Brass Force Pump, mounted in heavy galvanized tank or reservoir, holding about 70 gallons. Tank can be detached from truck and readily carried, by use of handles, as shown in cut, to any desired locality.

Engine is so built that, by the interchange of a single cap, suction can be taken either from the tank or through suction hose, attached to the outside of the tank at the end. The Pump proper is similar to one used in Fig. 1182 outfit, on previous page, except that levers are specially made so as to fold lengthwise of the Engine. Price does not include hose or couplings, which can be furnished as required, of any particular quality or lengths, at the lowest market rates. See pages 304 to 307.

FIG. 1183. SIZE, PRICE, ETC.

No.	Dia. Cyls.	Stroke.	Capacity per Min.	Suction.	Discharge.	Cipher.	Brass Cylinders.
10	4½ in.	6 in.	34 gals.	2½ in.	1½ in.	Tickwo	\$250.00



# GOULDS SWAN-NECK VILLAGE FIRE ENGINE.

275

WITH GUN-METAL CYLINDERS.




FIG. 465. SIZE 4½" X 6"

Fig. 465 represents our Swan-Neck Village Fire Engine with two gun-metal cylinders and arranged to be drawn by hand. This Engine is self-contained, and the swan neck allows it to be turned in its own length. The Pump is securely fastened to an iron bed-plate, doing away with the expense of a reservoir or box. Engine has strong wooden wheels with wrought-iron tires, hard-wood pole, fifth wheel, etc.

Pump has brakes or levers, which are reversible and folding. The valves are of an approved pattern, and everything is as complete as first-class workmanship and the best of materials can make it.

From eight to twelve men can work on the brakes and with this force an effective fire stream can be thrown from 100 to 125 feet horizontally, or 60 to 90 feet vertically.

FIG 465. SIZES, PRICES, ETC.

No.	Diameter Cylinders.	Stroke.	Capacity per Revolution.	Suction.	Discharge.	GUN-METAL CYLINDERS.	
						Cipher.	Price.
10	4½ in.	6 in.	.83 gal.	2½ in. hose	1½ in. hose	Glassell	\$200.00
16	6 "	8 "	1.96 "	3 "	2 "	Gleam	280.00

Prices do not include any hose. For list on Hose, Couplings, etc., see pages 304 to 307. Any length of drag rope can be furnished at extra price.

# GOULDS VILLAGE FIRE ENGINE.

WITH FOLDING BRAKES FOR TEN MEN TO OPERATE.




FIG. 539

Fig. 539 represents our Village Fire Engine with folding brakes for ten men. This engine is very strong and durable and specially adapted for use in small towns where the streets are poorly paved and Engine meets with the roughest kind of service. Engine has brass cylinders, brass pistons, iron-tired wheels with metal hubs, heavy iron axles and folding levers or brakes, with automatic locks. It will throw one  $\frac{5}{8}$ -inch stream about 110 feet. It is equipped with one nickel-plated play pipe with three nozzles, one pair suction hose couplings and suction strainer, rope reel, drag rope and all necessary wrenches.

Price does not include suction hose, which we can supply, as ordered, at market rates. See pages 304 to 307.

FIG. 539. SIZE, PRICE, ETC.

Fig. 539,  $4\frac{1}{2}$ -inch x 7 inch Cylinders, fitted for  $2\frac{1}{2}$ -inch suction hose and  $1\frac{1}{2}$  or 2-inch discharge hose. Complete as above.....(Laden) \$375.00



# GOULDS FACTORY HOSE CART.

277

Fig. 530 represents our most popular style of cheap Hose Cart. It is constructed of the best materials and is designed especially for village fire departments, lumber yards, factories, etc.




FIG. 530

## FIG. 530. SIZES, PRICES, ETC

No. 1, 4 ft. wheels, carrying capacity about 250 ft.			
	2 1/2 in.	rubber hose.	
or 350 "	2 "	" "	
or 500 "	2 1/2 "	linen "	
or 300 "	2 1/2 "	cotton rubber-lined.	
		(Blushe)	\$40.00
No. 2, 5 ft. wheels, carrying capacity about 700 ft.			
	2 in.	cotton hose.	
or 500 "	2 1/2 "	" "	
or 450 "	2 1/2 "	rubber "	
		(Blushf)	\$70.00

# GOULDS BALANCED HOSE CART.

Fig. 542, Hose Cart, is so balanced that there is no weight on the tongue, making it easily handled with a heavy weight of wet hose. It is furnished with handles on end of reel spokes for reeling. With each cart goes drag rope, reel, axe, crow-bar and tool box.

## FIG. 542. SIZE, PRICE, ETC.

No. 3, 5 ft. wheels, carrying capacity about 800 ft.			
	1 1/2 in.	{ Cotton rubber-	
or 700 "	2 "	{ lined	
or 500 "	2 1/2 "	{ mill hose.	
or 600 "	1 1/2 "	{ rubber hose.	
or 450 "	2 "	{ " "	
or 400 "	2 1/2 "	{ " "	
		(Waragl)	\$100.00





FIG. 542




For Hydrants,  
etc., see Pages  
279 to 284.






SECTIONAL VIEW OF "CRESCENT" VALVE.

See Figs. 860, 861, 811, 812, 1040, 813, 1240.



SECTIONAL VIEW OF "STAR" VALVE.

See Figs. 646 and 647.



SECTIONAL VIEW OF "SUN" AND "NO-SHOCK" VALVE.

See Figs. 1174, 1175 and 1116.

All our Hydrants and Street Washers are made with two pipes—wet and dry. All are anti-freezing and all are tested under pressure. "Crescent" Hydrants and Street Washers have "wet" and "dry" pipes side by side. "Wet" pipe conveys water to spout, while "dry" pipe simply contains the rod which operates plunger.

The illustration is so plain and construction so simple as to hardly need explanation. The rod in this hydrant is actuated by brass screw and handle above and raising plunger the smallest fraction of an inch closes waste before any water can enter discharge pipe. With the valve open, we have a full and unobstructed flow of water through Hydrant, which can well be compared to a straight-way valve or round-way cock. Closing the valve empties all water from wet pipe through drip-hole. Plunger and valve case and couplings are Brass.

To repair "Crescent" Hydrant or Washer, remove top cap or plate and withdraw plunger valve.

"Star" Hydrants and Street Washers have an outer or "dry pipe," inside of which is the "wet pipe," through which water passes to spout, which is screwed into elbow at its top and moves with it. Plunger is attached to lower end of "wet pipe." When wheel handle at top is turned, "wet pipe" is raised, lifting plunger from seat, instantly closing drip-hole, and allowing water an unobstructed passage through inner pipe and spout. Plunger can be withdrawn without taking up Hydrant. Valve case and plunger are brass.

"Sun" and "No-Shock" Hydrants are in valve construction and arrangement of "wet" and "dry" pipes similar to the "Star," with the addition of stop valve, which automatically shuts off the water if plunger is withdrawn for repacking.

# "CRESCENT" HYDRANTS AND STREET WASHERS.

WITH STRAIGHT-WAY VALVE.

The cuts show our new "Crescent" Hydrants and Street Washers with all necessary parts brass, and two pipes—one dry, through which the valve can be withdrawn for repacking, the other forming a passage for the water to the spout.

*They are perfectly anti-freezing. The valve closes against the pressure; the waste is ample and reliable, and no water whatever can enter the dry pipe.*

In both Hydrant and Street Washer a solid brass screw at the top actuates the plunger valve below. For details of valve construction see sectional view on page 279.

Fig. 860, Hydrant, has stock made in two halves bolted together. Inlet has thread for  $\frac{3}{4}$ -inch iron pipe and soldering tube for lead pipe. Spout is provided with brass bushing, cut to receive  $\frac{3}{4}$ -inch hose coupling.

Fig. 861, Street Washer, has same valve, pipes, etc., as are used with Hydrant. Inlet has thread for  $\frac{3}{4}$ -inch iron pipe and soldering tube for lead pipe. Discharge fitted to receive  $\frac{3}{4}$ -inch half hose coupling. Key is furnished with each Street Washer.

Figs. 811 and 812, Hydrant and Washer, are similar in design and construction to Figs. 860 and 861, just described, but carry larger connecting pipes, heavier valve cases and valves, stocks or sides, and are regularly fitted with bottom inlet for 1-inch iron pipe.




FIG. 860,  
 $\frac{3}{4}$ "



FIG. 861,  
 $\frac{3}{4}$ "




FIG. 812,  
1"




FIG. 811,  
1"

## SIZES, PRICES, ETC.

Length to Set in Ground.	Fig. 860. $\frac{3}{4}$ in.		Fig. 861. $\frac{3}{4}$ in.		Fig. 811. 1 in.		Fig. 812. 1 in.	
	Inlet Fitted for $\frac{3}{4}$ -in. Iron and Lead Pipe. Spout Fitted for $\frac{3}{4}$ -in. Hose.		Inlet Fitted for $\frac{3}{4}$ -in. Iron and Lead Pipe. Discharge Fitted for $\frac{3}{4}$ -in. Hose.		Inlet Fitted for 1-in. Iron Pipe. Spout Fitted for 1-in. Hose.		Inlet Fitted for 1-in. Iron Pipe. Discharge Fitted for 1-in. Hose.	
	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
18 in.	Wagein	\$9.80	Wailme	\$6.60	Wagtail	\$11.65	Waitin	\$7.70
24 "	Wagels	10.10	Wainc	6.85	Wahaby	11.95	Waitres	8.00
30 "	Clonged	10.35	Coldiv	7.10	Crafter	12.25	Curbed	8.30
36 "	Wagerd	10.60	Wainag	7.35	Waifer	12.55	Waiv	8.60
42 "	Clubbing	10.80	Colder	7.55	Crustic	12.85	Curiosity	8.90
48 "	Wagest	11.00	Wairn	7.75	Waift	13.15	Waived	9.20
54 "	Wagging	11.25	Craft	8.00	Crustier	13.45	Waiving	9.50
60 "	Waggis	11.50	Waist	8.25	Wailed	13.75	Waivjs	9.80
72 "	Waggle	12.10	Waister	8.85	Wailfa	14.35	Wakeb	10.40

Extra Street Washer Keys, \$0.20.



# GOULDS CRESCENT HYDRANTS AND STREET WASHERS. 281

WITH STRAIGHT-WAY VALVE.




FIG. 1040,  $\frac{3}{4}$ "  
FIG. 1240,  $\frac{3}{4}$ " 279.

Fig. 1040 represents our "Crescent" Hydrant, arranged with lever instead of screw handle. In all other respects it is the same as Fig. 860, shown on page 280, being perfectly anti-freezing. The flanged top permits the withdrawal of plunger through dry pipe whenever it needs repacking. Inlet has thread for  $\frac{3}{4}$ -inch iron pipe and soldering tube for lead pipe. Spout has brass bushing to receive  $\frac{3}{4}$ -inch hose coupling.

Fig. 1240, Street Washer, is our Fig. 861, described on previous page, with the addition of a swivel coupling, which will permit hose to be moved in any position and avoids all possibility of kinking, which is the cause of leaks. Key goes with each Street Washer. Extra keys 20c.

Fig. 813, Hydrant, is same as Fig. 811, page 280, stripped of stock or sides, making it somewhat lighter and cheaper. Inlet is fitted for 1-inch iron pipe. Spout 1-inch hose.

Fig. 1123, Hydrant, is same as Fig. 860, page 280, stripped of stock or sides. Inlet is fitted for  $\frac{3}{4}$ -inch iron or lead pipe. Spout for  $\frac{3}{4}$ -inch hose.

Sectional view of valve, used in above, is shown on page




FIG. 813, 1"  
FIG. 1123,  $\frac{3}{4}$ "

SIZES, PRICES, ETC.

Length to Set in Ground.	Length Over All of Hydrants (Figs. 1040, 813 and 1123.)	Fig. 1040, $\frac{3}{4}$ Inch.		Fig. 813, 1 Inch.		Fig. 1123, $\frac{3}{4}$ Inch.		Fig. 1240, $\frac{3}{4}$ Inch.	
		Inlet Fitted for $\frac{3}{4}$ -Inch Iron and Lead Pipe. Spout Fitted for $\frac{3}{4}$ -Inch Hose.		Inlet Fitted 1-Inch Iron Pipe. Spout Fitted 1-Inch Hose.		Inlet Fitted for $\frac{3}{4}$ -Inch Iron and Lead Pipe. Spout Fitted for $\frac{3}{4}$ -Inch Hose.		Inlet Fitted $\frac{3}{4}$ -Inch Iron and Lead Pipe, Discharge Fitted for $\frac{3}{4}$ -Inch Hose.	
		Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
18 in.	42 in.	Drebeha	\$10.75	Curiole	\$8.65	Loines	\$7.65	Pokjob	\$7.85
24 "	48 "	Drebeij	11.10	Curul	8.95	Loifu	7.95	Pokjul	8.10
30 "	54 "	Drebeju	11.40	Curvet	9.25	Loingx	8.25	Pollsac	8.35
36 "	60 "	Drebfal	11.65	Dagger	9.55	Loipa	8.55	Pollset	8.60
42 "	66 "	Drebfed	11.85	Damocles	9.85	Loipate	8.85	Polma	8.80
48 "	72 "	Drebfig	12.10	Danced	10.15	Loipid	9.15	Polmebo	9.00
54 "	78 "	Drebfos	12.35	Dashing	10.45	Loipow	9.45	Polmeck	9.25
60 "	84 "	Drebfub	12.65	Daystar	10.75	Loipum	9.75	Polmedu	9.50
72 "	96 "	Drebgoo	13.30	Decayed	11.35	Lumpis	10.35	Polmefo	10.10

## GOULDS "STAR" HYDRANT AND STREET WASHER.

WITH COMPRESSION VALVES AND MOVEABLE WATERWAYS.

FIG. 646,  
¾ AND 1"

These goods have been on the market now for several years, and are so familiar to those who have used them, that any description of their superior merits is unnecessary. There is not much opportunity to display constructive taste in a Street Washer, but it is universally conceded that our Hydrant is handsome in design and finish, and is quite an addition to the appearance of a yard or lawn. We have allowed no opportunity to pass to improve both our Hydrants and Washers; and while in general the principle of their mechanism is unchanged, many minor changes and improvements have been made. Sectional view, page 279, shows valve construction and arrangement of wet and dry pipes.

*They are perfectly anti-freezing. They are almost instantly opened or closed by means of the double-threaded brass screw, actuating the valve below. They can be repaired from the top without digging up.*

They have a brass swivel or coupling nut (not an iron one), and the brass tube for service pipe connection is ground to a joint with the valve case elbow. They readily sell for more money than any other, because no other bear any comparison with them. It would always be well to have a short piece of lead pipe between the coupling and service pipe, as its flexibility will prevent a fracture of the pipe when the frost heaves the ground, and in clay soil to make some provision for drainage of waste water, if it be nothing more than a small body of gravel or sand between the bottom attachment and clay. We measure from ground line to centre of service pipe inlet. Every Hydrant and Washer is thoroughly tested before leaving our factory.

Our ¾-inch "Star" Hydrants and Washers have inlet fitted for both iron and lead pipe—¾-inch. Spout fitted for ¾-inch hose coupling. Our 1-inch hydrant and washers have 1-inch inlet and outlet. An iron *turnkey* goes with each street washer. Extra keys, 20 cents.

FIG. 647,  
¾ AND 1"

FIG. 646 AND 647. SIZES, PRICES, ETC.

Length to set in the Ground.	Fig. 646. ¾ in.		Fig. 647. ¾ in.		Fig. 646. 1 Inch.		Fig. 647. 1-Inch.	
	Inlet Fitted for ¾-in. Iron and Lead Pipe. Spout for ¾-in. Hose.		Inlet Fitted for ¾-in. Iron and Lead Pipe. Spout for ¾-in. Hose.		Inlet Fitted for 1-In. Iron and Lead Pipe. Spout for 1-In. Hose.		Inlet Fitted for 1-Inch Iron and Lead Pipe. Spout for 1-Inch Hose.	
	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
18 in.	Veneild	\$9.00	Vengerl	\$7.50	Ventana	\$11.50	Veracit	\$9 00
24 "	Venejan	9.00	Venial	7.50	Venter	11.50	Veranda	9.00
30 "	Veneom	10.00	Venison	8.50	Ventilat	12.50	Verb	10.00
36 "	Venene	10.00	Venoma	8.50	Ventiles	12.50	Verbal	10.00
42 "	Venerat	11.00	Venous	9.50	Venture	13.50	Verbami	11.00
48 "	Venerel	11.00	Ventabc	9.50	Venue	13.50	Verbatu	11.00
54 "	Veney	12.00	Ventage	10.50	Venulos	14.50	Verbiag	12.00
60 "	Venge	12.00	Ventail	10.50	Venus	14.50	Verbose	12.00
72 "	Vocal	13.00	Vocaljx	11.50	Vocalic	15.50	Vocalks	13.00



# "SUN" AND "NO SHOCK" HYDRANTS AND WASHER. 283

WITH WROUGHT STOCK AND ADJUSTABLE BASE.

Fig. 1174, "Sun" Hydrant, possesses, we believe, all the best features contributing to a reliable anti-freezing two-pipe hydrant. It is also of handsome appearance. The stock and outer casing is formed of large wrought pipe, inside of which is the smaller or "wet pipe," conveying the water to spout. Base is adjustable. Plunger is actuated by wheel handle and brass screw. Plunger can be withdrawn *through the hydrant and automatic stop valve prevents water flowing when plunger is withdrawn.* Sectional view of plunger, valve, and waterways is shown on page 279.

Fig. 1175, "Sun" Street Washer, has same arrangements of pipes and valves, including the very desirable *automatic stop valve*. Box and cover are malleable. Key goes with each Street Washer. Extra keys, 20 cents list.

Fig. 1116, "No Shock" Self-Closing Hydrant, is in all respects identical with Fig. 1174, except that strong brass spring in the top of hydrant seats the plunger (*against the pressure*), unless it is held open by the lever or latch. Individuals and water companies appreciate the self-closing feature as waste of water is prevented.

See sectional view page 279.

Hydrants and Street Washer, described above, have inlet supplied with brass swivel nut and brass tube cut to receive  $\frac{3}{4}$ -inch iron pipe coupling and also suitable for wiping into lead pipe. The use of a short piece of lead pipe gives flexibility when frost heaves.

Spout or discharge is fitted for  $\frac{3}{4}$ -inch hose coupling.



FIG. 1174,  $\frac{3}{4}$ " FIG. 1175,  $\frac{3}{4}$ "



FIG. 1116,  $\frac{3}{4}$ "

FIGS. 1174, 1175 AND 1116. SIZES, PRICES, ETC.

		Fig. 1174. $\frac{3}{4}$ -in. Hydrant.		Fig. 1175. $\frac{3}{4}$ -in. Washer.		Fig. 1116. $\frac{3}{4}$ -in. Hydrant.	
Length to Set in Ground.	Length Over All of Hydrants.	Inlet Fitted for $\frac{3}{4}$ -in. Iron and Lead Pipe. Spout Fitted $\frac{3}{4}$ -in. Hose.		Inlet Fitted for $\frac{3}{4}$ -in. Iron and Lead Pipe. Discharge Fitted $\frac{3}{4}$ -in. Hose.		Inlet Fitted for $\frac{3}{4}$ -in. Iron and Lead Pipe. Spout Fitted $\frac{3}{4}$ -in. Hose.	
		Cipher.	Price.	Cipher.	Price.	Cipher.	Price.
18 in.	45 in.	Rudfeck	\$9.00	Rudfofs	\$7.50	Panijx	\$9.00
24 "	50 "	Rudfint	9.00	Rudgab	7.50	Fustal	9.00
30 "	57 "	Rudfisf	10.00	Rudgeda	8.50	Fustis	10.00
36 "	63 "	Rudfits	10.00	Rudgeck	8.50	Fustite	10.00
42 "	69 "	Panigsi	11.00	Panihy	9.50	Fustiud	11.00
48 "	75 "	Rudfofs	11.00	Rudgeds	9.50	Fustiva	11.00
60 "	87 "	Rudfoda	12.00	Rudequt	10.50	Fustjic	12.00
72 "	99 "	Rudfoes	13.00	Rudfaa	11.50	Fustjoe	13.00

# GOULDS "STAR" WALL HYDRANT AND WASHER.

Fig. 1156, Wall Hydrant and Washer, has solid brass compression valve, actuated by a double-threaded brass screw. Hydrant is operated from outside of building, but shuts off inside of building and out of reach of frost. The connection inside is effected by means of a brass swivel or coupling nut and elbow fitted for  $\frac{3}{4}$ -inch lead or iron pipe. The hub on the outside is cut for  $\frac{3}{4}$ -inch hose; can be cut for 1-inch, if so ordered. We furnish a key with each hydrant.


FIG. 1156,  $\frac{3}{4}$ "

FIG. 1156. SIZES, PRICES, ETC.

Inlet for Iron or Lead Pipe.	Outlet For Hose.	Length.	For Walls.	Cipher.	Price.
$\frac{3}{4}$ in.	$\frac{3}{4}$ in.	12 in.	9 in.	Tanto	\$4.25
$\frac{3}{4}$ "	$\frac{3}{4}$ "	16 "	13 "	Tantub	4.50
$\frac{3}{4}$ "	$\frac{3}{4}$ "	21 "	18 "	Tantva	4.75
$\frac{3}{4}$ "	$\frac{3}{4}$ "	27 "	24 "	Tantwy	5.00

Extra keys, each, 20 cents.

## ADJUSTABLE SERVICE OR CURB BOXES.

Fig. 1159 is variously known as "Curb-Box," "Service-Box" and "Stop-Cock-Box." The last name describes its use, which is to open and close Stop-Cocks in service pipes—both water and gas. Bottom part is cast-iron, shaped to fit over Stop-Cock. Through this extends a 1-inch wrought pipe, which can be raised or lowered to adjust the top cap to the level of the ground. This upper section is held adjusted by small spring. To admit key, top cap is removed. This is easily done by applying the spanner on the end of our key (as shown in cut). Threads in cap are cut in brass bushing; therefore cap cannot rust fast. Key fits over forked rod which is inside of box, and, turning the rod, opens and closes Stop-Cock. Forked rod is included with every box at prices below. Keys are only furnished when ordered, and then at 50 cents extra list. Fig. 1184 is the same as Fig. 1159, described above, except that a counter-sunk brass plug is inserted in top cap. To admit key, this plug can be removed instead of cap. Prices below include forked rod. Keys only furnished when ordered, and then at 50 cents list.

FIGS. 1159 AND 1184. SIZES, PRICES, ETC.

No.	Extension.	Top Section.	FIG. 1159.		FIG. 1184.	
			Cipher.	Price.	Cipher.	Price.
1	48 in. to 62 in.	1 in. pipe	Tiltist	\$3.00	Ondkip	\$3.00
2	58 " 72 "	1 "	Tiltito	3.40	Ondkos	3.40
3	70 " 84 "	1 "	Tiltiul	3.75	Ondkub	3.75

FIG. 1159

FIG. 1184




FIG. 827

## CURB BLOCK.

Fig. 827 shows a very neat and serviceable Curb Block to be used in connection with Figs. 1159 and 1184 Curb Boxes. The block measures 7 x 7 inches, with opening to receive cap of Curb Box.

PRICE.

Fig. 827, each.....(Whelk) \$0.60



# GOULDS NEW STEEL AMALGAM BELL.

285

COMPLETE WITH HANGINGS, AS SHOWN IN CUT.

Fig. 758 represents our well-known and popular Steel Amalgam Bell. We believe they are superior to many more expensive makes and that they will fully sustain the high standard of the "Goulds" Bell, and give the best satisfaction.

They are well adapted to farms, school houses, factories or any place where a cheap but serviceable Bell can be used.

FIG. 758. SIZES, PRICES, ETC.

No.	Diameter.	Approx. Weight.	Cipher.	Price.
A 1	15 in.	40 lbs.	Vaporing	\$4.00
A 2	17 "	50 "	Vaporiz	5.00
A 3	19 "	75 "	Vapory	7.50
A 4	21 "	100 "	Varanus	10.00




FIG. 758

# GOULDS LARGE STEEL AMALGAM BELL.

WITH HANGINGS AND FRAME.

Fig. 353 represents our Steel Amalgam Bell, as we mount them in the larger sizes for churches, school houses, factories, engine houses, etc. We have sent thousands of these Bells to various portions of the United States, as their cheapness places them in the reach of any church, and they have always given splendid satisfaction.

We send all our Bells to market richly gilded.

We put tolling attachment, as shown in cut, on Nos. 6 and 7 at \$4.00 extra, and on No. 8 at \$5.00 extra list.




FIG. 353. SIZES PRICES, ETC.

FIG. 353

No.	Diameter.	Approximate Weight of Bell Only.	Approximate Weight Complete.	Size of Frame.	Cipher.	Price.
3	18½ in.	65 lbs.	172 lbs.	27 x 41½ in.	Fabric	\$16.00
4	21 "	80 "	186 "	30 x 41½ "	Fabrile	20.00
5	24 "	134 "	240 "	32½ x 41½ "	Fable	25.00
6	28 "	247 "	396 "	36 x 48 "	Facel	40.00
7	30 "	325 "	487 "	36 x 48 "	Fact	50.00
8	33 "	414 "	689 "	38 x 48 "	Fade	75.00

# 286 GOULDS IMPROVED BURRALL'S IRON CORN SHELLER.

MADE EITHER RIGHT OR LEFT HAND. RIGHT HAND SENT UNLESS OTHERWISE ORDERED.

We are the only manufacturers of the genuine Burrall's Corn Sheller, which has for years been conceded the best in the market, and warn the Trade against spurious machines. *It is all iron, and very durable; it shells and separates perfectly clean; it will shell either large or small corn; and its repairs are cheap and easily placed.*

Get only the Burrall Sheller with our name on, and avoid all trouble.

FIG. 430. SIZE, PRICE, ETC.




FIG. 430

Corn Sheller Complete


130 lbs.

Flew

\$8.00

For export we pack one Sheller in a case, or from six to eight in a hogshead.

FIG. 431



CORN SHELLER PIECES

No. 1, Leg.....	\$0.35
No. 2, Leg.....	.35
No. 3, Leg.....	.35
No. 4, Leg.....	.35
No. 5, Cross Bar.....	.60
No. 6, Shell Wheel Box, flat side.....	.15
No. 7, Shell Wheel.....	1.75
No. 8, Shell Wheel Box, round side.....	.15
No. 9, Feed Wheel Box, flat side.....	.15
No. 10, Feed Wheel.....	.80
No. 11, Feed Wheel Box, round side.....	.15
No. 12, Balance Wheel.....	1.75
No. 13, Flat Side.....	2.00
No. 14, Round Side.....	2.00
No. 15, Handle.....	.40
No. 16, Wrench.....	.15
No. 17, Spring.....	.65

## GOULDS WROUGHT-IRON JACK SCREWS.

WITH IRON STANDS. SWIVEL CAPS.

Diameter of Screw.	Height Screwed Down.	Will Raise.	Cipher.	Price.
1½ inches	12 inches	6 inches	Fitch	\$6.00
1¾ " "	14 " "	7 " "	Fitz	7.00
2 " "	16 " "	9 " "	Fiveba	10.00
2½ " "	19 " "	10 " "	Flxif	14.00
3 " "	23 " "	12 " "	Flagol	22.50



FIG. 383



# GOULDS CAST-IRON JACK SCREWS.

287

WITH NUT TO LET INTO WOODEN BLOCK.

FIG. 385. SIZE, PRICE, ETC.

Diameter.	Length.	Cipher.	Price.
3 in.	24 in. cast threads	Finch	\$6.00




FIG. 385

## GOULDS WROUGHT-IRON CHEESE AND CIDER PRESS SCREWS.

FIG. 386. SIZES, PRICES, ETC.

Diameter.	Length.	Cipher.	Price.
2 1/4 in.	36 in.	Peels	\$13.25
2 3/4 in.	36 in.	Peepap	17.00
2 3/4 in.	42 in.	Peerso	18.75
3 in.	36 in.	Pelts	23.75
3 in.	48 in.	Pentup	27.50
4 in.	48 in.	Peonsi	37.50
4 in.	60 in.	Pert	40.00




FIG. 386

Screws of any length or size made to order.

## GOULDS CAST-IRON CIDER PRESS SCREWS.

FIG. 1246. SIZE, PRICE, ETC.

Diameter.	Length.	Cipher.	Price.
4 in.	4 ft.	Fiend	\$15.00



FIG. 1246

## GOULDS WINE OR LARD PRESS SCREWS.

FIG. 379. SIZES, PRICES, ETC.

Diameter.	Length.	Cipher.	Price.
1 1/4 in.	18 in.	Firm	\$5.75
1 1/2 in.	18 in.	Firstmo	6.00
1 3/4 in.	24 in.	Fish	6.75
2 1/2 in.	24 in.	Dagloam	12.50



FIG. 379

# WROUGHT STEEL SINKS.

## COLUMBUS STEEL SINK,

With Removable Strainer and Brass Screw Coupling.



FIG. 1301

## NEW ERA STEEL SINK.

With Ordinary Pipe Coupling.



FIG 1302

### COLUMBUS AND NEW ERA STEEL SINKS.

Size.	Depth.	Painted.	Galvanized.	Gray Enameled.	White Enameled.
16 x 24 in.	6 in.	\$2.00	\$4.00	\$6.50	\$7.50
18 x 30 "	6 "	2.80	5.10	8.50	10.00
18 x 36 "	6 "	3.25	6.50	9.50	11.00
20 x 30 "	6 "	3.00	6.25	9.00	10.50
20 x 36 "	6 "	3.70	7.75	10.50	12.00
20 x 40 "	6 "	4.00	8.50	11.50	13.00

Sinks with Patent Overflow, each 50 cents, net, extra.

## NEW ERA ROLLED RIM STEEL SINK.




FIG. 1303

## SINK BACKS, 15 IN. HIGH.




FIG. 1304

## SINK BRACKETS.

Suitable for all sizes wrought steel sinks.



FIG. 1305

Size.	Depth.	Painted.	Galvanized.	White Enam.	Blue Enam.
16x24 in.	6 in.	\$2.25	\$2.70	\$5.90	\$3.55
18x30 "	6 "	2.70	3.55	7.60	4.30
18x36 "	6 "	3.25	4.30	9.45	4.80
20x30 "	6 "	3.25	4.30	9.45	4.80
20x36 "	6 "	4.00	5.10	11.55	5.35
20x40 "	6 "	4.30	5.90	12.65	6.95

Width Inches.	24 in.	30 in.	36 in.	40 in.
Painted.....	\$1.60	\$1.90	\$2.20	\$2.60
Galvanized.....	2.20	2.60	3.00	3.50
Blue Enameled....	3.10	4.10	5.10	6.20
White Enameled	4.00	5.00	6.00	7.10

Plain, per pair.....\$1.00  
Painted, per pair..... 1.15  
Galvanized, per pair... 1.45

Sinks furnished with Rubber Stoppers, 25 cents each net, extra. Sinks furnished with Patent Overflow, 50 cents net, extra.



# GOULDS CAST-IRON SQUARE SINKS.

289




FIG. 428

Size.	Depth.	Painted.	Galvanized.	Enameled.
12 x 18 in.	6 in.	\$1.25	\$2.60	\$4.75
14 x 20 "	6 "	1.50	3.20	6.00
14 x 24 "	6 "	1.70		
16 x 24 "	6 "	1.80	4.00	6.50
15 x 27 "	6 "	2.00	4.25	7.25
16 x 28 "	6 "	2.10	4.50	7.50
16 x 30 "	6 "	2.25	4.75	7.75
17 x 28 "	6 "	2.20		
18 x 24 "	6 "	2.10	4.30	7.00
18 x 30 "	6 "	2.50	5.10	8.50
20 x 30 "	6 "	3.00	6.25	9.00
18 x 32 "	6 "	3.00	6.25	9.50
18 x 36 "	6 "	3.00	6.50	9.50
20 x 36 "	6 "	3.70	7.75	10.50
20 x 40 "	6 "	4.00	8.50	11.50
20 x 42 "	6 "	4.25	9.00	12.00
22 x 42 "	6 "	4.25	9.00	12.00
24 x 48 "	6 "	5.75	12.25	15.00
Patent Overflow Sinks with plug strainer, add to above list.....		\$1.20	\$1.25	\$1.50
Patent Overflow Sinks with open strainer, add to above list.....		1.00	1.00	1.00



SECTIONAL VIEW.

## GOULDS ADJUSTABLE SINK BRACKETS.

No.	For Sinks.	Painted.	Galvanized.
1	12 to 18 in. wide	\$0.60 each	\$1.00 each
2	18 to 24 "	1.00 "	1.50 "




FIG. 814

## GOULDS HALF CIRCLE SINKS.





FIG. 418

No.	Back.	Width.	Depth.	Painted.	Galvan- ized.	Enam- eled.
1	24 in.	14 in.	6 in.	\$1.50	\$3.25	\$6.00
2	27 "	14 "	6 "	1.80	3.90	7.00



SECTIONAL VIEW

## GOULDS CORNER SINKS.





FIG. 429

No.	Sides.	Front.	Depth.	Painted.	Galvan- ized.	Enam- eled.
1	20 in.	28 in.	6 in.	\$1.75	\$3.50	\$7.00
2	22 "	31 "	6 1/2 "	2.10	4.20	8.00



SECTIONAL VIEW

## GOULDS SLOP SINKS.





FIG. 419

No.	Size.	Depth.	Painted.	Galvanized.	Enameled.
1	16 x 16	10 in.	\$2.70	\$5.25	\$7.50
2	20 x 14	12 "	3.50	6.50	8.50
3	20 x 16	12 "	4.00	8.25	10.00
4	24 x 18	12 "	4.50	9.00	11.00
5	24 x 20	12 "	5.00	9.50	11.50
6	23 x 15	15 "	4.25	8.50	11.00
7	30 x 20	12 "	8.00	15.00	16.00
8	36 x 20	12 "	10.00	19.00	20.00
9	48 x 20	17 "	20.00	36.00	38.00



SECTIONAL VIEW

If with Patent Overflow add, each.....	1.00	1.00	1.00
If with Patent Overflow and Plug Strainer add, each.....	1.25	1.25	1.50





FIG. 403

## GOULDS SEWER TRAP.

No.	Size.	Depth.	Outlet.	Painted.	Enameled.
1	16 x 16 in.	8 in.	2 in.	\$2.50	\$5.50



SECTIONAL VIEW



# GOULDS LARGE CESS POOL.

291

WITH BELL TRAP.




FIG. 369


Size.	Depth.	Outlet.	Painted.	Galvanized.	Enameled.
16 x 16 in.	10 in.	4 in.	\$4.50	\$10.00	\$13.00

## GOULDS CELLAR TRAP.




FIG. 417

No.	Size.	Depth.	Outlet.	Price.
1	9 x 9 in.	2 1/4 in.	2 in.	\$1.25
2	12 x 12 "	2 1/4 "	2 "	1.60



SECTIONAL VIEW



SECTIONAL VIEW

## GOULDS SEWER TRAP AND SLOP SINK.

WITH TRAP AND STRAINER.





FIG. 416

No.	Size.	Depth.	Outlet.	Painted.
1	12 x 12 in.	6 in.	2 in.	\$2.25
2	15 x 15 "	11 1/2 "	2 "	3.35
3	18 x 18 "	12 "	3 "	4.25
4	20 x 20 "	12 "	3 "	5.25



SECTIONAL VIEW

## GOULDS IMPROVED HYDRANT CESS POOL.




FIG. 420

No.	Size.	Depth.	Outlet.	Painted.	Galvanized.	Enameled.
1	12 x 12 in.	6 in.	5 in.	\$1.00	\$1.50	\$2.25
2	14 x 14 "	6 "	5 "	1.15	1.75	2.75
3	16 x 16 "	6 "	5 "	1.30	1.95	3.50



SECTIONAL VIEW

## GOULDS IMPROVED HYDRANT CESS POOL.

WITH BELL TRAP.





FIG. 421

No.	Size.	Depth.	Outlet.	Painted.	Galvanized.	Enameled.
1	12 x 12 in.	6 in.	5 in.	\$1.50	\$2.25	\$3.50
2	14 x 14 "	6 "	5 "	1.65	2.50	3.75
3	16 x 16 "	6 "	5 "	1.80	2.75	4.25
4	18 x 18 "	6 "	5 "	2.10	3.25	5.00



SECTIONAL VIEW

# GOULDS CAST-IRON SINK BACKS.

FIG. 1307.

Length, Inches.	20	22	24	28	30	32	36	38	42	48
Plain .....	\$1.25	\$1.35	\$1.50	\$1.80	\$2.00	\$2.25	\$2.75	\$3.00	\$3.50	\$4.25
Galvanized .....	2.30	2.40	2.60	3.30	3.50	3.70	4.20	4.50	4.90	5.60
Enameled .....	2.30	2.40	2.60	3.30	3.50	3.70	4.20	4.50	4.90	5.60

Sink Backs will always be sent with two (2) Cock Holes, unless otherwise ordered.



FIG. 1307

## SINK STRAINER.




FIG. 435

Diameter.	Painted, per doz.	Galvanized, per doz.	Enameled, per doz.
4¾ in.	\$1.50	\$2.60	\$3.00

## SINK BOLT.

Fig. 368, per dozen.....	\$0.40
Fig. 368, per 100.....	2.00
Short Brass Sink Bolts, per dozen.....	1.00



FIG. 368

## OPEN END SINK COUPLING.

FOR LEAD PIPE.



FIG. 434

	Painted.	Galvanized.
Fig. 434, per dozen.....	\$1.50	\$2.00

## OPEN END SINK COUPLING.

FOR IRON PIPE.




FIG 366

	Painted.	Galvanized.
Fig. 366, each. ....	\$0.75	\$0.90

## IRON SINK PLUGS.

WITH RUBBER STOPPER.



FIG. 1306

Plain.	Galvanized.	Enameled.
\$0.20	\$0.25	\$0.30



## PART II.

---

Well Points and Tools, Wrought-Iron Pipe and Fittings,

Brass Goods, Engine Trimmings, Hose, Belting, Mill and

General Supplies, Etc., Etc.    ✕    ✕    ✕    ✕    ✕    ✕

## GOULDS BRASS JACKET DRIVE WELL POINTS.

*CUT No. 1*

Cut No. 1 shows our Brass Jacket Pipe Point, Fig. 524, before being covered with brass Jacket or wire Gauze. Our Open End, Flush and Single Screen Points are constructed the same except the heads. It will be observed that the holes in our pipe points are oblong and of large dimensions, thereby giving extensive filtering surface. Please note all our Pipe Points are made of Wrought-Iron Pipe, the holes being punched before galvanizing and the heads are securely riveted into the pipe.

*CUT No. 2*

Cut No. 2 illustrates the skeleton of our "Goulds Special" Point. This is an extra heavy Point, made of Malleable Iron, the head and body being cast in one piece, and is hence well adapted for heavy driving. This Point has the largest filtering surface of any Point made, and this being considered, is cheaper than the regular Pipe Point.

*CUT No. 3*

Cut No. 3 represents our Banner Point, not covered. The body and head of this Point is also made of Malleable Iron, cast together, and is somewhat lighter than the "Goulds Special," though it has very large filtering surface. The holes are countersunk and Point is galvanized outside and inside after holes are made. This Point is very popular on account of its cheapness and strength.



# GOULDS BRASS JACKET DRIVE WELL POINTS.

295

(See Cut No. 1 for Construction.)

FIG. 524. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	No. of Holes.	No. 60 Gauze per Dozen.	No. 70 Gauze per Dozen.	No. 80 Gauze per Dozen.	No. 90 Gauze per Dozen.	No. 100 Gauze per Dozen.
74	1 in.	24 in.	18 in.	72	\$33.00	\$40.00	\$46.00	\$52.00	\$62.00
76	1 "	30 "	24 "	96	42.00	49.00	56.00	64.00	78.00
78	1 "	36 "	30 "	120	51.00	59.00	66.00	76.00	94.00
80	1 "	42 "	36 "	144	60.00	68.00	76.00	88.00	120.00
82	1 1/4 "	48 "	42 "	168	69.00	78.00	86.00	100.00	136.00
84	1 1/4 "	54 "	48 "	197	78.00	87.00	96.00	112.00	152.00
86	1 1/4 "	20 "	14 "	80	30.00	36.00	42.00	50.00	64.00
90	1 1/4 "	24 "	18 "	100	36.00	44.00	52.00	60.00	80.00
94	1 1/4 "	30 "	24 "	130	46.00	55.00	64.00	75.00	100.00
98	1 1/4 "	36 "	30 "	165	56.00	66.00	76.00	90.00	120.00
100	1 1/4 "	42 "	36 "	200	66.00	77.00	88.00	105.00	140.00
102	1 1/4 "	48 "	42 "	270	76.00	88.00	100.00	120.00	160.00
106	1 1/4 "	54 "	48 "	260	86.00	99.00	112.00	135.00	180.00
110	1 1/4 "	60 "	54 "	290	96.00	110.00	124.00	150.00	200.00
112	1 1/4 "	66 "	60 "	320	106.00	121.00	136.00	165.00	220.00
114	1 1/4 "	72 "	66 "	350	116.00	132.00	148.00	180.00	240.00
136	1 1/2 "	24 "	18 "	120	48.00	57.00	65.00	78.00	94.00
140	1 1/2 "	30 "	24 "	162	60.00	70.00	80.00	96.00	118.00
144	1 1/2 "	36 "	30 "	198	72.00	84.00	95.00	114.00	142.00
146	1 1/2 "	42 "	36 "	240	84.00	97.00	110.00	132.00	166.00
148	1 1/2 "	48 "	42 "	276	96.00	111.00	125.00	150.00	188.00
150	1 1/2 "	54 "	48 "	312	108.00	124.00	140.00	168.00	204.00
152	1 1/2 "	60 "	54 "	348	120.00	138.00	155.00	186.00	228.00
154	1 1/2 "	66 "	60 "	384	132.00	151.00	170.00	204.00	252.00
156	1 1/2 "	72 "	66 "	420	144.00	165.00	185.00	222.00	276.00
160	2 "	24 "	18 "	144	75.00	85.00	94.00	110.00	130.00
164	2 "	30 "	24 "	208	90.00	101.00	112.00	132.00	160.00
168	2 "	36 "	30 "	264	105.00	118.00	130.00	154.00	190.00
170	2 "	42 "	36 "	288	120.00	134.00	148.00	176.00	220.00
172	2 "	48 "	42 "	336	135.00	151.00	166.00	198.00	250.00
174	2 "	54 "	48 "	384	150.00	167.00	184.00	220.00	280.00
176	2 "	60 "	54 "	432	165.00	184.00	202.00	242.00	310.00
178	2 "	66 "	60 "	480	180.00	200.00	220.00	264.00	340.00
180	2 "	72 "	66 "	528	195.00	217.00	238.00	286.00	370.00
184	2 1/2 "	36 "	30 "	300	180.00	205.00	230.00	260.00	300.00
188	2 1/2 "	48 "	42 "	360	230.00	265.00	300.00	340.00	400.00
192	2 1/2 "	60 "	54 "	420	280.00	325.00	370.00	420.00	500.00
196	2 1/2 "	72 "	66 "	480	330.00	385.00	440.00	500.00	600.00
200	3 "	36 "	30 "	300	240.00	275.00	310.00	340.00	410.00
204	3 "	48 "	42 "	420	300.00	345.00	390.00	430.00	520.00
208	3 "	60 "	54 "	540	360.00	415.00	470.00	520.00	630.00
212	3 "	72 "	66 "	660	420.00	485.00	550.00	610.00	740.00
216	4 "	48 "	36 "	360	480.00	520.00	560.00	600.00	700.00
220	4 "	72 "	60 "	600	630.00	695.00	760.00	840.00	1000.00
224	4 "	96 "	84 "	840	780.00	870.00	960.00	1080.00	1300.00
228	4 "	120 "	108 "	1080	930.00	1045.00	1160.00	1320.00	1600.00

FIG. 524




Con-  
structive  
View.

# GOULDS FLUSH OR TUBULAR WELL POINTS.

(See Cut No. 1 for Construction.)

FIG. 662. SIZES, PRICES, ETC.




Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	Number of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
73	1 in.	30 in.	18 in.	72	\$34.00	\$40.00	\$45.00	\$50.00	\$55.00
75	1 "	36 "	18 "	72	38.00	44.00	50.00	56.00	66.00
75½	1 "	36 "	24 "	96	43.00	49.00	55.00	62.00	77.00
77	1 "	42 "	24 "	96	47.00	54.00	60.00	68.00	82.00
77½	1 "	42 "	30 "	120	52.00	59.00	65.00	74.00	93.00
79	1 "	48 "	30 "	120	56.00	63.00	70.00	80.00	98.00
79½	1 "	48 "	36 "	144	61.00	68.00	75.00	86.00	109.00
81	1 "	54 "	36 "	144	65.00	73.00	80.00	92.00	114.00
81½	1 "	54 "	42 "	144	70.00	78.00	85.00	98.00	125.00
83	1 "	60 "	42 "	168	74.00	82.00	90.00	104.00	130.00
116	1¼ "	24 "	18 "	100	36.00	44.00	52.00	60.00	80.00
117	1¼ "	30 "	18 "	100	41.00	49.00	57.00	65.00	85.00
117½	1¼ "	30 "	24 "	130	46.00	55.00	64.00	75.00	100.00
118	1¼ "	36 "	24 "	130	51.00	60.00	68.00	80.00	105.00
119	1¼ "	42 "	24 "	130	56.00	65.00	73.00	85.00	110.00
120	1¼ "	48 "	24 "	130	61.00	70.00	78.00	90.00	115.00
121	1¼ "	36 "	30 "	165	56.00	66.00	76.00	90.00	120.00
122	1¼ "	42 "	30 "	165	61.00	71.00	80.00	95.00	125.00
123	1¼ "	48 "	30 "	165	66.00	76.00	85.00	100.00	130.00
124	1¼ "	54 "	30 "	165	71.00	81.00	91.00	105.00	135.00
125	1¼ "	42 "	36 "	200	66.00	77.00	88.00	105.00	140.00
126	1¼ "	48 "	36 "	200	71.00	82.00	92.00	110.00	145.00
127	1¼ "	54 "	36 "	200	76.00	87.00	97.00	115.00	150.00
128	1¼ "	60 "	36 "	200	81.00	92.00	102.00	120.00	155.00
129	1¼ "	48 "	42 "	230	76.00	87.00	97.00	115.00	150.00
130	1¼ "	54 "	42 "	230	81.00	92.00	104.00	125.00	165.00
130½	1¼ "	60 "	42 "	230	86.00	98.00	110.00	130.00	170.00
131	1¼ "	66 "	42 "	230	91.00	103.00	115.00	135.00	175.00
132	1¼ "	60 "	48 "	260	91.00	104.00	116.00	140.00	180.00
133	1¼ "	66 "	48 "	260	96.00	109.00	122.00	145.00	185.00
135	1¼ "	72 "	48 "	260	101.00	114.00	127.00	150.00	190.00
137	1¼ "	54 "	48 "	260	86.00	98.00	110.00	130.00	170.00
143	1¼ "	60 "	54 "	280	96.00	109.00	122.00	145.00	185.00
149	1¼ "	66 "	60 "	300	106.00	119.00	132.00	155.00	195.00
151	1¼ "	72 "	66 "	320	116.00	129.00	142.00	165.00	205.00

## OPEN END OR WELL POINT EXTENSIONS.

(See Cut No. 1 for Construction.)

FIG. 524½. SIZES, PRICES, ETC.



Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	Number of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
95	1¼ in.	30 in.	24 in.	126	\$46.00	\$55.00	\$64.00	\$75.00	\$100.00
99	1¼ "	36 "	30 "	165	56.00	66.00	76.00	90.00	120.00
101	1¼ "	42 "	36 "	200	66.00	77.00	88.00	105.00	140.00
145	1½ "	36 "	30 "	198	72.00	84.00	95.00	114.00	142.00
147	1½ "	42 "	36 "	240	84.00	97.00	110.00	132.00	166.00
169	2 "	36 "	30 "	250	105.00	118.00	130.00	154.00	190.00
171	2 "	42 "	36 "	288	120.00	134.00	148.00	176.00	220.00
173	2 "	48 "	42 "	300	135.00	151.00	166.00	198.00	250.00

FIG. 662

FIG.  
524½



# "GOULDS SPECIAL" DRIVE WELL POINTS.

297

(See Cut No. 2 for Construction.)

FIG. 138. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	Number of Openings.	No. 60 Gauze, Per Dozen.	No. 70 Gauze, Per Dozen.	No. 80 Gauze, Per Dozen.	No. 90 Gauze, Per Dozen.	No. 100 Gauze, Per Dozen.
5	1 in.	24 in.	18 in.	156	\$33.00	\$40.00	\$46.00	\$52.00	\$62.00
10	1 in.	36 in.	30 in.	260	51.00	59.00	66.00	76.00	94.00
15	1 1/4 in.	20 in.	14 in.	116	30.00	36.00	42.00	50.00	64.00
20	1 1/4 in.	24 in.	18 in.	152	36.00	44.00	52.00	60.00	80.00
25	1 1/4 in.	30 in.	24 in.	204	46.00	55.00	64.00	75.00	100.00
27	1 1/4 in.	36 in.	30 in.	272	56.00	66.00	76.00	90.00	120.00
28	1 1/4 in.	42 in.	36 in.	316	66.00	77.00	88.00	105.00	140.00
30	1 1/2 in.	24 in.	18 in.	156	48.00	57.00	65.00	78.00	94.00
35	1 1/2 in.	30 in.	24 in.	208	60.00	70.00	80.00	96.00	118.00
40	1 1/2 in.	36 in.	30 in.	260	72.00	84.00	95.00	114.00	142.00
45	2 in.	24 in.	18 in.	152	75.00	85.00	94.00	110.00	130.00
50	2 in.	30 in.	24 in.	200	90.00	101.00	112.00	132.00	160.00
55	2 in.	36 in.	30 in.	248	105.00	118.00	130.00	154.00	190.00

# "GOULDS SPECIAL" TUBULAR WELL POINTS.

FIG. 139. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	Number of Openings.	No. 60 Gauze, Per Dozen.	No. 70 Gauze, Per Dozen.	No. 80 Gauze, Per Dozen.	No. 90 Gauze, Per Dozen.	No. 100 Gauze, Per Dozen.
60	1 1/4 in.	28 in.	24 in.	204	\$46.00	\$55.00	\$64.00	\$75.00	\$100.00
65	1 1/4 in.	42 in.	24 in.	200	56.00	65.00	73.00	85.00	105.00
70	1 1/4 in.	42 in.	30 in.	225	61.00	71.00	80.00	95.00	120.00

# BRASS JACKET "BANNER" DRIVE WELL POINTS.

(See Cut No. 3 for Construction.)



FIG. 140. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	Length of Jacket.	Number of Holes.	No. 60 Gauze, Per Dozen.	No. 70 Gauze, Per Dozen.	No. 80 Gauze, Per Dozen.	No. 90 Gauze, Per Dozen.	No. 100 Gauze, Per Dozen.
186	1 1/4 in.	20 in.	14 in.	72	\$30.00	\$36.00	\$42.00	\$50.00	\$64.00
190	1 1/4 in.	24 in.	18 in.	90	36.00	44.00	52.00	60.00	80.00
194	1 1/4 in.	30 in.	24 in.	126	46.00	55.00	64.00	75.00	100.00
198	1 1/4 in.	36 in.	30 in.	156	56.00	66.00	76.00	90.00	120.00
336	1 1/2 in.	24 in.	18 in.	118	48.00	57.00	65.00	78.00	94.00
340	1 1/2 in.	30 in.	24 in.	150	60.00	70.00	80.00	96.00	118.00
344	1 1/2 in.	36 in.	30 in.	192	72.00	84.00	95.00	114.00	142.00
360	2 in.	24 in.	18 in.	120	75.00	85.00	94.00	110.00	130.00
364	2 in.	30 in.	24 in.	162	90.00	101.00	112.00	132.00	160.00
368	2 in.	36 in.	30 in.	204	105.00	118.00	130.00	154.00	190.00

FIG. 138

FIG. 139

## GOULDS SINGLE SCREEN WELL POINTS.

(See Cut No, 1 for Construction )




FIG. 138½

Fig. 138½ shows our Single Screen Well Points covered with brass jacket of No. 1, 2, 3 or 4 perforations, as ordered. For sizes and prices see lists of our Figs. 524 and 662, covered with No. 60 Gauze. We can furnish these Points, when so ordered, wire wound as shown in cut. For sizes and prices use our No. 80 Gauze lists of Figs. 524 and 662.



FIG. 139½

Fig. 139½ is the same Point in all respects as Fig. 138½, described above, only point is covered with slotted Brass Jacket, instead of having round holes in same. For sizes and prices take our Figs. 524 and 662 lists, No. 100 Gauze.




FIG. 140½

The above cut illustrates our Single Screen Well Point, covered with heavy woven wire cloth. For sizes and prices take our Figs. 524 and 662 lists for 1, 1¼ and 1½-inch Points, No, 100 Gauze. For 2-inch and larger take list of Fig. 141½.



# GOULDS WASHER DRIVE WELL POINTS.

299

These points are made of Galvanized Iron Pipe, bored and countersunk. Each hole is covered with gauze, held in its place by a brass washer and riveted.

FIG. 661. SIZES, PRICES, ETC.

Trade No.	Diameter Pipe.	Length of Pipe.	No. of Holes.	No. 60 Gauze, per Dozen.	No. 70 Gauze, per Dozen.	No. 80 Gauze, per Dozen.	No. 90 Gauze, per Dozen.	No. 100 Gauze, per Dozen.
300	1 1/4 in.	20 in.	50	\$30.00	\$36.00	\$42.00	\$50.00	\$64.00
301	1 1/4 "	2 ft.	60	36.00	44.00	52.00	60.00	80.00
302	1 1/4 "	2 1/2 "	80	46.00	55.00	64.00	75.00	100.00
303	1 1/4 "	3 "	100	56.00	66.00	76.00	90.00	120.00
304	1 1/4 "	3 1/2 "	120	66.00	77.00	88.00	105.00	140.00
305	1 1/4 "	4 "	140	76.00	88.00	100.00	120.00	160.00
320	1 1/2 "	2 "	80	48.00	57.00	65.00	78.00	94.00
321	1 1/2 "	2 1/2 "	110	60.00	70.00	80.00	96.00	118.00
322	1 1/2 "	3 "	130	72.00	84.00	95.00	114.00	142.00
323	1 1/2 "	3 1/2 "	150	84.00	97.00	110.00	132.00	160.00
324	2 "	2 1/2 "	140	90.00	101.00	112.00	132.00	160.00
325	2 "	3 "	170	105.00	118.00	130.00	154.00	190.00
326	2 "	3 1/2 "	220	120.00	134.00	148.00	176.00	220.00

## WELL POINTS FOR WATER WORKS.




FIG. 661

FIG. 141. SIZES, PRICES, ETC.

These prices are for Points, open end, or with plugs, as ordered, and are covered with the different size gauzes indicated, also with brass jacket.

Diameter Pipe. Black or Galvanized.	No. 60 Gauze, per Foot.	No. 70 Gauze, per Foot.	No. 80 Gauze, per Foot.	No. 90 Gauze, per Foot.	No. 100 Gauze, per Foot.
5 in.	\$5.00	\$5.75	\$6.50	\$7.25	\$8.00
6 "	5.80	6.50	7.25	8.00	9.00
7 "	7.00	7.75	8.50	9.25	10.50
8 "	8.50	9.25	10.00	11.00	12.00
10 "	13.00	14.00	15.25	16.50	18.00

For list on 4-inch or smaller, see Brass Jacket Points.

# GOULDS MALLEABLE SUCTION STRAINERS.



FIGS. 658

659

660

## PRICE LIST.

Fig. 658, with Set Screw. Trade Number.	Fig. 659, with Female Thread. Trade Number.	Fig. 660, with Male Thread Trade Number.	For	Galvanized with Brass Gauze. Each.	Galvanized Without Brass Gauze Each.	Plain Without Brass Gauze Each.
500	520	510	1 in. pipe	28 cents	22 cents	18 cents
501	521	511	1 1/4 "	32 "	24 "	20 "
502	522	512	1 1/2 "	36 "	26 "	24 "
503	523	513	2 "	50 "	40 "	36 "

# GOULDS WATER WORKS STRAINERS.

These Strainers are made of heavy pipe, galvanized after the holes are put in, and covered with heavy woven wire cloth.




FIG. 141 1/2

Size.	No. Holes per foot.	No. Square inches of Filtering Surface per Square Foot.	List Price per Foot.
2 in.	108	51	\$2.00
2 1/2 "	132	62	3.00
3 "	156	74	4.00
3 1/2 "	168	79	4.50
4 "	192	126	5.00
4 1/2 "	216	142	5.50
5 "	240	158	6.00
6 "	288	189	7.50
8 "	336	220	10.00
9 "	370	240	12.00
10 "	408	268	15.00

# COOKS SEAMLESS BRASS SLOTTED STRAINER.




FIG. 1279


Inside Diameter of Well, Inches.....	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8
Length in feet for Coarse Sand.....	4	6	6	6	8	8	8	8	10	10
Length in feet for Fine Sand.....	8	10	12	12	14	16	16	16	16	16
Price per Foot.....	\$2.50	\$3.00	\$4.00	\$4.50	\$5.00	\$5.75	\$6.25	\$8.00	\$10.00	\$12.00



# VALVE AND PLUNGER LEATHERS, ETC.

301

MADE OF PURE OAK TANNED STOCK.



TUBULAR WELL VALVE, RUBBER.

PLUNGER LEATHER—NOT CRIMPED.



LOWER VALVE LEATHER.



PLUNGER LEATHER—CRIMPED.



## SIZES AND PRICES.

Size, Inches (Diameter of Cylinders.).....	1½	1¾	2	2¼	2½	2¾	3	3¼	3½	3¾	4	4½	5	6	8
Tubular Well Valve Rubber, each.....			\$0.16		\$0.30		\$0.40				\$0.60				
Plunger Leathers, not Crimped, each.....	70.15	\$0.15	.15	\$0.15	.15	\$0.15	.15	\$0.20	\$0.20	\$0.20	.20	\$0.25	\$0.30	\$0.35	\$0.50
Lower Valve Leathers, each.....	.15	.15	.15	.15	.15	.15	.15	.20	.20	.20	.20	.25	.30	.35	.50
Plunger Leathers, Crimped, each.....	.15	.15	.15	.15	.15	.20	.25	.30	.35	.40	.45	.55	.60	.75	1.25


Valve Leather in Bulk, price \$1.00 per pound.

## PERFORATED SHEET BRASS.


We carry the above perforations in stock in widths suitable for covering the different sizes of pipe.

### PRICE LIST PER LINEAL FOOT.


	Nos. 1, 2, 3, 4.	No. 8.	No. 21.
4¾-inches wide for 1 inch pipe.....	\$0.20	\$0.14	\$0.30
5⅞ " " 1¼ " " .....	.28	.18	.40
6⅞ " " 1½ " " .....	.30	.20	.50
7⅞ " " 2 " " .....	.38	.25	.65
9¼ " " 2½ " " .....	.44	.30	.75
11 " " 3 " " .....	.50	.35	.85
12 " " 4 " " .....	.55	.40	.90
14¼ " " 4 " " .....	.65	.44	1.10




No. 1




No. 2




No. 3



No. 4



No. 8




No. 21

## BRASS WIRE CLOTH.

We carry in stock the following meshes Brass Wire Cloth, 36 inches in width.

### LIST PRICE PER SQUARE FOOT.

No. 20 Mesh.....	\$0.50	No. 70 Mesh.....	\$0.90
" 30 " .....	.65	" 80 " .....	1.00
" 40 " .....	.40	" 90 " .....	1.20
" 50 " .....	.50	" 100 " .....	1.50
" 60 " .....	.60	" 120 " .....	3.00



# GOULDS IRON AND WOOD ROD COUPLINGS.

## COUPLINGS FOR IRON RODS.




FIG. 232. SIZES AND PRICES.

Size Rods.	Threads to the Inch.	Galvanized, per Pound.	Plain, per Pound.
$\frac{3}{8}$	14, regular.	20c. pound.	16c. pound.
$\frac{3}{8}$	16, to order.	20c. "	16c. "
$\frac{7}{8}$	12 x 14	20c. "	16c. "
$\frac{1}{2}$	12	20c. "	16c. "
$\frac{1}{2}$	12	20c. "	16c. "

## HEXAGON COUPLINGS FOR IRON RODS.




FIG. 233½. SIZES AND PRICES.

Size Rods.	Threads to the Inch.	Galvanized, per Pound.	Plain, per Pound.	Brass per Pound.
$\frac{3}{8}$	14, regular.	20c. pound.	16c. pound.	50 cents.
$\frac{3}{8}$	16, to order.	20c. "	16c. "	50 "
$\frac{7}{8}$	12 x 14	20c. "	16c. "	50 "
$\frac{1}{2}$	12	20c. "	16c. "	50 "
$\frac{1}{2}$	12	20c. "	16c. "	50 "

## PIPE ROD COUPLINGS.


For  $\frac{3}{8}$ -inch Pipe.

FIG. 232½

	Galvanized, per Pound.	Plain, per Pound.
Pipe Thread.....	22 cents.	18 cents.

## REDUCER COUPLINGS.


For  $\frac{1}{2}$  and  $\frac{3}{4}$ -inch Pipe and Steel Pump Rods.

FIG. 234½

Size Rods.	Galvanized, per Pound.	Plain, per Pound.
$\frac{3}{8}$ -inch.	30 cents.	25 cents.
$\frac{1}{8}$ "	30 "	25 "
$\frac{3}{8}$ "	30 "	25 "
$\frac{1}{8}$ "	30 "	25 "

## WOOD ROD COUPLINGS.




FIG. 9

For 1 and $1\frac{1}{8}$ -inch Rod, plain,	2 hole, per pair, \$0.10
" 1 " $1\frac{1}{8}$ " " galvanized,	2 " " " .14
" 1 " $1\frac{1}{8}$ " " plain,	3 " " " .16
" 1 " $1\frac{1}{8}$ " " galvanized,	3 " " " .20
" $1\frac{1}{4}$ " $1\frac{3}{8}$ " " plain,	3 " " " .20
" $1\frac{1}{4}$ " $1\frac{3}{8}$ " " galvanized,	3 " " " .24



# GOULDS DRIVE CAPS AND WELL SHOES.

303

## TUBULAR WELL CYLINDER SHOE.



FIG. 16

Malleable.

2	in., with shoulder	\$0.50
2	" no "	.50
2 1/2	" " "	.70
3	" " "	.90
4	" " "	1.50

## MALLEABLE DRIVE CAP.



FIG. 510

For 1 1/4 in. pipe	each	\$0.20
" 1 1/2 "	"	.24
" 2 "	"	.44

## STEEL DRIVE HEADS.

For 1 1/4 in. pipe	each	\$1.50
" 1 1/2 "	"	2.00
" 2 "	"	2.50
" 2 1/2 "	"	6.00
" 3 "	"	9.00
" 4 "	"	16.00



FIG. 181

## PIPE DRIFTS FOR CLEANING OUT INSIDE OF PIPE.

Fig. 184 for 2 in. pipe	\$5.00
" " " 2 1/2 "	7.00
" " " 3 "	10.00




FIG. 184

## DRIVE PLATE.

Used on Top of Pipe to Receive the Blows of the Drive Block.




FIG. 185

No. 1, for 2 and 3 in. pipe-hole, for 1 in. rods	\$3.00
No. 2, for 3 and 4 1/2 in. pipe-hole, for 1 1/4 in. rods	5.00
No. 3, for 4 1/2 and 6 in. pipe-hole for 1 1/4 in. rods	10.00
Special sizes to order.	




FIG. 197

## FORGED WROUGHT STEEL DRIVE SHOES.

For Artesian and Tubular Wells.

## DRIVE TOP—HOLLOW.

Made of Pipe, with Steel Rings, and Will Outlast Any Other Style Made.

2 in.	\$5.00
2 1/2 "	6.00
3 "	8.00
4 "	10.00
4 1/2 "	12.00
6 "	20.00




FIG. 187

2 in.	\$0.80	4 1/2 in.	\$6.00
2 1/2 "	1.20	5 "	7.00
3 "	2.00	6 "	9.00
3 1/2 "	4.00	8 "	12.00
4 "	4.00		

Steel shoes for well casing can also be supplied at above list. Intermediate sizes of Casing Shoes will be charged at next higher prices.

## GOULDS "EUREKA" TUBULAR WELL CYLINDERS.

Fig. 142 represents Goulds "Eureka" Seamless Brass Tubular Well Cylinder. It can be used in rough pipe after the well is made, using the Seating Tool attached to drill rod to crowd it down to its place. The cylinder is held in well casing by the expansion rubber and spring dog coupling.

FIG. 142. SIZES, PRICES, ETC.

Complete With Valves and Spring Dog Coupling.

Size of Well.	Inside Dia.	Stroke.	Price of Cylinder Complete, with 2 Leather Plunger.	Price of Cylinder Complete, with 4 Leather Plunger and Bronze Ball Valves.	Size of Well.	Inside Dia.	Stroke.	Price of Cylinder Complete, with 2 Leather Plunger.	Price of Cylinder Complete, with 4 Leather Plunger and Bronze Ball Valves.
2 in.	1 $\frac{13}{16}$ in.	12 in.	\$6.40	\$9.00	4 in.	3 $\frac{1}{2}$ in.	24 in.	\$42.00	\$71.00
2 " "	1 $\frac{1}{8}$ in.	16 "	7.60	10.00	4 $\frac{1}{2}$ "	4 "	16 "	50.00	82.00
2 $\frac{1}{2}$ "	2 $\frac{1}{4}$ "	12 "	11.00	18.00	4 $\frac{1}{2}$ "	4 "	24 "	58.00	90.00
2 $\frac{1}{2}$ "	2 $\frac{1}{4}$ "	16 "	12.50	21.00	5 $\frac{1}{2}$ "	4 $\frac{1}{2}$ "	24 "	60.00	120.00
3 "	2 $\frac{3}{4}$ "	12 "	15.00	25.00	5 "	4 $\frac{1}{2}$ "	36 "	80.00	140.00
3 "	2 $\frac{3}{4}$ "	16 "	17.00	27.00	6 "	5 $\frac{1}{2}$ "	24 "	112.00	180.00
3 $\frac{1}{2}$ "	3 "	12 "	30.00	46.00	6 "	5 $\frac{1}{2}$ "	36 "	136.00	208.00
3 $\frac{1}{2}$ "	3 "	16 "	33.00	49.00	8 "	7 $\frac{7}{8}$ "	36 "	360.00	520.00
4 "	3 $\frac{1}{2}$ "	12 "	33.00	62.00	8 "	7 $\frac{7}{8}$ "	42 "	400.00	600.00
4 "	3 $\frac{1}{2}$ "	16 "	36.00	65.00					

## SEATING TOOL "EUREKA" CYLINDER.




FIG. 143½. SIZES AND PRICES.

For 2 in. cylinder.....	Each, \$0.60
" 2 $\frac{1}{2}$ " ".....	" .90
" 3 " ".....	" 1.20
" 4 " ".....	" 2.40
" 5 " ".....	" 4.00

FIG. 142

With  
Poppet Valves.

FIG. 142

With  
Ball Valves.



# GOULDS TUBULAR WELL CYLINDERS.

305

Fig. 728 illustrates our polished iron Tubular Well Cylinder, made from extra heavy pipe, bored out, *fitted with driving shoe*.

FIG. 728. SIZES, PRICES.

Diameter.	WITHOUT VALVES.				WITH THREE-FOOT WELL POINT, TWO LEATHER VALVES AND COUPLING.			
	3 FEET.		4 FEET.		3 FEET.		4 FEET.	
	Black.	Galvanized.	Black.	Galvanized.	Black.	Galvanized.	Black.	Galvanized.
2 in.	\$4.00	\$4.50	\$5.00	\$5.75	\$8.50	\$9.00	\$9.50	\$10.00
2½ "	6.65	7 50	8.50	9.25	16.50	17.00	18.50	19.00
3 "	9.00	10.00	11.50	12.25	22.50	23.50	25.00	26.00
4 "	14.00	15 75	17.50	20.00	41.00	43.00	45.00	48.00

Fig. 144, Brass-Lined Cylinder, is made similar to Fig. 728, the shell being bored out to insert a lining of brass tubing. The lining is forced in and swedged in position.

FIG. 144. SIZES, PRICES.

Diameter.	Length.	Without Point or Valves, but with Shoe.	With Shoe, 3-ft. "Perfect" Well Point, Four Leather Valves and Coupling.
2 in.	3 ft.	\$7.75	\$12.25
2½ "	3 "	10.50	18.00
3 "	3 "	13.00	26.00
4 "	3 "	19.00	41.50

FIG. 728.

FIG. 144.

# IMPROVED TUBULAR WELL VALVES.

TWO LEATHER  
POPPET PLUNGER.




FIG. 147

BALE TOP  
POPPET CHECK.

TWO LEATHER  
BALL PLUNGER.



FIG. 145

BALE TOP  
BALL CHECK.

FOUR LEATHER  
POPPET PLUNGER.



FIG. 153

SCREW TOP  
POPPET CHECK.

FOUR LEATHER  
BALL PLUNGER.



FIG. 153½

SCREW TOP  
BALL CHECK.

MARCY  
PLUNGER.




FIG. 149

MARCY  
CHECK.

BREMER  
PLUNGER.



FIG. 158½

**BREMER  
CHECK.**



FIG. 148




FIG. 146




FIG. 151½



FIG. 151



FIG. 150




FIG. 158

TUBULAR WELL VALVES. SIZES AND PRICES.

Figs. 147, 148, 145, 146, 151, 153,  $151\frac{1}{2}$  and  $153\frac{1}{2}$ .

2	in.	X 2	Leather, per set.....	\$2.40
2½	“	X 2	“ “ “ .....	6.00
3	“	X 2	“ “ “ .....	8.00
2	“	X 4	“ “ “ .....	3.20
2½	“	X 4	“ “ “ .....	7.00
3	“	X 4	“ “ “ .....	10.00
4	“	X 4	“ “ “ .....	18.00

Figs. 149, 150, 158½ and 158.

2	in. Marcy per set.....	\$3.20
2 1/2	“ “ “ “.....	8.40
3	“ “ “ “.....	12.80
2	“ “ “ “ with spring dog.....	4.20
2 1/2	“ “ “ “ “ “ “ “.....	10.20
3	“ “ “ “ “ “ “ “.....	15.40
2	“ Bremer “ “.....	2.40
2	“ “ “ “ with spring dog.....	3.20



# GOULDS HYDRAULIC AND JETTING DRILLS.

307



FIG. 169




FIG. 170




FIG. 171




FIG. 172



FIG. 173



FIG. 174

Fig. 169 is made of solid steel and is very strong.

These drills are named after size of pipe they pass through; thus a 2-inch drill will work through a 2-inch pipe. 4½-inch and 6-inch drills when used for the jetting process are threaded for 2-inch pipe coupling, but unless specially ordered for jetting purposes are threaded for 1¼-inch.

	2-inch.	2½-inch.	3-inch.	4½-inch.	6-inch.
Fig. 170, Twist Drill, for ball or bolt valve.....	\$4.00	\$5.00	\$6.00	\$9.00	\$12.00
" 171, Chisel Drill, for ball or bolt valve.....	4.00	5.00	6.00	9.00	12.00
" 169, Round Drill, for ball or bolt valve.....	5.00	6.00	7.00	12.00	18.00
" 173, Twist Drill, with leather valve.....	4.50	5.50	6.60	10.00	13.00
" 174, Chisel Drill, with leather valve.....	4.50	5.50	6.60	10.00	13.00
" 172, Hydraulic Z Drill.....	6.00	7.00	8.00	12.00	14.00

## SAND PUMP AND DRILL COMBINED.

FIG. 729. PRICE LIST.




FIG. 729

Gas Pipe Thread Connection.	Actual Size of Bit.	Price.
1 inch.....	1¾ inches.	\$1.25
1 ".....	2 " "	2.00
1 ".....	2½ " "	3.00
1¼ ".....	3 " "	4.00

## ENLARGING DRILL.

	2-inch.	3-inch.	4½-inch.	6-inch.
Fig. 175, Enlarging Drill.....	\$6.00	\$8.50	\$10.00	\$20.00




FIG. 175

# PADDY AND EXPANSION DRILLS.



FIG. 164



FIG. 165



FIG. 166



FIG. 167




FIG. 168



FIG. 168½

Figs. 164, 165, 167 are Drop Paddies for Jetting. Fig. 168½ is Drop Paddy for Hydraulic, and Fig. 168, Rotary Paddy, for Revolving process. All make the hole large enough for pipe to follow.

Fig. 166, Spring Paddy Reamer, trues up and enlarges a hole already sunk too small for pipe to follow, and is used with Jetting process.

## \*PRICES OF PATENT PADDY AND EXPANSION DRILLS.

Pipe will go through and cut hole for..	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Pipe screw to.....	1	1	1¼	1¼	2	2	2½	2½	3	3	3	4	4
Fig. 164 or 165, Drop Paddy.....	\$5.00	\$6.70	\$8.20	\$11.70	\$16.00	\$20.00	\$25.00	\$30.00	\$35.00	\$43.00	\$55.00	\$70.00	\$100.00
“ 167 “ “ .....	6.70	9.00	11.00	15.50	21.00	27.00	33.00	40.00	47.00	58.00	73.00	93.00	133.00
“ 168 Rotary Paddy.....	7.00	9.50	11.50	16.00	22.00	28.00	35.00	42.00	49.00	61.00	77.00	98.00	140.00
“ 166 Spring Paddy Reamer.....	9.40	12.60	15.50	22.00	30.00	38.00	47.00	56.00	66.00	81.00	103.00	132.00	188.00
“ 168½ Drop Paddy.....	5.50	7.50	9.00	13.00	18.00	22.00	27.50	33.00	38.50	47.50	61.00	77.00	110.00
Extra Rivets, all styles, each.....	\$0.20	.25	.35	.40	.50	.60	.70	.80	.90	1.00	1.25	1.50	1.90

\*Extra Wings only for Fig. 166, 40%, and all other styles 25% of price of complete drill. Drills ordered with shanks other than as listed are special and will be 10% higher. Drills to work in oil well casing at price of next larger standard drill.





PRICE FOR FIGS 13, 15, 176 AND 32.

2 in.....	\$6.00
2½ ".....	6.50
3 ".....	7.00
3½ ".....	8.50
4 ".....	10.00
4½ ".....	15.00
5 ".....	20.00
6 ".....	25.00

We make augers to go inside 2-inch pipe when ordered.

## END PIPE REAMER.

For reaming ends of pipe so that the plunger leathers will not catch in the joints.



FIG. 195

For reaming ends. 2 in. pipe, \$1.50
" " " 2½ " 2.00
" " " 3 " 3.00

## BLIND OR CHECK VALVES.



FIG. 192



Sec. View.

Fig. 192.

To fit 1 in. pipe.....	\$1.40
" 1¼ ".....	2.00
" 2 ".....	5.00

## SPECIAL TOOL COUPLING.

Made long and heavy, to attach drills and other well making tools to working rods.

FIG. 161

1 x 3½ in. long for 1 in. Tool Shanks.....	\$0.20
1¼ x 3¾ " " " 1¼ " " ".....	.26
1½ x 3¾ " " " 1½ " " ".....	.30
2 x 3¾ " " " 2 " " ".....	.40



FIG. 161

## TURNUED COUPLING.

FIG. 160



FIG. 160

1¼ in. for 2 in. cylinder.....	\$0.12 each.
1¼ x 1½ " 2½ " ".....	.20 "
1¼ x 2 " 3 " ".....	.30 "

## GOULDS WELL TOOLS.

ROPE SWIVEL.



FIG. 11.

WATER SWIVEL.



FIG. 189.

CASING SWIVEL.



FIG. 25.

ROD LIFTER.

For Raising Drill Rods.



FIG. 180½.

Handles 1 in. and 1¼-in. pipe in one end and 2-in. pipe in the other.

Diam. Iron made from, Inches...	1¼	1½
Price.....	\$3.25	\$3.75

ROPE HOOK.



FIG. 181½.

Diam. Iron made from	Price.
7/8	\$2.50
1	3.30
1¼	4.50
1½	6.50

HYDRAULIC AND JETTING SWIVEL.



FIG. 194.

Fig. 11.

For 1 in. pipe, heavy .....	\$4.00
For 1¼ in. pipe, heavy .....	8.00

Fig. 189.

For 1 in. pipe, .....	\$20.00
" 1¼ " .....	25.00

Fig. 25.

To fit 2 in. casing, .....	\$4.50
" 2½ " .....	5.50
" 3 " .....	6.50
" 4 " .....	9.00
" 4½ " .....	11.00
" 5 " .....	15.00
" 6 " .....	20.00

Fig. 194.

(Less Swivel.)

1 in.	1¼ in.	1½ in.	2 in.	2½ in.	3 in.
\$14.00	17.50	29.00	37.00	46.00	69.00

Inlet pipes to and including elbow only.

PULLEY BLOCKS.




FIG. 196.

Single Pulley Block, .....	\$ 5.00
Double " .....	10.00
Treble " .....	15.00



FIG. 178.

2 in. \$7.50



# GOULDS WELL TOOLS.

311

FRICION GRAB

SPRING GRAB

VALVE  
GRAB

STRAINER  
GRAB

LIFTING OR  
HOLDING TONGS.

SLIDING OR  
FRICION TONGS.



FIG. 195½



FIG. 194½



FIG. 197½



FIG. 196½



FIG. 21

FIGS. 21 AND 23.

Size Pipe.	¾ in.	1 in.	1¼ in.	1½ in.	2 in.
300 ft. Wells	\$5.00	\$6.00	\$7.50	\$8.00	\$10.00
500 ft. Wells	.....	.....	8.00	10.00	12.00
1000 ft. Wells	.....	.....	10.00	12.00	14.00



FIG. 23

TAPER TAP.



FIG. 179

Fitted for 1-in. Pipe  
to Pull ¾ to 1¼  
in. Pipe.

Fig. 179. Tap, \$4.50  
Fig. 180. Die, 8.00

Fitted for 1¼-in.  
Pipe to Pull ¾  
to 2-in. Pipe.

\$6.25  
12.00

TAPER DIE.



FIG. 180

For Working Inside of

2 or  
2½ in.

3 in.

4½ in.

6 in.

Valve Grab, Fig. 197½.....	\$2.00	\$3.00	.....	.....
Strainer Grab, Fig. 196½.....	2.00	2.50	.....	.....
Friction Grab, Fig. 195½.....	2.00	3.00	\$6.00	\$10.00
Spring Grab, Fig. 194½.....	.....	4.00	8.00	12.00

INSIDE PIPE PULLER OR CASING SPEAR.

This is Used for Pulling Pipe Broken off Under Ground.




FIG. 188½

Fitted for	¾ in. pipe to pull	1¼ in. pipe.....	\$5.00
"	1 " "	2 " "	7.00
"	1¼ " "	2½ " "	10.00
"	2 " "	3 " "	14.00
"	2½ " "	3½-4 " "	18.00
"	3 " "	4½ " "	22.00
"	3½ " "	5 " "	25.00
"	4½ " "	6 " "	35.00
"	5 " "	7 " "	40.00
"	6 " "	8 " "	50.00

PIPE LIFTING CLEVIS.



FIG. 171½

Fig. 171½.

For 1 and 1¼ in. pipe..... \$2.00

# PIPE PULLERS AND HOLDERS.



FIG. 192 1/2

## PIPE PULLER.

This Puller is arranged to draw all sizes of pipe. The Dies are serrated so as to hold fast to the pipe and not crush it. It is large enough for the Coupling of the Pipe to pass through. Pullers and Dies will be made to fit any size of Artesian Casing.

### PRICES OF PIPE PULLER WITH A SET OF DIES.

## "LITTLE GIANT" PIPE HOLDER.




FIG. 160 1/2

Price Complete.  
For 1, 1 1/4 and 1 1/2 in. Pipe ..... \$5.00

### SIZE OF IRON PIPE IT WILL HOLD IN INCHES.

	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8	9	10	11
No. 1 with 3/4, 1 or 1 1/4-in. dies...	c.	c.	\$2.50	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$
Extra dies for No. 1, per set.....	60	50															
No. 2.....					2.75												
Extra dies for No. 2.....		80	.75	.50	.50												
No. 3. with 2, 2 1/2 or 3-in. dies.....							5.00										
Extra dies for No. 3.....					.80	.75	.75										
No. 4. with 3 1/2 or 4-in. dies.....									8.50								
Extra dies for No. 4.....					3.00	2.50	2.25	2.00	1.75								
No. 5. with 4, 4 1/2 or 5-in. dies.....										10.							
Extra dies for No. 5.....							3.25	3.00	2.75	2.50	2.00						
No. 6. with 4, 4 1/2, 5 or 6-in. dies.....												12.					
Extra dies for No. 6.....								3.00	2.75	2.50	2.25						
No. 8. with 6, 7 or 8-in. dies for 4 screws.....														15.			
Extra dies for No. 8.....										4.50	4.00	3.50	3.00				
No. 10. with 7, 8, 9 or 10-in. dies, 4 screws.....															25.00		
Extra dies for No. 10.....														7.00	6.00	5.00	
No. 12. with 8, 9, 10, 11, or 12-in. dies.....																	40.00
Extra dies.....															8.00	7.00	6.00

## THE STANDARD AUTOMATIC PIPE LIFTER AND HOLDER.



FIG. 184 1/2

Price Complete.

For 1, 1 1/4 and 1 1/2-in. Pipe.....\$10.00

## BABCOCK'S PIPE LIFTER AND HOLDER.




FIG. 186 1/2

For 1-in. and 1 1/4-in. pipe.....\$7.00

## LITTLE'S AUTOMATIC PIPE HOLDER.



FIG. 187 1/2

Price Complete.

For 1, 1 1/4 and 1 1/2 in. Pipe..... \$5.00

## "MONITOR" PIPE HOLDER.




FIG. 159 1/2

Capacity 1, 1 1/4, 1 1/2 and 2-in. pipe. Handles 2-in. perfectly as well as the smaller sizes. Openings in Turret made to conform to each size of Pipe, insuring perfect support.

Price, each...\$5.00





## CAST-IRON WATER PIPE.

TABLE OF WEIGHTS AND THICKNESSES USED UNDER DIFFERENT PRESSURES.

Size, Inches.....	3	4	6	8	10	12	16	20	24	30	36	42	48
Thickness, Standard, inches.....	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{9}{16}$	$\frac{3}{4}$	$\frac{7}{8}$	$1\frac{1}{8}$	$1\frac{1}{8}$	$1\frac{3}{8}$	$1\frac{3}{8}$	$1\frac{1}{2}$
Wgt. per ft. for 100 lbs. pressure per sq. in.	18	22	33	45	60	75	125	197	250	350	475	600	775
Thickness, Medium, inches.....	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{9}{16}$	$1\frac{1}{8}$	$1\frac{1}{8}$	$\frac{7}{8}$	1	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{5}{8}$	$1\frac{7}{8}$
Wgt. per ft. for 150 lbs. pressure per sq. in.	19	23	35	50	73	95	150	225	300	425	600	800	1000
Thickness, Heavy, inches.....	$\frac{9}{16}$	$\frac{9}{16}$	$\frac{9}{16}$	$\frac{5}{8}$	$1\frac{1}{8}$	$1\frac{1}{8}$	1	$1\frac{1}{8}$	$1\frac{3}{8}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	2
Wgt. per ft. for 200 lbs. pressure per sq. in..	20	24	38	57	80	110	175	250	350	500	750	1000	1250

Conditions under which Water Pipe is used vary and we can make Cast-Iron Pipe to meet any requirements. The extra cost between a standard weight and the weight given for the duty required, as shown in the table, is very slight, and the question of weight to be used should have the careful consideration of any person ordering Cast-Iron Pipe.

All Water Pipe is coated with tar and tested to a hydrostatic pressure of 300 pounds per square inch.

## CAST-IRON GAS PIPE.

Size, Inches.....	3	4	6	8	10	12	16	20	24	30	36	42	48
Thickness, inches.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{7}{16}$	$1\frac{1}{2}$	$1\frac{1}{2}$	$\frac{5}{8}$	$1\frac{1}{16}$	$\frac{3}{4}$	$1\frac{1}{16}$	$\frac{7}{8}$	$\frac{7}{8}$	$1\frac{1}{8}$
Weight per foot, pounds.....	16	20	30	40	55	70	104	150	190	277	350	383	600


Gas Pipe is not coated unless so ordered. It is tested to a hydrostatic pressure of 300 pounds per square inch.

TABLE OF LEAD AND JUTE REQUIRED TO CALK THE JOINTS OF CAST-IRON PIPE.

Size, Inches.....	3	4	6	8	10	12	16	20	24	30	36	42	48
Lead per joint, pounds.....	3	$3\frac{1}{2}$	5	7	9	13	17	21	24	30	40	60	80
Jute per joint, ounces.....	8	9	12	15	17	24	29	32	37	50	60	80	120



We furnish specially prepared Jute for calking pipe.

## CAST-IRON FLANGED PIPE.



We can supply Flanged Pipe in sizes ranging from 4-inch to 36-inch. Estimates furnished on application.

## SPECIALS FOR CAST-IRON PIPE.

QUARTER BEND,  
90°.EIGHTH BEND,  
45°.SIXTEENTH BEND,  
22½°.

TEE.




CROSS.

## QUARTER BEND. EIGHTH BEND. SIXTEENTH BEND.

## TEES.

## CROSSES.

Size, Inches.	Weight, Pounds.	Size, Inches.	Weight, Pounds.	Size, Inches.	Weight, Pounds.	Size, Inches.	Weight, Pounds.	Size, Inches.	Weight, Pounds.
3	40	3	45	4	50	3 x 3 x 3	80	3 x 3 x 3	100
4	60	4	55	6	80	4 x 4 x 4	120	4 x 4 x 4	160
6	100	6	85	8	105	4 x 4 x 3	94	6 x 6 x 6	225
8	160	8	145	10	160	6 x 6 x 6	180	6 x 6 x 4 x 4	210
10	240	10	190	12	206	6 x 6 x 4	160	8 x 8 x 8	325
12	300	12	300			8 x 8 x 8	280	8 x 8 x 6 x 6	315
14	400	14	430			8 x 8 x 6	260	8 x 8 x 4 x 4	285
16	700	16	485			8 x 8 x 4	240	10 x 10 x 10	410
18	800	18	820			8 x 8 x 3	220	10 x 10 x 8 x 8	400
20	1,000	20	1,200			10 x 10 x 10	350	10 x 10 x 6 x 6	380
24	1,500	24	1,450			10 x 10 x 8	345	10 x 10 x 4 x 4	360
30	2,500	30	2,200			10 x 10 x 6	295	12 x 12 x 12	546
						10 x 10 x 4	275	12 x 12 x 10	480
						12 x 12 x 12	450	12 x 12 x 8 x 8	440
						12 x 12 x 10	385	12 x 12 x 6 x 6	400
						12 x 12 x 8	380	12 x 12 x 4 x 4	357
						12 x 12 x 6	350	16 x 16 x 16	1,020
						12 x 12 x 4	320	20 x 20 x 20	1,600
						16 x 16 x 16	770	24 x 24 x 24	2,400
						16 x 16 x 12	750	30 x 30 x 30	3,600
						16 x 16 x 10	740	36 x 36 x 36	6,160
						16 x 16 x 8	736	48 x 48 x 48	10,500
						16 x 16 x 6	700		
						20 x 20 x 20	1,390		
						24 x 24 x 24	2,000		
						30 x 30 x 30	2,880		
						36 x 36 x 36	4,920		
						48 x 48 x 48	9,000		



SLEEVE.



PLUG.



TAPER PLUG.



CAP.

Size, Inches.....		3	4	6	8	10	12	14	16	18	20	24	30	36	48
Sleeves, weight, lbs .....		40	50	80	110	146	190	212	240	360	557	710	1,175	1,222	1,650
Plugs, weight, " .....		10	10	20	30	45	65	70	95	125	150	185	370		
Taper Plugs, weight, " .....			10	18	30	44	53								
Caps, weight, " .....		20	30	40	75	100	120								



# SPECIALS FOR CAST-IRON PIPE.

315



REDUCER.



INCREASER.



OFFSET.



Y BRANCH.

## REDUCERS.

Size, In.	Weight, Lbs.
4 x 3	40
6 x 4	100
6 x 3	80
8 x 6	135
8 x 4	115
10 x 8	194
10 x 6	180
10 x 4	158
12 x 10	240
12 x 8	230
12 x 6	200

## INCREASERS.


Size, In.	Weight, Lbs.
12 x 4	200
14 x 12	475
14 x 10	430
14 x 8	340
16 x 12	395
16 x 10	330
20 x 16	690
20 x 12	540
24 x 16	920
30 x 24	1,690
36 x 30	1,730

## OFFSET.


Size, In.	Weight, Lbs.
4 x 6	80
4 x 24	106
6 x 6	135
6 x 12	160
6 x 24	207
8 x 12	220
10 x 12	285
12 x 12	380
.....	.....
.....	.....
.....	.....

## Y BRANCHES.

Size, In.	Weight, Lbs.
4 x 4	155
6 x 6	235
6 x 4	218
8 x 8	312
8 x 6	300
10 x 10	500
12 x 12	750
.....	.....
.....	.....
.....	.....



SPLIT TEE.



SPLIT SLEEVE.



TAPPED PLUG.

Size, Inches.....	3	4	6	8	10	12	14	16	18	20
Split Tee.....Each,	\$5.00	\$6.25	\$8.25	\$10.75	\$12.50	\$15.00	\$18.75	\$21.25	\$25.00	\$30.00
Split Sleeve....."	2.50	2.50	3.00	5.50	7.50	10.00	12.00	16.00	20.00	25.00
Tapped Plugs....."	1.50	1.50	1.75	2.75	3.50	4.00	5.00	5.00	.....	.....


Split Tees—made to order only, any size outlet required. Tapped Plugs—Best connection made for connecting wrought and cast-iron pipe. Plugs can be tapped for any size required. Split Sleeves—An excellent special for repairing.

We can supply all sizes and reductions in Specials, from 2 to 48 inch. If in stock, and unless otherwise specified, we will fill all orders with Bell End Specials. *The above weights are given as standard simply for the purpose of estimating, and are approximately correct.* All Specials are made with full water-way and easy bends. All descriptions of special water-works castings made to order, including Flanged Pipe and all special pump connections.

# STANDARD PIPE.

FOR GAS, STEAM AND WATER.

(Revised February 15, 1900.)



BUTT AND LAP-WELDED.

TABLE OF STANDARD DIMENSIONS AND SIZES.

TELEGRAPHIC CIPHER FOR ORDERING PIPE.

Nominal Size In- side Dia. Inches.	Actual Outside Diameter.	Price per Foot. Black. and Gal- vanized.	Thickness. Inches.	Nominal Weight per Foot. Pounds.	No. of Threads per Inch of Screw	Net for Cutting Extra Threads.
$\frac{1}{8}$	.405	.05 $\frac{1}{2}$	.068	0.24	27	.05
$\frac{1}{4}$	.54	.05 $\frac{1}{2}$	.088	0.42	18	.05
$\frac{3}{8}$	.675	.05 $\frac{1}{2}$	.091	0.56	18	.05
$\frac{1}{2}$	.84	.08 $\frac{1}{2}$	.109	0.84	14	.05
$\frac{3}{4}$	1.05	.11 $\frac{1}{2}$	.113	1.12	14	.05
1	1.315	.16 $\frac{1}{2}$	.134	1.67	11 $\frac{1}{2}$	.06
1 $\frac{1}{4}$	1.66	.22 $\frac{1}{2}$	.140	2.24	11 $\frac{1}{2}$	.07
1 $\frac{1}{2}$	1.9	.27	.145	2.68	11 $\frac{1}{2}$	.08
2	2.375	.36	.154	3.61	11 $\frac{1}{2}$	.10
2 $\frac{1}{2}$	2.875	.57 $\frac{1}{2}$	.204	5.74	8	.15
3	3.5	.75 $\frac{1}{2}$	.217	7.54	8	.20
3 $\frac{1}{2}$	4.	.95	.226	9.00	8	.25
4	4.5	1.08	.237	10.66	8	.35
4 $\frac{1}{2}$	5.	1.30	.246	12.49	8	.45
5	5.563	1.45	.259	14.50	8	.55
6	6.625	1.88	.280	18.76	8	.70
7	7.625	2.35	.301	23.27	8	.85
8	8.625	2.82	.322	28.18	8	1.00
9	9.625	3.40	.344	33.70	8	1.25
10	10.75	4.25	.366	40.00	8	1.50
11	11.75	4.75	.375	45.00	8	2.00
12	12.75	5.20	.375	49.00	8	2.50

Number of Feet.	Size.	Plain.	Size.	Galvan- ized.
100 Asia.	$\frac{1}{8}$	Allegheny		
200 Belgium.	$\frac{1}{4}$	Baltimore	$\frac{1}{4}$	Amazon.
300 Chili.	$\frac{3}{8}$	Camden	$\frac{3}{8}$	Bay.
400 Denmark.	$\frac{1}{2}$	Detroit	$\frac{1}{2}$	Colorado.
500 Egypt.	$\frac{3}{4}$	Erie	$\frac{3}{4}$	Danube.
600 France.	1	Fairmount	1	Elbe
700 Germany.	1 $\frac{1}{4}$	Galena	1 $\frac{1}{4}$	Firth
800 Holland.	1 $\frac{1}{2}$	Harrisburg	1 $\frac{1}{2}$	Ganges
900 Ireland.	2	Ithaca	2	Hudson.
1,000 Japan.	2 $\frac{1}{2}$	Jamestown	2 $\frac{1}{2}$	Indus
2,000 Kentucky.	3	Kensington	3	Juniata.
3,000 Liberia.	3 $\frac{1}{2}$	Lancaster	3 $\frac{1}{2}$	Kanawha.
4,000 Maine.	4	Macon	4	Lake.
5,000 Nevada.	4 $\frac{1}{2}$	Quincy	4 $\frac{1}{2}$	Miami.
6,000 Ohio.	5	Newark	5	Nile.
7,000 Peru.	6	Oneida	6	Osage.
8,000 Russia.	7	Paris	7	Po.
9,000 Spain.	8	Reading	8	Rhine.
10,000 Texas.	9	Salem	9	Seine.
15,000 Uruguay.	10	Troy	10	Tweed.
20,000 Valparaiso	12	Utica	12	Ural.
25,000 Washington				
30,000 Xenia.				
40,000 Yorkville.				
50,000 Zanesville.				



# X STRONG AND XX STRONG PIPE.

317

## BUTT AND LAP-WELDED.

Size, Inches.	Price per Foot.	Actual Outside Diameter.	Nominal Inside Diameter.	Thickness.	Nominal Weight per Foot.
<b>X STRONG.</b>					
$\frac{1}{8}$	\$0.11	.405	.205	.100	.29
$\frac{1}{4}$	.11	.540	.294	.123	.54
$\frac{3}{8}$	.11	.675	.421	.127	.74
$\frac{1}{2}$	.12	.840	.542	.149	1.09
$\frac{3}{4}$	.15	1.050	.736	.157	1.39
1	.22	1.315	.951	.182	2.17
1 $\frac{1}{4}$	.30	1.660	1.272	.194	3.00
<b>XX STRONG.</b>					
$\frac{1}{2}$	.25	.840	.244	.298	1.70
$\frac{3}{4}$	.30	1.050	.422	.314	2.44
1	.37	1.315	.587	.364	3.65
1 $\frac{1}{4}$	.52	1.660	.885	.388	5.20
<b>X STRONG.</b>					
1 $\frac{1}{2}$	.36	1.900	1.494	.203	3.63
2	.50	2.375	1.933	.221	5.02
2 $\frac{1}{2}$	.81	2.875	2.315	.280	7.67
3	1.05	3.500	2.892	.304	10.25
3 $\frac{1}{2}$	1.33	4.000	3.358	.321	12.47
4	1.50	4.500	3.818	.341	14.97
4 $\frac{1}{2}$	1.95	5.000	4.280	.360	18.22
5	2.16	5.563	4.813	.375	20.54
6	2.90	6.625	5.750	.437	28.58
7	3.80	7.625	6.625	.500	37.67
8	4.30	8.625	7.625	.500	43.00
<b>XX STRONG.</b>					
1 $\frac{1}{2}$	.65	1.900	1.088	.406	6.40
2	.95	2.375	1.491	.442	9.02
2 $\frac{1}{2}$	1.37	2.875	1.755	.560	13.68
3	1.92	3.500	2.284	.608	18.56
3 $\frac{1}{2}$	2.45	4.000	2.716	.642	22.75
4	2.85	4.500	3.136	.682	27.48
4 $\frac{1}{2}$	3.30	5.000	3.564	.718	32.53
5	3.80	5.563	4.063	.750	38.12
6	5.30	6.625	4.875	.875	53.11
7	6.25	7.625	5.875	.875	62.38
8	7.20	8.625	6.875	.875	71.62

Extra Strong and Double Extra Strong Pipe is always shipped without threads or couplings, unless otherwise specified.

# STANDARD STEEL BOILER TUBES.

Outside Diameter, Inches.....	1	1¼	1½	1¾	2	2¼	2½	2¾	3	3¼	3½	3¾	4
Per foot.....	.30	.28	.27	.22	.20	.24	.28	.34	.35	.40	.44	.50	.55
Thickness, inches.....	.095	.095	.095	.095	.095	.095	.109	.109	.109	.120	.120	.120	.134
Thickness, nearest Bgm. W. G.....	13	13	13	13	13	13	12	12	12	11	11	11	10
Nominal weight, per foot, pounds.....	.90	1.15	1.40	1.66	1.91	2.16	2.75	3.04	3.33	3.96	4.28	4.60	5.47
Outside Diameter, Inches.....	4½	5	6	7	8	9	10	11	12	13	14	15	16
Per foot.....	.62	.75	1.00	1.20	1.50	1.70	2.10	2.50	2.90	3.20	3.65	4.10	4.60
Thickness, inches.....	.134	.148	.165	.165	.165	.180	.203	.220	.229	.238	2.48	2.59	.270
Thickness, nearest Bgm. W. G.....	10	9	8	8	8	7	6	5	4½	4	3½	3	2½
Nominal weight, per foot, pounds.....	6.17	7.58	10.16	11.90	13.65	16.76	21.00	25.00	28.50	32.06	36.00	40.60	45.20

The above prices are for tubes up to 20 feet long. For tubes in excess of that length, 10 per cent. will be added to net. Extra thickness of tubes will be charged as per list of extra gauges. No deduction for tubes lighter than standard.

## EXTRA WIRE GAUGE OF BOILER TUBES AWAY FROM STANDARD.

For EXTRA wire gauge "Boiler Tubes" away from standard, not exceeding four wire gauges, add one cent for each inch in diameter to the net price per foot for each additional gauge. To calculate price, take discount from list prices of regular Tubes and add net charge for extra wire gauge.

For 1 number.	For 2 numbers.	For 3 numbers.	For 4 numbers.
2 inch, 2c.	2 inch, 4c.	2 inch, 6c.	2 inch, 8c.
2¼ " 2¼c.	2¼ " 4½c.	2¼ " 6¾c.	2¼ " 9c.
2½ " 2½c.	2½ " 5c.	2½ " 7½c.	2½ " 10c.

Beyond four numbers, price is per pound. Swaging or swelling 2-inch or 2¼-inch Tubes, 5c. per end extra. Cutting screws on Tubes, 80 cents per hour.

## COPPER FERRULES.

Inside diameter of Ferrules .....	1½	1¾	2	2¼	2½	3	3½	4
Price per hundred .....	\$11.50	\$12.00	\$13.00	\$15.00	\$17.00	\$21.00	\$27.00	\$31.00

## DOUBLE GALVANIZED FLANGED PRESSURE PIPE FOR EXHAUST STEAM, EXHAUST STEAM HEATING, BRINE CIRCULATING PIPE, ETC.



FLANGED PRESSURE PIPE.

Made of Galvanized Iron and re-galvanized after formation, thereby making all seams and laps perfectly solid. Each length tested to 150 lbs. hydrostatic pressure. Pipe and Fittings made to specifications and drawings when desired. Where lengths required are all 5 feet or less, they will be charged as being 5 feet each.


Diameter, Inches.	Price per Foot.	B. W. G. No.	Approximate Weight per Foot, Lbs.
3	\$ .50	20	2¼
4	.70	20	3
5	1.00	20	4
6	1.20	18	5
7	1.40	18	6
8	1.70	18	7
9	2.00	18	8
10	2.60	16	11
12	3.15	16	14
14	4.00	14	20
16	5.15	14	24
18	6.40	14	29
20	7.95	14	34
24	12.00	12	50





# INSERTED JOINT AND SCREW AND SOCKET.

319

(List adopted February 15, 1900.)



SCREW AND SOCKET JOINT.



INSERTED JOINT.

## LAP-WELDED CASING.

Nominal Inside  
Diameter, Inches.

Price per foot.

Actual Outside  
Diameter, Inches.


Nominal Weight per  
foot, Pounds.

No. of Threads per  
Inch of Screw.

2	\$0.23	2 1/4	2.22	14
2 1/4	.29	2 1/2	2.82	14
2 1/2	.32	2 3/4	3.13	14
2 3/4	.35	3	3.45	14
3	.41	3 1/4	4.10	14
3 1/4	.45	3 1/2	4.45	14
3 1/2	.48	3 3/4	4.78	14
3 3/4	.56	4	5.56	14
4	.60	4 1/4	6.00	14
4 1/4	.64	4 1/2	6.36	14
4 1/2	.68	4 3/4	6.73	14
4 3/4	.78	5	7.80	14
5	.82	5 1/4	8.20	14
5 1/8	.87	5 1/2	8.62	14
5 1/4	1.05	6	10.46	14
6 1/4	1.16	6 3/8	11.58	14
6 3/8	1.24	7	12.34	14
7 1/4	1.36	7 5/8	13.55	14
7 3/8	1.55	8	15.41	11 1/2
8 1/4	1.61	8 5/8	16.07	11 1/2
8 3/8	1.76	9	17.60	11 1/2
9 3/8	2.20	10	21.90	11 1/2
10 3/8	2.68	11	26.72	11 1/2
11 3/8	3.05	12	30.35	11 1/2
12 1/2	3.38	13	33.78	11 1/2

# ARTESIAN WELL CASING SOCKETS.

WITH PATENT PROTECTING SLEEVE.



STANDARD DIMENSIONS.

Size, Inches.	Price.	External Diameter, Inches.	Length, Inches.	Threads, per Inch, of Screw.	Weight of One Socket, Pounds.
1½	\$0.12	2.06	2	18	.68
2	.16	2.63	2⅜	14	1.02
2¼	.20	2.88	2⅝	14	1.24
2½	.25	3.23	3	14	1.90
2¾	.30	3.42	3	14	2.20
3	.35	3.77	3½	14	2.70
3¼	.40	4.00	3⅝	14	3.17
3½	.46	4.27	3⅝	14	3.44
3¾	.52	4.59	3⅝	14	3.94
4	.60	4.81	3⅝	14	4.15
4¼	.68	5.06	3⅝	14	4.20
4½	.74	5.50	3⅝	14	4.80
4¾	.80	5.56	3⅝	14	4.90
5	.90	5.93	3⅝	14	5.74
5⅛	1.00	6.18	3⅝	14	6.04
5½	1.20	6.62	3⅝	14	6.45
6¼	1.35	7.28	3⅝	14	7.22
6⅝	1.50	7.69	3¾	14	8.35
7⅝	1.75	8.70	3¾	11½	10.00
8¼	2.25	9.37	3¾	11½	11.52

## CASING FITTINGS.

Inside Diameter, Inches.....	3	3¼	3½	3¾	4	4¼	4½	4¾	5	5⅛	5⅝	6¼	6⅝
Elbows .....	\$1.10	\$1.35	\$1.80	\$1.80	\$2.50	\$2.50	\$3.00	\$3.00	\$3.50	\$4.00	\$4.00	\$7.00	\$7.00
Tees .....	1.50	2.00	2.50	2.50	3.50	3.50	4.00	4.25	5.00	5.50	5.50	10.00	10.00
Crosses .....	2.20	2.70	3.50	3.50	5.00	5.00	5.70	6.00	7.00	7.80	7.80	14.00	14.00
Plugs .....	.50	.75	.85	.85	1.35	1.35	1.75	1.75	2.00	2.40	2.40	3.75	3.75
Bushings .....	.60	.80	1.00	1.00	1.50	1.50	1.85	1.85	2.00	2.50	2.50	3.75	3.75
Flange, Unions .....	2.25	2.75	3.15	3.15	4.50	4.50	5.00	5.00	5.50	6.50	6.50	8.00	8.00
Locknuts .....	.50	.70	.95	.95	1.25	1.25	1.35	1.35	1.50	1.90	1.90	2.50	2.50
Ret. Bends, close .....	3.00	4.00	5.00	5.00	6.00	6.50							
Ret. Bends, open .....	3.75	4.50	5.75	5.75	8.00	8.00							
Reducers .....	1.20	1.50	2.00	2.00	2.75	2.75	3.00	3.00	3.50	4.00	4.00	8.00	8.00
Caps .....	.80	1.10	1.30	1.30	1.60	1.60	2.00	2.00	2.15	2.35	2.35	4.00	4.00
Y's .....	3.25	4.50	6.00	6.00	8.00	8.00	9.00	9.00	10.00	12.00	12.00	17.00	17.00

5⅝-inch Caps, with two holes for 2-inch Pipe, \$1.50  
 5⅝-inch Bushings, with two-holes for 2-inch Pipe, \$1.50.



# PIPE COUPLINGS.

321

## STANDARD WROUGHT-IRON COUPLINGS.




Size of Pipe, Inches.	Actual Outside Diameter, Inches.	Length of Coupling, Inches.	Weight of Coupling, Pounds.	No. of Threads per Inch of Screw.	Black, Each.	Galvanized, Each.	Right and Left, Black, Each.	Right Hand. Faced, Each.
$\frac{1}{8}$	$\frac{19}{32}$	$\frac{13}{16}$	$\frac{1}{32}$	27	\$0.05	\$0.06	\$0.07	
$\frac{1}{4}$	$\frac{25}{32}$	1	$\frac{1}{16}$	18	.05	.06	.07	\$0.09
$\frac{3}{8}$	$\frac{29}{32}$	$1\frac{3}{32}$	$\frac{3}{32}$	18	.06	.08	.08	.10
$\frac{1}{2}$	$1\frac{1}{32}$	$1\frac{5}{16}$	$\frac{5}{32}$	14	.07	.10	.11	.12
$\frac{3}{4}$	$1\frac{11}{32}$	$1\frac{9}{16}$	$\frac{1}{4}$	14	.10	.13	.15	.16
1	$1\frac{31}{32}$	$1\frac{3}{4}$	$\frac{3}{8}$	$11\frac{1}{2}$	.13	.18	.20	.22
$1\frac{1}{4}$	2	$1\frac{15}{16}$	$\frac{9}{16}$	$11\frac{1}{2}$	.17	.25	.25	.30
$1\frac{1}{2}$	$2\frac{9}{32}$	$2\frac{3}{16}$	$\frac{13}{16}$	$11\frac{1}{2}$	.21	.32	.30	.40
2	$2\frac{13}{16}$	$2\frac{5}{8}$	$1\frac{1}{4}$	$11\frac{1}{2}$	.28	.40	.50	.50
$2\frac{1}{2}$	$3\frac{9}{16}$	$2\frac{11}{16}$	$1\frac{5}{8}$	8	.40	.55	.85	.70
3	$4\frac{1}{64}$	3	$3\frac{1}{16}$	8	.60	.80	1.20	.90
$3\frac{1}{2}$	$4\frac{1}{2}$	$3\frac{1}{8}$	$3\frac{1}{4}$	8	.80	1.05	1.60	1.20
4	$5\frac{3}{32}$	$3\frac{1}{2}$	$4\frac{1}{4}$	8	1.00	1.40	2.00	1.50
$4\frac{1}{2}$	$5\frac{7}{32}$	$3\frac{1}{8}$	$4\frac{1}{4}$	8	1.50	2.00		2.10
5	$6\frac{1}{4}$	$3\frac{1}{16}$	$6\frac{3}{4}$	8	1.65	2.25		2.40
6	$7\frac{1}{32}$	$3\frac{1}{16}$	$8\frac{1}{2}$	8	2.40	3.25		3.60
7	$8\frac{1}{16}$	$4\frac{5}{16}$	$11\frac{1}{2}$	8	3.25			
8	$9\frac{1}{16}$	$4\frac{1}{8}$	$15\frac{3}{4}$	8	4.25			
9	$10\frac{5}{32}$	$5\frac{3}{4}$	$20\frac{3}{4}$	8	5.50			
10	$11\frac{1}{2}$	$6\frac{1}{4}$	$26\frac{3}{4}$	8	7.50			
12	$13\frac{3}{32}$	$6\frac{1}{4}$	$40\frac{1}{2}$	8	10.00			
14					13.00			

## MALLEABLE IRON COUPLINGS.

### RIBBED, RIGHT AND LEFT.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Price, Plain, each.....	\$0.04	\$0.05	\$0.08	\$0.12	\$0.16	\$0.25	\$0.36	\$0.52
Price, Galvanized, each.....	.06	.08	.10	.17	.25	.35	.55	.75





### RIGHT HAND.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Price, Plain, each .....	\$0.03	\$0.04	\$0.07	\$0.10	\$0.14	\$0.20	\$0.25	\$0.35
Price, Galvanized, each.....	.05	.07	.10	.17	.23	.30	.40	.55



## HYDRAULIC COUPLINGS.



Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Outside Diameter inches.....	1.13	1.44	1.63	1.94	2.31	2.75	3.31	4.00	4.63	5.13
Length, inches.....	1.88	2.13	2.38	2.63	2.94	3.13	3.50	3.69	4.25	4.25
Threads to inch of Screw.....	14	14	$11\frac{1}{2}$	$11\frac{1}{2}$	$11\frac{1}{2}$	$11\frac{1}{2}$	8	8	8	8
Weight, each, pounds.....	.28	.45	.56	.84	1.35	1.82	2.37	3.38	4.74	6.24
Price, plain, each.....	\$0.14	\$0.20	\$0.26	\$0.34	\$0.42	\$0.56	\$0.80	\$1.20	\$1.60	\$2.00
Price, galvanized, each.....	.20	.25	.32	.42	.55	.75	1.05	1.50	1.90	3.00

These Couplings are made extra heavy and long, and cut with a perfect taper and longer thread. Threads for these Couplings may be cut with an ordinary die.

## SPECIAL COUPLINGS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Outside Diameter inches.....	1.09	1.31	1.63	1.94	2.31	2.78	3.25	3.94	4.50	5.00
Length, inches.....	1.63	1.88	2.13	2.38	2.63	2.94	3.13	3.38	3.63	3.63
Threads to inch of Screw.....	14	14	$11\frac{1}{2}$	$11\frac{1}{2}$	$11\frac{1}{2}$	$11\frac{1}{2}$	8	8	8	8
Weight, each, pounds.....	.20	.33	.50	.74	1.15	1.75	1.84	2.87	4.00	4.87
Price plain, each.....	\$0.13	\$0.18	\$0.24	\$0.30	\$0.38	\$0.50	\$0.70	\$1.10	\$1.40	\$1.80
Price, galvanized, each.....	.19	.23	.30	.38	.50	.70	.95	1.40	1.70	2.20

These Couplings are similar to the others, but not so long or heavy.

## XX HYDRAULIC COUPLINGS.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Outside Diameter, inches.....	1.69	1.94	2.19	2.44	3.19	3.63	4.25	4.81	5.31
Length, inches.....	2.13	2.63	2.88	3.13	3.38	3.63	3.63	4.25	4.25
Threads to inch of Screw.....	14	$11\frac{1}{2}$	$11\frac{1}{2}$	$11\frac{1}{2}$	$11\frac{1}{2}$	8	8	8	8
Weight each, pounds.....	.80	1.04	1.50	1.75	3.28	4.00	4.85	5.50	6.00
Price, plain, each.....	\$0.40	.55	.70	.85	1.15	1.60	2.40	3.20	4.00

## RECESSED COUPLINGS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Price, Hydraulic, plain, each...	\$0.25	\$0.30	\$0.35	\$0.45	\$0.55	\$0.70	\$0.95	\$1.40	\$1.85	\$2.25
Price, Hydraulic, galv., each...	.30	.35	.40	.55	.70	.90	1.20	1.70	2.15	3.25
Price, Special, plain, each.....	.24	.28	.33	.40	.50	.65	.85	1.30	1.65	2.05
Price, Special, galv., each.....	.28	.33	.38	.50	.65	.85	1.10	1.60	1.95	2.45

In order to meet the requirements of the trade for a Hydraulic or Special Coupling WITH RECESSED ENDS, we deemed it advisable to use our present patterns, which are made extra heavy and longer than the common couplings.


The object of the Recessed Couplings is to make a better joint, protecting the pipe at the weak point, viz.: that part left exposed from cutting the thread and not covered with the ordinary coupling.



# WROUGHT-IRON NIPPLES.

323

(List Revised October 7, 1899.)



CLOSE NIPPLE.



SHOULDER NIPPLE.

TABLE OF SIZES AND LENGTHS KEPT IN STOCK.

LENGTH IN INCHES.					SIZES.	PRICES.		PRICES OF EXTRA LONG NIPPLES.										
Close.	Short.	Long.				Close or Short.	Long.	Lengths in Inches.										
								4	5	6	7	8	9	10	11	12		
$\frac{3}{4}$	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3, $3\frac{1}{2}$	$\frac{1}{8}$	\$0.04	\$0.06	\$0.07	\$0.08	\$0.10	\$0.12	\$0.14	\$0.15	\$0.17	\$0.18	\$0.19		
$\frac{7}{8}$	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3, $3\frac{1}{2}$	$\frac{1}{4}$	.04	.06	.07	.08	.10	.12	.14	.15	.17	.18	.19		
1	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3, $3\frac{1}{2}$	$\frac{3}{8}$	.04	.06	.07	.08	.10	.12	.14	.15	.17	.18	.19		
$1\frac{1}{8}$	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3, $3\frac{1}{2}$	$\frac{1}{2}$	.05	.07	.08	.10	.12	.14	.16	.18	.20	.22	.23		
$1\frac{3}{8}$	2	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$ , 4	$\frac{3}{4}$	.06	.09	.....	.11	.13	.17	.18	.20	.22	.24	.26		
$1\frac{1}{2}$	2	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$ , 4	1	.08	.13	.....	.15	.18	.23	.25	.28	.31	.34	.36		
$1\frac{5}{8}$	$2\frac{1}{2}$	3,	$3\frac{1}{2}$ ,	4, $4\frac{1}{2}$	$1\frac{1}{4}$	.11	.17	.....	.20	.24	.29	.33	.36	.40	.44	.47		
$1\frac{3}{4}$	$2\frac{1}{2}$	3,	$3\frac{1}{2}$ ,	4, $4\frac{1}{2}$	$1\frac{1}{2}$	.13	.20	.....	.25	.29	.36	.40	.45	.50	.54	.59		
2	$2\frac{1}{2}$	3,	$3\frac{1}{2}$ ,	4, $4\frac{1}{2}$	2	.18	.27	.....	.32	.38	.50	.54	.59	.65	.72	.77		
$2\frac{1}{2}$	3	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$ , 5	$2\frac{1}{2}$	.39	.59	.....	.....	.68	.90	.97	1.06	1.17	1.26	1.35		
$2\frac{1}{2}$	3	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$ , 5	3	.48	.72	.....	.....	.85	1.08	1.20	1.33	1.45	1.58	1.70		
$2\frac{3}{4}$	4	$4\frac{1}{2}$ ,	5,	$5\frac{1}{2}$ , 6	$3\frac{1}{2}$	.75	1.05	.....	.....	.....	1.30	1.45	1.60	1.75	1.90	2.05		
3	4	$4\frac{1}{2}$ ,	5,	$5\frac{1}{2}$ , 6	4	.85	1.20	.....	.....	.....	1.52	1.69	1.87	2.05	2.22	2.40		
3	4	$4\frac{1}{2}$ ,	5,	$5\frac{1}{2}$ , 6	$4\frac{1}{2}$	1.25	1.70	.....	.....	.....	2.25	2.50	2.75	2.95	3.17	3.40		
$3\frac{1}{4}$	$4\frac{1}{2}$	5,	$5\frac{1}{2}$ ,	6, $6\frac{1}{2}$	5	1.55	2.45	.....	.....	.....	2.58	2.83	3.10	3.35	3.60	3.85		
$3\frac{1}{4}$	$4\frac{1}{2}$	5,	$5\frac{1}{2}$ ,	6, $6\frac{1}{2}$	6	1.85	2.90	.....	.....	.....	3.05	3.35	3.70	4.00	4.30	4.65		
$3\frac{1}{2}$	5	6			7	3.20	3.60	.....	.....	.....	4.05	4.45	4.90	5.30	5.75	6.15		
$3\frac{1}{2}$	5	6			8	3.55	4.05	.....	.....	.....	4.55	5.05	5.50	6.00	6.50	7.00		
4	5	8			9	5.25	6.50	.....	.....	.....	.....	.....	7.10	7.75	8.40	9.00		
4	5	8			10	6.75	8.25	.....	.....	.....	.....	.....	8.90	9.70	10.40	11.15		
					11													
4	5	8			12	8.00	10.00					10.80				11.75	12.70	13.65

## WROUGHT-IRON NIPPLES.

## PLAIN RIGHT AND LEFT.

## TABLE OF SIZES AND LENGTHS.

LENGTH IN INCHES.			SIZES.	PRICES.		PRICES OF EXTRA LONG R. AND L. NIPPLES.									
Close.	Short.	Long.		Close or Short.	Long.	Lengths in Inches.									
						4	5	6	7	8	9	10	11	12	
$\frac{3}{4}$	$1\frac{1}{2}$	2, $2\frac{1}{2}$ , 3, $3\frac{1}{2}$	$\frac{1}{8}$	\$0.05	\$0.08	\$0.09	\$0.11	\$0.13	\$0.16	\$0.18	\$0.20	\$0.23	\$0.25	\$0.27	
$\frac{7}{8}$	$1\frac{1}{2}$	2, $2\frac{1}{2}$ , 3, $3\frac{1}{2}$	$\frac{1}{4}$	.05	.08	.09	.11	.13	.16	.18	.20	.23	.25	.27	
1	$1\frac{1}{2}$	2, $2\frac{1}{2}$ , 3, $3\frac{1}{2}$	$\frac{3}{8}$	.05	.08	.09	.11	.13	.16	.18	.20	.23	.25	.27	
$1\frac{1}{8}$	$1\frac{1}{2}$	2, $2\frac{1}{2}$ , 3, $3\frac{1}{2}$	$\frac{1}{2}$	.07	.10	.11	.13	.16	.18	.21	.24	.27	.29	.31	
$1\frac{3}{8}$	2	$2\frac{1}{2}$ , 3, $3\frac{1}{2}$ , 4	$\frac{3}{4}$	.08	.12	.....	.15	.17	.23	.25	.27	.29	.32	.35	
$1\frac{1}{2}$	2	$2\frac{1}{2}$ , 3, $3\frac{1}{2}$ , 4	1	.11	.18	.....	.20	.24	.31	.33	.37	.41	.45	.48	
$1\frac{5}{8}$	$2\frac{1}{2}$	3, $3\frac{1}{2}$ , 4, $4\frac{1}{2}$	$1\frac{1}{4}$	.15	.23	.....	.27	.32	.39	.45	.50	.55	.60	.65	
$1\frac{3}{4}$	$2\frac{1}{2}$	3, $3\frac{1}{2}$ , 4, $4\frac{1}{2}$	$1\frac{1}{2}$	.18	.27	.....	.34	.39	.48	.52	.60	.67	.72	.80	
2	$2\frac{1}{2}$	3, $3\frac{1}{2}$ , 4, $4\frac{1}{2}$	2	.24	.36	.....	.43	.51	.67	.72	.80	.87	.96	1.03	
$2\frac{1}{2}$	3	$3\frac{1}{2}$ , 4, $4\frac{1}{2}$ , 5	$2\frac{1}{2}$	.52	.79	.....	.....	.91	1.20	1.30	1.40	1.55	1.68	1.80	
$2\frac{1}{2}$	3	$3\frac{1}{2}$ , 4, $4\frac{1}{2}$ , 5	3	.65	.96	.....	.....	1.13	1.44	1.60	1.77	1.93	2.10	2.27	
$2\frac{3}{4}$	4	$4\frac{1}{2}$ , 5, $5\frac{1}{2}$ , 6	$3\frac{1}{2}$	1.00	1.40	.....	.....	.....	1.75	1.95	2.15	2.35	2.55	2.75	
3	4	$4\frac{1}{2}$ , 5, $5\frac{1}{2}$ , 6	4	1.15	1.60	.....	.....	.....	2.00	2.25	2.50	2.75	3.00	3.25	

Add 60 per cent. to above prices for galvanized nipples threaded right and left.



# WROUGHT-IRON NIPPLES.


325

## GALVANIZED RIGHT HAND.

TABLE OF SIZES AND LENGTHS.

LENGTH IN INCHES.						PRICES.		PRICES OF EXTRA LONG GALVANIZED NIPPLES.									
								Lengths in Inches.									
Close.	Short.	Long.			Sizes.	Close or Short.	Long.	4	5	6	7	8	9	10	11	12	
$\frac{3}{4}$	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$	$\frac{1}{8}$	\$0.06	\$0.11	\$0.12	\$0.15	\$0.17	\$0.21	\$0.24	\$0.26	\$0.29	\$0.31	\$0.34
$\frac{7}{8}$	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$	$\frac{1}{4}$	.06	.11	.12	.15	.17	.21	.24	.26	.29	.31	.34
1	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$	$\frac{3}{8}$	.06	.11	.12	.15	.17	.21	.24	.26	.29	.31	.34
$1\frac{1}{8}$	$1\frac{1}{2}$	2,	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$	$\frac{1}{2}$	.06	.11	.13	.16	.18	.23	.26	.28	.31	.33	.36
$1\frac{3}{8}$	2	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$ ,	4	$\frac{3}{4}$	.08	.14	.....	.18	.21	.26	.29	.32	.35	.38	.41
$1\frac{1}{2}$	2	$2\frac{1}{2}$ ,	3,	$3\frac{1}{2}$ ,	4	1	.11	.19	.....	.24	.28	.34	.38	.42	.47	.51	.55
$1\frac{5}{8}$	$2\frac{1}{2}$	3,	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$	$1\frac{1}{4}$	.17	.29	.....	.32	.38	.45	.51	.57	.63	.69	.75
$1\frac{3}{4}$	$2\frac{1}{2}$	3,	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$	$1\frac{1}{2}$	.21	.35	.....	.39	.46	.55	.63	.70	.77	.84	.91
2	$2\frac{1}{2}$	3,	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$	2	.27	.47	.....	.52	.61	.74	.83	.93	1.03	1.13	1.23
$2\frac{1}{2}$	3	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$ ,	5	$2\frac{1}{2}$	.56	.86	.....	1.00	1.26	1.41	1.56	1.71	1.86	2.01	2.01
$2\frac{1}{2}$	3	$3\frac{1}{2}$ ,	4,	$4\frac{1}{2}$ ,	5	3	.70	1.10	.....	1.30	1.60	1.80	2.00	2.20	2.40	2.60	2.60
$2\frac{3}{4}$	4	$4\frac{1}{2}$ ,	5,	$5\frac{1}{2}$ ,	6	$3\frac{1}{2}$	1.20	1.70	.....	.....	2.10	2.35	2.60	2.85	3.15	3.40	3.40
3	4	$4\frac{1}{2}$ ,	5,	$5\frac{1}{2}$ ,	6	4	1.35	1.87	.....	.....	2.30	2.60	2.90	3.20	3.50	3.80	3.80
3	4	$4\frac{1}{2}$ ,	5,	$5\frac{1}{2}$ ,	6	$4\frac{1}{2}$	1.85	2.60	.....	.....	3.30	3.65	4.05	4.45	4.85	5.25	5.25
$3\frac{1}{4}$	$4\frac{1}{2}$	5,	$5\frac{1}{2}$ ,	6,	$6\frac{1}{2}$	5	2.30	3.15	.....	.....	3.75	4.20	4.60	5.00	5.40	5.85	5.85
$3\frac{1}{4}$	$4\frac{1}{2}$	5,	$5\frac{1}{2}$ ,	6,	$6\frac{1}{2}$	6	2.80	4.25	.....	.....	4.50	5.00	5.55	6.05	6.60	7.15	7.15
$3\frac{1}{2}$	5	6				7	4.25	4.95	.....	.....	5.65	6.35	7.05	7.75	8.45	9.20	9.20
$3\frac{1}{2}$	5	6,				8	5.00	5.80	.....	.....	6.65	7.50	8.35	9.25	10.10	10.95	10.95

# 326 LONG SCREWS WITH COUPLING AND LOCKNUT FACED.



Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Standard Length, inches.....	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	$5\frac{1}{2}$	6	7	8
Standard Length, each.....	\$0.30	.35	.40	.55	.75	1.00	1.30	1.70	2.70	3.70

Long Screws, longer than standard, made to order and charged as cut pipe. Extra for threads, couplings and locknuts.  
Long Screws made to order from extra heavy pipe.

Locknut Nipples made to order and charged as cut pipe, threads extra.

## STANDARD THREADS FOR WROUGHT-IRON PIPE.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12	14	15
Each .....	\$0.05	.05	.05	.05	.05	.06	.07	.08	.10	.15	.20	.25	.35	.45	.55	.70	.85	1.00	1.25	1.50	2.50	3.50	5.00

## LOCKNUT THREADS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each.....	\$0.10	.10	.10	.10	.12	.14	.16	.20	.30	.40

FOR WROUGHT-IRON PIPE.



No. 1.

Sizes 2,  $2\frac{1}{2}$  and 3-inch.

## WATER PIPE CLAMPS.

MALLEABLE IRON.

FOR WROUGHT OR SHEET-IRON PIPE.




No. 2.

Sizes 4, 5, 6 and 7-inch.

Size of Pipe, In.....	2	$2\frac{1}{2}$	3	3	4	4	4	5	5	5	6	6	6	7	7	7	8	8
Tapped for Pipe, in...	$\frac{1}{2}$ to 1	1 to $1\frac{1}{4}$	$\frac{3}{4}$ to 1	$1\frac{1}{4}$ to 2	$\frac{3}{4}$ to $1\frac{1}{2}$	2	3	$\frac{3}{4}$ to $1\frac{1}{2}$	2	3	$\frac{3}{4}$ to $1\frac{1}{2}$	2	3	$\frac{3}{4}$ to $1\frac{1}{2}$	2	3	2 to 3	4
Price, each.....	\$1.00	1.25	1.25	1.50	1.75	2.00	4.00	1.80	2.15	4.00	2.25	2.50	5.00	2.50	2.70	5.00	5.50	6.00

## STEAM PIPE SADDLES.

MALLEABLE IRON.



Size of Pipe, Inches.....	2	$2\frac{1}{2}$	3	4	5	6	6	8
Tapped for Pipe, inches.....	1 to $1\frac{1}{2}$	1 to $1\frac{1}{2}$	1 to 2	1 to 2	1 to 2	1 to 2	$2\frac{1}{2}$ to 4	$2\frac{1}{2}$ to 4
Price, each.....	\$1.00	1.25	1.25	1.50	2.75	2.75	5.75	6.50




# CAST-IRON FITTINGS.

327



ELBOW.



REDUCING ELBOW.



45° ELBOW.

## ELBOWS.

Size, Inches..	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12	
R. H., each.....	\$0.05	\$0.05	\$0.06	\$0.08	\$0.10	$\frac{1}{2}$	\$0.16	\$0.20	\$0.28	\$0.50	\$0.75	\$1.05	\$1.20	\$1.75	\$2.00	\$2.75	\$4.70	\$6.75	\$9.00	\$13.50	\$20.00
R.H.,galv., ea.	.10	.10	.12	.16	.21		.32	.40	.56	1.00	1.50	2.10	2.40	3.50	4.00	5.50	9.40	13.50	18.00	27.00	40.00
R. and L. each	.06	.06	.07	.09	.12		.18	.23	.32	.60	.85	1.30	1.50	.....	.....	.....	.....	.....	.....	.....	.....
Pitched, each..	.....	.....	.....	.10	.13		.20	.25	.35	.65	1.00	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....


## REDUCING ELBOWS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each .....	\$0.07	\$0.09	\$0.12	\$0.18	\$0.23	\$0.32	\$0.60	\$0.85	\$1.20	\$1.40	\$2.00	\$2.30	\$3.15	\$5.40	\$7.75	\$10.50	\$15.50	\$23.00
Galvanized, each.....	.14	.18	.24	.36	.46	.64	1.20	1.70	2.40	2.80	4.00	4.60	6.30	10.80	15.50	21.00	31.00	46.00


## 45° ELBOWS.

Size, Inches..	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12	14
Each .....	\$0.06	\$0.07	\$0.10	\$0.12	\$0.19	\$0.24	\$0.34	\$0.60	\$0.90	\$1.25	\$1.45	\$2.20	\$2.50	\$3.45	\$5.90	\$8.50	\$11.25	\$17.00	\$25.00	\$50.00
Galv., each ....	.12	.14	.20	.24	.38	.48	.68	1.20	1.80	2.50	2.90	4.40	5.00	6.90	11.80	17.00	22.50	34.00	50.00	100.00


CAST-IRON FITTINGS.




TEE.



REDUCING TEE.



ECCENTRIC TEES.



TEES.

Size, Inches.....	1/4	3/8	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8	9	10	12	14
Each.....	\$0.08	.08	.09	.12	.15	.23	.29	.41	.73	1.10	1.50	1.75	2.55	3.00	4.00	6.80	9.75	13.00	19.50	29.00	55.00
Galvanized, each.....	.16	.16	.18	.24	.30	.46	.58	.82	1.46	2.20	3.00	3.50	5.10	6.00	8.00	13.60	19.50	26.00	39.00	58.00	110.00

REDUCING TEES.

Size, Inches.....	1 1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8	9	10	12	14
Each.....	\$0.10	.14	.17	.27	.33	.47	.83	1.25	1.75	2.00	2.95	3.50	4.60	7.80	11.25	15.00	22.50	33.50	65.00
Galvanized, each.....	.20	.28	.34	.54	.66	.94	1.66	2.50	3.50	4.00	5.90	7.00	9.20	15.60	22.50	30.00	45.00	67.00	130.00

ECCENTRIC TEES.

These fittings are designed to prevent the accumulation and lodgment of condensation.  
Orders must be accompanied with sketch, showing position in which the fitting is to be placed.  
Prices upon application.




# CAST-IRON FITTINGS.


329



CROSS.



REDUCING CROSS.



CAP.



LOCK NUT.

## CROSSES.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12	14
Each.....	\$0.16	\$0.22	\$0.27	\$0.42	\$0.53	\$0.75	\$1.30	\$2.00	\$2.70	\$3.15	\$4.60	\$5.50	\$7.25	\$12.25	\$17.50	\$23.50	\$35.00	\$52.50	\$100.00
Galvanized, each.....	.32	.44	.54	.84	1.06	1.50	2.60	4.00	5.40	6.30	9.20	11.00	14.50	24.50	35.00	47.00	70.00	105.00	200.00

## REDUCING CROSSES.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each.....	\$0.18	\$0.25	\$0.30	\$0.46	\$0.60	\$0.83	\$1.45	\$2.20	\$3.00	\$3.50	\$5.10	\$6.00	\$8.00	\$13.50	\$19.25	\$26.00	\$38.50	\$58.00
Galvanized, each.....	.36	.50	.60	.92	1.20	1.66	2.90	4.40	6.00	7.00	10.20	12.00	16.00	27.00	38.50	52.00	77.00	116.00

## CAPS.

Size, Inches.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each.....	\$0.26	\$0.40	\$0.54	\$0.75	\$0.87	\$1.05	\$1.20	\$1.55	\$2.50	\$2.85	\$4.75	\$5.50	\$7.00
Galvanized, each.....	.52	.80	1.08	1.50	1.74	2.10	2.40	3.10	5.00	5.70	9.50	11.00	14.00

## LOCK NUTS.

Size, Inches.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each.....	\$0.25	\$0.27	\$0.34	\$0.47	\$0.64	\$0.85	\$0.90	\$1.30	\$1.70	\$2.35	\$2.70	\$3.00	\$4.00
Galvanized, each.....	.50	.54	.68	.94	1.28	1.70	1.80	2.60	3.40	4.70	5.40	6.00	8.00


## CAST-IRON FITTINGS.



BUSHING.



FACED BUSHING.



PLUG.



COUNTERSUNK PLUG.



ECCENTRIC BUSHING.

## BUSHINGS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each .....	\$0.04	\$0.05	\$0.06	\$0.07	\$0.09	\$0.14	\$0.21	\$0.30	\$0.40	\$0.50	\$0.75	\$0.93	\$1.25	\$1.87	\$2.75	\$3.25	\$3.75	\$5.00
Galvanized, each .....	.08	.10	.12	.14	.18	.28	.42	.60	.80	1.00	1.50	1.85	2.50	3.75	5.50	6.50	7.50	10.00

NOTE—Bushings reducing one size only, up to and including  $2\frac{1}{2}$  inches, are malleable, and will be found listed among the Malleable Fittings.

Cast-Iron Bushings 3 inches and larger reduce one or more sizes.

## PLUGS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each.....	\$0.02	\$0.02	\$0.02	\$0.03	\$0.04	\$0.05	\$0.07	\$0.10	\$0.18	\$0.25	\$0.38	\$0.42	\$0.65	\$0.88	\$1.20	\$1.85	\$2.75	\$3.25	\$3.75	\$5.00
Galvanized, each.....	.04	.04	.04	.06	.08	.10	.14	.20	.36	.50	.76	.84	1.30	1.75	2.40	3.70	5.50	6.50	7.50	10.00
Countersunk, each.....			.04	.06	.08	.09	.11	.15												
Left Hand, each.....				.06	.08	.09	.11	.15												
Solid .....	.04	.04	.04	.06	.08	.09	.11	.15	.27	.38	.57	.63	1.00	1.35	1.80	2.80	4.15	5.00	5.75	7.50


## ECCENTRIC BUSHINGS.

REDUCING TWO OR MORE SIZES


Size .....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12	14
Price.....	\$0.27	.42	.60	.80	1.00	1.50	1.85	2.50	3.75	5.50	6.50	7.50	10.00	25.00

# CAST-IRON FITTINGS.

331



OFFSET.



REDUCER.



OFFSET REDUCING COUPLING.

## OFFSETS.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
To offset $1\frac{7}{8}$ inch, each.....	\$0.45	\$0.70	\$0.70								
" " $2\frac{1}{4}$ " ".....				\$1.20							
" " $2\frac{1}{2}$ " ".....					\$1.80						
" " $3\frac{1}{4}$ " ".....						\$3.00					
" " $3\frac{3}{4}$ " ".....							\$4.00				
" " 4 " ".....	.45	.70	1.00	\$1.20	1.80	3.00	\$4.00	\$5.00	\$6.00	\$8.00	\$10.00
" " $4\frac{1}{4}$ " ".....							4.00				
" " 6 " ".....	.67	1.05	1.50	1.80	2.70	4.50	6.00	7.50	9.00	12.00	15.00
" " 8 " ".....	.90	1.40	2.00	2.40	3.60	6.00	8.00	10.00	12.00	16.00	20.00

## REDUCERS.

Size, Inches.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Each.....	\$0.43	\$0.60	\$0.80	\$1.00	\$1.35	\$1.85	\$2.00	\$2.70	\$5.35	\$6.75	\$8.35	\$10.00	\$15.00
Galvanized, each..	.86	1.20	1.60	2.00	2.70	3.70	4.00	5.40	10.70	13.50	16.70	20.00	30.00


## ECCENTRIC.

### OFFSET REDUCING COUPLINGS.


Size.....	$2 \times 1\frac{1}{2}$	$2\frac{1}{2} \times 1\frac{1}{4}$	$2\frac{1}{2} \times 1\frac{1}{2}$	$2\frac{1}{2} \times 2$	$3 \times 2$	$3 \times 2\frac{1}{2}$	$3\frac{1}{2} \times 3$	$3\frac{1}{2} \times 2\frac{1}{2}$	$4 \times 3\frac{1}{2}$	$4 \times 3$	$5 \times 4$	$6 \times 4$
Each.....	\$1.00	1.50	1.50	1.50	2.40	2.40	3.00	3.00	4.00	4.00	6.00	8.00



CAST-IRON FITTINGS.



FLANGE UNION.



EXTRA HEAVY FLANGE UNION.

FLANGE UNIONS.

FACED. WITH RUBBER GASKET.

Size, Inches.....	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8	9	10	12
Diam. of Flanges, Inches....	3	3 1/4	3 1/2	4 1/8	4 3/8	5 1/8	5 5/8	6 5/8	6 7/8	7 1/2	8 1/4	9 1/4	10 1/4	12	13	14	16	18
Number of Bolts in each....	3	3	4	4	4	4	4	4	4	4	4	5	6	6	8	8	10	10
Each .....	\$0.40	\$0.46	\$0.52	\$0.64	\$0.78	\$1.00	\$1.25	\$1.50	\$1.80	\$2.10	\$2.70	\$3.15	\$3.95	\$5.50	\$7.00	\$10.00	\$11.50	\$16.00
Galvanized, each.....	.80	.92	1.04	1.28	1.56	2.00	2.50	3.00	3.60	4.20	5.40	6.30	7.90	11.00	14.00	20.00	23.00	32.00


EXTRA HEAVY FLANGE UNIONS.

FACED. NO PACKING. FOR A WORKING PRESSURE OF 200 POUNDS.


Size, Inches.....	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8
Diam. of Flanges, Inches.....	3 1/4	3 5/8	4 1/8	4 5/8	5 3/8	6	6 3/4	7 3/8	8	8 5/8	9 3/8	10 3/4	12	13 1/4
Number of Bolts in each .....	4	4	4	4	5	5	6	6	7	8	8	9	10	10
Each .....	\$0.70	.80	1.00	1.15	1.50	1.90	2.25	2.70	3.15	4.00	4.75	6.00	8.25	10.50

# CAST-IRON FITTINGS.

333



COMMON FLANGE.




SADDLE FLANGE.

## FLANGES.

Size of Pipe. Inches.	3/8	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	7	8	9	10	12
Dia. Flange. Inches.																			
3	*\$ .10	\$0.10																	
3 1/2	.15	*.15	*\$ .15	\$0.15	\$0.16														
4	.22	.22	.22	*.16	*.16														
4 1/2	.25	.25	.25	.25	.25	*\$ .22													
5	.35	.35	.30	.30	.30	.30	\$0.35												
5 1/2	.45	.45	.45	.40	.40	.40	*.35	\$0.40											
6	.50	.50	.50	.42	.40	.40	.42	.42	\$0.50										
6 1/2		.65	.60	.60	.60	.55	.50	.50	.50	\$0.65									
7		.75	.75	.75	.70	.70	.62	.62	.62	.75									
7 1/2		.90	.90	.90	.85	.85	.80	.80	.75	.85	\$0.90								
8		1.00	1.00	1.00	.95	.95	.90	.90	.90	.90	.90								
8 1/2		1.25	1.25	1.25	1.15	1.15	1.10	1.10	1.10	1.00	1.00								
9				1.35	1.35	1.35	1.30	1.25	1.15	1.15	1.15	\$1.15	\$1.40						
9 1/2					1.90	1.90	1.75	1.75	1.60	1.60	1.50	1.25	1.50	\$1.50					
10					2.25	2.25	2.15	2.00	1.80	1.50	1.50	1.50	1.50	1.50					
11							2.50	2.50	2.25	2.25	2.00	1.75	1.75	1.75	\$2.20				
12								3.00	3.00	2.75	2.50	2.50	2.20	2.20	2.20	\$2.80			
13									3.50	3.50	3.25	3.00	3.00	2.80	2.80	2.80			
14									4.00	4.00	3.75	3.75	3.50	3.25	3.25	3.25			
15															4.00	4.00	\$4.00	\$4.50	
16															5.00	5.00	5.00	5.00	\$6.00
17															6.50	6.50	5.75	5.75	7.00
18																8.00	8.00	7.00	7.00
19																		7.50	7.50
20																			8.50

Those marked \* are drilled for screw.  
Saddle Flanges made to order at double above prices.  
Blank Flanges to order at 25 per cent. advance on regular.  
Flanges of any required thickness to order.

## CAST-IRON FITTINGS.



RETURN BEND. CLOSE PATTERN.



RETURN BEND. OPEN PATTERN.

## RETURN BENDS.

## CLOSE PATTERN.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Center to Center, inches.....	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	$2\frac{1}{4}$	$2\frac{1}{2}$	$3\frac{1}{4}$	$3\frac{3}{4}$	$4\frac{1}{2}$
Right Hand, each.....	\$0.18	\$0.20	\$0.22	\$0.28	\$0.40	\$0.57	\$1.20	\$1.70
Right Hand, galvanized, each.....	.36	.40	.44	.56	.80	1.14	2.40	3.40
Right and Left, each.....	.21	.23	.26	.33	.46	.66	1.40	1.95

CLOSE PATTERN, PITCHED.  
SUITABLE FOR COILS AS PER TABLE BELOW.

Size, Inches.....	1	1	1	1	1	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$
Length of Pipe in Coil, feet.....	3	4	5	6	8	4	5	6
Right Hand, each.....	\$0.26	\$0.26	\$0.26	\$0.26	\$0.26	\$0.33	\$0.33	\$0.33
Right and Left, each.....	.26	.26	.26	.26	.26	.33	.33	.33

All Right and Left Pitched Return Bends are made to order.

## OPEN PATTERN.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Center to Center, Inches.....	$1\frac{7}{8}$	$2\frac{3}{8}$	3	$3\frac{1}{2}$	$4\frac{1}{2}$	$5\frac{1}{2}$	$6\frac{1}{2}$
Right Hand, each.....	\$0.26	\$0.30	\$0.40	\$0.55	\$0.80	\$1.35	\$2.20
Right Hand, galvanized, each.....	.52	.60	.80	1.10	1.60	2.70	4.40
Right and Left, each.....	.30	.35	.46	.64	.92	1.55	2.50



# CAST-IRON FITTINGS.

335

## RETURN BENDS.



RETURN BEND, WIDE PATTERN.



RETURN BEND, BACK-OUTLET.



Y BRANCH.

### WIDE PATTERN.

Size, Inches.....	1	1	1	1	1	1¼	1¼	1½	1½	1½	2	2	4	4
Center to Center, In..	3	4	5	6	8	4	6	4⅞	6	8	4⅞	6	7½	11
Right Hand, each.....	\$0.45	\$0.50	\$0.60	\$0.75	\$1.00	\$1.00	\$1.25	\$1.30	\$1.60	\$2.00	\$1.75	\$2.00	\$6.50	\$7.50
Galvanized, each.....	.80	.90	1.10	1.30	1.60	1.75	2.00	2.30	2.60	3.25	3.00	3.25	10.00	11.00

### SPECIAL PATTERN.

Size, Inches.....	1	1	1	1	1	1¼	1¼	1¼	1¼	1¼	1¼	1½	1½	2
Center to Center, In.....	2⅞	2¾	3	4	6	2¼	2⅜	3	4	6	8	3½	4¼	4½

Made to order only. Prices on application.

## BACK-OUTLET RETURN BENDS.

Size, Inches .....	¾	1	1¼	1½	2	2½	3
Center to Center, Inches.....	1⅞	2¼	2¼	2½	3¼	3¼	4¼
Right Hand, each.....	\$0.38	\$0.42	\$0.60	\$0.80	\$1.15	\$2.00	\$3.00
Right Hand, Galvanized, each.....	.76	.84	1.20	1.60	2.30	4.00	6.00
Right and Left, each.....	.42	.48	.70	.95	1.30	2.30	3.50

The Back Outlet of Right and Left Return Bends is always tapped right hand.

## Y BRANCHES.

Size, Inches.....	½	¾	1	1¼	1½	2	2½	3	3½	4	5	6	7	8
Each.....	\$0.20	\$0.28	\$0.34	\$0.54	\$0.66	\$0.94	\$1.66	\$2.50	\$3.50	\$4.00	\$7.00	\$9.20	\$15.60	\$22.50
Reducing. ....	.23	.33	.40	.62	.76	1.08	1.90	2.90	4.00	4.60	8.00	10.60	18.00	26.00
Galvanized, each...	.40	.56	.68	1.08	1.32	1.88	3.32	5.00	7.00	8.00	14.00	18.40	31.20	45.00

## CAST-IRON FITTINGS.

## BRANCH TEES.



No. 1. FOR CIRCULATION.



No. 2. FOR CIRCULATION.



No. 3. FOR BOX COILS.

All openings in Branch Tees for Circulation are tapped right hand. Branch Tees for Box Coils are always tapped left hand in branches and right hand in back inlet.

No. of Branches.	1-INCH BRANCH TEES.			1 1/4-INCH BRANCH TEES.			1 1/2-INCH BRANCH TEES.			2-INCH BRANCH TEES.		
	2 1/2 Inch Center to Center.			3 Inch Center to Center.			3 1/2 Inch Center to Center.			4 1/2 Inch Center to Center.		
	1-In. or 1 1/4-In. Run.	1 1/2-In. Run.	2-In. Run.	1 1/4-In. or 1 1/2-In. Run.	2-In. Run.	2 1/2-In. Run.	1 1/2-In. or 2-In. Run.	2 1/2-In. Run.	3-In. Run.	2-In. Run.	2 1/2-In. or 3-In. Run.	3 1/2-In. Run.
2	\$0.90	\$1.00	\$1.15									
3	1.05	1.15	1.35	\$1.65	\$1.90	\$2.40	\$2.70	\$3.45	\$3.80	\$5.25	\$5.75	\$6.25
4	1.15	1.30	1.60	2.00	2.40	2.85	3.35	4.15	4.60	6.40	7.00	7.75
5	1.35	1.45	1.85	2.40	2.90	3.55	4.00	5.00	5.50	7.65	8.50	9.25
6	1.60	1.75	2.10	2.80	3.30	3.95	4.65	5.75	6.25	8.80	9.75	10.75
7	1.90	2.20	2.45	3.20	3.90	4.20	5.25	6.50	7.25	10.60	11.75	13.00
8	2.20	2.45	2.75	3.60	4.50	4.95	5.85	7.00	7.75	11.50	12.75	14.00
9	2.65	2.90	3.40	4.30	5.25	6.15	6.50	8.25	9.00	12.25	13.50	15.00
10		3.30	4.00	4.80	5.85	6.85	7.60	9.25	10.00	13.50	15.00	16.50
11		4.50	4.80	5.00	6.25	7.25	8.00	9.75	10.75			
12		4.75	5.10	5.25	6.50	7.65	8.50	10.50	11.50			
13		5.50	6.00	6.00	7.00	8.25						
14		7.00	7.25	6.75	7.75	9.00						
15		7.50	7.75	7.50	8.50	9.75						
16		8.00	8.25	8.50	9.50	10.75						

One-inch Branch Tees, 1-inch or 1 1/4-inch run, are 1 3/4 inches inside diameter. One-inch Branch Tees, 1 1/2-inch or 2-inch run, are 2 1/4 inches inside diameter. One and one-quarter-inch Branch Tees are all 2 1/2 inches inside diameter. One and one-half-inch Branch Tees are all 2 3/4 inches inside diameter. Two-inch Branch Tees are all 3 1/2 inches inside diameter.

Always order Branch Tees by size and number.

One-inch Branch Tees, 1-inch and 1 1/4-inch run, are also made 2 1/4-inch inside diameter, as *large pattern*.


# CAST-IRON FITTINGS.

337



HOOK PLATES.


HOOK PLATES.



EXPANSION PLATE.



BEAM HOOK.



GAS HOOKS.

Number of Hooks.....	1	2	3	4	5	6	7	8	9	10	11	12
For ¾-inch pipe.....	\$0.08	\$0.16	\$0.21	\$0.24	\$0.28	\$0.34	\$0.40	\$0.45	\$0.50	\$0.56	\$0.68	\$0.72
For 1-inch pipe.....	.09	.18	.23	.26	.32	.38	.48	.59	.65	.70	.85	1.00
For 1¼-inch pipe.....	.10	.21	.27	.32	.41	.52	.68	.80	.90	1.20	1.35	1.40
For 1½-inch pipe.....	.15	.28	.43	.58	.72	.88	1.10	1.25	1.40	1.55	1.65	1.90
For 2-inch pipe.....	.22	.43	.65	.90	1.15	1.35	.....	.....	.....	.....	.....	.....

EXPANSION PLATES.

Number of Hooks.....	1	2	3	4	5	6	7	8	9	10	11	12
For ¾-inch pipe.....	\$0.12	\$0.23	\$0.34	\$0.45	\$0.55	\$0.65	\$0.77	\$0.90	\$1.05	\$1.25	\$1.45	\$1.65
For 1-inch pipe.....	.15	.25	.35	.50	.60	.70	.80	.95	1.10	1.35	1.55	1.70
For 1¼-inch pipe.....	.17	.27	.40	.60	.70	.80	.90	1.15	1.30	1.50	1.70	2.00
For 1½-inch pipe.....	.25	.40	.60	.75	.90	1.00	.....	.....	.....	.....	.....	.....

BEAM HOOKS.

LONG SHANK.

Size, Inches.....	½	¾	1	1¼	1½	2	2½	3
Each.....	\$0.13	.15	.18	.22	.24	.35	.65	.90

GAS HOOKS.

WROUGHT IRON.

Size of Pipe, Inches..	¼	⅜	½	¾	1	1¼	1½	2
Per 100.....	\$0.30	.35	.40	.50	.65	.85	1.00	1.10



## CEILING AND FLOOR PLATES, ETC.



CEILING PLATES IN HALVES.



CEILING PLATES IN ONE PIECE.



FLOOR PLATES.

## CAST-IRON CEILING PLATES IN HALVES.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Each.....	\$0.22	.28	.32	.40	.50	.65	.90	1.00	1.20

## CAST-IRON CEILING PLATES IN ONE PIECE.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
Each.....	\$0.11	.13	.16	.18	.23	.27	.36	.50	.55	.68	.95	1.25

## CAST-IRON FLOOR PLATES.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each.....	\$0.06	.06	.08	.11	.14	.16	.24	.30

This Floor Plate is made with grooves on the under side of the flange, as shown in cut, in order that it may be easily parted by a slight blow when required to be used in halves.



## EXCELSIOR STEAM PIPE INSULATOR.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Each.....	\$0.60	.70	.80	1.00	1.20	1.40	1.65	1.85	2.15

Standard sizes are adjustable from 12 inches to 24 inches. Special lengths made to order.



## PIPE RINGS.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Plain Iron, per 100.....	\$5.00	\$5.00	\$5.80	\$6.75	\$7.50	\$10.00	\$14.00
Galvanized Iron, per 100.....	6.50	6.50	7.00	8.00	9.00	12.00	16.00

## TINNED STRAPS.



Per pound.....\$0.18

# CEILING AND FLOOR PLATES.

339



ADJUSTABLE CEILING PLATE.



ADJUSTABLE FLOOR PLATE.

## CAST-IRON ADJUSTABLE FLOOR AND CEILING PLATES.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
Plain, each.....	\$0.09	\$0.09	\$0.12	\$0.14	\$0.16	\$0.20	\$0.35	\$0.60	\$0.90	\$1.25	\$1.60	\$2.00
Nickel Plated, each.....	.25	.25	.28	.32	.35	.38	.52	.75	1.10	1.50	2.00	2.50

The Nickel-plated Plates are packed one dozen in a box.



CLOSED.




OPEN.

## RUSSELL'S ADJUSTABLE FLOOR AND CEILING PLATES.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Brass, Nickel Plated, each.....	\$0.25	.25	.25	.28	.32	.35	.38	.52	.75



BRASS FLOOR OR CEILING PLATE.



CAST-BRASS FLOOR PLATE.


## STAMPED FLOOR OR CEILING PLATES.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Nickel Plated, each.....	\$0.09	.10	.11	.12	.13	.15

## CAST-BRASS FLOOR PLATE.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Nickel Plated, each.....	\$0.20	.25	.30	.35	.40

## EXPANSION PIPE HANGERS, OR RING HOOKS.




Size, Inches .....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6	7	8
Complete, each .....	\$0.17	.18	.19	.25	.29	.36	.44	.55	.63	1.12	1.35	1.80	2.25
Size of Pipe, Rings and Buttons are Tapped for, inches.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$

## PARTS OF EXPANSION PIPE HANGERS.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6	7	8
Plates, each.....	\$0.08	\$0.08	\$0.08	\$0.09	\$0.09	\$0.10	\$0.10	\$0.10	\$0.10	\$0.10	\$0.10	\$0.10	\$0.10
Buttons, each.....	.06	.06	.06	.07	.07	.08	.08	.08	.08	.08	.08	.08	.08
Rings, each.....	.08	.12	.15	.20	.25	.30	.40	.50	.60	1.00	1.25	1.70	2.15

## EXPANSION PIPE HANGERS.

## SECTIONAL PATTERN.



The object of this Sectional Pipe Hanger is readily understood. Pipe can be run and supported upon temporary wood hangers, and when in proper line these Sectional Hangers can be conveniently applied.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
Price, each .....	\$0.32	.33	.35	.45	.55	.65	.80	1.00	1.15	2.00	2.50
Size of Pipe, Rings and Buttons are Tapped for, Inches..	$\frac{1}{8}$	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{3}{4}$







LONG RADIUS ELL.



LONG RADIUS DOUBLE BRANCH ELL.



LONG RADIUS TEE.



LONG RADIUS CROSS.

## LONG RADIUS ELLS.

Size, Inches...	1	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Straight, each...	\$0.32	\$0.40	\$0.55	\$0.80	\$1.20	\$2.25	\$3.25	\$3.50	\$5.50	\$6.50	\$8.75	\$13.00	\$17.00	\$25.50	\$30.00	\$40.00
Reducing, each.	.48	.60	.83	1.20	1.80	3.38	4.88	5.25	8.25	9.75	13.13	19.50	25.50	38.25	45.00	60.00

## LONG RADIUS DOUBLE BRANCH ELLS.

Size, Inches...	1	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Straight, each...	\$0.64	\$0.80	\$1.10	\$1.60	\$2.40	\$4.50	\$6.50	\$7.00	\$11.00	\$13.00	\$17.50	\$26.00	\$34.00	\$51.00	\$60.00	\$80.00
Reducing, each.	.96	1.20	1.65	2.40	3.60	6.75	9.75	10.50	16.50	19.50	26.25	39.00	51.00	76.50	90.00	120.00


## LONG RADIUS TEES.

Size, Inches...	1	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Straight, each...	\$0.48	\$0.60	\$0.82	\$1.20	\$1.80	\$3.40	\$4.90	\$5.25	\$8.25	\$9.75	\$13.25	\$19.50	\$25.50	\$38.00	\$45.00	\$60.00
Reducing, each.	.72	.90	1.23	1.80	2.70	5.10	7.35	7.88	12.38	14.63	19.88	29.25	38.25	57.00	67.50	90.00


## LONG RADIUS CROSSES.

Size, Inches...	1	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Each .....	\$0.85	1.10	1.50	2.15	3.20	6.00	8.75	9.50	15.00	17.50	24.00	35.00	45.00	68.00	80.00	107.00

## CAST-IRON FITTINGS.



LONG RADIUS TEE, FLANGED.



LONG RADIUS REDUCING TEE, FLANGED.



DOUBLE LONG RADIUS TEE, FLANGED.

## LONG RADIUS TEES.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	6	7	7½	8½	9	9½	10	11	12½	13½	15	16	19	21	23½	25
Flanges Faced.....	\$8.00	\$8.25	\$9.50	\$11.00	\$12.00	\$15.00	\$16.25	\$20.00	\$26.50	\$33.50	\$43.50	\$53.50	\$74.00	\$96.00	\$140.00	\$178.00
Flanges Faced & Drilled	9.50	10.00	11.25	12.75	15.00	18.00	19.25	23.00	32.00	39.00	50.00	60.00	83.00	107.00	153.00	193.00

## LONG RADIUS REDUCING TEES.

Size, Inches.....	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Flanges Faced.....	\$9.50	\$11.00	\$12.50	\$13.75	\$17.25	\$18.75	\$23.00	\$30.00	\$38.50	\$50.00	\$61.50	\$85.00	\$110.00	\$160.00	\$205.00
Flanges Faced and Drilled...	11.25	12.75	14.25	16.75	20.25	21.75	26.00	35.50	44.00	56.50	68.00	94.00	121.00	173.00	220.00

Long Radius Tees with side opening larger than the run, special price.

## LONG RADIUS DOUBLE TEES.

Size, Inches.....	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	7	7½	8½	9	9½	10	11	12½	13½	15	16	19	21	23½	25
Flanges Faced.....	\$8.25	\$9.50	\$11.00	\$12.00	\$15.00	\$16.25	\$20.00	\$26.50	\$33.50	\$43.50	\$53.50	\$74.00	\$96.00	\$140.00	\$178.00
Flanges Faced and Drilled...	10.00	11.25	12.75	15.00	18.00	19.25	23.00	32.00	39.00	50.00	60.00	83.00	107.00	153.00	193.00

## LONG RADIUS DOUBLE TEES, REDUCING.


Size, Inches.....	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Flanges Faced.....	\$9.50	11.00	\$12.50	\$13.75	\$17.25	\$18.75	\$23.00	\$30.00	\$38.50	\$50.00	\$61.50	\$85.00	\$110.00	\$160.00	\$205.00
Flanges Faced and Drilled ...	11.25	12.75	14.25	16.75	20.25	21.75	26.00	35.50	44.00	56.50	68.00	94.00	121.00	173.00	220.00

List on Long Radius Double Tees, Reducing, is for sizes increasing one or two sizes on the Branch. If Branch is wanted more than two sizes larger, or reducing on the run, special price will be charged.





FLANGED ELBOW.



FLANGED 45° ELBOW.

## FLANGED ELBOWS.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	6	7	7½	8½	9	9¼	10	11	12½	13½	15	16	19	21	23½	25
With Flanges Faced.....	\$4.75	\$5.00	\$5.75	\$6.50	\$7.25	\$9.00	\$9.75	\$12.00	\$16.00	\$20.00	\$26.00	\$32.00	\$44.00	\$58.00	\$84.00	\$108.00
With Flanges Faced and Drilled.	5.75	6.25	7.00	7.75	9.25	11.00	11.75	14.00	19.75	23.75	30.00	36.00	50.00	65.00	93.00	118.00

## FLANGED 45° ELBOWS.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	6	7	7½	8½	9	9¼	10	11	12½	13½	15	16	19	21	23½	25
Flanges Faced.....	\$5.25	\$5.50	\$6.25	\$7.25	\$8.00	\$10.00	\$10.75	\$13.00	\$16.00	\$20.00	\$26.00	\$32.00	\$44.00	\$58.00	\$84.00	\$108.00
Flanges Faced and Drilled.	6.25	6.75	7.50	8.50	10.00	12.00	12.75	15.00	19.75	23.75	30.00	36.00	50.00	65.00	93.00	118.00



FLANGED TEE.

## FLANGED TEES.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	6	7	7½	8½	9	9¼	10	11	12½	13½	15	16	19	21	23½	25
Flanges Faced.....	\$7.00	\$7.25	\$8.25	\$9.50	\$10.50	\$13.00	\$14.25	\$17.50	\$23.00	\$29.00	\$38.00	\$46.50	\$64.00	\$84.00	\$122.00	\$155.00
Flanges Faced and Drilled.	8.50	9.00	10.00	11.25	13.50	16.00	17.25	20.50	28.75	34.75	44.00	52.50	73.00	95.00	135.00	170.00

Flanged Fittings will always be furnished *faced only*, unless otherwise ordered.




## CAST-IRON FITTINGS.

## STANDARD



FLANGED REDUCING TEE.



FLANGED CROSS.

## REDUCING TEES.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
With Flanges Faced.....	\$8.00	\$8.25	\$9.50	\$11.00	\$12.00	\$15.00	\$16.25	\$20.00	\$26.50	\$33.50	\$43.50	\$53.50	\$74.00	\$96.00	\$140.00	\$178.00
Flanges Faced & Drilled	9.50	10.00	11.25	12.75	15.00	18.00	19.25	23.00	32.00	39.00	50.00	60.00	83.00	107.00	153.00	193.00

## CROSSES.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	6	7	7½	8½	9	9¼	10	11	12½	13½	15	16	19	21	23½	25
With Flanges Faced.....	\$9.50	\$10.00	\$11.50	\$13.00	\$14.50	\$18.00	\$19.50	\$24.00	\$32.00	\$40.00	\$52.00	\$64.00	\$88.00	\$116.00	\$168.00	\$216.00
Flanges Faced & Drilled	11.50	12.50	14.00	15.50	18.50	22.00	23.50	28.00	39.50	47.50	60.00	72.00	100.00	130.00	186.00	236.00



FLANGED Y BRANCH.

## Y BRANCHES.


Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18
Diameter of Flanges.....	6	7	7½	8½	9	9¼	10	11	12½	13½	15	16	19	21	23½	25
With Flanges Faced.....	\$9.50	\$10.00	\$11.50	\$13.00	\$14.50	\$18.00	\$19.50	\$24.00	\$32.00	\$40.00	\$52.00	\$64.00	\$88.00	\$116.00	\$168.00	\$216.00
Flanges Faced & Drilled	11.50	12.50	14.00	15.50	18.50	22.00	23.50	28.00	39.50	47.50	60.00	72.00	100.00	130.00	186.00	236.00

# CAST-IRON FITTINGS.

345

## STANDARD FLANGES.

FACED AND DRILLED.



FACED FLANGES.




BLIND FLANGES.

FACED BLIND FLANGES.

PRICE.			PRICE.		
Size, Inches.	Faced, Each.	Faced and Drilled, Each.	Size, Inches.	Faced, Each.	Faced and Drilled, Each.
2 x 6	\$1.20	\$1.50	2 x 6	\$1.40	\$1.70
2½ x 7	1.40	2.00	2½ x 7	1.60	2.20
3 x 7½	1.60	2.25	3 x 7½	1.85	2.50
3½ x 8½	1.80	2.50	3½ x 8½	2.10	2.80
4 x 9	2.15	3.00	4 x 9	2.50	3.35
4½ x 9¼	2.50	3.35	4½ x 9¼	2.90	3.75
5 x 10	2.80	3.65	5 x 10	3.25	4.10
6 x 11	3.20	4.00	6 x 11	3.70	4.50
7 x 12½	4.35	5.75	7 x 12½	5.00	6.40
8 x 13½	5.00	6.50	8 x 13½	5.75	7.25
9 x 15	6.75	8.25	9 x 15	7.75	9.25
10 x 16	7.75	9.25	10 x 16	9.00	10.60
12 x 19	10.50	12.50	12 x 19	14.00	16.00
14 x 21	13.75	16.00	14 x 21	17.50	19.75
16 x 23½	22.50	26.00	16 x 23½	28.00	31.50
			18 x 25	33.00	36.50
			20 x 27½	36.00	40.00
			22 x 29½	41.00	46.00
			24 x 31½	50.00	55.00

## CAST-IRON FITTINGS.

## FLANGES AND TEMPLATES FOR DRILLING.



Size, Inches.	Diameter of Flanges, Inches.	CHICAGO STANDARD.			MASTER STEAM FITTERS' STANDARD.		
		Bolt Circle, Inches.	Number of Bolts.	Size of Bolts.	Bolt Circle, Inches.	Number of Bolts.	Size of Bolts.
2	6	4 $\frac{3}{4}$	4	$\frac{5}{8}$	4 $\frac{3}{4}$	4	$\frac{1}{2}$
2 $\frac{1}{2}$	7	5 $\frac{1}{2}$	4	$\frac{5}{8}$	5 $\frac{1}{2}$	4	$\frac{1}{2}$
3	7 $\frac{1}{2}$	6	4	$\frac{5}{8}$	6	4	$\frac{1}{2}$
3 $\frac{1}{2}$	8 $\frac{1}{2}$	6 $\frac{3}{4}$	4	$\frac{5}{8}$	7	4	$\frac{1}{2}$
4	9	7 $\frac{1}{4}$	8	$\frac{5}{8}$	7 $\frac{1}{2}$	4	$\frac{5}{8}$
4 $\frac{1}{2}$	9 $\frac{1}{4}$	7 $\frac{3}{4}$	8	$\frac{5}{8}$	7 $\frac{3}{4}$	8	$\frac{5}{8}$
5	10	8 $\frac{1}{4}$	8	$\frac{5}{8}$	8 $\frac{1}{2}$	8	$\frac{5}{8}$
6	11	9 $\frac{1}{4}$	8	$\frac{5}{8}$	9 $\frac{1}{2}$	8	$\frac{5}{8}$
7	12 $\frac{1}{2}$	11	12	$\frac{5}{8}$	10 $\frac{3}{4}$	8	$\frac{5}{8}$
8	13 $\frac{1}{2}$	12	12	$\frac{5}{8}$	11 $\frac{3}{4}$	8	$\frac{5}{8}$
9	15	13	12	$\frac{3}{4}$	13 $\frac{1}{4}$	12	$\frac{5}{8}$
10	16	14 $\frac{1}{4}$	12	$\frac{3}{4}$	14 $\frac{1}{4}$	12	$\frac{3}{4}$
12	19	17	16	$\frac{3}{4}$	17	12	$\frac{3}{4}$
14	21	18 $\frac{1}{2}$	16	$\frac{7}{8}$	18 $\frac{3}{4}$	12	$\frac{7}{8}$
16	23 $\frac{1}{2}$	21 $\frac{1}{2}$	20	$\frac{7}{8}$	21 $\frac{1}{4}$	16	$\frac{7}{8}$
18	25	22 $\frac{1}{2}$	20	$\frac{7}{8}$	22 $\frac{3}{4}$	16	1
20	27 $\frac{1}{2}$	24 $\frac{3}{4}$	20	1	25	20	1
22	29 $\frac{1}{2}$	27 $\frac{1}{2}$	24	1	27 $\frac{1}{4}$	20	1
24	31 $\frac{1}{2}$	29 $\frac{1}{2}$	24	1	29 $\frac{1}{2}$	20	1

We will execute orders to Chicago Standard unless otherwise ordered.







# CAST-IRON FITTINGS.

347

## EXTRA HEAVY FITTINGS.

FOR A WORKING PRESSURE OF 200 POUNDS.



Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	10	12
Elbows, each.....	\$0.30	\$0.35	\$0.45	\$0.60	\$0.75	\$1.25	\$2.00	\$2.75	\$3.50	\$4.25	\$5.50	\$8.00	\$12.00	\$17.00	\$28.00	\$40.00
Elbows, Reducing, each.....	.40	.45	.55	.75	.95	1.55	2.50	3.40	4.40	5.30	6.80	10.00	15.00	21.00	35.00	50.00
Elbows, 45°, each.....	.40	.45	.55	.70	.90	1.50	2.50	3.50	4.50	5.50	6.75	9.75	14.50	21.00	34.00	48.00
Tees, each.....	.50	.55	.70	.90	1.15	1.80	3.00	4.25	5.50	6.75	8.25	12.00	18.00	25.00	42.00	60.00
Tees, Reducing, each.....	.65	.70	.90	1.15	1.40	2.25	3.75	5.30	6.85	8.50	10.25	15.00	22.50	31.00	52.00	75.00
Crosses, each.....	.65	.70	.90	1.20	1.50	2.50	4.00	5.50	7.00	8.50	11.00	16.00	24.00	34.00	56.00	80.00
Crosses, Reducing, each.....	.85	.90	1.15	1.50	1.85	3.15	5.00	6.85	8.75	10.00	13.75	20.00	30.00	42.00	70.00	100.00

# 348 LIST OF STANDARD SIZES OF CAST-IRON FITTINGS.

(Adopted at Meeting of Makers of Cast-Iron Fittings, June 24, 1897.)

Sizes differing from Standard Sizes, if furnished, are to be charged at 5 per cent. gross discount higher than Standard Sizes.

## STRAIGHT SIZES.

Elbows and Tees— $\frac{1}{4}$  to 12 inch.  
Elbows, 45°— $\frac{3}{8}$  to 12 inch.  
Return Bends— $\frac{3}{4}$  to 3 inch.  
Caps and Locknuts—2 to 12 inch.

Y Branches— $\frac{1}{2}$  to 10 inch.  
Elbows, Right and Left— $\frac{1}{4}$  to 3 inch.  
Crosses— $\frac{1}{2}$  to 12 inch.

Offsets— $\frac{3}{4}$  to 6 to offset 4 inch, 6 inch and 8 inch.  
Plugs— $\frac{1}{4}$  to 12 inch.  
Flange Unions— $\frac{1}{2}$  to 12 inch.

## ELBOWS—REDUCING SIZES.

$\frac{1}{2}$ x $\frac{3}{8}$ $\frac{3}{4}$ x $\frac{1}{2}$ 1 x $\frac{3}{4}$ 1 x $\frac{1}{2}$ $1\frac{1}{4}$ x 1	$\frac{1}{4}$ x $\frac{3}{4}$ $\frac{1}{4}$ x $\frac{1}{2}$ $\frac{1}{2}$ x $\frac{1}{4}$ $\frac{1}{2}$ x 1 $\frac{1}{2}$ x $\frac{3}{4}$	2 x $1\frac{1}{2}$ 2 x $1\frac{1}{4}$ 2 x 1 2½ x 2 2½ x $1\frac{1}{2}$	3 x $2\frac{1}{2}$ 3 x 2 3½ x 3 4 x $3\frac{1}{2}$ 4 x 3	4 x $2\frac{1}{4}$ 4½ x 4 5 x 4 6 x 5 6 x 4	8 x 6 ..... ..... ..... .....
--	---	--	--	---	---

## REDUCING COUPLINGS.

2½ x 2 2½ x $1\frac{1}{2}$ 3 x $2\frac{1}{2}$ 3 x 2	3½ x 3 3½ x $2\frac{1}{2}$ 4 x $3\frac{1}{2}$ 4 x 3	4 x $2\frac{1}{2}$ 4 x 2 4½ x 4 .....	5 x 4 5 x 3 .....	6 x 5 6 x 4 6 x 3 7 x 6	8 x 6 10 x 8 12 x 10 .....
--	--	--	-------------------------	----------------------------------	-------------------------------------

## TEES—BULL HEAD.

Tees with both ends of run the same size, with the outlet larger, thus:  $1 \xrightarrow{2} 1$  are known as Bull Head, and are read, 1 x 2.

$\frac{3}{8}$ x $\frac{1}{2}$ $\frac{1}{2}$ x 1 $\frac{1}{2}$ x $\frac{3}{4}$ $\frac{3}{4}$ x 2 $\frac{3}{4}$ x $1\frac{1}{2}$	$\frac{3}{4}$ x $1\frac{1}{4}$ $\frac{3}{4}$ x 1 1 x 2 1 x $1\frac{1}{2}$ 1 x $1\frac{1}{4}$	$1\frac{1}{4}$ x 2 $1\frac{1}{4}$ x $1\frac{1}{2}$ $1\frac{1}{2}$ x $2\frac{1}{2}$ $1\frac{1}{2}$ x 2 2 x 3	2 x $2\frac{1}{2}$ $2\frac{1}{2}$ x 4 $2\frac{1}{2}$ x 3 3 x 4 3 x $3\frac{1}{2}$	$3\frac{1}{2}$ x 4 4 x 6 4 x 5 5 x 6 6 x 8	6 x 7 ..... ..... ..... .....
--	--	---	---	--	---

## TEES—REDUCING ON OUTLET.

Tees which reduce on the outlet, thus:  $2 \xrightarrow{1\frac{1}{4}} 2$  are read, 2 x  $1\frac{1}{4}$ .

$\frac{1}{2}$ x $\frac{3}{8}$ $\frac{3}{4}$ x $\frac{1}{2}$ $\frac{3}{4}$ x $\frac{3}{8}$ 1 x $\frac{3}{4}$ 1 x $\frac{1}{2}$ 1 x $\frac{3}{8}$ $1\frac{1}{4}$ x 1 $1\frac{1}{4}$ x $\frac{3}{4}$ $1\frac{1}{4}$ x $\frac{1}{2}$ $1\frac{1}{2}$ x $1\frac{1}{4}$ $1\frac{1}{2}$ x 1 $1\frac{1}{2}$ x $\frac{3}{4}$ $1\frac{1}{2}$ x $\frac{1}{2}$	2 x $1\frac{1}{2}$ 2 x $1\frac{1}{4}$ 2 x 1 2 x $\frac{3}{4}$ 2 x $\frac{1}{2}$ $2\frac{1}{2}$ x 2 $2\frac{1}{2}$ x $1\frac{1}{2}$ $2\frac{1}{2}$ x $1\frac{1}{4}$ $2\frac{1}{2}$ x 1 $2\frac{1}{2}$ x $\frac{3}{4}$ 3 x $2\frac{1}{2}$ 3 x 2 3 x $1\frac{1}{2}$	3 x $1\frac{1}{4}$ 3 x $1\frac{1}{2}$ 3 x $\frac{3}{4}$ $3\frac{1}{2}$ x 3 $3\frac{1}{2}$ x $2\frac{1}{2}$ $3\frac{1}{2}$ x 2 $3\frac{1}{2}$ x $1\frac{1}{2}$ $3\frac{1}{2}$ x $1\frac{1}{4}$ $3\frac{1}{2}$ x 1 4 x $3\frac{1}{2}$ 4 x 3 4 x $2\frac{1}{2}$ 4 x 2	4 x $1\frac{1}{2}$ 4 x $1\frac{1}{4}$ 4 x 1 4 x $\frac{3}{4}$ $4\frac{1}{2}$ x 4 $4\frac{1}{2}$ x $3\frac{1}{2}$ $4\frac{1}{2}$ x 3 $4\frac{1}{2}$ x $2\frac{1}{2}$ $4\frac{1}{2}$ x 2 5 x 4 5 x $3\frac{1}{2}$ 5 x 3 5 x $2\frac{1}{2}$	5 x 2 5 x $1\frac{1}{2}$ 5 x $1\frac{1}{4}$ 6 x 5 6 x 4 6 x $3\frac{1}{2}$ 6 x 3 6 x $2\frac{1}{2}$ 6 x 2 7 x 6 7 x 5 7 x 4 8 x 6	8 x 5 8 x 4 8 x $3\frac{1}{2}$ 8 x 3 8 x $2\frac{1}{2}$ 8 x 2 10 x 8 10 x 6 10 x 5 10 x 4 12 x 10 12 x 8 12 x 6
---	--	--	--	---	---

# LIST OF STANDARD SIZES OF CAST-IRON FITTINGS.

349

## TEES—REDUCING ON RUN.

Tees reducing on run, thus :  $\frac{1\frac{1}{4}}{2}$  are read, 2 x  $1\frac{1}{2}$  x  $1\frac{1}{4}$ .

$\frac{1}{2}$ x $\frac{3}{8}$ x $\frac{1}{2}$	$1\frac{1}{4}$ x $1\frac{1}{2}$ x $1\frac{1}{4}$	2 x $1\frac{1}{4}$ x $1\frac{1}{4}$	3 x $2\frac{1}{2}$ x $1\frac{1}{2}$	4 x 3 x $3\frac{1}{2}$	5 x 3 x $2\frac{1}{2}$
$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{8}$	$1\frac{1}{2}$ x $1\frac{1}{4}$ x 2	2 x $1\frac{1}{4}$ x $1\frac{3}{4}$	3 x $2\frac{1}{2}$ x $1\frac{1}{4}$	4 x 3 x $3\frac{1}{2}$	5 x 3 x 2
$\frac{3}{4}$ x $\frac{1}{2}$ x 1	$1\frac{1}{2}$ x 1 x 2	2 x $1\frac{1}{4}$ x 2	3 x 2 x 3	4 x 3 x $2\frac{1}{2}$	5 x $2\frac{1}{2}$ x 5
$\frac{3}{4}$ x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x $1\frac{3}{4}$ x 2	2 x 1 x $1\frac{1}{2}$	3 x 2 x $2\frac{1}{2}$	4 x 3 x 2	5 x $2\frac{1}{2}$ x 4
$\frac{3}{4}$ x $1\frac{1}{2}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x $1\frac{1}{4}$ x $1\frac{1}{2}$	2 x 1 x $1\frac{1}{4}$	3 x 2 x 2	4 x 3 x $1\frac{1}{2}$	5 x $2\frac{1}{2}$ x 3
$\frac{3}{4}$ x $1\frac{3}{4}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x $1\frac{1}{4}$ x 1	2 x 1 x 1	3 x 2 x $1\frac{1}{2}$	4 x 3 x $1\frac{1}{4}$	5 x 2 x 5
1 x $\frac{3}{4}$ x $2\frac{1}{8}$	$1\frac{1}{2}$ x $1\frac{1}{4}$ x $\frac{3}{4}$	2 x 1 x $\frac{3}{4}$	3 x 2 x $1\frac{1}{4}$	4 x 3 x 1	6 x 5 x 6
1 x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x $1\frac{1}{4}$ x $1\frac{1}{2}$	2 x $\frac{3}{4}$ x 2	3 x 2 x 1	4 x $2\frac{1}{2}$ x $\frac{3}{4}$	6 x 5 x 5
1 x $\frac{3}{4}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x $1\frac{1}{4}$ x 1	2 x $\frac{3}{4}$ x $1\frac{1}{2}$	3 x $1\frac{1}{2}$ x 3	4 x $2\frac{1}{2}$ x 4	6 x 4 x 6
1 x $\frac{3}{4}$ x 1	$1\frac{1}{2}$ x 1 x $1\frac{1}{4}$	2 x $\frac{3}{4}$ x 2	3 x $1\frac{1}{2}$ x $2\frac{1}{2}$	4 x $2\frac{1}{2}$ x 3	6 x 3 x 6
1 x $\frac{3}{4}$ x $\frac{3}{4}$	$1\frac{1}{2}$ x 1 x 1	2 x 1 x 1	3 x $1\frac{1}{2}$ x 2	4 x $2\frac{1}{2}$ x $2\frac{1}{2}$	6 x $2\frac{1}{4}$ x 6
1 x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x $2\frac{1}{2}$ x 2	7 x 6 x 7
1 x $\frac{3}{4}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x 1 x 1	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 2	4 x $2\frac{1}{2}$ x $1\frac{1}{2}$	7 x 6 x 6
1 x $\frac{3}{4}$ x 1	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x $2\frac{1}{2}$ x 4	7 x 5 x 5
1 x $\frac{3}{4}$ x $\frac{3}{4}$	$1\frac{1}{2}$ x 1 x $1\frac{1}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x 2 x $2\frac{1}{2}$	8 x 7 x 6
1 x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x 1 x 1	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x 2 x 2	8 x 6 x 8
1 x $\frac{3}{4}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x 2 x $1\frac{1}{2}$	8 x 6 x 7
1 x $\frac{3}{4}$ x 1	$1\frac{1}{2}$ x 1 x $1\frac{1}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x $1\frac{1}{2}$ x 4	8 x 6 x 6
1 x $\frac{3}{4}$ x $\frac{3}{4}$	$1\frac{1}{2}$ x 1 x 1	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x $1\frac{1}{2}$ x 4	8 x 5 x 8
1 x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	4 x 1 x 4	8 x 5 x 5
1 x $\frac{3}{4}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x 1 x 1	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 4 x 5	8 x 4 x 8
1 x $\frac{3}{4}$ x 1	$1\frac{1}{2}$ x 1 x $1\frac{1}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 4 x 4	10 x 8 x 8
1 x $\frac{3}{4}$ x $\frac{3}{4}$	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 4 x 3	12 x 8 x 10
1 x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x 1 x 1	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 4 x $2\frac{1}{2}$	12 x 8 x 8
1 x $\frac{3}{4}$ x $1\frac{1}{4}$	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 4 x 2	.....
1 x $\frac{3}{4}$ x 1	$1\frac{1}{2}$ x 1 x 1	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 3 x 5	.....
1 x $\frac{3}{4}$ x $\frac{3}{4}$	$1\frac{1}{2}$ x 1 x $1\frac{1}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 3 x 4	.....
1 x $\frac{3}{4}$ x $1\frac{1}{2}$	$1\frac{1}{2}$ x 1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$ x 3	5 x 3 x 3	.....

## CROSSES—REDUCING SIZES.

The outlets of a Cross are always the same size, and are indicated by the last figure. Thus : A Cross  $\frac{3}{4}$ — $\frac{1}{2}$ — $\frac{3}{4}$  is called a  $\frac{3}{4}$  x  $\frac{1}{2}$  Cross.  
A Cross reducing on the run, thus :  $\frac{1}{2}$ — $\frac{1}{4}$ — $\frac{1}{2}$  is called a  $1\frac{1}{2}$  x  $1\frac{1}{4}$  x 1 Cross.

$\frac{1}{2}$ x $\frac{3}{8}$	$1\frac{1}{4}$ x $\frac{3}{4}$	2 x $1\frac{1}{4}$	$2\frac{1}{2}$ x $\frac{3}{4}$	$3\frac{1}{2}$ x 3	5 x 4	6 x 3	10 x 8
$\frac{1}{2}$ x $\frac{1}{2}$	$1\frac{1}{4}$ x $\frac{1}{2}$	2 x 1	3 x $2\frac{1}{2}$	$3\frac{1}{2}$ x $2\frac{1}{2}$	5 x 3	6 x $2\frac{1}{2}$	10 x 7
$\frac{3}{4}$ x $\frac{3}{8}$	$1\frac{1}{2}$ x $1\frac{1}{4}$	2 x $\frac{3}{4}$	3 x 2	$3\frac{1}{2}$ x 2	5 x $2\frac{1}{2}$	6 x 2	12 x 10
$\frac{3}{4}$ x $\frac{1}{2}$	$1\frac{1}{2}$ x 1	$2\frac{1}{2}$ x 2	3 x $1\frac{1}{2}$	4 x $3\frac{1}{2}$	5 x 2	7 x 6	12 x 8
1 x $\frac{3}{4}$	$1\frac{1}{2}$ x $\frac{3}{4}$	$2\frac{1}{2}$ x $1\frac{1}{2}$	3 x $1\frac{1}{4}$	4 x 3	6 x 5	7 x 5	.....
$1\frac{1}{4}$ x $\frac{1}{2}$	$1\frac{1}{2}$ x $1\frac{1}{2}$	$2\frac{1}{2}$ x $1\frac{1}{4}$	3 x 1	4 x $2\frac{1}{2}$	6 x 4	8 x 7	.....
$1\frac{1}{4}$ x 1	2 x $1\frac{1}{2}$	$2\frac{1}{2}$ x 1	3 x $\frac{3}{4}$	4 x 2	6 x $3\frac{1}{2}$	8 x 6	.....

## BUSHINGS.

[NOTE.—Bushings reducing one size only, up to and including  $2\frac{1}{2}$  inches are malleable, and will be found, therefore, listed among the malleable fittings.]

$\frac{1}{2}$ x $\frac{1}{4}$	$1\frac{1}{2}$ x $\frac{3}{4}$	3 x $2\frac{1}{2}$	$3\frac{1}{2}$ x 1	$4\frac{1}{2}$ x 3	6 x 4	7 x 3	9 x 6
$\frac{3}{4}$ x $\frac{3}{8}$	$1\frac{1}{2}$ x $\frac{1}{2}$	3 x 2	4 x $3\frac{1}{2}$	$4\frac{1}{2}$ x $2\frac{1}{2}$	6 x $3\frac{1}{2}$	7 x $2\frac{1}{2}$	10 x 8
$\frac{3}{4}$ x $\frac{1}{2}$	2 x $1\frac{1}{4}$	3 x $1\frac{1}{2}$	4 x 3	5 x $4\frac{1}{2}$	6 x 3	7 x 2	10 x 6
1 x $\frac{3}{8}$	2 x 1	3 x $1\frac{1}{4}$	4 x $2\frac{1}{2}$	5 x 4	6 x $2\frac{1}{2}$	8 x 7	12 x 10
1 x $\frac{1}{2}$	2 x $\frac{3}{4}$	3 x 1	4 x 2	5 x $3\frac{1}{2}$	6 x 2	8 x 6	12 x 8
1 x $\frac{3}{4}$	2 x $1\frac{1}{2}$	$3\frac{1}{2}$ x 3	4 x $1\frac{1}{2}$	5 x 3	7 x 6	8 x 5	12 x 6
$1\frac{1}{4}$ x $\frac{3}{4}$	$2\frac{1}{2}$ x $1\frac{1}{2}$	$3\frac{1}{2}$ x $2\frac{1}{2}$	4 x $1\frac{1}{4}$	5 x $2\frac{1}{2}$	7 x 5	8 x 4	.....
$1\frac{1}{4}$ x $\frac{1}{2}$	$2\frac{1}{2}$ x $1\frac{1}{4}$	$3\frac{1}{2}$ x 2	4 x 1	5 x 2	7 x $4\frac{1}{2}$	8 x 3	.....
$1\frac{1}{4}$ x $\frac{3}{8}$	$2\frac{1}{2}$ x 1	$3\frac{1}{2}$ x $1\frac{1}{2}$	$4\frac{1}{2}$ x 4	6 x 5	7 x 4	9 x 8	.....
$1\frac{1}{2}$ x 1	$2\frac{1}{2}$ x $\frac{3}{4}$	$3\frac{1}{2}$ x $1\frac{1}{4}$	$4\frac{1}{2}$ x $3\frac{1}{2}$	6 x $4\frac{1}{2}$	7 x $3\frac{1}{2}$	9 x 7	.....



# MALLEABLE-IRON FITTINGS.



GAS ELBOW.



BEADED ELBOW.




45° ELBOW.

## ELBOWS.


Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Plain, each.....	\$0.04	\$0.04	\$0.06	\$0.10	\$0.15	\$0.22	\$0.25	\$0.35	\$0.50	\$ .80	\$1.50	\$2.25	\$3.00
Galvanized, each.....	.....	.05	.08	.14	.20	.32	.40	.60	.90	1.35	2.60	3.75	5.00

## ELBOWS, 45°.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Plain, each.....	\$0.10	\$0.12	\$0.18	\$0.26	\$0.36	\$0.54	\$ .82	\$1.25
Galvanized, each.....	.15	.20	.25	.40	.50	.85	1.35	2.00



STREET ELBOW.



SIDE OUTLET ELBOW.



DROP ELBOW.

## STREET ELBOWS.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Plain, each.....	\$0.10	\$0.12	\$0.20	\$0.25	\$0.40	\$0.55	\$0.90
Galvanized, each.....	.12	.15	.28	.35	.55	.80	1.30

## SIDE OUTLET ELBOWS.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$
Each.....	\$0.08	.10	.18	.30	.45	.60

## DROP ELBOWS.


Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1
Plain, each.....	\$0.06	\$0.08	\$0.12	\$0.20	\$0.25
Galvanized, each.....	.....	.12	.20	.35	.40

# MALLEABLE IRON FITTINGS.

351



DROP ELBOW, FLANGE RIGHT.



DROP ELBOW, FLANGE LEFT.



LONG DROP ELBOW.

## DROP ELBOWS.

Size, Inches.....	
Right or Left Drop Elbows, each.....	
Long Drop Elbows, each.....	
Long Drop Elbows, Galvanized, each.....	

$\frac{1}{4}$  x  $\frac{3}{8}$

\$0.08  
.10  
.18

$\frac{3}{8}$  x  $\frac{3}{8}$

\$0.08  
.10  
.18



GAS TEE.



BEADED TEE.

## TEES.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Plain, each.....	\$0.07	\$0.07	\$0.08	\$0.11	\$0.15	\$0.25	\$0.30	\$0.45	\$0.60	\$1.05	\$1.70	\$2.50	\$3.40
Galvanized, each.....		.09	.10	.16	.20	.38	.50	.70	1.00	1.90	3.00	4.25	5.75



FOUR-WAY TEE.



CROSS-OVER FITTING.

## FOUR-WAY AND DROP TEES AND CROSS-OVER FITTINGS.



DROP TEE.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$
Four-Way Tees, Plain, each.....		\$0.12	\$0.14	\$0.20	\$0.35	\$0.50	\$0.80
Drop Tees, Plain, each.....	\$0.08	.10	.14	.22	.30		
Drop Tees, Galvanized, each.....		.15	.25	.40	.55		
Long Drop Tees, each.....		.12					
Cross-over Fittings, Galvanized, each.....			.22	.32	.50		

# MALLEABLE-IRON FITTINGS.




GAS CROSS.



BEADED CROSS.

## CROSSES.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Plain, each.....	\$0.08	\$0.10	\$0.12	\$0.20	\$0.30	\$0.40	\$0.60	\$1.00	\$1.75	\$3.00	\$3.25	\$5.25
Galvanized, each.....		.15	.17	.25	.45	.60	.90	1.50	2.75	4.25	5.00	8.00



REDUCER.



CAP.

## REDUCERS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Plain, each.....	\$0.03	\$0.03	\$0.05	\$0.10	\$0.16	\$0.20	\$0.28	\$0.45	\$0.70	\$1.00	\$1.50	\$1.85
Galvanized, each.....		.05	.08	.15	.25	.35	.45	.75	1.05	1.65	2.40	3.05

## CAPS.


Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Plain, each.....	\$0.03	\$0.04	\$0.05	\$0.08	\$0.12	\$0.16	\$0.24	\$0.32	\$0.45	\$0.85	\$1.00	\$1.20
Galvanized, each.....	.04	.05	.08	.12	.17	.24	.38	.52	.76	1.30	2.25	3.00




# MALLEABLE-IRON FITTINGS.

353

## RETURN BENDS.



CLOSE PATTERN.



OPEN PATTERN.

### RETURN BENDS, CLOSE PATTERN.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Distance Between Centers.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	$2\frac{3}{16}$	$2\frac{3}{8}$
Right Hand, Each.....	\$0.13	\$0.25	\$0.35	\$0.50	\$0.75	\$1.00
Right and Left, Each.....	.15	.30	.45	.60	.90	1.25
Right Hand Galvanized, Each.....	.25	.35	.55	.75	1.15	1.65

### RETURN BENDS, OPEN PATTERN.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Distance Between Centers.....	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5
Right Hand, Each.....	\$0.15	\$0.30	\$0.50	\$0.65	\$0.85	\$1.25	\$2.00	\$3.00
Right and Left, Each.....	.20	.38	.60	.80	1.05	1.55	2.50	3.75
Right Hand, Galvanized, Each.....	.25	.45	.70	.90	1.25	2.00	3.50	5.00

### RETURN BENDS, MEDIUM PATTERN.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Distance Between Centers.....	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{7}{8}$	$2\frac{1}{4}$	$2\frac{1}{2}$	3
Right Hand, Each.....	\$0.13	\$0.25	\$0.35	\$0.50	\$0.75	\$1.00
Right and Left or Left Hand, Each.....	.15	.30	.45	.60	.90	1.25
Right Hand, Galvanized, Each.....	.25	.35	.55	.75	1.15	1.65



Y BEND.



DOUBLE Y.

## Y BENDS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Y Bend, Plain, Each.....	\$0.25	\$0.40	\$0.60	\$0.80	\$1.00	\$1.70	\$2.00	\$3.00
Y Bend, Galvanized, Each.....	.38	.60	.90	1.25	1.50	2.50	3.00	4.50
Double Y Bend Plain, Each.....			.90	1.25	1.50	2.50	3.00	5.00
Double Y Bend, Galvanized, Each.....			1.35	1.90	2.25	3.75	4.50	7.50

# MALLEABLE-IRON FITTINGS.




BUSHING.



FACED BUSHING.




LOCKNUT.




EXTENSION.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Bushings, Plain, Each.....		\$0.04	\$0.04	\$0.05	\$0.06	\$0.07	\$0.09	\$0.14	\$0.21	
Bushings, Galvanized, Each.....		.08	.08	.10	.12	.14	.18	.28	.42	
Faced Bushings, Plain, Each.....				.11	.13	.17	.22	.32	.48	
Locknuts, Plain, Each.....	\$0.02	.03	.04	.05	.07	.09	.11	.18	.40	\$0.50
Locknuts, Galvanized, Each.....	.03	.04	.05	.07	.10	.14	.20	.30	.55	.70
Extension Pieces, Each.....		.06	.09	.12						



HEXAGON NIPPLE.



OFFSET COUPLING.



WASTE NUT.



WALL PLATE.

## HEXAGON NIPPLES.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Each.....	\$0.25	.30	.40	.50	.70

## OFFSET REDUCING COUPLINGS.

Size, Inches.....	$1 \times \frac{3}{4}$	$1\frac{1}{4} \times 1$	$1\frac{1}{2} \times 1\frac{1}{4}$	$2 \times 1\frac{1}{2}$	$2\frac{1}{2} \times 2$	$3 \times 2\frac{1}{2}$	$3\frac{1}{2} \times 3$	$4 \times 3$	$5 \times 4$
Each.....	\$0.60	.70	.90	1.10	1.80	2.50	3.00	4.00	6.00

## WASTE NUTS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1
Plain, Each.....	\$0.04	\$0.05	\$0.06	\$0.08	\$0.10
Galvanized, Each.....	.08	.10	.12	.16	.20

## WALL PLATES.

Size, Inches.....	$\frac{3}{8}$
Each.....	\$0.12



LOOP.



HOOK, MALE.



HOOK, FEMALE.

## CHANDELIER LOOPS AND HOOKS.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$
Chandelier Loops, Each.....	\$0.10	\$0.12
Chandelier Hooks ".....	.10	.12

# MALLEABLE-IRON FITTINGS.


355

## CIRCULATING BOILER FITTINGS.


GALVANIZED.




No. 1.



No. 2.



No. 3.



No. 4.

Size, Inches.....

No. 1. Boiler Elbows, each.....  
 No. 2. Boiler Elbows, with Union, each.....  
 No. 3. Boiler Coupling, each.....  
 No. 4. Boiler Coupling, with Union, each.....

Female. Male.  
 $\frac{3}{4} \times \frac{3}{4} \times 1$

\$0.40  
 .75  
 .40  
 .75

Female. Male.  
 $\frac{3}{4} \times \frac{1}{2} \times 1$

\$0.40  
 .75  
 .40  
 .75

Female. Male.  
 $\frac{1}{2} \times \frac{1}{2} \times 1$


\$0.40  
 .60  
 .40  
 .60

## HYDRANT HANDLES.



No. 1.

WITH  $\frac{3}{8}$  INCH PIPE THREAD.



No. 2.

Per Pound.....\$0.15

Per Pound.....\$0.20

## HYDRANT ROD SOCKETS.



Per Pound.....\$0.15

## HYDRANT CLAMPS.



Size, Inches.....

With Square Hole, per Pound.....  
 Tapped for  $\frac{3}{8}$  Inch Pipe, per Pound.....  
 Tapped for  $\frac{1}{2}$  Inch Pipe, per Pound.....  
 Brass, each.....

$\frac{1}{2}$

\$0.15  
 .18  
 .20  
 .20

$\frac{5}{8}$


\$0.15  
 .18  
 .20  
 .20

$\frac{3}{4}$

\$0.15  
 .18  
 .20  
 .25

1

\$0.15  
 .18  
 .20  
 .30






# MALLEABLE-IRON FITTINGS.



UNION.



KEYSTONE UNION.



SECTIONAL KEYSTONE UNION.

## MALLEABLE UNIONS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Plain, each.....	\$0.18	\$0.20	\$0.22	\$0.27	\$0.33	\$0.46	\$0.58	\$0.75	\$1.55	\$2.10	\$3.65	\$4.35
Galvanized, each.....	.27	.30	.33	.40	.50	.70	.90	1.15	2.35	3.15	5.50	6.50


## KEYSTONE UNIONS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Plain, each.....	\$0.20	\$0.24	\$0.28	\$0.35	\$0.40	\$0.56	\$0.80	\$0.95	\$2.00	\$2.75
Galvanized, each.....	.24	.28	.35	.46	.55	.78	1.12	1.35	2.90	3.75




FEMALE UNION ELBOW.

## UNION ELBOWS.



MALE UNION ELBOW.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Female, Plain, each.....	\$0.42	\$0.54	\$0.63	\$0.90	\$1.05	\$1.55	\$2.85
Male, Plain, each.....	.48	.62	.72	1.05	1.20	1.80	3.30



FEMALE UNION TEE.

## UNION TEES.



MALE UNION TEE.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Female, Plain, each.....	\$0.45	\$0.57	\$0.70	\$0.95	\$1.15	\$1.70	\$3.20
Male, Plain, each.....	.52	.65	.80	1.10	1.30	1.95	3.70

Galvanized Union Ells and Tees, 50 per cent. added to Plain list.

# MALLEABLE-IRON FITTINGS.

357



No. 1. ELBOW.




No. 2. SIDE OUTLET ELBOW.




No. 3. TEE.



No. 4. SIDE OUTLET TEE.



No. 5. CROSS.



No. 6. SIDE OUTLET CROSS.




No. 7. ORNAMENT.



No. 8. BUSHING.



No. 9. FLANGE.



No. 10. CAST-IRON FLANGE.

## RAILING FITTINGS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 1. Elbow, each.....	\$0.15	\$0.18	\$0.20	\$0.35	\$0.45	\$0.72
No. 2. Side Outlet Elbow, each.....	.20	.23	.25	.40	.50	.80
No. 3. Tee, each.....	.20	.23	.25	.40	.50	.75
No. 4. Side Outlet Tee, each.....	.30	.33	.35	.45	.55	.90
No. 5. Cross, each.....	.30	.33	.35	.45	.58	1.00
No. 6. Side Outlet Cross, each.....	.35	.38	.40	.50	.65	1.35
No. 7. Acorn Ornament each.....	.16	.18	.20	.25	.35	.90
No. 8. Bushing, each.....		.06	.07	.10	.12	.18

Right and Left or Left Hand charged at 25 per cent. additional.

Bushings reduce one or two sizes.

## RAILING FLANGES.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 9, each.....		\$0.14	\$0.15	\$0.15	\$0.20	\$0.28	\$0.30
No. 10, each.....	\$0.12	.14	.15	.15	.20	.28	.30

## BRASS FINISHED RAILING FITTINGS.

Size, Inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 1. Elbow each.....	\$0.80	\$1.20	\$1.60	\$2.50
No. 2. Side Outlet Elbow, each.....	1.10	1.70	2.00	3.00
No. 3. Tee, each.....	1.10	1.70	2.00	3.00
No. 4. Tee. Side Outlet, each.....	1.50	2.00	2.40	3.50
No. 5. Cross, each.....	1.50	2.00	2.40	3.50
No. 6. Cross, Side Outlet, each.....	1.70	2.25	3.00	4.00
No. 7. Acorn Ornament, each.....	2.00	2.50	3.25	4.50
No. 9. Floor Flange, each.....	.40	.70	1.00	1.30

# 358 CLASSIFICATION AND PRICE LIST MALLEABLE FITTINGS.

(Superseding all Previous Classifications.)

ADOPTED BY MANUFACTURERS JUNE 19, 1895.

## CLASS A.—30 CENTS PER POUND.

Elbows .....	$\frac{1}{8}$ , $\frac{1}{4} \times \frac{1}{8}$ , $\frac{3}{8} \times \frac{1}{8}$ .
Tees.....	$\frac{1}{8}$ , $\frac{1}{8} \times \frac{1}{4}$ , $\frac{1}{4} \times \frac{1}{8}$ , $\frac{3}{8} \times \frac{1}{8}$ .
R. & L. Couplings.....	$\frac{1}{8}$ in.
Reducers.....	$\frac{1}{4} \times \frac{1}{8}$ , $\frac{3}{8} \times \frac{1}{8}$ .
R. H. Couplings.....	$\frac{1}{8}$ in.
Ells. R. & L.....	$\frac{1}{4}$ , $\frac{3}{8}$ .
R. & L. Return Bends.....	$\frac{3}{8}$ , $\frac{1}{2}$ .
Rod Couplings.....	

## CLASS B.—20 CENTS PER POUND.

Elbows.....	$\frac{3}{8}$ , $\frac{1}{4}$ , $\frac{3}{8} \times \frac{1}{4}$ , $\frac{1}{2} \times \frac{1}{4}$ .
Tees.....	$\frac{1}{4}$ , $\frac{3}{8}$ , $\frac{1}{4} \times \frac{3}{8}$ , $\frac{3}{8} \times \frac{1}{4} \times \frac{1}{4}$ , $\frac{3}{8} \times \frac{1}{4}$ , $\frac{3}{8} \times \frac{1}{4} \times \frac{3}{8}$ .
Elbows, Side Outlets.....	$\frac{1}{2}$ in. and smaller.
Tees, Side Outlets.....	$\frac{1}{2}$ in. and smaller.
Street Ells.....	$\frac{1}{4}$ , $\frac{3}{8}$ .
Crosses.....	$\frac{1}{4}$ , $\frac{3}{8}$ , $\frac{1}{2}$ .
Reducing Crosses.....	1 in. and smaller.
Drop Ells and Tees.....	$\frac{1}{2}$ in. and smaller.
Caps.....	$\frac{1}{4}$ , $\frac{3}{8}$ .
Lock Nuts.....	$\frac{1}{4}$ , $\frac{3}{8}$ , $\frac{1}{2}$ .
Reducers.....	$\frac{3}{8} \times \frac{1}{4}$ , to $\frac{3}{4} \times \frac{3}{8}$ in., inclusive.
Extension Pieces .....	$\frac{3}{8}$ and $\frac{1}{2}$ in.
R. & L. Couplings.....	$\frac{1}{4}$ , $\frac{3}{8}$ .
R. H. Couplings.....	$\frac{1}{4}$ , $\frac{3}{8}$ .
R. & L. Elbows.....	$\frac{1}{2}$ in.
Waste Nuts.....	$\frac{3}{4}$ in. and smaller.
Chandelier Hooks.....	all sizes.
Return Bends.....	$\frac{3}{8}$ and $\frac{1}{2}$ in.
Return Bends, R. & L.....	$\frac{3}{4}$ , 1.
Wall Plates.....	all sizes.
45° Ells.....	$\frac{1}{2}$ in. and smaller.
Y's.....	$\frac{1}{2}$ , $\frac{3}{4}$ .

## CLASS C.—16 CENTS PER POUND.

Elbows .....	$\frac{1}{2}$ and $\frac{1}{2} \times \frac{3}{8}$ in.
Elbows, R. & L.....	$\frac{3}{4}$ , 1.
Tees.....	$\frac{1}{2}$ and $\frac{1}{2}$ reducing.

Elbows, Side Outlets.....	$\frac{3}{4}$ in. and larger.
Tees, Side Outlets .....	$\frac{3}{4}$ in. and larger.
Street Ells .....	$\frac{1}{2}$ , $\frac{3}{4}$ , $\frac{3}{4} \times \frac{1}{2}$ , $1 \times \frac{3}{4}$ .
Crosses.....	1 and $\frac{3}{4}$ in., straight.
Drop Ells.....	$\frac{3}{4}$ in. and larger.
Drop Tees.....	$\frac{3}{4}$ in. and larger.
Caps.....	$\frac{1}{2}$ , $\frac{3}{4}$ and 1 in.
Lock Nuts.....	$\frac{3}{4}$ , 1, $1\frac{1}{4}$ .
Reducers.....	$\frac{3}{4} \times \frac{1}{2}$ to 1 in. inclusive.
R. & L. Couplings.....	$\frac{1}{2}$ , $\frac{3}{4}$ .
R. H. Couplings.....	$\frac{1}{2}$ , $\frac{3}{4}$ .
Extension Pieces .....	$\frac{3}{4}$ in. and larger.
Waste Nuts.....	1 in. and larger.
Return Bends.....	$\frac{3}{4}$ , 1.
45° Ells.....	$\frac{3}{4}$ to 2 in., inclusive.
Y's.....	1 in. and larger.
Return Bends, R. & L.....	$1\frac{1}{4}$ in. and larger.

## CLASS D.—13 CENTS PER POUND.

Elbows and Tees.....	$\frac{3}{4}$ and 1 in.
Crosses.....	$1\frac{1}{4}$ in. and larger.
Street Ells.....	1 in. and larger.
Caps.....	$1\frac{1}{4}$ in. and larger.
Lock Nuts.....	$1\frac{1}{2}$ in. and larger.
Reducers.....	$1\frac{1}{4}$ in. and larger.
R. H. Couplings.....	1 and $1\frac{1}{4}$ in.
R. & L. Couplings.....	1 in. and larger.
R. & L. Elbows.....	$1\frac{1}{4}$ in. and larger.
45° Ells.....	$2\frac{1}{2}$ in. and larger.
Return Bends .....	$1\frac{1}{4}$ in. and larger.

Such Fittings as have smaller outlets than  $\frac{3}{4}$  in. will be classed "C."

## CLASS E.—11 CENTS PER POUND.

Elbows and Tees.....	$1\frac{1}{4}$ in. and larger.
R. H. Couplings.....	$1\frac{1}{2}$ , 2.

Such Fittings in this class that have outlets smaller than 1 in. to be classed "D."

The run of Tees (Bullheads) gives the size for the purpose of classification, and the outlet being larger does not change it.  
Return Bends, reduced; Return Bends, tapped on spread; Elbows, tapped on pitch, 15 per cent. added; R. & L. Fittings, not classified above, in lots less than 100 pounds, 15 per cent. added.

## GALVANIZED FITTINGS.

Class.....	A	B	C	D	E
Price per Pound.....	\$0.40	.27	.23	.20	.18



## ELBOWS.

	Size.	Class.		Size.	Class.
Gas.....	$\frac{1}{8}$	A	*Steam and Gas.....	$1\frac{1}{2} \times 1\frac{1}{4}$	E
Gas.....	$\frac{1}{4} \times \frac{1}{2}$	A	*Steam and Gas.....	$1\frac{1}{2}$	E
*Steam and Gas.....	$\frac{1}{4}$	B	Steam.....	2 x 1	E
*Steam and Gas.....	$\frac{3}{8} \times \frac{1}{4}$	B	Steam.....	2 x $1\frac{1}{4}$	E
*Steam and Gas.....	$\frac{3}{8}$	B	*Steam and Gas.....	2 x $1\frac{1}{2}$	E
Gas.....	$\frac{1}{2} \times \frac{1}{4}$	B	*Steam and Gas.....	2	E
*Steam and Gas.....	$\frac{1}{2} \times \frac{3}{8}$	C	Steam.....	$2\frac{1}{2} \times 1\frac{1}{2}$	E
*Steam and Gas.....	$\frac{1}{2}$	C	Steam.....	$2\frac{1}{2} \times 2$	E
*Gas.....	$\frac{3}{4} \times \frac{3}{8}$	C	*Steam.....	$2\frac{1}{2}$	E
*Steam and Gas.....	$\frac{3}{4} \times \frac{1}{2}$	C	Steam.....	3 x 2	E
*Steam and Gas.....	$\frac{3}{4}$	D	Steam.....	3 x $2\frac{1}{2}$	E
Gas.....	1 x $\frac{3}{8}$	C	*Steam and Gas.....	3	E
*Steam and Gas.....	1 x $\frac{1}{2}$	C	Steam.....	$3\frac{1}{2} \times 3$	E
*Steam and Gas.....	1 x $\frac{3}{4}$	D	Steam.....	$3\frac{1}{2}$	E
*Steam and Gas.....	1	D	Steam.....	4 x 3	E
Steam.....	$1\frac{1}{4} \times \frac{3}{4}$	D	Steam.....	4 x $3\frac{1}{2}$	E
*Steam and Gas.....	$1\frac{1}{4} \times 1$	E	*Steam.....	4	E
*Steam and Gas.....	$1\frac{1}{4}$	E	Steam.....	5	E
Steam.....	$1\frac{1}{2} \times \frac{3}{4}$	D	Steam.....	6	E
Steam.....	$1\frac{1}{2} \times 1$	E			

## STREET ELBOWS.

	Size.	Class.		Size.	Class.
Beaded.....	$\frac{1}{4}$	B	*Beaded.....	$1\frac{1}{4}$	D
*Beaded.....	$\frac{3}{8}$	B	Beaded.....	$1\frac{1}{2} \times 1$	D
*Beaded.....	$\frac{1}{2}$	C	Beaded.....	$1\frac{1}{2} \times 1\frac{1}{4}$	D
Beaded.....	$\frac{3}{4} \times \frac{1}{2}$	C	*Beaded.....	$1\frac{1}{2}$	D
*Beaded.....	$\frac{3}{4}$	C	Beaded.....	2 x 1	D
Beaded.....	1 x $\frac{3}{4}$	C	Beaded.....	2 x $1\frac{1}{4}$	D
*Beaded.....	1	D	Beaded.....	2 x $1\frac{1}{2}$	D
*Beaded.....	$1\frac{1}{4} \times 1$	D	*Beaded.....	2	D
Beaded.....	$1\frac{1}{4} \times \frac{3}{4}$	D	Beaded.....	$2\frac{1}{2}$	D

In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.

# MALLEABLE-IRON FITTINGS.

## 45° ELBOWS.

	Size.	Class.		Size.	Class.
Beaded .....	$\frac{1}{4}$	B	*Beaded and Plain .....	$1\frac{1}{2}$	C
Beaded .....	$\frac{3}{8}$	B	*Beaded and Plain .....	2	C
*Beaded .....	$\frac{1}{2}$	B	Beaded .....	$2\frac{1}{2}$	D
*Beaded .....	$\frac{3}{4}$	C	Beaded .....	3	D
*Beaded .....	1	C	Beaded .....	$3\frac{1}{2}$	D
*Beaded and Plain .....	$1\frac{1}{4}$	C	Beaded .....	4	D

## 60° ELBOWS.

	Size.	Class.
Plain .....	$1\frac{1}{2}$	C
Plain .....	2	C
Plain .....	2 x $1\frac{1}{2}$	C

## 60° Y'S.

	Size.	Class.
Plain .....	$1\frac{1}{2}$	C
Plain .....	2	C
Plain .....	2 x $1\frac{1}{2}$	C

## Y BENDS.

	Size.	Class.		Size.	Class.
Beaded .....	$\frac{3}{4}$	C	Beaded and Plain .....	2 x $1\frac{1}{2}$	D
Beaded .....	1	D	Beaded .....	$2\frac{1}{2}$	D
Beaded and Plain .....	$1\frac{1}{4}$	D	Beaded .....	$2\frac{1}{2}$ x 2	D
Beaded and Plain .....	$1\frac{1}{2}$	D	Beaded .....	3	D
Beaded and Plain .....	$1\frac{1}{2}$ x $1\frac{1}{4}$	D	Beaded .....	3 x $2\frac{1}{2}$	D
Beaded and Plain .....	2	D			

## ELBOWS.

### WITH SIDE OUTLET.

	Size.	Class.		Size.	Class.
Gas .....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{1}{4}$	B	Gas .....	1 x 1 x $\frac{3}{8}$	B
*Gas .....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{3}{8}$	B	Gas .....	1 x 1 x $\frac{1}{2}$	B
Gas .....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{8}$	B	Gas .....	1 x 1 x $\frac{3}{4}$	C
*Gas .....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{1}{2}$	B	*Gas .....	1 x 1 x 1	C
Gas .....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{3}{8}$	B	Gas .....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x 1	C
Gas .....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{1}{2}$	B	*Gas .....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x $1\frac{1}{4}$	C
*Gas .....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{3}{4}$	C	*Gas .....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x $1\frac{5}{8}$	C

## FOUR-WAY TEES.

	Size.	Class.		Size.	Class.
Gas .....	$\frac{3}{8}$	B	Gas .....	1	C
Gas .....	$\frac{1}{2}$	B	Gas .....	$1\frac{1}{4}$	C
Gas .....	$\frac{3}{4}$	C	Gas .....	$1\frac{1}{2}$	C

In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.

# MALLEABLE-IRON FITTINGS.

361

## DROP ELBOWS.

	Size.	Class.		Size.	Class.
Gas.....	$\frac{1}{4} \times \frac{1}{4}$	B	*Gas.....	$\frac{3}{4} \times \frac{1}{2}$	B
Gas.....	$\frac{3}{8} \times \frac{1}{4}$	B	*Gas.....	$\frac{3}{4} \times \frac{3}{4}$	C
*Gas.....	$\frac{3}{8} \times \frac{3}{4}$	B	Gas.....	$1 \times 1\frac{1}{4}$	C
*Gas.....	$\frac{1}{2} \times \frac{1}{2}$	B			

## MALE AND FEMALE.

	Size.	Class.		Size.	Class.
Gas.....	$\frac{1}{8} \times \frac{3}{8}$	B	*Gas.....	$\frac{3}{8} \times \frac{3}{8}$	B
*Gas.....	$\frac{1}{4} \times \frac{3}{8}$	B	Gas.....	$\frac{1}{2} \times \frac{3}{8}$	B

## WITH DROP $2\frac{1}{2}$ INCHES LONG.

	Size.	Class.		Size.	Class.
Gas.....	$\frac{3}{8} \times \frac{3}{8}$	B	Gas.....	$\frac{1}{4} \times \frac{3}{8}$	B

## FLANGE RIGHT SIDE.

	Size.	Class.
Gas.....	$\frac{1}{4} \times \frac{3}{8}$	B
Gas.....	$\frac{3}{8} \times \frac{3}{8}$	B

## FLANGE LEFT SIDE.

	Size.	Class.
Gas.....	$\frac{3}{8} \times \frac{3}{8}$	B
Gas.....	$\frac{1}{4} \times \frac{3}{8}$	B

## TEES.

In describing Tees the run is first named, then the outlet, thus :

$$\frac{1}{2} \text{ T } \frac{3}{8} = \frac{1}{2} \times \frac{3}{8} \times \frac{3}{4}$$

$\frac{3}{4}$

	Size.	Class.		Size.	Class.
Gas.....	$\frac{1}{2} \times \frac{1}{2} \times \frac{1}{2}$	A	*Gas.....	$\frac{3}{8} \times \frac{3}{8} \times \frac{1}{4}$	B
Gas.....	$\frac{1}{8} \times \frac{1}{8} \times \frac{1}{4}$	A	*Steam and Gas.....	$\frac{3}{8} \times \frac{3}{8} \times \frac{1}{2}$	B
Gas.....	$\frac{1}{4} \times \frac{1}{8} \times \frac{1}{4}$	A	*Steam and Gas.....	$\frac{3}{8} \times \frac{3}{8} \times \frac{1}{2}$	C
Gas.....	$\frac{1}{4} \times \frac{1}{4} \times \frac{1}{8}$	A	Gas.....	$\frac{1}{2} \times \frac{3}{8} \times \frac{1}{4}$	C
Gas.....	$\frac{3}{8} \times \frac{3}{8} \times \frac{1}{4}$	A	*Steam and Gas.....	$\frac{1}{2} \times \frac{3}{8} \times \frac{3}{8}$	C
*Steam and Gas.....	$\frac{1}{4} \times \frac{1}{4} \times \frac{1}{4}$	B	Gas.....	$\frac{1}{2} \times \frac{1}{4} \times \frac{1}{2}$	C
Gas.....	$\frac{1}{4} \times \frac{1}{4} \times \frac{3}{8}$	B	*Steam and Gas.....	$\frac{1}{2} \times \frac{3}{8} \times \frac{1}{2}$	C
Gas.....	$\frac{3}{8} \times \frac{1}{4} \times \frac{1}{4}$	B	Steam and Gas.....	$\frac{1}{2} \times \frac{3}{8} \times \frac{3}{4}$	C
Gas.....	$\frac{3}{8} \times \frac{1}{4} \times \frac{3}{8}$	B	Gas.....	$\frac{1}{2} \times \frac{1}{2} \times \frac{1}{4}$	C

In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.



# MALLEABLE-IRON FITTINGS.

## TEES.—Continued.

	Size.	Class.		Size.	Class.
*Steam and Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{8}$	C	*Steam and Gas.....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x $\frac{3}{4}$	D
*Steam and Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{1}{2}$	C	*Steam and Gas.....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x 1	E
*Steam and Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{4}$	C	*Steam and Gas.....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x $1\frac{1}{4}$	E
*Gas.....	$\frac{3}{4}$ x $\frac{3}{8}$ x $\frac{3}{8}$	C	*Steam.....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x $1\frac{1}{2}$	E
*Gas.....	$\frac{3}{4}$ x $\frac{3}{8}$ x $\frac{1}{2}$	C	Steam.....	$1\frac{1}{2}$ x $\frac{3}{8}$ x $1\frac{1}{2}$	D
*Gas.....	$\frac{3}{4}$ x $\frac{3}{8}$ x $\frac{3}{4}$	C	Steam.....	$1\frac{1}{2}$ x $\frac{1}{2}$ x $1\frac{1}{2}$	D
Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{1}{4}$	C	Steam.....	$1\frac{1}{2}$ x $\frac{3}{4}$ x $1\frac{1}{2}$	D
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{3}{8}$	C	*Steam.....	$1\frac{1}{2}$ x 1 x 1	E
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{1}{2}$	C	*Steam.....	$1\frac{1}{2}$ x 1 x $1\frac{1}{4}$	E
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{3}{4}$	C	*Steam.....	$1\frac{1}{2}$ x 1 x $1\frac{1}{2}$	E
*Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x 1	C	*Steam.....	$1\frac{1}{2}$ x $1\frac{1}{4}$ x $\frac{3}{4}$	D
Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{1}{4}$	C	*Steam.....	$1\frac{1}{2}$ x $1\frac{1}{4}$ x 1	E
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{3}{8}$	C	*Steam.....	$1\frac{1}{2}$ x $1\frac{1}{4}$ x $1\frac{1}{4}$	E
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{1}{2}$	C	*Steam and Gas.....	$1\frac{1}{2}$ x $1\frac{1}{4}$ x $1\frac{1}{2}$	E
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{3}{4}$	D	Steam.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x $\frac{3}{8}$	D
*Steam and Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x 1	D	*Steam.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x $\frac{1}{2}$	D
Gas.....	1 x $\frac{3}{8}$ x $\frac{3}{4}$	C	*Steam and Gas.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x $\frac{3}{4}$	D
Steam and Gas.....	1 x $\frac{3}{8}$ x 1	C	*Steam and Gas.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x 1	E
*Steam and Gas.....	1 x $\frac{1}{2}$ x $\frac{1}{2}$	C	*Steam and Gas.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x $1\frac{1}{4}$	E
*Steam.....	1 x $\frac{1}{2}$ x $\frac{3}{4}$	C	*Steam and Gas.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x $1\frac{1}{2}$	E
*Steam and Gas.....	1 x $\frac{1}{2}$ x 1	C	*Steam.....	$1\frac{1}{2}$ x $1\frac{1}{2}$ x 2	E
*Gas.....	1 x $\frac{3}{4}$ x $\frac{3}{8}$	C	Steam.....	2 x $\frac{3}{8}$ x 2	D
*Steam and Gas.....	1 x $\frac{3}{4}$ x $\frac{1}{2}$	C	Steam.....	2 x $\frac{1}{2}$ x 2	D
*Steam and Gas.....	1 x $\frac{3}{4}$ x $\frac{3}{4}$	D	Steam.....	2 x $\frac{3}{4}$ x 2	D
*Steam and Gas.....	1 x $\frac{3}{4}$ x 1	D	Steam.....	2 x 1 x 2	E
*Steam.....	1 x $\frac{3}{4}$ x $1\frac{1}{4}$	D	*Steam.....	2 x $1\frac{1}{4}$ x $1\frac{1}{4}$	E
Gas.....	1 x 1 x $\frac{1}{4}$	C	Steam.....	2 x $1\frac{1}{4}$ x $1\frac{1}{2}$	E
*Steam and Gas.....	1 x 1 x $\frac{3}{8}$	C	Steam.....	2 x $1\frac{1}{4}$ x 2	E
*Steam and Gas.....	1 x 1 x $\frac{1}{2}$	C	*Steam.....	2 x $1\frac{1}{2}$ x $1\frac{1}{4}$	E
*Steam and Gas.....	1 x 1 x $\frac{3}{4}$	D	*Steam and Gas.....	2 x $1\frac{1}{2}$ x $1\frac{1}{2}$	E
*Steam and Gas.....	1 x 1 x 1	D	*Steam and Gas.....	2 x $1\frac{1}{2}$ x 2	E
*Steam and Gas.....	1 x 1 x $1\frac{1}{4}$	E	*Steam.....	2 x 2 x $\frac{1}{2}$	D
Gas.....	$1\frac{1}{4}$ x $\frac{3}{8}$ x $1\frac{1}{4}$	D	*Steam and Gas.....	2 x 2 x $\frac{3}{4}$	D
Steam.....	$1\frac{1}{4}$ x $\frac{1}{2}$ x 1	D	*Steam and Gas.....	2 x 2 x 1	E
*Steam.....	$1\frac{1}{4}$ x $\frac{1}{2}$ x $1\frac{1}{4}$	D	*Steam and Gas.....	2 x 2 x $1\frac{1}{4}$	E
Steam.....	$1\frac{1}{4}$ x $\frac{3}{4}$ x $\frac{3}{4}$	D	*Steam and Gas.....	2 x 2 x $1\frac{1}{2}$	E
*Steam.....	$1\frac{1}{4}$ x $\frac{3}{4}$ x 1	D	*Steam and Gas.....	2 x 2 x 2	E
*Steam.....	$1\frac{1}{4}$ x $\frac{3}{4}$ x $1\frac{1}{4}$	D	Steam.....	2 x 2 x $2\frac{1}{2}$	E
Gas.....	$1\frac{1}{4}$ x 1 x $\frac{3}{8}$	D	*Steam.....	$2\frac{1}{2}$ x $2\frac{1}{2}$ x 1	E
*Steam.....	$1\frac{1}{4}$ x 1 x $\frac{1}{2}$	D	Steam.....	$2\frac{1}{2}$ x $2\frac{1}{2}$ x $1\frac{1}{4}$	E
*Steam.....	$1\frac{1}{4}$ x 1 x $\frac{3}{4}$	D	Steam.....	$2\frac{1}{2}$ x $2\frac{1}{2}$ x $1\frac{1}{2}$	E
*Steam and Gas.....	$1\frac{1}{4}$ x 1 x 1	E	*Steam.....	$2\frac{1}{2}$ x $2\frac{1}{2}$ x 2	E
*Steam and Gas.....	$1\frac{1}{4}$ x 1 x $1\frac{1}{4}$	E	*Steam.....	$2\frac{1}{2}$ x $2\frac{1}{2}$ x $2\frac{1}{2}$	E
Steam.....	$1\frac{1}{4}$ x 1 x $1\frac{1}{2}$	E	Steam.....	3 x 3 x $1\frac{1}{4}$	E
Steam and Gas.....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x $\frac{3}{8}$	D	Steam.....	3 x 3 x $1\frac{1}{2}$	E
*Steam and Gas.....	$1\frac{1}{4}$ x $1\frac{1}{4}$ x $\frac{1}{2}$	D	*Steam.....	3 x 3 x 2	E

In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.

# MALLEABLE-IRON FITTINGS.

363

## TEES—Continued.

	Size.	Class.		Size.	Class.
*Steam.....	3 x 3 x 2 $\frac{1}{2}$	E	Steam.....	4 x 4 x 2 $\frac{1}{2}$	E
*Steam and Gas.....	3 x 3 x 3	E	Steam.....	4 x 4 x 3	E
Steam.....	3 $\frac{1}{2}$ x 3 $\frac{1}{2}$ x 2 $\frac{1}{2}$	E	Steam.....	4 x 4 x 3 $\frac{1}{2}$	E
Steam.....	3 $\frac{1}{2}$ x 3 $\frac{1}{2}$ x 3	E	*Steam and Gas.....	4 x 4 x 4	E
Steam.....	3 $\frac{1}{2}$ x 3 $\frac{1}{2}$ x 3 $\frac{1}{2}$	E	Steam.....	5 x 5 x 5	E
Steam.....	4 x 4 x 2	E	Steam.....	6 x 6 x 6	E

## DROP TEES.

### FEMALE.

	Size.	Drop.	Class.		Size.	Drop.	Class.
Gas.....	$\frac{3}{4}$ x $\frac{1}{4}$ x $\frac{1}{4}$		B	Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{3}{8}$		B
Gas.....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{1}{4}$		B	*Gas.....	$\frac{3}{4}$ x $\frac{3}{8}$ x $\frac{1}{2}$		B
*Gas.....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{3}{8}$		B	*Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{3}{8}$		B
Gas.....	$\frac{1}{2}$ x $\frac{3}{8}$ x $\frac{1}{2}$		B	*Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{1}{2}$		B
Gas.....	$\frac{1}{2}$ x $\frac{3}{8}$ x $\frac{3}{4}$		B	*Gas.....	$\frac{3}{4}$ x $\frac{3}{4}$ x $\frac{3}{4}$		C
Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{1}{2}$		B	Gas.....	1 x $\frac{3}{4}$ x $\frac{3}{8}$		B
*Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{4}$		B	Gas.....	1 x 1 x $\frac{3}{8}$		B
*Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{1}{2}$		B	Gas.....	1 x 1 x $\frac{1}{2}$		B
Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{1}{4}$		B	Gas.....	1 x 1 x 1		C

### MALE AND FEMALE.

	Size.	Drop.	Class.		Size.	Drop.	Class.
Gas.....	$\frac{1}{4}$ x $\frac{1}{4}$ x $\frac{3}{8}$		B	Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{3}{8}$		B
Gas.....	$\frac{3}{8}$ x $\frac{1}{4}$ x $\frac{3}{8}$		B	Gas.....	$\frac{3}{4}$ x $\frac{3}{8}$ x $\frac{3}{8}$		B
*Gas.....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{3}{8}$		B	Gas.....	1 x $\frac{3}{4}$ x $\frac{3}{8}$		B
Gas.....	$\frac{1}{2}$ x $\frac{3}{8}$ x $\frac{3}{8}$		B	Gas.....	1 x 1 x $\frac{3}{8}$		B
*Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{8}$		B				

## WITH DROP 2 $\frac{1}{2}$ INCHES LONG.

	Size.	Class.
Gas.....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{3}{8}$	B

## CROSSES.

The outlets of a Cross are always the same size, and both denoted by the last figure.

	Size.	Class.		Size.	Class.
Gas.....	$\frac{1}{4}$ x $\frac{1}{4}$ x $\frac{1}{4}$	B	Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{1}{4}$	B
Gas.....	$\frac{3}{8}$ x $\frac{1}{4}$ x $\frac{1}{4}$	B	*Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{3}{8}$	B
Gas.....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{1}{4}$	B	*Steam and Gas.....	$\frac{1}{2}$ x $\frac{1}{2}$ x $\frac{1}{2}$	B
Steam and Gas.....	$\frac{3}{8}$ x $\frac{3}{8}$ x $\frac{3}{8}$	B	Gas.....	$\frac{3}{4}$ x $\frac{3}{8}$ x $\frac{3}{8}$	B
Gas.....	$\frac{1}{2}$ x $\frac{3}{8}$ x $\frac{1}{4}$	B	Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{3}{8}$	B
Gas.....	$\frac{1}{2}$ x $\frac{3}{8}$ x $\frac{3}{8}$	B	*Gas.....	$\frac{3}{4}$ x $\frac{1}{2}$ x $\frac{1}{2}$	B

\*In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.

# MALLEABLE-IRON FITTINGS.

## CROSSES.—Continued.

	Size.	Class.		Size.	Class.
Steam and Gas.....	$\frac{3}{4} \times \frac{3}{4} \times \frac{3}{8}$	B	Steam.....	$1\frac{1}{2} \times 1\frac{1}{2} \times \frac{1}{2}$	C
*Steam and Gas.....	$\frac{3}{4} \times \frac{3}{4} \times \frac{1}{2}$	B	*Steam and Gas.....	$1\frac{1}{2} \times 1\frac{1}{2} \times \frac{3}{4}$	D
*Steam and Gas.....	$\frac{3}{4} \times \frac{3}{4} \times \frac{3}{4}$	C	*Steam.....	$1\frac{1}{2} \times 1\frac{1}{2} \times 1$	D
Gas.....	$1 \times \frac{1}{2} \times \frac{3}{8}$	B	*Steam.....	$1\frac{1}{2} \times 1\frac{1}{2} \times 1\frac{1}{4}$	D
Gas.....	$1 \times \frac{3}{4} \times \frac{3}{8}$	B	*Steam and Gas.....	$1\frac{1}{2} \times 1\frac{1}{2} \times 1\frac{1}{2}$	D
Steam and Gas.....	$1 \times \frac{3}{4} \times \frac{1}{2}$	B	*Steam.....	$2 \times 2 \times \frac{3}{4}$	D
Steam and Gas.....	$1 \times \frac{3}{4} \times \frac{3}{4}$	C	*Steam.....	$2 \times 2 \times 1$	D
Steam and Gas.....	$1 \times 1 \times \frac{3}{8}$	B	*Steam.....	$2 \times 2 \times 1\frac{1}{4}$	D
*Steam and Gas.....	$1 \times 1 \times \frac{1}{2}$	B	*Steam.....	$2 \times 2 \times 1\frac{1}{2}$	D
*Steam and Gas.....	$1 \times 1 \times \frac{3}{4}$	C	*Steam and Gas.....	$2 \times 2 \times 2$	D
*Steam and Gas.....	$1 \times 1 \times 1$	C	Steam.....	$2\frac{1}{2} \times 2\frac{1}{2} \times 2$	D
Steam.....	$1\frac{1}{4} \times 1 \times \frac{3}{4}$	D	*Steam.....	$2\frac{1}{2} \times 2\frac{1}{2} \times 2\frac{1}{2}$	D
Steam.....	$1\frac{1}{4} \times 1 \times 1$	D	Steam.....	$3 \times 3 \times 2$	D
Steam.....	$1\frac{1}{4} \times 1\frac{1}{4} \times \frac{3}{8}$	C	Steam.....	$3 \times 3 \times 2\frac{1}{2}$	D
*Steam.....	$1\frac{1}{4} \times 1\frac{1}{4} \times \frac{1}{2}$	C	Steam and Gas.....	$3 \times 3 \times 3$	D
*Steam.....	$1\frac{1}{4} \times 1\frac{1}{4} \times \frac{3}{4}$	D	Steam.....	$3\frac{1}{2} \times 3\frac{1}{2} \times 3\frac{1}{2}$	D
*Steam.....	$1\frac{1}{4} \times 1\frac{1}{4} \times 1$	D	Steam.....	$4 \times 4 \times 2$	D
*Steam and Gas.....	$1\frac{1}{4} \times 1\frac{1}{4} \times 1\frac{1}{4}$	D	Steam.....	$4 \times 4 \times 4$	D
Steam.....	$1\frac{1}{2} \times 1\frac{1}{4} \times 1\frac{1}{4}$	D			

## CAPS.

	Size.	Class.		Size.	Class.
*Gas.....	$\frac{1}{4}$	B	*Steam and Gas.....	$1\frac{1}{2}$	D
*Gas.....	$\frac{3}{8}$	B	*Steam and Gas.....	2	D
*Gas.....	$\frac{1}{2}$	C	*Steam.....	$2\frac{1}{2}$	D
*Steam and Gas.....	$\frac{3}{4}$	C	*Steam.....	3	D
*Steam and Gas.....	1	C	*Steam.....	$3\frac{1}{2}$	D
*Steam and Gas.....	$1\frac{1}{4}$	D	*Steam.....	4	D

## COUPLINGS.

### RIGHT HAND.

Size.	Class.	Size.	Class.
* $\frac{1}{4}$ .....	B	* $1\frac{1}{2}$ .....	E
* $\frac{3}{8}$ .....	B	* 2 .....	E
* $\frac{1}{2}$ .....	C	* $2\frac{1}{2}$ .....	E
* $\frac{3}{4}$ .....	C	* 3 .....	E
* 1 .....	D	* 4 .....	E
* $1\frac{1}{4}$ .....	D		

In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.



# MALLEABLE-IRON FITTINGS.

365

## COUPLINGS.

RIGHT AND LEFT.

Size.	Class.	Size.	Class.
$\frac{1}{4}$ .....	B	1 .....	D
$\frac{3}{8}$ .....	B	$1\frac{1}{4}$ .....	D
$\frac{1}{2}$ .....	C	$1\frac{1}{2}$ .....	D
$\frac{3}{4}$ .....	C	2 .....	D

## REDUCING.

Size.	Class.	Size.	Class.
Gas..... $\frac{1}{4}$ x $\frac{1}{8}$	A	Steam and Gas..... 2 x $\frac{3}{4}$	D
Gas..... $\frac{3}{8}$ x $\frac{1}{8}$	A	*Steam and Gas..... 2 x 1	D
Steam and Gas..... $\frac{3}{4}$ x $\frac{1}{4}$	B	*Steam and Gas..... 2 x $1\frac{1}{4}$	D
Gas..... $\frac{1}{2}$ x $\frac{1}{4}$	B	*Steam and Gas..... 2 x $1\frac{1}{2}$	D
*Steam and Gas..... $\frac{1}{2}$ x $\frac{3}{8}$	B	Steam..... $2\frac{1}{2}$ x 1	D
Gas..... $\frac{3}{4}$ x $\frac{1}{4}$	B	*Steam..... $2\frac{1}{2}$ x $1\frac{1}{4}$	D
Gas..... $\frac{3}{4}$ x $\frac{3}{8}$	B	Steam..... $2\frac{1}{2}$ x $1\frac{1}{2}$	D
Steam and Gas..... $\frac{3}{4}$ x $\frac{1}{2}$	C	*Steam..... $2\frac{1}{2}$ x 2	D
Gas..... 1 x $\frac{1}{4}$	C	Steam..... 3 x 1	D
Gas..... 1 x $\frac{3}{8}$	C	Steam..... 3 x $1\frac{1}{4}$	D
*Gas..... 1 x $\frac{1}{2}$	C	*Steam..... 3 x $1\frac{1}{2}$	D
*Steam and Gas..... 1 x $\frac{3}{4}$	C	Steam and Gas..... 3 x 2	D
*Steam and Gas..... $1\frac{1}{4}$ x $\frac{1}{2}$	C	*Steam..... 3 x $2\frac{1}{2}$	D
*Steam and Gas..... $1\frac{1}{4}$ x $\frac{3}{4}$	D	Steam..... $3\frac{1}{2}$ x $2\frac{1}{2}$	D
*Steam and Gas..... $1\frac{1}{4}$ x 1	D	*Steam..... $3\frac{1}{2}$ x 3	D
*Steam..... $1\frac{1}{2}$ x $\frac{1}{2}$	D	Steam..... 4 x 2	D
*Steam and Gas..... $1\frac{1}{2}$ x $\frac{3}{4}$	D	Steam..... 4 x $2\frac{1}{2}$	D
*Steam and Gas..... $1\frac{1}{2}$ x 1	D	Steam..... 4 x 3	D
*Steam and Gas..... $1\frac{1}{2}$ x $1\frac{1}{4}$	D	*Steam..... 4 x $3\frac{1}{2}$	D
Steam..... 2 x $\frac{1}{2}$	C		

## LOCK NUTS.

Size.	Class.	Size.	Class.
* $\frac{1}{4}$ .....	B	*1 .....	C
* $\frac{3}{8}$ .....	B	* $1\frac{1}{4}$ .....	C
* $\frac{1}{2}$ .....	B	* $1\frac{1}{2}$ .....	E
* $\frac{3}{4}$ .....	C	*2 .....	E

## WASTE NUTS.

Size.	Class.	Size.	Class.
* $\frac{1}{4}$ .....	B	* $\frac{3}{4}$ .....	B
* $\frac{3}{8}$ .....	B	*1 .....	C
* $\frac{1}{2}$ .....	B	* $1\frac{1}{4}$ .....	C

In ordering, be particular to mention steam or gas. Such sizes as are marked with a \* are carried in stock, galvanized.

# MALLEABLE-IRON FITTINGS.

## RETURN BENDS.

### OPEN PATTERN.

Size.	Dist. Between Centers.	Class.	Size.	Dist. Between Centers.	Class.
* $\frac{1}{2}$ .....	$1\frac{1}{2}$ .....	B	* $1\frac{1}{2}$ .....	$3\frac{1}{2}$ .....	D
* $\frac{3}{4}$ .....	2.....	C	* 2.....	4.....	D
* 1.....	$2\frac{1}{2}$ .....	C	* $2\frac{1}{2}$ .....	$4\frac{1}{2}$ .....	D
* $1\frac{1}{4}$ .....	3.....	D	* 3.....	5.....	D

### CLOSE PATTERN.

Size.	Dist. Between Centers.	Class.	Size.	Dist. Between Centers.	Class.
* $\frac{1}{8}$ .....	1.....	B	* $1\frac{1}{4}$ .....	$1\frac{3}{4}$ .....	D
* $\frac{3}{4}$ .....	$1\frac{1}{4}$ .....	C	* $1\frac{1}{2}$ .....	$2\frac{3}{8}$ .....	D
* 1.....	$1\frac{1}{2}$ .....	C	* 2.....	$2\frac{5}{8}$ .....	D

### MEDIUM PATTERN.

Size.	Dist. Between Centers.	Class.	Size.	Dist. Between Centers.	Class.
$\frac{1}{2}$ .....	$1\frac{1}{4}$ .....	B	$1\frac{1}{4}$ .....	$2\frac{1}{4}$ .....	D
$\frac{3}{4}$ .....	$1\frac{1}{2}$ .....	C	$1\frac{1}{2}$ .....	$2\frac{1}{2}$ .....	D
1.....	$1\frac{7}{8}$ .....	C	2.....	3.....	D

## CHANDELIER LOOPS.

### MALE.

Size.	Class.
$\frac{3}{8}$ .....	B
$\frac{1}{2}$ .....	B

### FEMALE.

Size.	Class.
$\frac{3}{8}$ .....	B

## CHANDELIER HOOKS.

### MALE OR FEMALE.

Size.	Class.
* $\frac{3}{8}$ .....	B
$\frac{1}{2}$ .....	B

## EXTENSION PIECES.

### MALE OR FEMALE.

Size.	Class.
$\frac{3}{8}$ x $\frac{3}{8}$ .....	B
$\frac{1}{2}$ x $\frac{1}{2}$ .....	B
$\frac{3}{4}$ x $\frac{3}{4}$ .....	C

## WALL PLATES.

Size.	Class.
$\frac{3}{8}$ .....	B

## STEAM-COCK WRENCHES.

Eight Sizes..... $\frac{1}{2}$  to 3 inches.

Such sizes as are marked with a \* are carried in stock, galvanized.

We also keep in stock : Galvanized Malleable-Iron Bushings,  $\frac{3}{8}$  to  $2\frac{1}{2}$  inch, inclusive ; Galvanized Malleable-Iron Unions,  $\frac{1}{4}$  to 4-inch, inclusive.

# BRASS STEAM AND WATER FITTINGS.

367


ROUGH AND FINISHED.



ELBOW.



TEE.



FINISHED UNION.

## ELBOWS.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Rough, each.....	\$0.12	\$0.17	\$0.21	\$0.28	\$0.35	\$0.50	\$0.85	\$1.10	\$1.50	\$3.50	\$4.50	\$7.00	\$10.00
Reducing, Rough, each.....		.22	.26	.35	.45	.62	1.10	1.40	1.90	4.40	5.65	8.75	12.50
45° Rough, each.....		.25	.30	.40	.50	.75	1.25	1.65	2.25	5.25	6.75		
Street, Rough, each.....				.55	.75	1.00	1.80	2.50	3.25				

## TEES.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Rough, each.....	\$0.15	\$0.20	\$0.30	\$0.40	\$0.50	\$0.75	\$1.00	\$1.30	\$1.75	\$4.00	\$5.50	\$9.00	\$13.00
Reducing, Rough, each.....		.25	.38	.50	.63	.95	1.25	1.65	2.20	5.00	6.90	11.25	16.25

## CROSSES.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Rough, each.....	\$0.30	\$0.40	\$0.50	\$0.60	\$0.80	\$1.50	\$2.00	\$3.50	\$5.00	\$7.00	\$10.00	\$14.50
Reducing, Rough, each.....	.38	.50	.65	.75	1.00	1.90	2.50	4.40	6.25	8.75	12.50	18.00

## REDUCERS.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Rough, each.....	\$0.22	.32	.45	.65	.90	1.12	1.85	3.00	4.50

## RETURN BENDS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Close Pattern, Rough, each.....	\$0.40	\$0.75	\$1.15	\$1.65	\$2.50	\$4.00
Open Pattern, Rough, each.....	.50	1.00	1.35	2.00	3.00	4.50

## UNIONS.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Finished, each.....	\$0.32	\$0.36	\$0.50	\$0.70	\$0.90	\$1.25	\$1.70	\$2.50	\$3.60	\$6.00	\$7.75
Rough, Extra Heavy, each..	.35	.40	.55	.75	1.00	1.40	1.90	2.75	4.00	6.50	8.50

Finished Fittings, double above list.



# BRASS STEAM AND WATER FITTINGS.

ROUGH AND FINISHED.



COUPLING.



CAP.



PLUG.

## COUPLINGS, CAPS AND PLUGS.

Size Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Couplings, Rough, each .....	\$0.10	\$0.14	\$0.16	\$0.25	\$0.37	\$0.50	\$0.60	\$0.90	\$1.35	\$2.40	\$3.50
Couplings R. & L., Rough, each.....	.17	.20	.20	.30	.45	.60	.75	1.12	1.75	2.00	3.00
Caps, Rough, each.....	.15	.15	.20	.25	.35	.45	.60	.80	1.10	2.00	3.00
Plugs, Rough, each.....	.09	.10	.12	.15	.20	.28	.40	.50	.90	1.25	2.00



NIPPLE.



LOCKNUT.



BUSHING.

## NIPPLES.

Size, Inches .....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Close, each.....	\$0.12	\$0.15	\$0.20	\$0.25	\$0.30	\$0.40	\$0.60	\$0.90	\$1.25	\$2.50	\$3.50
Rough, to 4 in. long, each.....	.15	.20	.30	.35	.45	.60	.90	1.25	1.60	3.00	4.50

## LOCK NUTS AND BUSHINGS.

Size, Inches .....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Locknuts, Rough, each.....	\$0.10	\$0.10	\$0.12	\$0.15	\$0.20	\$0.30	\$0.45	\$0.70	\$0.95	\$1.50	\$2.75
Bushings, each.....	.10	.12	.14	.21	.38	.50	.67	1.00	1.50	2.50	

Bushings reducing more than two sizes, made to order at special price. Finished Fittings double above list.

## SEAMLESS DRAWN BRASS TUBING.


MADE TO CORRESPOND WITH IRON PIPE, AND TO FIT IRON PIPE FITTINGS.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
Approx. Weight. Ft., Lbs	.25	.43	.62	.90	1.25	1.70	2.50	3.00	4.00	5.75	8.30	10.90	20.70	15.75	18.31
Per Pound .....	\$0.62	.54	.48	.44	.32	.32	.32	.32	.32	.32	.32	.36	.36	.44	.52

These tubes are kept in stock up to 4-inch in 12-foot lengths. Special lengths to order. We can furnish Copper Tubes same size as above. Brass and Copper Tubes are always shipped without threads or couplings, unless otherwise specified. Threads and Couplings charged extra.

# STANDARD BRASS VALVES.

369



GLOBE VALVE.



ANGLE VALVE.




CROSS VALVE.

## GLOBE AND ANGLE VALVES, SCREWED.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Each .....	\$0.72	.72	.77	1.00	1.26	1.80	2.52	3.50	5.30	10.00	14.40	26.50	36.00

## CROSS VALVES, SCREWED.


Size, Inches .....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each .....	\$1.25	1.25	1.50	2.00	2.50	3.50	5.00	8.00	16.00	24.00



HORIZONTAL CHECK.



VERTICAL CHECK.



ANGLE CHECK.




HORIZONTAL CHECK WITH DRIP COCK.


## CHECK VALVES.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Horizontal Check, each.....	\$0.65	\$0.65	\$0.70	\$0.90	\$1.15	\$1.60	\$2.25	\$3.15	\$4.75	\$9.00	\$13.00
Vertical and Angle Check, each .....	.72	.72	.77	1.00	1.26	1.80	2.52	3.50	5.30	10.00	14.40
Horizontal Check With Drip Cock, each.....				2.15	2.55	3.15	4.05	5.40			
Horizontal Check Without Drip Cock, each.....				1.85	2.20	2.70	3.60	4.90			

## BRASS VALVES.



GLOBE VALVE.



LOCK AND SHIELD VALVE.



LOCK AND SHIELD VALVE.


## BRASS GLOBE, ANGLE AND CHECK VALVES, FLANGED.

Size, Inches.....	1	1¼	1½	2	2½	3	3½	4
Globe and Angle, each.....	\$6.75	\$8.50	\$10.50	\$16.00	\$23.00	\$35.00	\$50.00	\$70.00
Horizontal Check, each.....	6.50	8.25	10.15	15.50	22.00	33.50	47.50	66.50
Diameter Flanges, Inches.....	4	4½	5	6	7	7½	8½	9

## LOCK AND SHIELD VALVES.

Size, Inches.....	¾	1½	¾	1	1¼	1½
Rough Body, Plain, each.....	\$1.10	\$1.35	\$1.60	\$2.25	\$3.25	\$4.85
Rough Body, N. P. All Over, each.....	1.40	1.65	1.95	2.65	3.70	5.35

Keys, Plain, each, 20 cents. Finished and Nickel Plated, each, 50 cents.




## SWING CHECK VALVE.

Size, Inches.....	½	¾	1	1¼	1½	2	2½	3
Price, each.....	\$2.25	2.75	3.50	4.25	5.50	7.50	15.00	22.00



# SPECIAL BRASS VALVES.

371



GLOBE VALVE.



ANGLE VALVE.



CROSS VALVE.


## ASBESTOS DISC BRASS VALVES.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Globe and Angle Valves, each.....	\$1.10	\$1.25	\$1.60	\$2.20	\$2.80	\$4.00	\$5.50	\$8.00	\$15.75	\$22.00
Cross Valves, each.....			2.25	2.50	3.25	4.75	6.25	9.50	20.00	30.00
Extra Discs and Holders, complete, each.....	.14	.07	.09	.10	.12	.18	.25	.36	.48	.60



No. 1. RADIATOR VALVE, FEMALE.

## ASBESTOS DISC RADIATOR VALVES.



No. 2. RADIATOR VALVE, WITH UNION.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
1. Rough Body, N. P. all Over, each.....	\$2.85	\$3.65	\$4.90	\$6.75	\$11.00
2. Rough Body, N. P. all Over, each.....	3.80	4.75	6.40	8.10	13.10


## BRASS VALVES WITH JENKINS DISC.



GLOBE VALVE.



ANGLE VALVE.



GLOBE VALVE, WOOD WHEEL.

## GLOBE AND ANGLE VALVES WITH JENKINS DISC.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each .....	\$1.10	\$1.25	\$1.60	\$2.20	\$2.80	\$4.00	\$5.50	\$8.00	\$15.75	\$22.00
Extra Discs .....	.03	.04	.04	.05	.06	.09	.12	.18	.24	.33

## GLOBE AND ANGLE VALVES WITH JENKINS DISC, WOOD WHEEL.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Rough Body, Plain, each.....	\$2.00	\$2.50	\$3.20	\$4.50	\$6.25	\$10.50
Rough Body, Plated Trimmings, each....	2.30	2.80	3.50	4.80	6.55	10.80
Rough Body, Plated All Over, each.....	2.40	2.90	3.60	4.90	6.65	10.90
Finished All Over, each.....	2.50	3.00	3.75	5.25	7.25	11.75
Finished and Plated All Over, each.....	2.90	3.40	4.15	5.65	7.65	12.15



HORIZONTAL CHECK.



VERTICAL CHECK.




ANGLE CHECK.


## CHECK VALVES WITH JENKINS DISC.

Size, Inches .....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each .....	\$1.10	1.20	1.30	1.90	2.60	3.60	5.00	7.50	13.50	20.50





SAFETY VALVE.




LOW-PRESSURE SAFETY VALVE.

## SAFETY VALVES, STEAM METAL.


Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Brass Disc, each.....	\$2.20	\$2.50	\$3.25	\$3.90	\$4.70	\$7.15	\$9.00	\$12.50	\$22.50	\$33.50
Jenkins Disc, each.....			4.12	4.95	5.50	8.25	10.15	15.40		

## LOW PRESSURE SAFETY VALVES, STEAM METAL.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Each .....	\$2.60	3.30	4.50	6.35	8.65



THROTTLE VALVE.



BUTTERFLY VALVE.



VACUUM VALVE.


## THROTTLE, BUTTERFLY AND VACUUM VALVES.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
*Throttle Valves, Steam Metal, each..				\$10.00	\$11.50	\$14.00	\$20.00	\$25.00	\$35.00	
†Butterfly Valves, each.....				3.10	4.40	5.65	6.75	10.00	13.75	\$21.00
Vacuum Valves, each.....	\$1.00	\$1.25	\$1.50	2.00	2.50					


\* Suitable for a working pressure of 175 pounds. † Butterfly Valves do not close steam or water tight.




## HOSE VALVES.




HOSE VALVE, WHEEL HANDLE.



HOSE VALVE, TEE HANDLE.



GARDEN HOSE VALVE.



GATE HOSE VALVE.

## HOSE VALVES (BRASS).

Size, Inches.....	1	1¼	1½	2	2½
Rough Body, Plain, each.....	\$3.15	\$3.70	\$4.75	\$7.00	\$8.50
Rough Body, Nickel-Plated all over, each.....	3.65	4.30	5.50	8.00	9.75
Polished Brass all over, each.....				11.50	14.50

These Valves have standard iron pipe thread on bottom and Chicago standard hose thread on side, 1 to 2-inch inclusive. The 2½-inch has the Chicago Fire Department thread on side. Can be furnished with other threads than specified when wanted.

## GARDEN HOSE VALVES (BRASS.)

Size, Inches.....	½	¾	1	1¼	1½	2	2½
Rough Body, Finished Trimmings, each...	\$1.65	1.65	2.20	3.40	4.75	7.00	12.00

These Valves have standard iron pipe thread on bottom, and are made with either Chicago or California hose thread on side. Can be furnished with other threads than those specified when so ordered.

## HOSE VALVES, DOUBLE GATE.

## IRON WHEEL.

Size, Inches.....	1	1¼	1½	2	2½
Rough Body, Plain, with Brass Cap and Chain, each.....	\$3.75	\$4.85	\$6.50	\$9.25	\$16.50
Rough Body, Plain, without Cap and Chain, each.....	2.50	3.50	5.00	7.50	14.00

## WITH FINISHED BRASS WHEEL.

Size, Inches.....	1	1¼	1½	2	2½
Finished all over, with Brass Cap and Chain, each.....	\$6.75	\$8.60	\$10.25	\$15.00	\$24.50
Finished all over, without Cap and Chain, each.....	5.50	7.25	8.75	13.25	22.00
Finished and Plated all over, with Brass Cap and Chain, each.....	7.35	9.35	11.00	16.00	26.00
Finished and Plated all over, without Cap and Chain, each...	5.90	7.70	9.25	14.00	23.00


These Valves have standard iron pipe thread on female end and hose thread on male end. When ordering send sample hose thread. They are always made to order.

# RADIATOR VALVES WITH UNION.

375

## BRASS DISCS AND JENKINS DISCS.

WOOD WHEELS.



Threads : Male right-hand on union, female right hand on bottom.

### BRASS DISC.

No.	Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
11	Rough Body, Finished Trimmings, each.....	\$2.15	\$2.50	\$3.30	\$4.40	\$5.90	\$9.25
12	Rough Body, Plated Trimmings, each.....	2.35	2.75	3.60	4.70	6.25	9.75
13	Rough Body, Plated all over, each.....	2.50	2.90	3.75	5.00	6.50	10.00
14	Finished all over, each.....	3.00	3.40	4.25	5.75	7.75	12.00
15	Finished and Plated all over, each.....	3.35	3.80	4.70	6.35	8.35	12.75

### JENKINS DISC.

No.	Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
26	Rough Body, Finished Trimmings, each.....	\$2.75	\$3.50	\$4.30	\$5.85	\$7.75	\$12.60
27	Rough Body, Plated Trimmings, each.....	3.05	3.80	4.60	6.15	8.05	12.90
28	Rough Body, Plated all over, each.....	3.15	3.90	4.70	6.25	8.15	13.00
29	Finished all over, each.....	3.20	4.00	4.80	6.40	8.75	13.85
30	Finished and Plated all over, each.....	3.60	4.40	5.20	6.80	9.15	14.25


In ordering, always use valve numbers and sizes.

We shall fill orders for these styles Radiator Valves tapped as above, unless otherwise specified, and shall invariably refuse to allow the return of such as may be incorrectly ordered.


## CORNER RADIATOR VALVES.

WITH JENKINS DISCS.

WOOD WHEELS.



RIGHT HAND VALVE.



LEFT HAND VALVE.

No.	Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
31	Rough Body, Finished Trimmings, each.....	\$2.75	\$3.50	\$5.00	\$7.00	\$11.55
32	Rough Body, Plated Trimmings, each.....	3.05	3.80	5.30	7.30	11.85
33	Rough Body, Plated all over, each.....	3.15	3.90	5.40	7.40	11.95
34	Finished all over, each.....	3.25	4.25	5.75	8.00	12.95
35	Finished and Plated all over, each.....	3.65	4.65	6.15	8.40	13.35

WITH UNION.

No.	Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
36	Rough Body, Finished Trimmings, each.....	\$3.85	\$4.75	\$6.45	\$8.55	\$13.85
37	Rough Body, Plated Trimmings, each.....	4.15	5.05	6.85	8.85	14.15
38	Rough Body, Plated all over, each.....	4.25	5.15	6.95	8.95	14.25
39	Finished all over, each.....	4.40	5.30	7.05	9.65	15.25
40	Finished and Plated all over, each.....	4.80	5.70	7.45	10.05	15.65

All corner valves are tapped left hand in both openings.

Valves fitted with lock and shield at same list; keys extra.



# "DETROIT" SCREW STEM STEAM RADIATOR VALVES. 377

WITH UNION.

## PRICE LIST FOR BRASS DISC.

No.	Size.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
60	Rough body, finished trimmings.....	\$2.45	\$3.25	\$4.50	\$6.50	\$10.00
61	Rough body, plated trimmings.....	2.60	3.35	4.90	6.60	10.25
62	Rough body, plated all over.....	2.85	3.65	5.05	7.10	10.85
63	Finished body.....	3.00	3.85	5.25	7.50	11.50
64	Finished body, plated all over.....	3.40	4.30	5.80	8.10	12.35

## WITH JENKINS DISC.


No.	Size.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
70	Rough body, finished trimmings.....	\$3.50	\$4.30	\$5.85	\$7.75	\$12.60
71	Rough body, plated trimmings.....	3.75	4.65	6.25	8.00	12.85
72	Rough body, plated all over.....	3.80	4.75	6.40	8.10	13.10
73	Finished body.....	4.00	4.80	6.40	8.75	13.85
74	Finished body, plated all over.....	4.25	5.25	7.00	9.25	14.35
	Jenkins Discs.....	.10	.12	.18	.25	.36

In ordering use numbers and sizes *only*.

All valves threaded as described, unless otherwise specified, and we shall decline to allow the return of such as may be incorrectly ordered.

Valves with Jenkins Disc will be furnished unless otherwise specified.

Threads: Right-hand on union. Right-hand on bottom.



# "DETROIT" IMPROVED QUICK-OPENING HOT WATER RADIATOR VALVE.

WITH UNION.

## PRICE LIST.

No.	Size .....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
99	Rough body, finished trimmings.....	\$2.05	\$2.45	\$3.25	\$4.50	\$6.50	\$10.00
100	Rough body, plated trimmings.....	2.30	2.60	3.35	4.90	6.65	10.25
101	Rough body, plated all over.....	2.40	2.85	3.65	5.05	7.10	10.85
102	Finished body.....	2.60	3.00	3.85	5.25	7.50	11.50
103	Finished body, plated all over.....	2.90	3.40	4.30	5.80	8.10	12.35

All valves threaded as described, unless otherwise specified, and we shall decline to allow the return of such as may be incorrectly ordered.

Threads: Right-hand on union. Right-hand on bottom.



# HOT WATER RADIATOR VALVE.

## QUICK OPENING QUARTER TURN.



Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Rough Body, Finished Trimmings, each.....	\$1.50	\$1.75	\$2.50	\$3.75	\$5.50
Rough Body, Plated Trimmings, each.....	1.75	2.05	2.80	4.05	6.00
Rough Body, Plated all over, each.....	1.85	2.15	3.00	4.25	6.25
Finished all over, each.....	2.25	2.85	4.05	5.50	8.25
Finished and Plated all over, each.....	2.60	3.25	4.50	6.00	9.00

## WITH UNION.


Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Rough Body, Finished Trimmings, each.....	\$2.00	\$2.50	\$3.50	\$5.00	\$7.00
Rough Body, Plated Trimmings, each.....	2.30	2.85	3.90	5.40	8.00
Rough Body, Plated all over, each.....	2.40	3.00	4.10	5.60	8.25
Finished all over, each.....	3.00	4.05	5.15	7.40	11.25
Finished and Plated all over, each.....	3.40	4.50	5.75	8.00	12.00

These valves are made with Male Union *only*.

In ordering female valves, state whether *left* hand thread is wanted at bottom or side.

## UNION ELBOWS. BRASS.


### FOR HOT WATER RADIATORS.



Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Rough Body. Plain, each.....	\$1.25	\$1.60	\$2.15	\$2.85	\$4.50
Rough Body, Plated, each.....	1.50	1.85	2.40	3.15	4.80
Finished all over, each.....	1.70	2.10	2.80	3.75	5.35
Finished and Plated all over, each.....	1.95	2.35	3.05	4.05	5.65

## KEYS. BRASS.

### FOR LOCK AND SHIELD VALVES.



No. 1.



No. 2.

	Plain.	Plated.
No. 1. For Valves $\frac{3}{8}$ to $\frac{1}{2}$ -inch inclusive, each.....	\$0.1B	\$0.25
	Plain.	Plated.
No. 2. For Valves $\frac{3}{4}$ to 2-inches, inclusive, each.....	\$0.50	\$0.70

# COMPRESSION RADIATOR AIR VALVES.

379

## BRASS.



No. 1.



No. 2.



No. 3.



No. 4.



No. 5.

### CHASED IRON PIPE.

Size, Inches.....	
No. 1 All Brass, each.....	
No. 2. Wood Wheel, each.....	
No. 3. Wood Wheel, with nose, each.....	
No. 4 Lock and Shield, each.....	
No. 5. Lock and Shield, each.....	

### PLAIN.

$\frac{1}{8}$	$\frac{1}{4}$
\$0.30	\$0.35
.40	.50
.65	.70
.30	.35
.50	

### PLATED.

$\frac{1}{8}$	$\frac{1}{4}$
\$0.35	\$0.40
.45	.50
.70	.75
.35	.40
.57	

Keys for Nos. 4 and 5 extra : Plain, each, 12 cents; Plated, each, 18 cents.



No. 3.


## VICTOR AUTOMATIC AIR VALVES.



No. 1.



No. 2.



No. 4.



No. 7.

Number.....	1	2	3	4	7
Price, Plated, per dozen.....	\$7.50	7.50	9.00	9.00	15.00

## MARSH AUTOMATIC AIR VALVES.



No. 1.



No. 2.



No. 3.



No. 5.



No. 6.




No. 6B.

Figure.....	1	2	3	5	6	6B
Nickel-plated, each...	\$1.15	1.25	1.15	1.50	1.25	1.40



## EXPANSION JOINTS.



STEAM METAL.



STEAM METAL.

## EXPANSION JOINTS.

## STANDARD TRAVERSE.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Traverse, Inches.....	2	$2\frac{1}{4}$	$2\frac{1}{4}$	$2\frac{1}{4}$	$2\frac{1}{4}$	$2\frac{1}{2}$	$2\frac{1}{2}$	$2\frac{3}{4}$
Each .....	\$1.50	2.20	2.75	4.00	5.00	8.00	17.50	24.00

## SPECIAL TRAVERSE.

Traverse.	Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
6 inches.....	Each.....	\$8.25	\$9.00	\$10.00	\$11.50	\$13.50
8    ".....	".....	9.00	10.00	11.25	13.00	15.50
10   ".....	".....	9.75	11.00	12.50	14.50	17.50
12   ".....	".....	10.50	12.00	13.75	16.00	19.50


When used for high pressure steam, the expansion is 1 inch in 50 feet of pipe.

## SWING JOINT.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Rough, each.....	\$1.00	\$1.25	\$1.75	\$2.40	\$3.50	\$4.50	\$6.25	\$9.00
Finished, each.....	1.25	1.50	2.00	2.75	4.00	5.00	7.00	10.00

# STANDARD IRON-BODY VALVES.


381



GLOBE VALVE, PLAIN TOP.



ANGLE VALVE, PLAIN TOP.



CROSS VALVE, PLAIN TOP.

## IRON-BODY GLOBE AND ANGLE VALVES, PLAIN TOP. SCREWED.

Size, Inches.....	1	1¼	1½	2	2½	3
Each.....	\$2.25	2.75	3.50	5.40	7.35	9.80

### FLANGED.

Size, Inches.....	2	2½	3
Each.....	\$7.00	9.00	12.50
Diameter of Flanges, Inches.....	6	7	7½

## IRON-BODY CROSS VALVES, PLAIN TOP. SCREWED.


Size, Inches.....	2	2½	3
Each.....	\$6.50	9.00	12.50

### FLANGED.


Size, Inches.....	2	2½	3
Each.....	\$9.00	11.75	16.50
Diameter of Flanges, Inches.....	6	7	7½

## STANDARD IRON-BODY VALVES.


WITH YOKE.




GLOBE VALVE, SCREWED.



GLOBE VALVE, FLANGED.



ANGLE VALVE, SCREWED.



CROSS VALVE.

## IRON-BODY GLOBE AND ANGLE VALVES—WITH YOKE.

SCREWED.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	10	12
Each .....	\$7.00	9.00	12.50	15.25	19.00	24.00	27.00	37.50	63.00	72.00	114.00	170.00

FLANGED.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	10	12	*14	*16
Each .....	\$8.60	10.75	15.00	18.50	22.50	27.50	31.00	42.00	68.00	77.00	123.00	187.00	350.00	475.00
Diameter of Flanges, Inches..	6	7	7½	8½	9	9¼	10	11	12½	13½	16	19	21	23½

\* NOTE.—The 14 and 16-inch valves are made to order only, and at a special discount.

## IRON-BODY CROSS VALVES.—WITH YOKE.

SCREWED.

Size, Inches.....	3	3½	4	4½	5	6	7	8	10	12
Each .....	\$16.25	20.00	23.50	30.65	35.25	47.25	78.00	92.00	162.00	240.00

FLANGED.

Sizes, Inches.....	3	3½	4	4½	5	6	7	8	10	12
Each .....	\$20.00	25.00	28.50	36.00	41.00	54.00	85.00	100.00	175.00	265.00
Diameter of Flanges, Inches...	7½	8½	9	9¼	10	11	12½	13½	16	19





HORIZONTAL CHECK.



ANGLE CHECK.

## HORIZONTAL CHECK VALVES.

## SCREWED.

Size, Inches.....	1	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8	10	12
Each.....	\$1.50	2.20	2.65	3.60	6.50	8.90	12.25	14.25	19.00	22.00	30.00	45.00	57.00	105.00	155.00

## FLANGED.

Size, Inches.....	1	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8	10	12	*14
Diameter of Flanges, inches.....	4	4½	5	6	7	7½	8½	9	9¼	10	11	12½	13½	16	19	21
Each .....	\$2.50	3.25	4.00	5.25	8.25	11.50	15.50	18.00	22.50	26.00	35.00	50.00	62.00	115.00	175.00	300.00

## ANGLE CHECK VALVES.

## SCREWED.

Size, Inches.....	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8
Each .....	\$2.20	2.65	3.60	6.50	8.90	12.25	14.25	19.00	22.00	30.00	45.00	57.00

## FLANGED.


Size, Inches.....	1¼	1½	2	2½	3	3½	4	4½	5	6	7	8
Each .....	\$3.25	4.00	5.25	8.25	11.50	15.50	18.00	22.50	26.00	35.00	50.00	62.00
Diameter of Flanges, inches.	4½	5	6	7	7½	8½	9	9¼	10	11	12½	13½

\*NOTE.—The 14-inch Valves are made to order only, and at a special discount.

## STANDARD IRON-BODY VALVES.



VERTICAL CHECK VALVE.



SWING CHECK VALVE.

## VERTICAL CHECK VALVES.

## SCREWED.

Size, Inches.....	2½	3	3½	4	4½	5	6	7	8
Each .....	\$9.50	12.50	17.00	21.00	30.00	33.00	40.00	62.00	73.00

## FLANGED.

Size, Inches.....	2½	3	3½	4	4½	5	6	7	8
Each .....	\$11.50	15.00	20.00	25.00	33.50	37.00	45.00	67.00	78.00
Diameter of Flanges, Inches .....	7	7½	8½	9	9¼	10	11	12½	13½


## SWING CHECK VALVES.

Size, Inches.....	2½	3	3½	4	5	6	7	8	10	12	14
Each, Screwed Ends.....	\$15.00	\$18.00	\$24.00	\$27.00	\$38.00	\$48.00	\$62.00	\$75.00	\$125.00	\$200.00	.....
Each, Flanged Ends .....	17.00	21.00	27.00	30.00	42.00	52.00	67.00	80.00	135.00	220.00	\$350.00
Each, Hub Ends.....	.....	.....	.....	35.00	48.00	60.00	.....	90.00	160.00	265.00	.....
Diameter of Flanges, Inches.....	7	7½	8½	9	10	11	12½	13½	16	19	.....
Distance from end to end, Screwed, Inches.....	6⅝	7½	8½	9½	11	12½	14	16	18¾	22	.....
Length face to face of Flanges, Inches.....	8½	9½	10½	11	13	13½	16	17	20	24	.....


Swing Check Valves, screwed and flanged, for water, have leather discs; for steam have brass discs.

Hub End Swing Check Valves always have leather discs.

If not otherwise specified, screwed and flanged Swing Check Valves with brass discs will always be sent.



SAFETY VALVE.



BUTTERFLY VALVE.

## IRON-BODY SAFETY VALVES. SCREWED.

Size, Inches .....	1	1 $\frac{1}{4}$	1 $\frac{1}{2}$	2	2 $\frac{1}{2}$	3	3 $\frac{1}{2}$	4	4 $\frac{1}{2}$	5	6	7	8
Each .....	\$4.00	\$5.00	\$5.80	\$7.80	\$13.25	\$17.25	\$23.00	\$28.75	\$34.50	\$41.50	\$57.75	\$93.50	\$132.00

## FLANGED.

Size, Inches.....	2	2 $\frac{1}{2}$	3	3 $\frac{1}{2}$	4	4 $\frac{1}{2}$	5	6	7	8
Each .....	\$10.25	\$16.00	\$21.50	\$27.50	\$34.00	\$40.00	\$48.00	\$65.00	\$100.00	\$140.00
Diameter of Flanges .....	6	7	7 $\frac{1}{2}$	8 $\frac{1}{2}$	9	9 $\frac{1}{4}$	10	11	12 $\frac{1}{2}$	13 $\frac{1}{2}$

## IRON-BODY SAFETY VALVES. WITH JENKINS DISC.

Size, Inches.....	2	2 $\frac{1}{2}$	3	3 $\frac{1}{2}$	4	5	6
Screwed, each.....	\$10.25	\$16.75	\$22.00	\$31.00	\$38.00	\$55.00	\$73.00
Flanged, each.....	12.25	19.00	25.50	34.00	41.50	62.00	80.00


## IRON-BODY BUTTERFLY VALVES.

Size, Inches.....	1 $\frac{1}{4}$	1 $\frac{1}{2}$	2	2 $\frac{1}{2}$	3	3 $\frac{1}{2}$	4	5	6
Screwed, each.....	\$6.35	\$7.00	\$8.00	\$9.50	\$12.00	\$16.00	\$18.50	\$28.50	\$42.50
Flanged, each.....	7.50	8.50	9.50	11.50	15.00	19.00	22.00	32.00	47.00


Butterfly Valves do not close steam or water tight.




## JENKINS DISC IRON-BODY VALVES.



GLOBE VALVE, PLAIN TOP.



GLOBE VALVE, YOKE TOP.



GLOBE VALVE, FLANGER ENDS.

## JENKINS DISC IRON-BODY GLOBE AND ANGLE VALVES.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	10	12
Plain Top, Screwed, each.....	\$7.25	\$11.00	\$16.00									
Yoke Top, Screwed, each.....	10.00	12.00	16.75	\$19.50	\$24.00	\$36.00	\$40.00	\$48.00	\$80.00	\$90.00	\$130.00	\$185.00
Plain Top, Flanged, each.....	8.50	13.00	18.00									
Yoke Top, Flanged, each.....	11.75	14.00	18.50	21.50	26.00	39.00	42.00	50.00	80.00	90.00	130.00	185.00

## DIMENSIONS OF IRON-BODY VALVES WITH JENKINS DISC.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	10	12
Diameter of Flanges.....	6	7	7½	8½	9	9½	10	11	12½	13½	16	19
Face to Face Globe Valves.....	6	7½	9½	10	11¾	12½	13	16	16	18½	21¼	24½
Center to Face Angle Valves..	3¾	4½	4¾	5¾	5¾	6¼	6½	8	8½	9¼	11	12¾

## JENKINS DISC IRON-BODY CHECK VALVES.

Size, Inches.....	2½	3	3½	4	5	6
Screwed Ends, each.....	\$10.50	\$14.00	\$17.00	\$20.00	\$30.00	\$40.00
Flanged Ends, each.....	12.50	16.50	20.00	23.00	33.00	43.00

## JENKINS DISC IRON-BODY CROSS VALVES.


Size, Inches.....	2½	3	3½	4	4½	5	6
Screwed Ends, each.....	\$16.00	\$21.00	\$26.00	\$30.00	\$42.00	\$45.00	\$58.00
Flanged Ends, each.....	19.00	24.00	29.00	33.00	45.00	48.00	62.00

## JENKINS DISCS.

Size, Inches.....	¼	⅜	½	¾	1	1¼	1½	2	2½	3	3½	4	5	6	7	8	10	12
Each.....	\$0.03	.04	.04	.05	.06	.09	.12	.18	.24	.33	.45	.52	.68	.90	.98	1.20	1.75	2.25




GLOBE VALVE, PLAIN TOP.




GLOBE VALVE, YOKE TOP.

## ASBESTOS DISC GLOBE AND ANGLE VALVES.

Size, Inches.....	2	2½	3	3½	4	5	6	7	8	10	12
Screwed, Plain Top, each.....	\$7.25	\$11.00	\$16.00	\$18.50	\$23.00						
Flanged Plain Top, each.....	8.50	13.00	18.00	20.50	25.00						
Screwed, Yoke Top, each.....	10.00	12.00	16.75	19.50	24.00	\$40.00	\$48.00	\$80.00	\$90.00	\$130.00	\$185.00
Flanged, Yoke Top, each.....	11.75	14.00	18.50	21.50	26.00	42.00	50.00	80.00	90.00	130.00	185.00



ASBESTOS PACKED COCK.




WITH GLAND.

## ASBESTOS PACKED IRON COCKS.


Size, Inches.....	½	¾	1	1¼	1½	2	2½	3	3½	4	5	6
Screwed Ends, each .....	\$1.60	\$2.10	\$2.50	\$3.50	\$4.75	\$7.00	\$12.00	\$18.00	\$27.00	\$30.00	\$45.00	\$60.00
Flanged Ends, each .....			2.50	3.50	4.75	7.00	12.00	18.00	27.00	30.00	45.00	60.00
With Gland, each.....	2.10	2.50	3.50	4.75	7.00	12.00	18.00	27.00				
4-Way Cocks, each .....	3.75	5.25	7.25	10.00	18.00	25.00	30.00	35.00	50.00			

Brass Three-way Cocks can also be furnished. Prices upon application.

## BACK-PRESSURE VALVES.



DAVIS' BACK-PRESSURE VALVE.



SECTIONAL.



IRON-BODY BACK-PRESSURE VALVE.

## DAVIS' NOISELESS BACK-PRESSURE VALVES.

Screwed.		Each.	Flanged.		Each.
2 inch.....		\$14.00	8 inch, 14 inch flange.....		\$100.00
2½ ".....		16.00	10 " 17 " ".....		145.00
3 ".....		18.00	12 " 19 " ".....		220.00
3½ ".....		22.00	14 " 21 " ".....		345.00
4 ".....		25.00	16 " 24 " ".....		465.00
4½ ".....		30.00	18 " 26 " ".....		600.00
5 ".....		40.00	20 " 29 " ".....		750.00
6 ".....		60.00	22 " 31 " ".....		900.00
7 ".....		80.00	24 " 34 " ".....		1,050.00

## IRON-BODY BACK-PRESSURE VALVES.

## SCREWED.


Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	10	12
Each. ....	\$11.00	13.00	15.00	19.00	22.50	28.50	33.50	43.00	70.00	85.00	120.00	180.00

## FLANGED.


Size, Inches. ....	3	3½	4	4¼	5	6	7	8	10	12	*14	*16
Each. ....	\$17.50	22.00	26.00	32.00	37.00	47.00	75.00	90.00	130.00	200.00	350.00	475.00

\* NOTE.—The 14 and 16-inch valves are made only to order, and at a special discount.





NO. 1



NO. 2

## SCREWED.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
No. 1, each.....	\$20.00	\$22.00	\$24.00	\$25.00	\$30.00	\$35.00	\$40.00	\$50.00	\$60.00
No. 2, each.....	25.00	27.00	29.00	30.00	36.00	42.00	48.00	58.00	70.00
Distance End to End, Inches.....	$3\frac{1}{4}$	4	5	7	$7\frac{1}{2}$	$7\frac{1}{2}$	$9\frac{1}{2}$	$9\frac{1}{2}$	$10\frac{1}{2}$

## FLANGED.

Size, Inches.....	3	4	5	6	7	8	10	12
No. 1, each.....	\$40.00	\$60.00	\$75.00	\$100.00	\$135.00	\$175.00	\$275.00	\$350.00
No. 2, each.....	48.00	70.00	90.00	120.00	160.00	200.00	300.00	385.00
Length, Face to Face of Flanges, Inches.....	9	$10\frac{1}{4}$	11	$11\frac{3}{4}$	$13\frac{1}{2}$	16	20	21
Diameter of Flanges, Inches.....	7	$8\frac{1}{2}$	10	12	13	15	18	20


The  $\frac{3}{4}$ , 1 and  $1\frac{1}{4}$ -inch Regulators are made of brass; larger sizes have iron body with brass trimmings.

No. 1 is designed for all purposes where there is no pulsation of pressure, viz.: Steam heating, boiling, drying, distilling and all places requiring a constant, unvarying pressure below that of boiler.


No. 2 is the same as No. 1, with the addition of oil cylinder or dash pot, and is to be used where there is a vibration or pulsation of pressure, as in the steam pipe of engine or pump when valves are opened or closed, and in steam heating systems caused by exhaust from engines, pumps, steam elevators, etc.

In ordering, please state boiler pressure that is carried, purpose to be used for, and what pressure want to reduce to.

## IRON-BODY EXPANSION JOINTS.



EXPANSION JOINT, SCREWED ENDS.



EXPANSION JOINT, FLANGED ENDS.

## IRON-BODY EXPANSION JOINTS, STANDARD TRAVERSE.

Size, Inches.....	2	2½	3	3½	4	5	6	7	8	9	10	12
Traverse, Inches.....	2½	2½	2¾	3	3¼	4	5	6	7	7	7	8
Screwed Ends, each.....	\$7.00	\$8.00	\$10.00	\$14.00	\$18.00	\$38.00	\$45.00	\$70.00	\$100.00	\$110.00	\$160.00	\$225.00
Flanged Ends, each.....	15.00	16.00	18.50	25.00	30.00	48.00	55.00	80.00	110.00	120.00	175.00	250.00
Diameter of Flanges, inches.....	6	7	7½	8½	9	10	11	12½	13½	15	16	19

When used for high-pressure steam, the expansion is 1 inch in 50 feet of pipe.

## IRON-BODY EXPANSION JOINTS, SPECIAL TRAVERSE.

Traverse.....	Size, Inches.....	2	2½	3	3½	4	5	6	7
6 Inches.....	Screwed Ends, each.....	\$11.00	\$13.00	\$17.50	\$25.00	\$30.00	\$45.00	\$55.00	\$70.00
10 ".....	" " ".....	16.00	19.00	25.00	35.00	42.00	62.00	80.00	100.00
12 ".....	" " ".....	18.50	22.00	29.00	40.00	48.00	70.00	92.50	115.00
14 ".....	" " ".....	21.00	25.00	33.00	45.00	54.00	78.00	.....	.....
16 ".....	" " ".....	23.50	28.00	37.00	50.00	60.00	86.00	.....	.....
18 ".....	" " ".....	26.00	31.00	41.00	55.00	66.00	.....	.....	.....


## IRON-BODY EXPANSION JOINTS, SPECIAL TRAVERSE, FLANGED ENDS.

Traverse.....	Size, Inches.....	2	2½	3	3½	4	5	6	7
6 Inches.....	Each.....	\$18.00	\$20.00	\$25.00	\$35.00	\$40.00	\$55.00	\$65.00	.....
10 ".....	".....	23.00	26.00	32.50	45.00	52.00	72.00	90.00	\$112.00
12 ".....	".....	25.50	29.00	36.50	50.00	58.00	80.00	102.50	127.00
14 ".....	".....	28.00	32.00	40.50	55.00	64.00	88.00	.....	.....
16 ".....	".....	30.50	35.00	44.50	60.00	70.00	96.00	.....	.....
18 ".....	".....	33.00	38.00	48.50	65.00	76.00	.....	.....	.....

When used for high-pressure steam, the expansion is 1 inch in 50 feet of pipe.

# STANDARD FOOT VALVES.

391



WITH STRAINER.




## SCREWED.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	10	12
Price, each.....	\$1.15	1.30	1.40	1.90	2.40	3.30	3.90	5.60	7.30	10.50	11.25	14.75	35.00	41.00	64.00	100.00

## FLANGED.


Size, Inches.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	10	12	14	16
Price, each.....	\$3.50	4.50	5.75	7.50	9.50	13.00	14.00	17.50	38.00	45.00	70.00	112.00	150.00	200.00
Dia. of Flanges, In.	6	7	$7\frac{1}{2}$	$8\frac{1}{2}$	9	$9\frac{1}{4}$	10	11	$12\frac{1}{2}$	$13\frac{1}{2}$	16	19	21	$23\frac{1}{2}$

These Valves as constructed insure free openings.



IRON.

# BLOW OFF VALVES.



HARD METAL.


Size, Inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Price, Iron Screwed Ends, each.....				\$15.00	\$20.00	\$30.00
Price, Iron Flanged Ends, each.....				15.00	20.00	30.00
Price, Hard Metal Screwed Ends, each.....	\$3.50	\$5.00	\$7.00			
Distance center to inlet or outlet, Screwed, inches.....				$4\frac{1}{2}$	5	$5\frac{3}{4}$
Distance center to inlet or outlet Flanged, inches.....				5	$5\frac{3}{4}$	$6\frac{5}{8}$

These Valves are suitable for extreme high steam pressure up to 250 pounds.

The Hard Metal Blow Off Valves can be made either in Angle or Globe. The Angle will always be furnished unless otherwise ordered.




## THE MASON RHEOSTAT REGULATOR.



This apparatus was designed to automatically govern an electrically-driven pump operating hydraulic elevators. Operating as it does a switch, which controls the passage of the current to the electric motor, it starts and stops the pump as often as the pressure in the tank rises above or falls below the desired point. The pressure pipe from tank enters the Regulator at two different points; namely, at the union connection leading to the diaphragm chamber, shown on the left of the cut, and also at the lower union connection, shown on the right of the cut, the upper connection being used for a drip pipe. The operating portion of this Regulator is mounted on a bracket, and the piston, instead of being connected to a valve, is connected to a bell-crank arm, which is drawn back and forth by the operating cylinder, thereby controlling the pump through the medium of a switch. The operation of this apparatus is positive, there being no intermediate movement. The machine is very powerful, as it is operated by the direct water pressure in the system. It is also very sensitive, as the diaphragm under which the controlling pressure is admitted has only to move the switch.

This Regulator is made in one size only, the price of which is \$50.00 net.

## THE MASON BY-PASS OR WATER-RELIEF VALVE.




In many cases it is desirable to use a power pump for elevator or other service, driven from a line shaft or motor which has other work to perform, and which cannot be constantly stopping and starting, but which must run continuously. It is for this purpose that this By-Pass Valve is used.


It is placed in a branch pipe leading from the discharge to the suction pipe of the pump. The tank pressure enters the By-Pass Valve at two different points; namely, the union connection shown at the left of the cut, and also the upper union connection shown at the right of cut. The connection directly underneath this latter is for a drip pipe. The apparatus is adjusted by means of sliding and hanging weights. Users should be careful and not screw stuffing boxes too tight, causing the stems to bind.

### PRICE LIST.

2	inch.....	\$45.00
2½	".....	55.00
3	".....	70.00
3½	".....	80.00
4	".....	90.00
5	".....	110.00
6	".....	150.00



BRASS,



IRON.


## STANDARD WATER RELIEF VALVES.

Size, Inches.....	1	1¼	1½	2	2½	3	3½	4	5	6
Brass, each.....	\$12.00	\$15.00	\$20.00	\$30.00	\$50.00	\$65.00	\$80.00	\$100.00	\$150.00	\$180.00
Iron, each.....				30.00	50.00	65.00	80.00	100.00		


# BRASS STRAIGHT-WAY VALVES.

393

DOUBLE GATE.



PLAIN.



QUICK OPENING.

## SCREWED.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	* $3\frac{1}{2}$	*4	*5	*6
Price, each.....	\$1.25	1.25	1.30	1.75	2.50	3.50	5.00	7.50	14.00	20.00	32.00	50.00	70.00	120.00
Distance End to End, Inches.....	$1\frac{7}{8}$	$2\frac{1}{8}$	$2\frac{3}{8}$	$2\frac{1}{2}$	$2\frac{7}{8}$	$3\frac{1}{4}$	$3\frac{7}{8}$	4	$4\frac{1}{2}$	$5\frac{1}{4}$	$7\frac{1}{2}$	$7\frac{3}{4}$	$8\frac{3}{4}$	$9\frac{3}{4}$

## FLANGED.

Size, Inches.....	2	$2\frac{1}{2}$	3	* $3\frac{1}{2}$	*4	*5	*6
Price, each.....	\$14.00	24.00	34.00	45.00	60.00	85.00	135.00
Diameter of Flanges, inches.....	6	7	$7\frac{1}{2}$	$8\frac{1}{2}$	9	10	11
Length, Face to Face of Flanges, inches...	5	6	$6\frac{3}{4}$	$7\frac{1}{2}$	$8\frac{1}{4}$	$9\frac{1}{4}$	$10\frac{3}{4}$

These Valves open to the left and have rising stems up to 3 inch, inclusive.

\* NOTE—The  $3\frac{1}{2}$  to 6-inch Valves have flanged bonnet, non-rising stems and are made to order only, at a special discount.

## QUICK OPENING.

### SCREWED.


Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Price, each.....	\$3.25	4.50	6.00	8.00	12.00	22.00	30.00
Distance, End to End, inches.....	$2\frac{1}{2}$	$2\frac{7}{8}$	$3\frac{1}{4}$	$3\frac{7}{8}$	4	$4\frac{1}{2}$	$5\frac{1}{4}$

### FLANGED.


Size, Inches... ..	2	$2\frac{1}{2}$	3
Price, each.....	\$18.50	32.00	45.00
Diameter of Flanges, inches.....	6	7	$7\frac{1}{2}$
Length, Face to Face of Flanges, inches.....	5	6	$6\frac{3}{4}$

## BRASS STRAIGHT-WAY VALVES.

DOUBLE GATE.



WOOD WHEEL.



BRASS WHEEL.

WOOD WHEEL.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Price, Rough Body, Plain, each.....	\$1.70	\$2.25	\$3.05	\$4.25	\$5.85	\$9.05
Price, Rough Body, Plated Trimmings, each.....	1.90	2.50	3.35	4.55	6.15	9.55
Price, Rough Body, Plated all over, each.....	2.00	2.60	3.45	4.70	6.35	9.80
Price, Finished all over, each .....	2.65	3.25	4.50	6.00	7.50	12.00
Price, Finished and Plated all over, each.....	2.95	3.60	4.90	6.45	8.00	12.75
Distance End to End, inches.....	$2\frac{3}{8}$	$2\frac{1}{2}$	$2\frac{7}{8}$	$3\frac{1}{4}$	$3\frac{7}{8}$	4

WOOD WHEEL WITH UNION.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Price, Rough Body, plain, each.....	\$2.75	\$3.35	\$4.20	\$5.50	\$7.25	\$11.35
Price, Rough Body, Plated all over, each.....	3.10	3.75	4.65	6.10	7.85	12.10

FINISHED BRASS WHEEL.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Price, Rough Body, each.....	\$2.70	\$3.25	\$4.05	\$5.50	\$7.10	\$10.30	\$18.00	\$25.00
Price, Finished all over, each.....	3.65	4.25	5.50	7.25	8.75	13.25	22.00	30.00
Price, Finished and Plated all over, each .....	3.95	4.60	5.90	7.70	9.25	14.00	23.00	31.50
Distance End to End, Inches.....	$2\frac{3}{8}$	$2\frac{1}{2}$	$2\frac{7}{8}$	$3\frac{1}{4}$	$3\frac{7}{8}$	4	$4\frac{1}{2}$	$5\frac{1}{4}$

These Valves are made only to order.




# IRON-BODY STRAIGHT-WAY VALVES.

395

WEDGE GATE BRASS TRIMMINGS.



SCREWED.



FLANGED.

## SCREWED.

Size, Inches .....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Price, each .....	\$10.00	12.00	15.00	18.00	20.00	23.00	25.00	30.00	45.00	55.00	80.00	90.00	125.00
Distance end to end, inches.....	5½	5¾	6¾	6¾	6¾	7	7¼	7¾	8¾	8¾	9¾	10¾	11½


## FLANGED.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8
Price, each .....	\$10.00	12.00	15.00	18.00	20.00	23.00	25.00	30.00	45.00	55.00
Diameter of Flanges, inches.....	6	7	7½	8½	9	9¼	10	11	12½	13½
Face to Face of Flanges, inches.....	6¾	6¾	7	7¾	7¾	8	8¼	8¾	9½	9¾
Size, Inches.....	9	10	12	14	16	18	20	22	24	30
Price, each .....	\$80.00	90.00	125.00	190.00	275.00	375.00	425.00	525.00	600.00	1,200.00
Diameter of Flanges, inches.....	15	16	19	21	23½	25	27½	29½	31½	38
Face to Face of Flanges, inches.....	10¾	11¾	12¾	13¼	14¼	15¼	16½	18½	20	30

These Valves have stationary stems, and open to the left.

# IRON-BODY STRAIGHT-WAY VALVES.

WEDGE DISC. BRASS TRIMMINGS.



PLAIN.



WITH GEARING.

## WATER GATES.

Size, Inches .....	2	3	4	5	6	7	8	10	12	14	16	18	20	22	24	30
Price, each.....	\$10.00	15.00	20.00	25.00	30.00	45.00	55.00	90.00	125.00	190.00	275.00	375.00	425.00	525.00	600.00	1,200.00
End to End of Pipe when Laid in Bell, Inches.....	3 $\frac{1}{4}$	3 $\frac{1}{2}$	4 $\frac{1}{4}$	4 $\frac{1}{4}$	4 $\frac{3}{4}$	5	5	5 $\frac{3}{4}$	6 $\frac{1}{2}$	6 $\frac{3}{4}$	8	9	9	9 $\frac{1}{2}$	10	21
Inside Diameter Bell Socket, In.	3 $\frac{1}{8}$	4 $\frac{5}{8}$	5 $\frac{3}{4}$	6 $\frac{7}{8}$	7 $\frac{7}{8}$	8 $\frac{7}{8}$	10	12	14 $\frac{1}{4}$	16 $\frac{1}{4}$	18 $\frac{1}{2}$	20 $\frac{5}{8}$	22 $\frac{3}{4}$	24 $\frac{3}{4}$	26 $\frac{3}{4}$	35

These Valves have stationary stems and open to the left Can furnish, when so ordered, Valves to open to the right at same price.

## WATER GATES WITH GEARING.

WITH OR WITHOUT BY-PASS RELIEF.

Size, Inches.....	16	18	20	22	24	30
Price, with either Spur or Bevel Gearing, each.....	\$375.00	\$475.00	\$550.00	\$650.00	\$725.00	\$1,400.00
Price, with Gearing and By-Pass Relief, each.....	450.00	550.00	650.00	750.00	850.00	1,600.00
Size of By-Pass, Inches.....	2 $\frac{1}{2}$	2 $\frac{1}{2}$	3	3	3	6

Flanged End Valves, with Gearing or with Gearing and By-Pass Relief, same list as above. These Valves can be furnished with either Spur Gearing (to stand upright), or with Bevel Gearing (to lie on side).

# IRON-BODY STRAIGHT-WAY VALVES.

397


## BRASS TRIMMINGS.



WITH SCREW AND YOKE.



WITH INDICATOR.



QUICK OPENING.

## WITH OUTSIDE SCREW AND YOKE.

WHICH INDICATES WHETHER VALVE IS OPEN, PARTLY OPEN OR SHUT.

Size, Inches.....	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16	18	20
Price, Screwed Ends. each.....	\$20.00	23.00	28.00	33.00	40.00	46.00	55.00	70.00	90.00	115.00	135.00	170.00	.....	.....	.....	.....
Price, Flanged Ends. each.....	\$20.00	23.00	28.00	33.00	40.00	46.00	55.00	70.00	90.00	115.00	135.00	170.00	240.00	350.00	475.00	550.00
Price, with By-Pass, each.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	\$230.00	315.00	425.00	550.00	650.00

## WITH INDICATOR.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16
Price, Screwed Ends. each	\$15.00	18.00	22.00	27.00	30.00	34.00	36.00	44.00	60.00	75.00	100.00	115.00	155.00	.....	.....
Price, Flanged Ends. each	\$15.00	18.00	22.00	27.00	30.00	34.00	36.00	44.00	60.00	75.00	100.00	115.00	155.00	225.00	325.00

The Indicator attachment enables the operator at a glance to determine the position of valves, when open, partly open or shut.

## QUICK OPENING.

### SCREWED.

Size, Inches.....	2½	3	3½	4	5	6	7	8	9	10	12
Price, each.....	\$18.00	22.00	25.00	27.00	34.00	40.00	57.00	69.00	96.00	110.00	150.00

### FLANGED.

Size, Inches.....	2½	3	3½	4	5	6	7	8	9	10	12	14	16
Price, each.....	\$18.00	22.00	25.00	27.00	34.00	40.00	57.00	69.00	96.00	110.00	150.00	225.00	325.00
Diameter of Flanges, ins..	7	7½	8½	9	10	11	12½	13½	15	16	19	21	23½



## ALL IRON STRAIGHT-WAY VALVES.



PLAIN.

WEDGE GATE. FOR GAS, ACIDS, ETC.



QUICK OPENING.

## SCREWED.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Price, each.....	\$10.00	12.00	15.00	18.00	20.00	23.00	25.00	30.00	45.00	55.00	80.00	90.00	125.00

## FLANGED.

Size, Inches.....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12	14	16
Price, each.....	\$10.00	12.00	15.00	18.00	20.00	23.00	25.00	30.00	45.00	55.00	80.00	90.00	125.00	190.00	275.00

## HUB ENDS.

Size, Inches.....	3	4	6	8	10	12	14	16
Price, each.....	\$15.00	20.00	30.00	55.00	90.00	125.00	190.00	275.00

QUICK OPENING.  
SCREWED.

Size, Inches.....	2½	3	3½	4	5	6	7	8	9	10	12
Price, each.....	\$18.00	22.00	25.00	27.00	34.00	40.00	57.00	69.00	96.00	110.00	150.00

## FLANGED.


Size, Inches.....	2½	3	3½	4	5	6	7	8	9	10	12	14	16
Price, each.....	\$18.00	22.00	25.00	27.00	34.00	40.00	57.00	69.00	96.00	110.00	150.00	225.00	325.00
Diameter of Flanges, inches.....	7	7½	8½	9	10	11	12½	13½	15	16	19	21	23½

# RADIATORS.

399



ROCOCO.



FAVORITE.



PERFECTION AND SUPERIOR.

## STEAM AND WATER, DIRECT RADIATION.

Height, Inches.....	45	44	38	32	31	26	25	23	20	18	16	14	13
Price, per Square Foot, cents.....	41	41	42	46	46	49	49	53	57	58	60	64	66
Verona, Steam and Water.....			4	3 $\frac{1}{3}$		2 $\frac{2}{3}$			2				
Perfection } Steam.....	5		4	3 $\frac{1}{3}$		2 $\frac{2}{3}$		2 $\frac{1}{3}$	2				
Superior } Water.....	5 $\frac{1}{4}$		4 $\frac{1}{3}$	3 $\frac{1}{3}$		2 $\frac{2}{3}$			2				
Detroit } Ornamented, Steam and Water.....	5 $\frac{1}{4}$		4 $\frac{1}{3}$		3 $\frac{1}{2}$		2 $\frac{3}{4}$		2 $\frac{1}{4}$				
Detroit } Plain, Steam and Water.....	5 $\frac{1}{4}$		4 $\frac{1}{3}$		3 $\frac{1}{2}$		2 $\frac{3}{4}$		2 $\frac{1}{4}$				
National, Steam and Water.....	5		4	3 $\frac{1}{3}$		2 $\frac{2}{3}$		2 $\frac{1}{3}$	2				
Ideal, Steam.....	5		4	3 $\frac{1}{3}$		2 $\frac{2}{3}$		2 $\frac{1}{3}$	2				
National Single Column, Steam and Water.....			3	2 $\frac{1}{3}$		2		1 $\frac{2}{3}$	1 $\frac{1}{2}$				
Rococo, Steam and Water.....		6	5	4 $\frac{1}{2}$		3 $\frac{3}{4}$				2 $\frac{1}{4}$			
National Four Column, Steam or Water.....			8	6 $\frac{2}{3}$		5 $\frac{1}{3}$		4 $\frac{2}{3}$	4				
Italian Flue, Steam and Water.....			7	5 $\frac{3}{4}$		4 $\frac{1}{2}$			3 $\frac{1}{4}$				
Monarch Flue, Steam.....			9 $\frac{1}{2}$	8		6		5			3 $\frac{1}{3}$	3 $\frac{1}{3}$	
Detroit Flue, Steam or Water.....									6	5 $\frac{1}{4}$	4 $\frac{2}{3}$	4	3 $\frac{2}{3}$
Favorite, Steam and Water.....	5		4						2				
Kalamazoo, Steam and Water.....	5		4	3 $\frac{1}{3}$		2 $\frac{2}{3}$			2				


Figures in above columns opposite names of patterns of radiators indicate the heights in which the various patterns are made, and amount of heating surface contained in each height section.

## STANDARD STEAM TRAPS.


Diameter, Inches.....	12	15	18
Drainage Capacity, Feet of 1-inch Pipe... Each .....	1500 \$23.00	3500 \$36.00	5000 \$54.00

## NASON IMPROVED STEAM TRAPS.

Number.....	1	2	3	4	5
Drainage Capacity, Feet of 1-Inch Pipe... Greatest Number of Square feet to which it should be applied.....	1050 350	2700 900	4200 1400	6000 2000	10500 3500
Each .....	\$16.00	\$20.00	\$27.50	\$42.50	\$70.00




STANDARD STEAM TRAP.




NASON IMPROVED STEAM TRAP.

## ECLIPSE FIRE HYDRANTS.



ECLIPSE No. 3, STANDARD FIRE HYDRANT.



No. 3 SECTIONAL.



ECLIPSE No. 2, CORPORATION HYDRANT.

## No. 3. SIZES AND LIST PRICE.

Diameter of Inlet Pipe.	Pavement to Center of Inlet.	One 2½ in. Hose Nozzle.	Two 2½ in. Hose Nozzles.	Three 2½ in. Hose Nozzles.	One Steamer Nozzle.	One Steamer and one 2½ in. Nozzle.	One Steamer and two 2½ inch Nozzles.	Frost Case, Standard Length.	Each foot in Length of Stand Pipe Extra.	Each foot in Length of Frost Case, extra.
4 in.	5 ft.	\$32.00	\$34.00	\$36.00	\$34.00	\$36.00	\$38.00	\$4.00	\$1.50	\$0.75
5 "	5 "	38.00	40.00	42.00	40.00	42.00	44.00	5.00	1.75	1.00
6 "	5 "	47.00	49.00	51.00	49.00	51.00	53.00	6.00	2.25	1.25

Unless otherwise ordered, all Hydrants will be made up to turn to the left when opening. Above Hydrants also made with wrought stand pipe, if so ordered. The nut for opening hydrant and nut on nozzle caps will always be made pentagon (or five sides), unless otherwise ordered.

## ECLIPSE CORPORATION HYDRANT No. 2.

INLET THREADED FOR IRON PIPE.

To be Set in Ground, Feet.....	1½	2	3	4	5	6	8	10
1¼ inch Inlet and Outlet, each.....	\$11.85	\$12.00	\$12.30	\$12.65	\$13.00	\$13.50	\$15.00	\$17.00
1½ " " " " .....	16.30	16.45	16.80	17.15	17.50	18.00	19.50	22.00
2 " " " " .....	22.25	22.50	23.00	23.50	24.00	24.75	27.00	30.00



# EXTENSION SERVICE BOXES.

401



NO. 1



NO. 2



NO. 3



NO. 4



NO. 5



NO. 6

## SERVICE BOXES, 2½-INCH DIAMETER. FOR SERVICE COCKS ¼-INCH AND SMALLER.

Number of Box.....	88	89 A	90 B	91 C	92 C	92 D	93 D	93 E	94 D	94 E	95 E	100 E	100 F
Extending, inches.....	12	12-20	18-26	21-33	24-38	24-42	36-48	36-54	42-57	42-60	48-66	54-72	54-78
Each.....	\$0.55	.60	.65	.70	.73	.75	.80	.83	.85	.90	.95	1.00	1.10

## STANDARD SERVICE BOXES, 3-INCH DIAMETER.

Number of Box.....	100	101	102	103	104	105	106	107	108
Extending, inches.....	10	13-21½	18-28	24-39	32-48	34-58	42-66	48-72	72-96
Each.....	\$0.65	.70	.75	.83	.90	.95	1.10	1.25	1.45

## SERVICE BOXES, 2½-INCH DIAMETER, WITH STOP-COCK HOLDER.

Number of Box.....	288	289	290	291	292	293	294	295	296	297	298	299	300
Extending, inches.....	12	12-20	18-26	21-33	24-38	24-42	36-48	36-54	42-57	42-60	48-66	54-72	54-78
Each.....	\$0.85	.90	.97	1.03	1.07	1.10	1.15	1.19	1.23	1.29	1.35	1.40	1.55

## STANDARD SERVICE BOXES, 3-INCH DIAMETER, WITH STOP-COCK HOLDER.

Number of Box.....	200	201	201½	202	203	204	205	207	208
Extending, inches.....	10	13-21½	18-28	24-39	32-48	34-58	42-66	48-72	72-96
Each.....	\$0.80	.85	.90	.98	1.05	1.10	1.25	1.40	1.60

## SERVICE BOXES, 2½-INCH DIAMETER, WITH ROD AND RING.

Number of Box.....	388	389	390	391	392	393	394	395	396	397	398	399	400
Extending, inches.....	12	12-20	18-26	21-33	24-38	24-42	36-48	36-54	42-57	42-60	48-66	54-72	54-78
Each.....	\$0.95	1.00	1.07	1.13	1.17	1.20	1.25	1.29	1.33	1.39	1.45	1.50	1.65

## EXTENSION SECTIONS FOR SERVICE BOXES.

Number of Box Section.....	151	152	153	154	155	156	157
Increasing Length of Box, inches.....	9	16½	28	33	20	24	30
2½-inch Diameter each.....	\$0.25	.30	.35	.40			
3-inch Diameter, each.....					.30	.35	.40

No. 6.—Enlarged Base for Service Boxes, 3-inch diameter, to allow use of 2-inch cocks, each 50 cents.

## VALVE BOXES.



No. 1. VALVE BOX.



No. 2. ROADWAY BOX.



No. 3. LARGE SERVICE BOX.

**VALVE BOXES WITH No. 6 BASE. NO 1.**  
DIAMETER OF SHAFT, 5 $\frac{1}{4}$  INCHES.

Number of Box	AAA	AA	A	B	C	CC	D	DD	E	F	G	H
Extending. Inches.....	17	22-28	28-40	36-48	42-54	48-60	42-65	48-72	60-72	60-84	72-84	72-96
Each .....	\$3.15	3.60	3.80	4.00	4.20	4.40	4.60	4.85	5.00	5.15	5.40	5.65

Extension Section No. 58. to extend Valve Box 14 inches, 80 cents each.

**BASES FOR VALVE BOXES.**

Style of Base.....	No. 4 Round. For 4-Inch Valves.	No. 6 Round. For 6 and 8-Inch Valves.	No. 8 Round. For 10-Inch Round Valves.	No. 16 Round. For 12 and 16-Inch Round Valves.	No. 160 Oval. For 10, 12 and 16- Inch Oval Valves.	No. 162 Oval. For 18 and 20-Inch Oval Valves.
Each.....	Deduct from Price of Box. \$0.25	Included in Price of Box.	Add to Price of Box 0.30	Add to Price of Box 1.60	Add to Price of Box 0.45	Add to Price of Box 1.60

**ROADWAY OR SMALL VALVE BOXES FOR 3-INCH OR SMALLER VALVES. NO. 2.**  
DIAMETER OF BOX, 4 $\frac{1}{4}$  INCHES. WITH FLANGE BASE.


Number of Box.....	41 Q	42 Q	42 R	43 R	44 R	45 R
Extending. Inches.....	18 to 24	27 to 34	27 to 42	34 to 48	39 to 54	46 to 60
Each .....	\$2.35	2.50	2.85	2.95	3.00	3.20

**EXTRA LARGE SERVICE BOXES FOR 3-INCH SERVICE. NO. 3.**  
DIAMETER OF BOX, 4 $\frac{1}{4}$  INCHES. WITH OPEN BASE.


Number of Box.....	141 Q	142 Q	142 R	143 R	144 R	145 R
Extending. Inches.....	18 to 24	27 to 34	27 to 42	34 to 48	39 to 54	46 to 60
Each .....	\$2.35	2.50	2.85	2.95	3.00	3.20

# ROUGH STOPS.

403




T. H. ROUND-WAY.



L. H. ROUND-WAY.



T. H. FLAT-WAY.



L. H. FLAT-WAY.

## ROUGH STOPS, ROUND-WAY, FOR IRON PIPE.


Size, Inches .....	$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
T. H. Stops, per doz.....	\$19.00	\$23.00	\$28.00	\$48.00	\$75.00	\$107.00	\$190.00
T. H. Stops, with Check and Waste per doz..	21.00	25.00	30.00	51.00	79.00	113.00	200.00
L. H. Stops, per doz.....	20.00	24.50	29.50	50.00	77.50	110.50	195.00
L. H. Stops, with Check and Waste, per doz..	22.00	26.50	31.50	53.00	81.50	116.50	205.00

## ROUGH STOPS, FLAT-WAY, FOR IRON PIPE.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
T. H. Stops, per doz.....	\$13.00	\$15.00	\$18.00	\$22.00	\$32.00	\$51.00	\$71.00	\$120.00
T. H. Stops, with Check and Waste, per doz..	15.00	17.00	20.00	24.00	35.00	55.00	77.00	130.00
L. H. Stops, per doz.....	14.00	16.00	19.50	23.50	34.00	53.50	74.50	125.00
L. H. Stops, with Check and Waste, per doz..	16.00	18.00	21.50	25.50	37.00	57.50	80.50	135.00



T. H. NEWPORT.



L. H. NEWPORT.





MINNEAPOLIS PATTERN.

## SPECIAL ROUND-WAY STOPS, FOR IRON PIPE.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1
Tee Handle Stops, per dozen.....	\$12.00	\$17.00	\$30.00
Tee Handle Stops, with Check and Waste, per dozen.....	14.00	19.00	33.00
Lever Handle Stops, per dozen.....	13.00	18.50	32.00
Lever Handle Stops, with Check and Waste, per dozen.....	15.00	20.50	35.00




## ROUGH STOPS.



ROUGH STOPS, FOR IRON PIPE.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
T Handle Stops, per dozen.....	\$15.00	\$18.00	\$22.00	\$32.00	\$51.00	\$71.00	\$120.00
With Check and Waste, per dozen.....	17.00	20.00	24.00	35.00	55.00	77.00	130.00
L. Handle Stops, per dozen.....	16.00	19.50	23.50	34.00	53.50	74.50	125.00
With Check and Waste, per dozen.....	18.00	21.50	25.50	37.00	57.50	80.50	135.00

## HYDRANT COCKS.




Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$
Straight Way, per dozen.....	\$21.00	\$25.00	\$29.50	\$41.50	\$64.00
Round Way, per dozen.....	25.00	30.00	35.50	57.50	88.00

## COPPER BALLS.



WITH LEVER.



WITH SPUD TAPPED, FOR IRON PIPE.


Size, Inches.....	5	6	7	8	9	10	12
With Lever, per dozen.....	\$6.00	\$7.00	\$10.50	\$24.00	\$36.00	\$48.00	\$72.00
With Spud Threaded, for Iron Pipe, per dozen.....	4.00	6.00	9.00	15.00	25.00	40.00	60.00

# MUELLER STOP COCKS.

405



No. 36. TEE HANDLE, NUT AND WASHER BOTTOM.




No. 37. TEE HANDLE, NUT AND WASHER BOTTOM.

## STRAIGHT-WAY, ROUGH STOP COCKS.


Sizes, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 36, per dozen .....	\$15.00	18.00	22.00	32.00	51.00	71.00	120.00

## STRAIGHT-WAY, ROUGH STOP AND WASTE COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 37, per dozen .....	\$17.00	20.00	24.00	35.00	55.00	77.00	130.00



No. 42. LEVER HANDLE, NUT AND WASHER BOTTOM.



No. 43. LEVER HANDLE, NUT AND WASHER BOTTOM.


## STRAIGHT-WAY, ROUGH STOP COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 42, per dozen.....	\$16.00	19.50	23.50	34.00	53.50	74.50	125.00

## STRAIGHT-WAY, ROUGH STOP AND WASTE COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 43, per dozen .....	\$18.00	21.50	25.50	37.00	57.50	80.50	135.00

## MUELLER STOP COCKS.



No. 24. TEE HANDLE NUT AND WASHER BOTTOM.




No. 31. LEVER HANDLE, NUT AND WASHER BOTTOM.

## ROUND-WAY, ROUGH STOP COCKS.


Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 24, per dozen.....	\$19.00	23.00	28.00	48.00	75.00	107.00	190.00

## ROUND-WAY, ROUGH STOP AND WASTE COCKS.


Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 31, per dozen.....	\$22.00	26.50	31.50	53.00	81.50	116.50	205.00



No. 48. RIGHT OR LEFT HAND, TEE OR LEVER HANDLE OR SOCKET, NUT AND WASHER BOTTOM.



No. 49.



No. 55. RIGHT OR LEFT HAND, TEE OR LEVER HANDLE OR SOCKET, NUT AND WASHER BOTTOM.

## STRAIGHT-WAY PATENT STOP COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 48, per dozen*.....	\$16.00	19.50	23.50	34.00	53.50	74.50	125.00

## STRAIGHT-WAY PATENT STOP AND WASTE COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 49, per dozen*.....	\$18.00	21.50	25.50	37.00	57.50	80.50	135.00

## ROUND-WAY PATENT STOP AND WASTE COCKS.


Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 55, per dozen*.....	\$22.00	26.50	31.50	53.00	81.50	116.50	205.00

\* Tee Handles never sent unless specially ordered.




# LEVER HANDLE AND COMPRESSION BIBBS.


407



PLAIN BIBB.



HOSE BIBB.



PLAIN STOP.

## LEVER HANDLE PLAIN AND HOSE BIBBS, FOR IRON PIPE.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Plain, Finished, per dozen.....	\$12.00	\$14.00	\$17.00	\$20.00	\$26.00	\$39.00	\$64.00	\$90.00	\$180.00
Plain, Nickel-Plated, per dozen.....	14.00	16.00	19.50	22.50	28.50	42.00			
Plain, Rough, per dozen.....	11.00	13.00	16.00	18.00	23.00	35.00	56.00	78.00	160.00
Hose, Finished, per dozen.....			19.00	22.00	28.00	42.00	68.00	96.00	190.00
Hose, Nickel-Plated, per dozen.....			21.50	24.50	30.50	45.00			
Hose, Rough, per dozen.....			18.00	20.00	25.00	38.00	60.00	84.00	170.00

## PLAIN STOPS, LEVER HANDLE, FOR IRON PIPE.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$17.50	\$19.50	\$23.00	\$29.50	\$43.00
Nickel-Plated, per dozen.....	19.50	22.00	25.50	32.00	46.00



PLAIN BIBB.



HOSE BIBB.



HOSE BIBB, WITH STUFFING-BOX.


## COMPRESSION BIBBS, FOR IRON PIPE.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Plain Bibbs, Finished, per dozen.....	\$12.00	\$13.00	\$15.00	\$20.00	\$37.00	\$56.00	\$86.00	\$170.00
Plain Bibbs, Nickel-Plated, per dozen.....	14.00	15.50	17.50	22.50	40.00			
Hose Bibbs, Plain, per dozen.....	14.00	15.00	17.00	22.00	40.00	60.00	92.00	180.00
Hose Bibbs, Nickel-Plated, per dozen.....	16.00	17.50	19.50	24.50	43.00			


## COMPRESSION PLAIN OR HOSE BIBBS, WITH STUFFING-BOX.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Add to above Lists, per dozen.....	\$2.00	2.00	2.00	3.00	4.00

# COMPRESSION BIBBS AND STOPS.




PLAIN BIBB, LOOSE KEY.




HOSE BIBB, LOOSE KEY.

## COMPRESSION BIBBS, WITH LOOSE KEY, FOR IRON PIPE.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1
Plain, Finished, per dozen.....	\$19.00	\$21.00	\$27.00	\$45.00
Plain, Nickel-Plated, per dozen.....	21.50	23.50	29.50	48.00
Hose, Finished, per dozen.....	21.00	23.00	29.00	48.00
Hose, Nickel-Plated, per dozen.....	23.50	25.50	31.50	51.00



PLAIN STOP.



STOP, WITH STUFFING-BOX.



PLAIN STOP, LOOSE KEY.

## COMPRESSION STOPS, FOR IRON PIPE.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$13.00	\$14.00	\$16.00	\$24.00	\$40.00
Nickel-Plated, per dozen.....	15.00	16.50	18.50	26.50	43.00

## COMPRESSION STOPS, FOR IRON PIPE, WITH STUFFING BOX.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$15.00	\$16.00	\$18.00	\$27.00	\$44.00
Nickel-Plated, per dozen.....	17.00	18.50	20.50	29.50	47.00

## COMPRESSION STOPS, LOOSE KEY, FOR IRON PIPE.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$20.00	\$22.00	\$31.00	\$48.00
Nickel-Plated, per dozen.....	22.50	24.50	33.50	51.00



PLAIN BIBB, L. P.




HOSE BIBB, L. P.

## FULLER PLAIN BIBBS, FOR LEAD PIPE.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$18.00	\$20.00	\$26.00	\$36.00
Nickel-Plated, per dozen.....	22.00	24.00	32.00	46.00

## FULLER HOSE BIBBS, FOR LEAD PIPE.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$21.00	\$24.00	\$30.00	\$40.00
Nickel-Plated, per dozen.....	25.00	28.00	36.00	50.00



PLAIN BIBB, I. P.



HOSE BIBB, I. P.

## FULLER PLAIN BIBBS, FOR IRON PIPE.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$21.00	\$24.00	\$30.00	\$40.00
Nickel-Plated, per dozen.....	25.00	28.00	36.00	50.00

## FULLER HOSE BIBBS, FOR IRON PIPE.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1
Finished, per dozen.....	\$24.00	\$28.00	\$34.00	\$44.00
Nickel-Plated, per dozen.....	28.00	32.00	40.00	54.00



## WATER GOODS.



IMPROVED BALL COCK.




RAIN AND WELL WATER COCK.

## IMPROVED BALL COCKS, FOR IRON PIPE.


Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Per dozen.....	\$12.00	14.00	20.00	34.00	56.00	80.00	150.00

## RAIN AND WELL WATER COCKS, FOR IRON PIPE.


Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Per dozen.....	\$56.00	79.00	96.00	138.00	230.00



No. 1. SILL COCK, STRAIGHT.




No. 2. SILL COCK, ANGLE.



No. 3. SILL COCK, LOOSE KEY.


## SILL COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$
No. 1. Finished, per dozen.....	\$22.00	\$24.00
No. 1. Nickel Plated, per dozen.....	25.00	27.00
No. 2. Finished, per dozen.....	28.00	28.00
No. 2. Nickel Plated, per dozen.....	32.00	32.00
No. 3. Finished, Loose Key, per dozen.....	34.00	34.00
No. 3. Nickel Plated, Loose Key, per dozen.....	38.00	38.00



BRINE COCK, IRON PIPE.

## BRASS BRINE COCKS.




BRINE COCK, FOR HOSE.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$
Each.....	\$2.00	3.00	4.50

# "OUR SPECIAL" DRY PIPE AND GAS TAPPING MACHINE. 411

(Patent Applied For.)



B-110

"Our Special" Dry Pipe and Gas Main Tapping Machine is a substitute for the old style Crow Hook for drilling and tapping of any kind. It is much superior to the Crow and cheaper, as it performs the same work that would require three or more wrought-iron Crow Hooks. With this machine any size pipe can be tapped, depending on the length of chain. The body of machine is made of malleable iron to fit any size pipe or column. The upright post is made from steel and is driven into the body and securely riveted. Feed screw guide is made from malleable iron and is held in place by a thumbscrew, thus allowing tool to be removed by releasing thumbscrew and raising guide. Ratchet handle is built for heavy work, but is not finished as well as ratchet handle with foregoing machines.

In ordering a machine, state size of tools desired and size of the largest main to be tapped. If not specified, chain for a 12-inch pipe will be sent. Tools with standard iron pipe thread will be sent unless otherwise ordered.

Machine Complete, with Ratchet Handle, Less Drills and Taps..... \$17.25

## COMBINED DRILLS AND TAPS.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Standard Iron Pipe Thread, each.....	\$3.00	\$4.00	.....	\$4.50	\$5.00	\$6.25	\$7.50	\$9.50	\$12.00	\$15.00
Standard Corp. Cock Thread, each .....		4.00	\$4.25	4.50	5.00					


## LIST OF EXTRAS.

Hand Wheel.....	\$0.60	Tool Guide Thumb Screw.....	\$0.20
Feed Screw.....	1.70	Flat Head Key.....	.50
Chain Hook.....	.70	Wrench.....	.60
Chain Eye.....	.70	Ratchet Wheel.....	1.75
Chain Hook and Eye Nuts (2).....	.70	Ratchet Dog.....	1.50
Chain Hook Straps (2).....	.80	Ratchet Bolt and Nut.....	.40
Tool Guide.....	1.70	Ratchet Handle complete.....	8.25
Chain for Pipe.....	<div> <div></div> <div>2 to 12-inch inclusive.....</div> <div>2 to 16-inch inclusive.....</div> <div>2 to 36-inch inclusive.....</div> </div>		<div>2.00</div> <div>2.50</div> <div>3.00</div>

Machine and Ratchet, boxed, without drills and taps, weighs 54 pounds.

# MUELLER'S TAPPING MACHINE.

## FOR DRILLING AND TAPPING AGAINST PRESSURE



Water Tapping Machine, complete, includes: 1 each, Combined Drill and Tap,  $\frac{1}{2}$ ,  $\frac{5}{8}$ ,  $\frac{3}{4}$ , 1 inch; 1 each, Screw or Hexagon Plug,  $\frac{1}{2}$ ,  $\frac{5}{8}$ ,  $\frac{3}{4}$ , 1 inch; 4 Malleable Iron Saddles, any size; 1 Chain for any size of Pipe.


Complete.....	\$100.00
1 inch Combined Drill and Tap.....	6.50
$\frac{3}{4}$ " " " " ".....	5.50
$\frac{5}{8}$ " " " " ".....	4.50
$\frac{1}{2}$ " " " " ".....	4.00
$\frac{3}{8}$ " " " " ".....	3.75
Plugs, Screw or Hexagon, each.....	.60
Malleable Iron Saddles, each.....	1.00
7½ inch Pure Rubber Gasket, each.....	1.00
4½ " " " " ".....	.25
Power Clevis. for extreme pressure.....	5.00

In ordering a machine, it is necessary to state the size of tools desired, also the sizes of pipes to be tapped (if sizes of pipes are not mentioned in the order, 4, 6, 8 and 10 inch saddles will be sent), and whether screw plugs or hexagon plugs are wanted (if style of plug is not mentioned, screw plugs will be sent).



# LENNOX IMPROVED TAPPING MACHINE.

413



Lennox Tapping Machine Complete, includes :

1 each Combined Drill and Tap.....	$\frac{1}{2}$ , $\frac{5}{8}$ , $\frac{3}{4}$ , 1 inch	} Price .....\$100.00
1 each Screw or Hexagon Plug.....	$\frac{1}{2}$ , $\frac{5}{8}$ , $\frac{3}{4}$ , 1 inch	
4 Malleable-Iron Saddles, any size.....		
1 Chain for any size of Pipe.....		

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Combined Drill and Tap, each.....	* \$3.75	\$4.00	\$4.50	\$5.50	\$6.50
Screw or Hexagon Plug, each.....	1.00	1.00	1.00	1.00	1.00


\* Made to order.

Safety Plug, each.....	\$4.50
Pinion, each.....	4.00
Feed Screw each.....	3.00
Chain Hooks, each.....	1.00
Nuts for Hooks, each.....	.10
Washers, each.....	.15
Ratchet Wrench, each.....	5.00

In ordering a machine it is necessary to state the *size of tools* desired, also *sizes of pipes* to be tapped, cocks you intend to use. If sizes of saddles are not mentioned in the order, saddles for 4, 6, 8 and 10-inch pipe will be sent. Also screw plugs, when plugs are not mentioned.

# MUELLER CORPORATION STOP COCK.


THREADED ON LONG END FOR MUELLER TAPPING MACHINE TOOLS.



No. 1.

## BENT COUPLING, FITTED FOR HEXAGON PLUG.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 1, each .....	\$1.20	1.35	1.70	2.50	3.85	8.65	11.30	17.50



No. 2.

## STRAIGHT COUPLING, FITTED FOR HEXAGON PLUG.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 2, each .....	\$1.20	1.35	1.70	2.50	3.85	8.65	11.30	17.50



No. 3.

## SHORT END THREADED FOR IRON PIPE, FITTED FOR HEXAGON PLUG.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 3, each .....	\$1.10	1.40	2.10	3.35	7.50	9.50	15.00


Can furnish Corporation Cocks to fit any style Tapping Machine on very short notice.

Genuine Mueller Corporation Cocks have Trade Mark, H. M., on side of cock.

All H. M. Cocks are made from special composition of red brass metal, and thoroughly tested under 200 lbs. hydraulic pressure.

All Corporation Cocks with coupling and nut are furnished with fiber washers. Should plain lead or corrugated copper washers be required they can be furnished at a slight advance in cost of cock.

# CORPORATION STOP COCKS FOR PAYNE MACHINES. 415




No. 13.

## BENT COUPLING, FITTED FOR SCREW PLUG.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
No. 13, per dozen .....	\$16.00	19.00	23.00	34.00	53.00	104.00	136.00	210.00


Fitted with Straight Coupling at same price.




No. 14.

## FITTED FOR SCREW PLUG; IRON PIPE THREAD SHORT END.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$
No. 14, per dozen.....	\$13.00	16.00	20.00	29.00	46.00	90.00



No. 15.



## CORPORATION STOP COCK TO DRIVE IN MAIN.

## QUARTER BEND COUPLING AND NUT.

Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
No. 15, each.....	\$1.50	1.90	2.80	4.35

All Corporation Cocks with bent or straight couplings can be furnished with quarter bend coupling, as shown above, at same price as listed. Ground joint couplings can be supplied at a slight increase in cost of regular goods. All Corporation Cocks with coupling and nut are supplied with fiber washers. Should plain lead or corrugated copper washers be required they can be furnished at a slight advance in cost of cock. Can furnish cocks to fit the Lennox, New Style Haddesty, Hubbell, Sperring, Letzkus, Hall, Jones, National Tube Works and other styles of Tapping Machines, and guarantee them first-class in every way. All genuine Mueller Corporation Cocks bear the H. M. brand, are made from special composition of red brass metal and thoroughly tested under 200 lbs. hydraulic pressure.



## CORPORATION COCKS.


THREADED FOR MUELLER'S WATER TAPPING MACHINE.

FITTED FOR SCREW OR HEXAGON PLUG.



BENT COUPLING, SCREW PLUG.      THREADED FOR IRON PIPE,  
SCREW PLUG.


Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Bent or Straight Coupling, each.....	\$1.20	\$1.35	\$1.70	\$2.50	\$3.85
For Iron Pipe, each.....		1.10	1.40	2.10	3.35



## LEAD GOOSE NECKS.


Size, Single Goose Neck, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Price, each.....	\$2.70	3.00	3.50	5.00

## PLAIN COUPLING.




Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Plain Face, per dozen..	\$3.50	4.00	6.50	10.00	15.00	20.00	30.00

## SOLDERING UNION.



Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Plain Face, per dozen.....	\$2.75	3.25	4.00	6.00	8.50	12.00	18.00

## SOLDERING NIPPLES.



NO. 1.


NO. 2.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Screw Outside, per dozen.....	\$2.25	\$2.50	\$3.00	\$5.00	\$7.50	\$10.00	\$14.00
Screw Inside, per dozen.....	2.25	2.50	3.00	5.00	7.50	10.00	14.00

# DRAWN LEAD TRAPS AND BENDS.

417

## REGULAR.



Calibre-Thickness, per Square Foot.	STANDARD WEIGHT.					SPECIAL W'T.
	4½ lb.	5 lb.	6 lb. Lead.			5½ lb.
REGULAR TRAPS.	1¼-inch.	1½-inch.	2-inch.	3-inch.	4-inch.	4-inch.
Full S.....	\$0.50	\$0.60	\$1.05	\$1.85	\$2.40	\$2.20
¾ S.....	.50	.60	1.05	1.80	2.20	2.05
½ S or P.....	.45	.55	.95	1.60	1.85	1.70
Running.....	.40	.50	.80	1.40	1.70	1.55
Running Y.....	.45	.55	.95	1.70	2.15	2.00
Bag.....	.60	.80	1.35	2.15	3.45	3.10
Long Bend.....	.28	.35	.60	.95	1.40	1.25
Short Bend.....	.22	.30	.45	.75	1.10	1.00

# DRAWN LEAD-TRAPS AND BENDS.


## VENTED.



VENTED TRAPS.		1¼-inch with 1¼-inch Vent.	1½-inch with 1½-inch Vent.	2-inch with 1½-inch Vent.	2-inch with 2-inch Vent.	3-inch with 2-inch Vent.	4-inch with 2-inch Vent.	4-inch with 2-inch Vent.
Full S,	With Rough Vent-Connection.....	\$1.05	\$1.30	\$1.75	\$2.05	\$2.85	\$3.40	\$3.20
¾ S,	“ “ “ “ .....	1.05	1.30	1.75	2.05	2.80	3.20	3.05
½ S or P,	“ “ “ “ .....	1.00	1.25	1.65	1.95	2.60	2.85	2.70
Running,	“ “ “ “ .....	.95	1.20	1.50	1.80	2.40	2.70	2.55
Running Y,	“ “ “ “ .....	1.00	1.25	1.65	1.95	2.70	3.15	3.00
Bag,	“ “ “ “ .....	1.15	1.50	2.05	2.35	3.15	4.45	4.10
Full S,	With Finished Vent-Connection.....	1.55	1.90	2.35	2.80	3.60	4.15	3.95
¾ S,	“ “ “ “ .....	1.55	1.90	2.35	2.80	3.55	3.95	3.80
½ S or P,	“ “ “ “ .....	1.50	1.85	2.25	2.70	3.35	3.60	3.45
Running,	“ “ “ “ .....	1.45	1.80	2.10	2.55	3.15	3.45	3.30
Running Y,	“ “ “ “ .....	1.50	1.85	2.25	2.70	3.45	3.90	3.75
Bag,	“ “ “ “ .....	1.65	2.10	2.65	3.10	3.90	5.20	4.85
Full S,	With Nickel-Plated Vent Connection.....	1.80	2.15	2.60	3.05	3.85	4.40	4.20
¾ S,	“ “ “ “ .....	1.80	2.15	2.60	3.05	3.80	4.20	4.05
½ S or P,	“ “ “ “ .....	1.75	2.10	2.50	2.95	3.60	3.85	3.70
Running,	“ “ “ “ .....	1.70	2.05	2.35	2.80	3.40	3.70	3.55
Running Y,	“ “ “ “ .....	1.75	2.10	2.50	2.95	3.70	4.15	4.00
Bag,	“ “ “ “ .....	1.90	2.35	2.90	3.35	4.15	5.45	5.10

Prices include Brass Drainscrews on all sizes except 4-inch. Regular Traps have Rough Brass Drainscrews. On Vented Traps the finish on Drainscrews and Vent-Connections will correspond. All 2-inch Vented Traps have 1½-inch Vents, unless otherwise ordered. 3-inch or 4-inch Traps have 2-inch Vents. In the absence of specifications we send "Standard Weight." Traps, for 1¼-inch, 1½-inch, 2-inch and 3-inch sizes, and "Special Weights" for 4-inch sizes. Vents may be ¼, ½, ¾ Bend or straight. In absence of Specification, orders will be filled with ½ Bend Vents. For finished or nickel-plated Drainscrews on Regular Traps, 15 cents will be added to list price.

## EXTRA-LONG LEAD TRAPS.




## REVISED PRICE LIST.

No.	Shape.	Extended End.	STANDARD WEIGHT.					
			4½ Pounds.		5 Pounds.		6 Pound Lead.	
			1¼-Inch.		1½-Inch.		2-Inch.	
				With 1¼-inch Vent.		With 1½-inch Vent.	With 1½-inch Vent.	With 2-inch Vent.
1	Full S.....	Outlet.....	\$0.90		\$1.05		\$1.65	
2	Full S.....	Inlet.....	.90		1.05		1.65	
3	½ S. or P.....	Inlet.....	.75		.85		1.35	
4	½ S. or P.....	Outlet.....	.70		.80		1.25	
7	Full S.....	Outlet.....		\$1.45		\$1.75		\$2.35
8	Full S.....	Inlet.....		1.45		1.75		2.35
9	½ S. or P.....	Inlet.....		1.30		1.55		2.05
10	½ S. or P.....	Outlet.....		1.25		1.50		1.95
11	¾ S.....	Inlet.....	.80		.95		1.60	
12	¾ S.....	Outlet.....	.85		1.00		1.65	
13	Running Y.....	Outlet.....	.80		.95		1.45	
14	Running.....	Outlet.....	.75		.85		1.30	
15	Running.....	Inlet.....		1.30		1.55		2.00
16	Running Y.....	Outlet.....		1.35		1.65		2.15
17	¾ S.....	Outlet.....		1.40		1.70		2.35
18	¾ S.....	Inlet.....		1.35		1.65		2.30
19	Full S.....	Both Ends.....	.90		1.05		1.65	
20	Full S.....	Both Ends.....		1.45		1.75		2.35
21	Bag, Straight Outlet.....	Both Ends.....	1.00		1.15		1.90	
22	Bag, Straight Outlet.....	Both Ends.....		1.55		1.85		2.60
23	Bag, Straight Outlet.....	Both Ends.....	1.00		1.15		1.90	
24	Bag, Straight Outlet.....	Both Ends.....		1.55		1.85		2.60
25	Bag, Side Outlet.....	Inlet.....	.80		.95		1.60	
26	Bag, Side Outlet.....	Inlet.....		1.35		1.65		2.30
On Lengths not Listed add for each inch of Excess.....			.03	.03	.04	.04	.06	.06
For Full Finish on Vents and Trap Screws add to List, each.....				.50		.60	.60	.75
For Nickel-Plated Vents and Trap Screws add to List, each.....				.75		.85	.85	1.00



# LEAD BENDS, ETC.

419



## EXTENSION BENDS.

Short Inlet-ends are same dimensions as Inlets on Short Bends of corresponding size.

Long Inlet-ends are the same as on Long Bends.

For measurements see Dimension Scale.

	STANDARD WEIGHT.					SPECIAL WEIGHT.
	4½ lb.	5 lb.	6 lb. Lead.			5½ lb.
	1¼-Inch.	1½-Inch.	2-Inch.	3-Inch.	4-Inch.	4-Inch.
Short Inlet-ends x 12 inches on Outlet-ends.....	\$0.40	\$0.45	\$0.70	\$1.05	\$1.40	\$1.25
“ “ x 15 “ “ “ “ .....	.45	.55	.80	1.25	1.65	1.50
“ “ x 18 “ “ “ “ .....	.50	.60	.90	1.45	1.90	1.70
“ “ x 20 “ “ “ “ .....	.55	.65	1.00	1.55	2.05	1.85
Long Inlet-ends x 12 “ “ “ “ .....	.45	.55	.85	1.30	1.75	1.55
“ “ x 15 “ “ “ “ .....	.50	.65	.95	1.50	2.00	1.80
“ “ x 18 “ “ “ “ .....	.55	.70	1.10	1.70	2.25	2.00
“ “ x 20 “ “ “ “ .....	.60	.75	1.20	1.80	2.40	2.15
For each inch of excess length over Listed size, on any shape of Trap or Bend, add to the list of nearest listed size.....	.03	.04	.06	.08½	.11	.10

## COMBINATION FERRULES.

### LEAD AND IRON.

FOR CONNECTING LEAD TO CAST IRON PIPE.

Lengths.—(In inches.)

	4	4½	5	6	8	10	12	14	16	18	20	24	30	36
1½ in. for 2 in. C. I. P.....	\$0.28	\$0.38	\$0.43	\$0.49	\$0.56	\$0.61	\$0.65	\$0.70	\$0.75	\$0.80	\$0.90	\$1.10	\$1.30	
2 in. for 2 in. C. I. P.....	\$0.22		.32	.37	.43	.50	.55	.60	.65	.70	.75	.85	1.05	1.25
3 in. for 3 in. C. I. P.....	.32		.45	.50	.60	.70	.80	.90	1.00	1.05	1.10	1.25	1.50	1.75
4 in. for 4 in. C. I. P.....	.38		.50	.60	.72	.83	.95	1.00	1.10	1.20	1.30	1.50	1.80	2.10




Four inch “Extra Heavy,” five inches long, 60 cents each.

## WEIGHTS AND SIZES OF LEAD PIPE.



LEAD PIPE.



SHEET LEAD.

Caliber.		Weight, Per Foot.		Caliber.		Weight, Per Foot.		Caliber.		Weight, Per Foot.	
Lbs.		Ozs.	Lbs.		Ozs.	Lbs.		Ozs.	Lbs.		Ozs.
¼ in. Tubing.....	6	.....	5/8-in. Ex. ex. Strong....	3	8	1¼-in. Strong.....	4	12	2½-in. Waste.....	4	.....
Fish Seine .....	15	.....	¾-in. Aqueduct.....	1	.....	Ex. Strong.....	6	.....	Light.....	6	.....
⅜-in. Aqueduct.....	8	.....	Ex. Light.....	1	8	Ex. ex. Strong....	6	12	Medium, ⅜, Thick	8	.....
Ex. Light.....	10	.....	Light.....	2	.....	1½-in. Aqueduct.....	3	.....	Strong, ¼, "	11	.....
Light.....	12	.....	Medium.....	2	4	Ex. Light.....	3	8	Ex. Strong, ⅝, "	14	.....
Medium.....	1	.....	Strong.....	3	.....	Light.....	4	.....	Ex. ex. Strong, ¾, "	17	.....
Strong.....	1	8	Ex. Strong.....	3	8	Medium.....	5	.....	3-in. Waste.....	3	8
Ex. Strong.....	2	.....	Ex. ex. Strong....	4	.....	Strong.....	6	.....	Light.....	6	3
½-in. Aqueduct.....	10	.....	¾-in. Aqueduct.....	1	8	Ex. Strong.....	7	8	Medium, ⅜, Thick	9	.....
Ex. Light.....	12	.....	Ex. Light.....	2	.....	Ex. ex. Strong....	9	.....	Strong, ¼, "	12	.....
Light.....	1	.....	Light.....	2	8	1¾-in. Ex. Light.....	3	12	Ex. Strong, ⅝, "	16	.....
Medium.....	1	4	1-in. Aqueduct.....	1	8	Light.....	4	8	Ex. ex. Strong, ¾, "	20	.....
Strong.....	1	12	Ex. Light.....	2	.....	Medium.....	5	8	3½-in. Waste.....	5	.....
AA.....	2	.....	Light.....	2	8	Strong.....	6	8	Strong, ¼, Thick	15	.....
Ex. Strong.....	2	8	Medium.....	3	4	Ex. Strong.....	8	.....	Ex. Strong, ⅝, "	18	.....
Ex. ex. Strong....	3	.....	Strong.....	4	.....	2-in. Waste.....	3	.....	4-in. Waste.....	5	.....
5/8-in. Aqueduct.....	12	.....	Ex. Strong.....	4	12	Ex. Light.....	4	.....	Medium.....	10	.....
Ex. Light.....	1	4	Ex. ex. Strong....	5	8	Light.....	5	.....	Strong, ¼, Thick	16	.....
Light.....	1	12	1¼-in. Aqueduct.....	2	.....	Medium.....	7	.....	Ex. Strong, ⅝, "	22	.....
Medium.....	2	.....	Ex. Light.....	2	8	Strong.....	8	.....	Ex. ex. Strong, ¾, "	25	.....
Strong.....	2	8	Light.....	3	.....	Ex. Strong.....	9	.....	5-in. Waste.....	8	.....
Ex. Strong.....	3	.....	Medium.....	3	12	Ex. ex. Strong....	10	8			


Coils of Supply Pipe weigh about 200 pounds; Aqueduct about 90 pounds; Suction Pipe 100 to 180 pounds each.

## WEIGHTS AND SIZES OF SHEET LEAD.

Thickness. Inches.....	⅜	7/16	1/8	1/16	1/4	1/2	1	2	3	4	5	6	7	8	9	10	11	12
Pounds, per square foot ...	2½	3	3½	4	4½	5	6	7	8	9	10	11	12	13	14	15	16	17

Stock Rolls of Sheet Lead average 20 feet in length and from 7 feet to 9 feet 2 inches in width.


Special weights and lengths rolled to order on short notice.



Pigs weigh about 100 pounds. Market rates.



40-60 Solder. Market Rates.  
Half and Half. Market Rates.



Pigs weigh about 100 pounds. Market rates.  
Bars weigh about 1½ pounds. Market rates.

# BABBITT METALS.

421



Phoenix Metal, for bearings subjected to constant concussion, or very heavy work, or high speeds.

Nickel Babbitt, per pound.....	\$.....	No. 1, Babbitt, per pound.....	\$.....
Genuine Babbitt, ".....	.....	No. 2, Babbitt, ".....	.....
Extra Babbitt, ".....	.....	No. 3, Babbitt, ".....	.....
Engine Babbitt, ".....	.....	No. 4, Babbitt, ".....	.....
Aluminum Copper, extra Babbitt, per pound.....	.....		
Aluminum Copper, genuine Babbitt, ".....	.....		

All Babbitt put up in boxes of 50 pounds, or in bars from 5 to 10 pounds.

## MAGNOLIA METAL.



Best anti-friction metal for high speed engine, dynamo, rolling mill, steamship, railroad, sawmill, cotton mill, paper mill, woolen mill, silk mill, jute mill, rubber mill, sugar mill, flour mill and all machinery bearings. It prevents hot boxes. It will not cut or heat journals. Its lasting qualities are of the highest order. It is a self-lubricant. It saves a large percentage of oil. It accomplishes its work with much cheaper grades of lubricants. It increases the motive power. It is the only metal that protects and does not wear journals—it enamels them. It is adapted to high and low speed machinery. It will stand the heavy work of rolling, sugar, saw and wire mills, etc. It is especially adapted to all steamship bearings.

Price, per pound..... \$0.25

## BABBITT LADLES.

### MALLEABLE IRON LADLES.



Number.....	1	2	3	4	5	6	7	8	9	10	11
Diameter, inches.....	2½	3	3½	4	5	6	6	EXTRA HEAVY.			
								7	8	9	10
Price, per dozen.....	\$3.75	4.65	5.50	6.50	8.75	10.00	.....	22.00	28.00	45.00	54.00



# RANGE BOILERS AND STANDS.

## GALVANIZED RANGE BOILERS.

### SIZES AND PRICES.

Capacity, gals.....	18	21	24	27	28	30	32	35	36	40	42	47	48
Diameter, Inches....	12	12	14	12	14	12	14	13	14	14	16	16	14
Height, Feet.....	3	3½	3	4½	3½	5	4	5	4½	5	4	4½	6
Each .....	\$14.50	15.50	19.00	18.50	20.25	19.00	21.00	21.00	21.50	24.00	26.00	30.00	30.00

Capacity, gals.....	52	53	63	66	79	82	98	100	120	120	144	168	192
Diameter, Inches....	16	18	16	18	18	20	20	22	22	24	24	24	24
Height, Feet.....	5	4	6	5	6	5	6	5	6	5	6	7	8
Each .....	\$31.00	31.50	38.00	38.00	44.00	45.50	61.50	63.50	74.00	72.50	103.00	120.00	132.00

N. B.—The above prices are for Boilers only.

## BOILER STANDS.

### SIZES AND PRICES.

Diameter of Ring, Inches.....	12	13	14	16	18	20	22	24
For Boilers, Capacity, gallons.....	18 to 30	35	40	52 and 63	66	82	100 to 120	120 to 192
Price, each.....	\$1.25	1.35	1.40	1.85	2.00	2.25	2.75	3.50




# GALVANIZED HOT WATER EXPANSION TANKS.

### SIZES AND PRICES.

Capacity, gals.....	10	12	15	18	20	24	26	32	42	66	82	100	120
Diameter, Inches ...	12	12	12	12	14	14	16	16	16	18	20	22	24
Height, " ...	20	24	30	36	30	36	30	36	48	60	60	60	60
Each.....	\$8.00	8.50	9.00	9.50	12.50	13.00	14.00	15.00	16.50	31.00	37.00	51.00	58.00


N. B.—These prices are for Tanks only.




# GALVANIZED STEEL TANKS.

423

## OBLONG TANKS.



SQUARE ENDS.



ROUND ENDS.


### SQUARE ENDS.

No.	Width.	Height.	Length.	Capacity.	Price, Each.	No.	Width.	Height.	Length.	Capacity.	Price, Each.
0	2 ft.	1 ft.	4 ft.	2 bbls.	\$6.00	34	4 ft.	2 ft.	8 ft.	15 bbls.	\$18.15
A 28	2 "	2 "	4 "	4 "	7.70	35	4 "	2 1/2 "	8 "	17 "	20.90
C 29	2 "	2 "	6 "	6 "	9.90	36	4 "	3 "	8 "	23 "	25.30
28	2 "	2 "	8 "	7 1/2 "	12.10	37	3 "	2 "	10 "	14 "	17.00
29	2 "	2 1/2 "	8 "	9 1/2 "	13.20	38	3 "	2 1/2 "	10 "	18 "	21.45
30	2 1/2 "	2 "	8 "	9 1/2 "	13.20	39	3 "	3 "	10 "	21 "	23.65
31	2 1/2 "	2 1/2 "	8 "	12 "	14.30	40	4 "	2 "	10 "	19 "	22.00
32	3 "	2 "	8 "	12 "	14.30	41	4 "	2 1/2 "	10 "	24 "	26.40
33	3 "	2 1/2 "	8 "	14 "	17.00	42	4 "	3 "	10 "	29 "	29.70

### ROUND ENDS.

No.	Width.	Height.	Length.	Capacity.	Price, Each.	No.	Width.	Height.	Length.	Capacity.	Price, Each.
13	2 ft.	2 ft.	8 ft.	7 1/2 bbls.	\$11.00	21	4 ft.	3 ft.	8 ft.	23 bbls.	\$24.00
14	2 "	2 1/2 "	8 "	8 "	12.50	22	3 "	2 "	10 "	14 "	16.00
15	2 1/2 "	2 "	8 "	9 1/2 "	12.50	23	3 "	2 1/2 "	10 "	18 "	21.00
16	2 1/2 "	2 1/2 "	8 "	12 "	14.00	24	3 "	3 "	10 "	21 "	22.00
17	3 "	2 "	8 "	12 "	14.00	25	4 "	2 "	10 "	19 "	21.00
18	3 "	2 1/2 "	8 "	14 "	16.00	26	4 "	2 1/2 "	10 "	24 "	24.00
19	4 "	2 "	8 "	15 "	17.00	27	4 "	3 "	10 "	29 "	27.00
20	4 "	2 1/2 "	8 "	17 "	20.00	44	4 "	2 "	16 "	30 "	30.00

### ROUND TANKS.



ROUND TANK.

No.	Diameter.	Height.	Capacity.	Price, Each.
1	4 ft.	2 ft.	6 bbls.	\$9.00
2	4 "	2 1/2 "	7 "	10.00
3	4 "	3 "	9 "	12.00
4	4 "	4 "	12 "	14.00
5	5 "	4 "	9 1/2 "	12.50
6	5 "	2 1/2 "	12 "	15.00
7	5 "	3 "	14 "	16.50
8	5 "	4 "	19 "	21.00
9	6 "	2 "	14 "	17.50
10	6 "	2 1/2 "	17 "	20.50
11	6 "	3 "	20 "	22.00
12	6 "	4 "	27 "	26.00
13	6 "	5 "	34 "	32.00

Always order by number. Tight or Hinged Covers for any of our Tanks furnished when desired. Prices on application.

# LUNKENHEIMER'S MEDIUM PATTERN REGRINDING VALVES.

SCREW ENDS. BRASS.

WARRANTED FOR 175 POUNDS WORKING PRESSURE.




FIG. 407 L. GLOBE VALVE.




FIG. 588 L. CROSS VALVE.



FIG. 408 L. ANGLE VALVE.

## PRICE LIST.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Globe Valves, Brass, each.....	\$0.70	\$0.70	\$0.85	\$1.15	\$1.45	\$2.00	\$2.80	\$3.90	\$6.20	\$12.00	\$16.50
Angle Valves, Brass, each.....	.70	.70	.85	1.15	1.45	2.00	2.80	3.90	6.20	12.00	16.50
Cross Valves, Brass, each.....	1.00	1.00	1.00	1.50	2.00	2.70	3.50	5.10	8.00	16.00	24.00
Globe or Angle Valves, finished all over with Finished Brass Wheel, Brass, each.....	1.75	1.90	2.15	2.50	3.10	3.65	5.25	7.25	10.75	22.00	33.50
Cross Valves, finished all over with Finished Brass Wheel, Brass, each.....	2.40	2.60	2.90	3.30	4.20	4.90	7.00	9.70	14.30	29.30	44.70

All genuine valves have **Lunkenheimer** cast in valve shell and wheel has letter S on same.



# LUNKENHEIMER'S MEDIUM PATTERN REGRINDING CHECK VALVES.

425

SCREW ENDS. BRASS.

WARRANTED FOR 175 POUNDS WORKING PRESSURE.

The discs in these valves are guided both at top and bottom, and so constructed that they will always seat themselves perfectly and not leak, stick nor pound, and their action is quick and positive. As regards height of lift of discs, they are made to have an opening of one-eighth of the diameter of the valve seat, but where more or less lift is desired we can make them accordingly.

Check valves with enlarged seats have one size larger opening through same than regular, therefore requiring less lift and giving more discharge.

## PRICE LIST.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Check Valves, Horizontal, Angle or Vertical.....each }	\$0.50	\$0.50	\$0.60	\$0.85	\$1.15	\$1.55	\$2.30	\$3.25	\$5.20	\$10.00	\$14.00
Check Valves, Horizontal, Enlarged Seats.....each }				1.15	1.55	2.30	3.25	5.20	10.00		
Check Valves, with Drain Cocks.....each }			1.05	1.30	1.60	2.00	2.75	3.70	5.65	10.50	14.50
Check Valves, Enlar'd Seats, with Drain Cocks.....each }				1.60	2.00	2.75	3.70	5.65	10.50		

## BALL CHECK VALVES.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Horizontal, Angle or Vertical Brass Ball Check Valves.....each }	\$1.10	\$1.60	\$2.30	\$3.10	\$4.00	\$6.20	\$9.40	\$18.00	\$25.00
Brass Ball Check Valves, with Drain Cocks.....each }	1.50	2.00	2.70	3.50	4.40	6.60	9.80	18.50	25.50

## BRASS BALLS.

We have had long experience in making Brass Balls by special tools of our own invention, and can guarantee those made by us to be absolutely spherical. Sizes above  $1\frac{1}{2}$  inches diameter are cast hollow.

## PRICE LIST.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	$2\frac{3}{4}$	3	$3\frac{1}{2}$	$3\frac{3}{4}$	4	5	6
Price, each.....	\$0.60	.65	.75	1.00	1.50	2.75	4.50	5.25	6.00	7.00	8.00	9.00	13.00	18.50




FIG. 414 L. HORIZONTAL CHECK VALVE.



FIG. 415 L. ANGLE CHECK VALVE.




FIG. 418 L. VERTICAL CHECK VALVE.




FIG. 416 L. BALL CHECK VALVE.




FIG. 417 L. BRASS BALL.

# LUNKENHEIMER'S MEDIUM PATTERN REGRINDING SWING CHECK VALVES.

**BRASS. SCREW ENDS.**

**WARRANTED FOR 175 POUNDS WORKING PRESSURE.**





FIG. 554 L. EXTERIOR.



SECTIONAL.

The Lunkenheim Regrinding Swing Check Valve is much superior in point of excellence of material, design and workmanship, to any other valve of its class now upon the market. The body is heavy and well proportioned, the seat is carefully finished, and the general workmanship is first-class. This valve is so designed that when the disc is raised the passage through the body is fully equal to the diameter of the connecting pipes.

We call particular attention to the quality of metal used, it being the best gun metal composition, the presence of which tends to make the valve more durable than if a common metal (such as other makers are using) was used.

By means of the regrinding feature the usefulness of the valve can be prolonged indefinitely. When worn in the seat it can be reground without removing valve body from connecting pipes.

**TO REGRIND.**—Unscrew cap of valve and place some powdered sand and soap on seat, also unscrew plug opposite disc, which will give access to the top of the disc, and by inserting a nail or pointed tool in hole in same it can be ground upon the seat, thus forming a new bearing. Should the disc become badly worn or cut, it can be rubbed down to a smooth service on a piece of fine emery cloth, or we can furnish new ones at a reasonable price. All parts of this valve are interchangeable, and any worn out piece can be renewed.

Size, Inches.....	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	2 3/4	3	3 1/2	3 3/4	4	5	6
Price, each.....	\$0.60	.65	.75	1.00	1.50	2.75	4.50	5.25	6.00	7.00	8.00	9.00	13.00	18.50

## IRON BODY, BRASS MOUNTED, SCREW OR FLANGE ENDS.

### PRICE LIST.




FIG. 597 L. SCREW ENDS.



FIG. 598 L. FLANGE ENDS.

Size, Inches.....	2	2 1/2	3	3 1/2	4	4 1/2	5	6
Iron Body, Brass Mounted, Screw Ends, each.....	\$6.25	10.00	12.00	16.00	18.00	21.00	25.00	32.00
Iron Body, Brass Mounted, Flange ends, each.....	\$6.25	10.00	12.00	16.00	18.00	21.00	25.00	32.00
Diameter of Flanges on Flange End Valves, inches.....	6	7	7 1/2	8 1/2	9	9 1/4	10	11

All genuine valves have **Lunkenheim** cast on the valve body.

# LUNKENHEIMER'S COMPOSITION DISC GLOBE, ANGLE 427 AND RADIATOR VALVES.




FIG. 423 L. GLOBE VALVE.




FIG. 424 L. RADIATOR VALVE.

## COMPOSITION DISC GLOBE VALVE.

### PRICE LIST.

Size, Inches .....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Fig. 423 L. Brass, Globe or Angle, each.....	\$1.10	\$1.25	\$1.60	\$2.20	\$2.80	\$4.00	\$5.50	\$8.00	\$15.75	\$22.00
Fig. 423 L, Iron Body, Globe or Angle, each.....									11.00	16.00
Fig. 423 L, Extra Discs, each .....	.04	.05	.06	.07	.08	.12	.16	.24	.32	.40

## COMPOSITION DISC RADIATOR VALVE, FEMALE ENDS.

### PRICE LIST.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Fig. 424 L, Rough Body, Finished Trimmings, each.....	\$2.00	\$2.50	\$3.20	\$4.50	\$6.25	\$10.50
Fig. 424 L, Finished all over, each .....	2.50	3.00	3.75	5.25	7.25	11.75
Fig. 424 L, Rough Body, Plated Trimmings, each .....	2.25	2.70	3.50	4.75	6.50	10.75
Fig. 424 L, Rough Body, Plated all over, each .....	2.50	2.85	3.65	4.90	6.75	11.00
Fig. 424 L, Finished and Plated all over, each .....	2.85	3.10	4.00	5.40	7.75	12.25

Keys for Lock Shield Valves each net 12 cents.

These Valves are provided with the best Composition Discs, which when worn can be renewed.

Radiator Valves are furnished with either Wood Wheel, T Handle or Lock Shield at same price; when ordering please designate, also Style, Finish and Threads wanted (whether Right or Left Hand). Unless otherwise specified, valves will be sent with Wood Wheel.



# 428 LUNKENHEIMER'S DOUBLE-SEATED "CLIP" GATE VALVE.

IRON BODY, BRASS MOUNTED, AND ALL IRON.


FOR 100 POUNDS WORKING PRESSURE.



FIG. 600 L. SCREW ENDS.



FIG. 638 L. FLANGE ENDS.



SECTIONAL.

The construction is free from complicated mechanism, and the operating parts consist of the bronze wedge-shaped disc, which has two faces and is seated in the valve shell between seat rings of the same material. The valve will take pressure from either end and can be connected in any position. The hub or bonnet of the valve is secured to the body by means of a round steel clip which surrounds it and passes through lugs on sides of hub and is fastened by means of two nuts. This simple arrangement has the advantage over other means of connecting the parts of a valve, inasmuch as it permits of easy access to the interior at all times. The joint between the hub and the body is indestructible and consists of a seamless copper wire washer, partially imbedded in the top surface of the valve body the portion which protrudes above said surface forming the joint against the under face of the hub when the two parts are connected together. This valve can be opened or closed quicker than any other, an advantage which users will appreciate. All the bearing parts of the valve (i. e., stem, disc, seats and stuffing-box) are made of bronze and the hub and body of iron; the several parts are well proportioned and heavy, and the body is rigid, there is no liability of springing the seats when connecting to pipes, as is sometimes the case with light brass valves. The construction of the valve also permits of repacking the stuffing-box while the valve is either open or closed. Each valve is carefully tested and fully warranted in every respect and it is beyond doubt the lowest-priced gate valve on the market. Made in Screw or Flange Ends, sizes  $\frac{1}{2}$  inch to 6 inch. It is also made all iron for acids, etc., at a special discount from list below.

## SCREW OR FLANGE ENDS.

### PRICE LIST.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6
Iron Body, Brass Mounted, Screw Ends, each..	\$1.50	\$1.90	\$2.50	\$3.50	\$5.00	\$7.50	\$12.00	\$15.00	\$18.00	\$20.00	\$23.00	\$25.00	\$30.00
Iron Body, Brass Mounted, Flange Ends, each..						8.50	13.50	16.90	20.30	22.50	26.00	28.30	33.80
All Iron, Screw Ends, each.....	1.50	1.90	2.50	3.50	5.00	7.50	12.00	15.00	18.00	20.00	23.00	25.00	30.00
All Iron, Flange Ends, each.....						8.50	13.50	16.90	20.30	22.50	26.00	28.30	33.80

Unless otherwise specified we will fill all orders with Iron Body, Brass Mounted, Screw End Valves.  
All genuine valves have **Lunkenheim** cast on hub.

# LUNKENHEIMER'S MEDIUM PATTERN DOUBLE DISC 429 GATE VALVES.

WARRANTED FOR 175 POUNDS WORKING PRESSURE.

## BRASS. SCREW ENDS.

These Valves are heavy and substantial throughout and the bodies are so designed as to be very rigid. The discs are wedged between the seats in the valve shell by means of a ball and socket bearing between them; are easily seated and will not stick in opening. The stuffing box is so constructed that it can be repacked while valve is open and steam on.

### PRICE LIST.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Brass, Screw Ends, each.....	\$1.10	\$1.10	\$1.30	\$1.90	\$2.50	\$3.50	\$5.00	\$7.50	\$14.00	\$20.00
Finished Brass, With Wood Wheels, ea. ....			2.60	3.30	4.50	6.00	7.50	12.00		

## QUICK-OPENING GATE VALVES. DOUBLE DISC.

BRASS AND IRON-BODY; BRASS MOUNTED, SCREW OR FLANGE ENDS.

### PRICE LIST.

Size, Inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6
Quick Opening, Brass, Screw Ends, each...	\$4.00	\$5.00	\$7.00	\$10.00	\$19.00						
Quick Opening, Iron-Body, Screw or Flange Ends, each..				12.00	16.00	\$20.00	\$22.00	\$25.00	\$28.00	\$30.00	\$35.00
Diameter of Flanges on Iron-Body Valves, inches.....				6	7	$7\frac{1}{2}$	$8\frac{1}{2}$	9	$9\frac{1}{4}$	10	11

All genuine Valves have **Lunkenheimer** cast in the valve shell.




Fig. 427 L. Exterior. Fig. 427 L. Sectional.




Fig. 429 L. Brass. Screw Ends.



Fig. 562 L. Iron Body, Brass Mounted, Screw Ends.



# LUNKENHEIMER'S DOUBLE SEATED "VICTOR" GATE VALVES.

IRON BODY, BRASS MOUNTED, AND ALL IRON.  
FOR 175 POUNDS WORKING PRESSURE.



FIG. 602 L. SCREW ENDS.




FIG. 603 L. FLANGE ENDS.




FIG. 636 L. SCREW ENDS.




FIG. 637 L. FLANGE ENDS.

## SCREW OR FLANGE ENDS. STANDARD PATTERN. PRICE LIST.

Size, Inches .....	2	2½	3	3½	4	4½	5	6	7	8	9	10	12
Iron Body, Brass M'td. Screw Ends, each	\$9.00	\$11.00	\$14.00	\$22.00	\$29.00	\$34.00	\$42.00	\$53.00	\$60.00	\$75.00	\$90.00	\$115.00	\$170.00
Iron Body, Brass M'td. Flange Ends, each	9.00	11.00	14.00	22.00	29.00	34.00	42.00	53.00	60.00	75.00	90.00	115.00	170.00
All Iron. Screw Ends, each .....	9.00	11.00	14.00	22.00	29.00	34.00	42.00	53.00	60.00	75.00	90.00	115.00	170.00
All Iron, Flange Ends, each.....	9.00	11.00	14.00	22.00	29.00	34.00	42.00	53.00	60.00	75.00	90.00	115.00	170.00
Diameter of Standard Size Flanges, inches	6	7	7½	8½	9	9¼	10	11	12½	13½	15	16	19

## SCREW OR FLANGE ENDS, WITH BY-PASS. PRICE LIST.

Size, Inches .....	5	6	7	8	9	10	12
Iron Body, Brass Mounted, Screw Ends, each .....	\$46.50	\$58.50	\$66.00	\$82.50	\$98.50	\$126.50	\$187.00
Iron Body, Brass Mounted, Flange Ends, each.....	46.50	58.50	66.00	82.50	98.50	126.50	187.00
All Iron. Screw Ends, each.....	46.50	58.50	66.00	82.50	98.50	126.50	187.00
All Iron, Flange Ends, each.....	46.50	58.50	66.00	82.50	98.50	126.50	187.00
Diameter of Standard Size Flanges, inches.....	10	11	12½	13½	15	16	19

All genuine valves have **Lunkenheimer** cast on shell of same.



# LUNKENHEIMER'S "HANDY" GATE VALVES.

431

(Patented.)

BRASS, IRON BODY, BRASS MOUNTED, AND  
ALL IRON.

SCREW ENDS ONLY.



FIG. 430 L. BRASS.



FIG. 628 L. IRON.

## PRICE LIST.

SCREW ENDS ONLY, NOT MADE WITH FLANGE ENDS.

Size, Inches.....	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	6	8
Brass Body, each.....	\$1.60	\$1.80	\$2.50	\$3.50	\$5.00	\$7.50	\$13.50	\$19.00	\$40.00	\$60.00				
Iron Body, Brass Mounted, each.....						7.00	12.00	15.00	18.00	21.00	\$25.00	\$30.00	\$35.00	\$65.00
All Iron, each.....		3.40	4.00	4.50	6.00	7.00	12.00	15.00	18.00	21.00	25.00	30.00	35.00	65.00

# LUNKENHEIMER'S LEVER THROTTLE VALVES.

(Patented.)

SPECIAL HEAVY PATTERN FOR HIGH PRESSURES.




FIG. 431 L. BRASS BODY.




FIG. 432 L.

BRASS. SCREW ENDS ONLY, NOT MADE WITH FLANGE ENDS. IRON BODY BRASS MOUNTED.

## PRICE LIST.

Size, Inches.....	3/4	1	1 1/4	1 1/2	2	2 1/2
Brass Body, each.....	\$3.00	4.00	5.00	7.00	10.00	19.00

IRON. BRASS MOUNTED.

Size, Inches.....	2 1/2	3	3 1/2	4	5	6
Iron Body, Brass Mounted, each.....	\$6.00	20.00	25.00	30.00	35.00	40.00

All Brass Valves are provided with Gun Metal Disc Carriers (C).

# 432 LUNKENHEIMER'S IMPROVED POP SAFETY VALVES.



FIG. 433 L. TOP OUTLET.




FIG. 629 L. ANGLE OUTLET.



FIG. 434 L. SCREW ENDS.



FIG. 630 L. FLANGE ENDS.

The Brass Valves are made in two styles with screw ends, as illustrated above, but we can also furnish them with flanges when so desired. They are fully described on the preceding pages and a complete direction card is sent with each valve. We make no charge for setting pressures up to and inclusive of 175 pounds, but for higher pressures we make a heavier valve with a stronger spring to withstand the greater strain, and charge same at a special discount from the list prices of the medium pattern valves. Unless otherwise specified, we will send valves set at 100 pounds, and in ordering always specify pressure at which valves are to be set. Special Low Pressure Pop Safety Valves, also Relief Valves made to order. Prices furnished upon application.

## BRASS-TOP OR ANGLE OUTLET. FOR STATIONARY, PORTABLE AND MARINE STEAM BOILERS.

### PRICE LIST.

Size Pipe, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Brass, Top Outlet, each.....	\$5.50	\$6.00	\$6.50	\$7.50	\$9.00	\$11.50	\$18.00	\$28.00	\$38.00
Brass, Angle Outlet, each.....	6.00	6.50	7.00	8.20	9.80	12.40	19.50	30.00	41.00

The simplest and most reliable way in which to ascertain the size of valve required, is to find the number of square feet of grate surface of boiler. Divide this amount by three and the quotient will be the number of square inches of valve area necessary.

## IRON BODY, BRASS MOUNTED. FOR MARINE OR STATIONARY BOILERS.

### SCREW OR FLANGE ENDS.

### PRICE LIST.

Size, Inches.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6
Screw Ends, each.....	\$22.00	\$32.00	\$40.00	\$56.00	\$72.00	\$84.00	\$100.00	\$120.00
Flange Ends, each.....	22.00	32.00	40.00	56.00	72.00	84.00	100.00	120.00
Diameter of Flanges, inches.....	6	7	$7\frac{1}{2}$	$8\frac{1}{2}$	9	$9\frac{1}{4}$	10	11



# LUNKENHEIMER'S MOCKING-BIRD WHISTLE.

433

(Patented.)

This is a simple and practical variable sound Steam Whistle, especially adapted for Traction Engines, Locomotives, Steamboats, Factory and Mill use. It makes an excellent fire alarm, and is attached like any ordinary whistle. The bell is provided with a piston, which is pulled downward by a chain running between pulleys, and when not in use, is always at the top, being drawn upward by means of a spring. *To change the sound, pull the chain.*

The dome-shaped bell is securely supported at its base by a three-armed prong, the stem of which is adjustably screwed into the whistle base, and fastened by jam-nut E. Owing to this construction, the lower edge of the bell is always exactly in line with the slot in the base through which the steam escapes, thereby insuring best results and a perfect, clear and loud tone. The bell must be raised or lowered to suit the steam pressure by screwing same up or down and when properly set, fastened by jam-nut E.

## PRICE LIST.

Diameter of Bells, Inches.....	2½	3	3½	4	5	6
Size of Pipe, Connection, Inches .....	¾	¾	1	1¼	1½	1½
All Brass, with Valve, each.....	\$10.50	\$14.00	\$20.00	\$28.00	\$40.00	\$56.00
All Brass, without Valve, each .....	9.00	12.00	17.50	25.00	37.00	50.00
Iron Base, without Valve, each.....		11.50	16.50	23.00	34.00	46.00




Fig. 445 L.  
All Brass with Valve.

# LUNKENHEIMER'S SINGLE BELL CHIME WHISTLES.

## PRICE LIST.

Diam. of Bells, In...	1½	2	2½	3	3½	4	5	6	8	10
Size of Pipe Connection.....Inches	¾	1½	¾	¾	1	1¼	1½	1½	2	2½
All Brass with Adjustable Lever, each	\$7.00	10.00	13.00	16.00	22.00	28.00	44.00	60.00	145.00	235.00
All Brass, without Valve.....each	5.50	8.50	10.50	13.50	18.50	24.00	37.00	49.00	120.00	188.00
Iron Base without Valve.....each				12.00	16.50	22.00	33.00	45.00	108.00	155.00
All Brass Locomotive Style.....each					27.50	43.00	59.00			

## WHISTLE VALVES.

## PRICE LIST.

Size, Inches.....	¾	1½	¾	1	1¼	1½	2	2½	3
Brass, each.....	\$2.00	2.50	3.00	3.50	5.00	6.00	9.00	18.00	27.00




Fig. 447 L.

All Brass with  
Adjustable Lever.



Fig. 448 L.

All Brass with-  
out Valve.



Fig. 449 L.

Locomotive Style  
with Upright  
Valve.



# LUNKENHEIMER'S IMPROVED COMBINATION OR FIRE ALARM WHISTLE.

(Patented.)



FIG. 446 L. COMPLETE WITH VALVE.

The Whistle is designed to answer both the purposes of an ordinary whistle as well as that of a Fire Alarm. It is provided with a piston that can be moved up or down within the bell or tube, thus changing the interior length of same and consequently also the sound of the whistle. When the piston is not operated the whistle gives but one sound, like any ordinary whistle, but when pulled up and down, a howling, penetrating noise is produced. When placed above the roof of a building, an extension rod should be coupled to the piston stem and a rope or wire to the whistle valve lever. The bell is dome-shaped at its upper end and at its lower securely supported by a three-armed spider, the stem of which is adjustably screwed into the whistle base and fastened by jam-nut E. Owing to this construction the lower edge of the bell is always exactly in line with the slot in the base through which the steam escapes, thereby insuring best results and a perfect, clear and loud tone. The bell is raised or lowered to suit steam pressure by screwing it up or down, and when properly set is fastened by jam-nut E.

## PRICE LIST.

Diameter of Bells, Inches.....	2½	3½	5	8
Size Pipe Connection, inches.....	¾	1	1½	2
With Whistle Valve Complete, each.....	\$24.00	31.00	40.00	100.00

# LUNKENHEIMER'S IMPROVED "SENIOR" SIGHT FEED LUBRICATOR.

435

DOUBLE CONNECTION.

## PRICE LIST.

Size .....	$\frac{1}{4}$ Pt.	$\frac{1}{3}$ Pt.	$\frac{1}{2}$ Pt.	$\frac{2}{3}$ Pt.	1 Pt.	$1\frac{1}{2}$ Pt.	1 Qt.	$1\frac{1}{2}$ Gal.	1 Gal.
Suitable for Engine Cylinders .....	Up to 4 inches.	4 to 6 inches.	6 to 10 inches.	10 to 14 inches.	14 to 18 inches.	18 to 24 inches.	24 to 30 inches.	From 30 up.	
Shanks, Pipe Thread, inch .....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$
Finished, Brass, each.....	\$12.00	\$15.00	\$17.00	\$20.00	\$22.00	\$25.00	\$28.00	\$38.00	\$60.00
Nickel-Plated, each.....	13.50	17.00	19.00	22.50	25.00	28.50	32.00	43.00	65.00
Condenser Connections, Brass } Tubing and Angle Valve, each.... }	.60	.70	.80	1.00	1.20	1.40	1.50	1.60	1.70
Condenser Connections, Brass } Tubing and Angle Valve, Nickel- Plated, each..... }	.70	.80	.90	1.15	1.40	1.60	1.70	1.80	2.00
Length of Condenser Pipes } Necessary, inches..... }	15	18	24	30	36	42	48	60	72




FIG. 482 L. "SENIOR."

Lubricators are sent without Condenser Pipes and Angle Valves unless otherwise ordered.

# LUNKENHEIMER'S "JUNIOR" SINGLE CONNECTION SIGHT-FEED LUBRICATOR.

## PRICE LIST.

Size, pint .....	$\frac{1}{4}$	$\frac{1}{3}$	$\frac{1}{2}$
Shank, Pipe Thread, inch.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$
Partly Finished, each.....	\$7.00	\$8.00	\$10.00
All Finished (Brass Condensers and Pipes and Wood Handles) each.....	8.50	10.00	12.00
All Finished and Nickel-Plated (Brass Condensers and Pipes and Wood Handles.) each..	10.00	11.50	13.50

$\frac{1}{4}$  and  $\frac{1}{3}$ -pint sizes are also made with  $\frac{1}{2}$ -inch pipe shank, but will be sent as above ( $\frac{3}{8}$ -inch), unless otherwise specified. These Lubricators can also be furnished with glass gauge, to indicate quantity of oil in reservoir, at an extra charge of 50 cents each net, but will be sent without, unless specially ordered. Where sizes larger than  $\frac{1}{2}$  pint are wanted, we recommend the "Senior."




Fig. 486 L.  
"JUNIOR."

# LUNKENHEIMER'S GLASS BODY OIL PUMP.

(Patented.)




Fig. 495 L.

The Lunkenheimer Glass Body Oil Pump is easily filled and operated and is intended to be used in connection with Sight-Feed Lubricators on Stationary or Marine Engines. No large engine should be without a cup of this kind as an auxiliary to the Sight-Feed Lubricator.

We have recently changed these pumps from two to four sizes, ranging in capacity from  $\frac{1}{8}$  pint to one quart. We have also made changes in the design, making them much more compact and consequently neater in appearance.

## PRICE LIST.

Size, Number. ....	3	5	6	8
Outside Diameter of Glass, inches.....	2 $\frac{1}{4}$	3	3 $\frac{1}{2}$	4 $\frac{1}{4}$
Height of Glass, inches.....	2 $\frac{1}{8}$	3	4	5
Capacity.....	$\frac{1}{8}$ Pint	$\frac{1}{2}$ Pint	1 Pint	1 Quart
Shank Pipe Thread, inch.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$
Finished Brass, each.....	\$7.50	\$8.50	\$10.00	\$15.00
Nickel-Plated, each.....	8.25	9.50	11.00	16.50
Extra Glasses, each.....	.15	.35	.65	1.50
Extra Cork Washers, per dozen.....	.45	.60	.75	1.50

We can still furnish glasses and cork washers for our old sizes, i. e., numbers one and two, and when ordering be sure and give these numbers to distinguish them from the sizes now made.



# LUNKENHEIMER'S AUTOMATIC NEEDLE VALVE OIL FEEDER.

437




Fig. 496 L.

Lunkenheimer's Automatic Needle Valve Oil Feeder is intended for Slide Valve Engines only, works automatically by pulsation, and must be placed on the steam chest. The stop valve must always be left open, except when filling cup with oil. Do not drain off the water until ready to recharge the cup. The Lubricator stops feeding when the engine stops, and is about properly adjusted as shipped. To regulate the feed, screw yoke up or down, thereby increasing or decreasing the lift of the needle. The greater the lift of the needle the more oil is fed; the needle works up and down like a check valve while the engine is in motion.

## PRICE LIST.

Diameter, Inches .....	1 $\frac{3}{4}$	2	2 $\frac{1}{2}$	3
Capacity, pint.....	$\frac{1}{4}$	$\frac{1}{2}$	$\frac{3}{4}$	1
Shank Pipe Thread, inch.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$
Plain Top, each.....	\$4.70	\$6.20	\$7.70	.....
Cross Top with Glass Gauge, each.....		10.60	11.30	\$14.50

A card with full directions for using Oil Feeder is attached to every cup.

# 438 LUNKENHEIMER'S SCALE REMOVING AND PREVENTING "STANDARD" BOILER OIL INJECTOR.

FOR STEAM BOILERS.




FIG. 492 L. "STANDARD."

## PRICE LIST.

Capacity .....	½ Pt.	1 Pt.	1 Qt.	½ Gal.	1 Gal.	1½ Gal.	2 Gal.
Iron, Brass Trimmings, each.....				\$16.50	\$19.50	\$22.50	\$30.00
Brass, Part Finished, each.....	\$7.50	\$10.00	\$13.50				
Brass, All Finished, each.....	8.00	10.60	14.25				
All Finished and Nickered, each.....	8.50	11.20	15.00				
Suitable for Boilers, H. P.....	10	25	75	100	150	200	250

Reservoirs above one quart are of cast iron, and have lugs on body for bolting to place; smaller sizes have a brace-stud and lock-nut at lower end of oil chamber for same purpose.

# "EMERALD" BOILER OIL INJECTOR.

FOR LOCOMOTIVE AND STATIONARY BOILERS.



FIG. 493 L. "EMERALD"



FIG. 488 L. "BULL'S EYE."

## PRICE LIST.

Capacity .....	½ Pt.	1 Pt.	1 Qt.	½ Gal.	1 Gal.	1½ Gal.	2 Gal.
Iron, Brass Trimmings, each.....				\$16.50	\$19.50	\$22.50	\$30.00
Brass, Part Finished, each.....	\$7.50	\$10.00	\$13.50				
Brass, All Finished, each.....	8.00	10.60	14.25				
All Finished and Nickel-Plated, each.....	8.50	11.20	15.00				
Extra Bull's Eyes, each.....	30	30	30	30	30	30	30

All injectors have ¾-inch pipe connection on shank.

All of the brass cups have brace-stud and lock-nut on lower end of reservoir; the iron body cups, lugs on back of reservoir, to permit of their being securely braced or bolted in place.

# LUNKENHEIMER'S "PARAGON" INDEX LEVER SIGHT-FEED LUBRICATOR.

439

FOR GAS, GASOLINE OR OIL ENGINES.




Fig. 553 L.

Is all that the name implies, and fulfills all the requirements of modern gas engine service.

It has been produced to meet the demand for a low-priced, compact and efficient Sight-feed Gas Engine Lubricator, and one in which the height of oil in the cup can be readily seen. We have not only embraced these important features, but have added to them, and are pleased to present to the trade a cup, while having a glass body, is fully strong enough to withstand ordinary usage.

The feed is easily regulated and the jarring of the engine does not affect its working when set, nor will the cup shake apart from this cause as is the case with other makes.

When once the feed is adjusted it can be easily turned on or off by turning the index lever from the indicator arm to notch in top of cup and the position of the index lever shows from a distance whether or not the cup is in operation. The cup is carefully made of the best materials, the parts are correctly proportioned which gives it a handsome and ornamental appearance, and each one is fully warranted.

**Directions to Set Feed.**—Raise the index lever from notch in top of cup and place it in indicator arm and move both until the desired rate of feed is obtained. The feed can be shut off by returning the index lever to notch in top of cup.

## PRICE LIST.

Size, Number.....	2	4	5	6	8
Outside Diameter of Glass, inches.....	2	2½	3	3½	4¼
Height of Glass, inches.....	17⁄8	2¾	3	4	5
Capacity, ounces.....	2½	5	10	18	32
Shank Pipe Thread, inch.....	3⁄8	3⁄8	½	½	¾
Finished Brass, each.....	\$2.80	\$4.00	\$5.40	\$7.00	\$14.00
Nickel-Plated, each.....	3.25	4.60	6.25	8.20	16.40

When ordering extra glasses and cork washers, give number of cup as stamped on same.



# 440 LUNKENHEIMER'S "VULCAN" FORCE-FEED SIGHT-FEED LUBRICATOR.

FOR GAS ENGINES, AIR COMPRESSORS, ETC.




FIG. 491 L. "VULCAN."

## PRICE LIST.

Number.....	1	2	3	4
Outside Diameter of Cup, inches.....	1 $\frac{3}{4}$	2 $\frac{1}{4}$	2 $\frac{3}{4}$	3 $\frac{1}{4}$
Capacity (Grease), ounces.....	1 $\frac{1}{2}$	3	4 $\frac{1}{2}$	6 $\frac{1}{2}$
Shank Pipe Thread, inch.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$
Brass, each.....	\$5.00	\$6.00	\$8.00	\$10.00
All Finished and Nickel-Plated, each.....	6.00	7.25	9.50	12.00
Extra Sight-Feed Glasses, per dozen.....	.60	.60	.60	.60

# LUNKENHEIMER'S "BANNER" SIGHT-FEED LUBRICATOR.

FOR GAS ENGINES, AIR COMPRESSORS, ETC.

Description.—A, Oil Chamber; B, Stop Valve; C, Oil Regulating Valve; E, Filling Plug.

Directions.—To fill and operate, close valves B and C and fill with oil. Then open valve B wide and regulate flow of oil at C.



FIG. 489 L. "BANNER."

## PRICE LIST.

Size, Number.....	0	1	2	3	4	5	6
Diameter of Oil Chamber, inches.....	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2	2 $\frac{1}{4}$	2 $\frac{1}{2}$	3	3 $\frac{1}{2}$
Capacity, ounces.....	1	1 $\frac{1}{2}$	2 $\frac{1}{2}$	4	5	10	18
Shank Pipe Thread, inch.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$
Brass, each.....	\$3.50	\$4.00	\$5.00	\$6.00	\$8.00	\$10.00	\$12.00
All Finished and Nickel-Plated, each.....	4.20	5.00	6.00	7.25	9.50	12.00	14.00
Extra Sight-Feed Glasses, per dozen.....	.60	.60	.60	.60	.60	.60	.60

# LUNKENHEIMER'S "IDEAL" AUTOMATIC GREASE CUP. 441

FOR ENGINE CRANK PINS, JOURNALS, ETC.




FIG. 510 L. EXTERIOR.




FIG. 510 L. SECTIONAL.

The "Ideal" is a first-class brass highly finished automatic compression cup, suitable for engine bearings, journals, etc. It is provided with a leather packed plunger (insuring a tight joint and smooth working), which is so constructed that it is easily raised when cup requires recharging with grease. The spring and plunger are conveniently controlled by thumb-nut A, which is provided with an automatic lock arrangement to prevent its jarring from position on stem. The hole through the shank can be regulated to suit the grease used, by means of regulating screw H. As a high grade cup of superior design and perfect regulation of feed, the "Ideal" has no equal.

**Directions.**—Turn thumb-nut A to the right until plunger is drawn to the top of cup; then unscrew cover and fill the cup with grease. Replace cover and adjust pressure on grease by screwing up thumb-nut A to top of stem T, thereby allowing plunger to compress and feed the grease.

The rate of feed must be regulated by set-screw H, which has a hole through it in line with the slot, thus is regulated like a stop cock.

If it is desired to stop the flow of grease, turn thumb-nut A down to cover, thereby taking tension off spring.

## PRICE LIST.

Number.....	00	0	1	2	3	4
Inside Diameter, inches.....	1	1 1/4	1 1/2	2	2 1/2	3
Extreme Outside Diameter, inches.....	1 1/2	1 3/4	2	2 1/8	3 1/8	3 5/8
Extreme Height over all (plunger raised—cup open), inches..	3 1/2	4 1/2	5 3/8	6 3/8	7 1/2	8 3/8
Shank Pipe Thread, inch.....	1/8	1/4	1/4	3/8	1/2	1/2
Capacity (Grease) ounces.....	1/3	1	1 1/2	3	6	10
Finished Brass, each.....	\$1.50	\$2.00	\$2.50	\$3.20	\$4.30	\$6.00
Nickel-Plated, each.....	1.75	2.25	2.80	3.60	5.00	6.75

442 LUNKENHEIMER'S "JEWEL" AUTOMATIC GREASE CUP.  
FOR BEARINGS, SHAFTING, LOOSE PULLEYS, ETC.




FIG. 511 L. EXTERIOR.




FIG. 511 L. SECTIONAL.

The "Jewel" Grease Cup we have designed to meet the demand for a simple and inexpensive automatic cup, and to take the place of iron cups. The base is of cast brass, while the top is of tubing and spun brass. This cup will be found far superior to iron cups although the price is about the same. They are of brass throughout, provided with leather-packed plunger, are of neat design, well made and light in weight.

**Directions.**—When cup is empty and plunger is at bottom of same, unscrew and take off the reservoir, then screw the plunger to top of reservoir by means of the thumb-nut. Then fill the reservoir with grease and after screwing it back to its base, screw the thumb-nut up to the top of the plunger so as to put the pressure of the spring on the grease. The base of the cup is provided with a simple feed regulating screw adjustable to suit any kind of grease.

PRICE LIST.

Number.....	00	0	1	2	3	4
Inside Diameter, inches.....	1	1¼	1½	2	2½	3
Extreme Outside Diameter, inches.....	1⅜	1⅝	2	2⅜	3⅛	3⅞
Extreme Height over all (plunger raised, cup open), inches.....	3	3⅛	4¼	5½	6⅛	7⅝
Shank Pipe Thread, inch.....	⅝	¾	¾	⅞	½	½
Capacity (Grease), ounces.....	⅓	1	1½	3	6	10
Finished Brass, each.....	\$0.80	\$1.00	\$1.30	\$1.70	\$2.30	\$3.20
Nickel-Plated, each.....	1.00	1.30	1.70	2.20	2.90	3.90



# LUNKENHEIMER'S "APOLLO" COMPRESSION IRON GREASE CUP.

443

## FOR BEARINGS, SHAFTING, ETC.

The "Apollo" Compression Iron Grease Cup is heavy and designed for use in all places where the finish of the article used is not important. It works well on Shafting, Pulleys and all Bearings, and will feed from any direction. The threaded shank consists of a common pipe nipple inserted in base of cup, which can easily be replaced if broken.

**To Fill:** Raise plunger by means of ring at top of same and lock plunger stem over top of cup by means of lugs on sides of stem. Remove cover, fill with grease, regulate feed by screw in base, replace cover and put pressure on grease by unlocking stem lugs from hole in cover.

This cup is very economical in operation and one filling can be so regulated as to last a long time. Each cup fully guaranteed.

### PRICE LIST.

Number.....	1	2	3	4
Inside Diameter, inches.....	1½	2	2½	3
Shank Pipe Thread, inch.....	¼	⅜	½	½
Capacity (Grease), ounces.....	1½	3	6	10
Iron, each.....	\$1.50	1.70	2.30	3.20



FIG. 669 L.  
EXTERIOR.




FIG. 669 L.  
SECTIONAL.

# LUNKENHEIMER'S SCREW FEED "MARINE" GREASE CUP.

### PRICE LIST.

Number.....	00	0	1	2	3	4
Inside Diameter, inches.....	1	1¼	1½	2	2½	3
Extreme Outside Diameter, inches.....	1½	1¾	2	2½	3	3½
Extreme Height over all (Plunger Raised — Cup Open), inches.....	3½	4	5	6	7	8
Shank Pipe Thread, inch.....	⅜	¼	¼	⅜	½	½
Capacity (Grease), ounces.....	1	1	1½	3	6	10
Finished Brass, each.....	\$1.00	\$1.20	\$1.60	\$2.00	\$2.80	\$4.00
Nickel-Plated, each.....	1.20	1.45	1.90	2.40	3.40	4.75



FIG. 512 L.  
EXTERIOR.





FIG. 512 L.  
SECTIONAL.

# 444 LUNKENHEIMER'S "TIGER" PLAIN BRASS GREASE CUP.



Fig. 513 L.



SECTIONAL.

Lunkenheimer's "Tiger" Plain Grease Cup is a cast brass cup, well adapted for jarring machinery, is unsurpassed where a simple, compact and efficient plain cup is required. By screwing down cap (A) the lubricant is forced to the bearing. The leather washer (H) prevents the grease from leaking out of cup, and can be easily replaced when worn out; spring lock arrangement (B), the projection (E) of which engages (K) at each turn, prevents the cap from jarring off, also cuts and loosens the grease.

Always keep leather washer (H) well expanded against the thread in cap by screwing up plate (C). This plate can easily be tightened or unscrewed by using a pointed tool, inserting it in one of the holes in plate and striking it with a hammer.

These cups are furnished in three styles, viz: Finished Brass, Nickel Plated or Rough (see price list below).

When no style is mentioned, orders will be filled with Finished Brass, same as shown in cut.

## PRICE LIST.

Number .....	00	0	1	2	3	4
Inside Diameter, inches.....	1	1 $\frac{1}{4}$	1 $\frac{1}{2}$	2	2 $\frac{1}{2}$	3
Extreme Outside Diameter, Finished Pattern, inches.....	1 $\frac{1}{4}$	1 $\frac{1}{2}$	1 $\frac{11}{16}$	2 $\frac{1}{4}$	2 $\frac{3}{4}$	3 $\frac{1}{4}$
Extreme height over all (cup open), Finished Pattern, inches.....	1 $\frac{3}{4}$	2	2 $\frac{6}{16}$	2 $\frac{9}{16}$	2 $\frac{7}{8}$	3 $\frac{1}{4}$
Extreme Outside Diameter, Rough Pattern, inches.....	1 $\frac{1}{4}$	1 $\frac{5}{16}$	1 $\frac{7}{8}$	2 $\frac{5}{16}$	2 $\frac{7}{8}$	3 $\frac{7}{16}$
Extreme height over all (cup open) Rough Pattern, inches.....	1 $\frac{13}{16}$	2 $\frac{1}{16}$	2 $\frac{3}{8}$	2 $\frac{11}{16}$	2 $\frac{15}{16}$	3 $\frac{3}{8}$
Shank Pipe Thread, inch.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$
Capacity (Grease), ounces.....	$\frac{1}{2}$	$\frac{2}{3}$	1	2	3 $\frac{1}{2}$	5
Finished Brass, each.....	\$0.70	\$0.90	\$1.15	\$1.50	\$2.15	\$2.90
Finished Brass, Nickel-Plated, each.....	.82	1.06	1.36	1.80	2.60	3.40
Rough Brass, each .....	.56	.74	.96	1.28	1.76	2.30

# LUNKENHEIMER'S "GEM" PLAIN BRASS GREASE CUP. 445




Fig. 556 L.

## PRICE LIST.

Number.....	00	0	1	2	3	4
Inside Diameter, Inches.....	1	1 $\frac{1}{4}$	1 $\frac{1}{2}$	2	2 $\frac{1}{2}$	3
Extreme Outside Diameter, Inches.....	1 $\frac{1}{8}$	1 $\frac{3}{8}$	1 $\frac{5}{8}$	2 $\frac{3}{8}$	2 $\frac{11}{8}$	3 $\frac{1}{4}$
Extreme Height over all (cup open), Inches.....	1 $\frac{3}{8}$	2 $\frac{5}{8}$	2 $\frac{1}{2}$	2 $\frac{7}{8}$	3 $\frac{1}{2}$	3 $\frac{7}{8}$
Shank Pipe Thread, Inch.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$
Capacity (Grease), ounces.....	$\frac{1}{4}$	$\frac{2}{3}$	1	2	3 $\frac{1}{2}$	5
Finished Brass, each.....	\$0.70	\$0.90	\$1.15	\$1.50	\$2.15	\$2.90
Nickel Plated, each.....	.80	1.00	1.30	1.70	2.45	3.20

# LUNKENHEIMER'S "REX" SPUN-TOP PLAIN BRASS GREASE CUP.



Fig. 514 L.

## PRICE LIST.

Number .....	6	7	8	9
Inside Diameter, inches .....	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2 $\frac{3}{8}$	2 $\frac{5}{8}$
Extreme Outside Diameter, inches .....	1 $\frac{1}{2}$	1 $\frac{5}{8}$	2 $\frac{5}{8}$	2 $\frac{3}{4}$
Extreme Height over all (cup open), inches .....	2 $\frac{3}{4}$	2 $\frac{1}{2}$	2 $\frac{7}{8}$	3
Shank Pipe Thread, inch.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{3}{8}$
Capacity (Grease), ounces .....	$\frac{2}{3}$	1 $\frac{1}{2}$	3 $\frac{1}{2}$	5
Brass, each.....	\$0.55	.70	.90	1.20



# LUNKENHEIMER'S "PIONEER" SLIDE-TOP GLASS OIL CUP.



Fig. 515 L.

The "Pioneer" Oil Cups have become an "acknowledged standard," being by far the best designed and constructed, and consequently the most perfect oilers of their class, and are adapted for all engine and machinery bearings where it is desirable to use a first-class cup. They are made of cast brass (not spun brass), are highly finished, compact and very ornamental. These and the other styles of glass oil cups, manufactured by us are the only ones on the market which will not come apart when placed on jarring machinery, neither will the feed unset nor slide loosen, thereby spilling the oil. These excellent features being exclusive with our cups and covered by patents, gives them a very considerable prestige over all other makes. They are easily filled and regulated and are satisfactory to users in every respect. They are especially adapted to traction engines, steam rollers and other machinery of like character where it is necessary to use a durable and substantial oiler.

## PRICE LIST.

Number.....	000	00	0	1	1½	2	3	4	5	6
Extreme Outside Diameter of Cup, inches.....	1⅜	1⅞	1⅞	1⅞	2⅞	2⅞	2⅞	2⅞	5⅞	3⅞
Extreme Height of Cup (over all), inches.....	2¾	2⅞	3⅞	3¾	4⅞	4⅞	4¾	5	6	7¼
Outside Diameter of Glass, inches.....	1	1⅞	1¼	1½	1¾	2	2¼	2½	3	3½
Height of Glass, inches.....	⅞	1	1⅞	1⅞	1⅞	1⅞	2⅞	2⅞	3	4
Capacity, ounces.....	¼	½	⅝	1	1½	2½	4	5	10	18
Shank Pipe Thread, inch.....	⅞	⅞	⅞	¼	¼	⅜	⅜	⅜	½	½
Finished Brass, each.....	\$0.70	\$0.75	\$0.80	\$1.00	\$1.25	\$1.50	\$1.90	\$2.40	\$3.10	\$4.00
Nickel-Plated, each.....	.80	.85	.95	1.20	1.50	1.75	2.20	2.75	3.50	4.50

To avoid mistakes when ordering glasses and cork washers, specify name and number of cup as stamped on same.




FIG. 516 L.

Lunkenheimers "Victor" Index Glass Oil Cup is provided with a simple "index" device for regulating the feed of oil, and has an indicator arm pivoted on the stem and turning on the lid to mark the notch giving the desired rate of feed. The feed can be instantly turned off and on again by replacing the lever in the notch of the indicator arm. When the index arm is closed the lever can be left to stand up out of the notch, thus acting as an indicator, to show from a distance that the feed is shut off.

## PRICE LIST.

Number .....	0	1	1½	2	3	4	5	6
Extreme Outside Diameter of Cup (Lever Included), inches	2 <sup>5</sup> / <sub>16</sub>	2 <sup>11</sup> / <sub>16</sub>	2 <sup>15</sup> / <sub>16</sub>	3 <sup>1</sup> / <sub>4</sub>	3 <sup>3</sup> / <sub>4</sub>	4	4 <sup>11</sup> / <sub>16</sub>	5 <sup>1</sup> / <sub>4</sub>
Extreme Height of Cup (Over All), inches.....	3 <sup>13</sup> / <sub>16</sub>	4 <sup>1</sup> / <sub>2</sub>	4 <sup>13</sup> / <sub>16</sub>	5 <sup>1</sup> / <sub>4</sub>	6	6 <sup>1</sup> / <sub>2</sub>	7 <sup>7</sup> / <sub>16</sub>	8 <sup>1</sup> / <sub>4</sub>
Outside Diameter of Glass, inches.....	1 <sup>1</sup> / <sub>4</sub>	1 <sup>1</sup> / <sub>2</sub>	1 <sup>3</sup> / <sub>4</sub>	2	2 <sup>1</sup> / <sub>4</sub>	2 <sup>1</sup> / <sub>2</sub>	3	3 <sup>1</sup> / <sub>2</sub>
Height of Glass, inches.....	1 <sup>1</sup> / <sub>8</sub>	1 <sup>3</sup> / <sub>8</sub>	1 <sup>5</sup> / <sub>8</sub>	1 <sup>7</sup> / <sub>8</sub>	2 <sup>1</sup> / <sub>8</sub>	2 <sup>3</sup> / <sub>8</sub>	3	4
Capacity, ounces.....	<sup>5</sup> / <sub>8</sub>	1	1 <sup>1</sup> / <sub>2</sub>	2 <sup>1</sup> / <sub>2</sub>	4	5	10	18
Shank Pipe Thread, inch.....	<sup>1</sup> / <sub>8</sub>	<sup>1</sup> / <sub>4</sub>	<sup>1</sup> / <sub>4</sub>	<sup>3</sup> / <sub>8</sub>	<sup>3</sup> / <sub>8</sub>	<sup>3</sup> / <sub>8</sub>	<sup>1</sup> / <sub>2</sub>	<sup>1</sup> / <sub>2</sub>
Finished Brass, each.....	\$1.00	\$1.20	\$1.45	\$1.75	\$2.15	\$2.70	\$3.40	\$4.30
Nickel Plated, each.....	1.15	1.40	1.70	2.00	2.45	3.05	3.80	4.80

To avoid mistakes, when ordering glasses and cork washers, specify name and number of cup as stamped on same.

# LUNKENHEIMER'S "CROWN" INDEX SIGHT-FEED GLASS OIL CUP.




FIG. 518 L.

Lunkenheimer's "Crown" Index Sight-Feed Glass Oil Cup is of first-class quality throughout, very ornamental in appearance and made of cast brass. It has an "index" device for regulating the feed of oil, and an indicator arm turning on the lid to mark the notch giving the desired feed. The feed can be instantly turned off and on again by replacing the index lever in the notch of the indicator arm. When the feed is shut off, the lever can be left to stand up out of the notch, thus acting as an indicator to show from a distance that the feed is shut off.. It fulfills all the requirements for dynamo and engine use, and we recommend it where a first-class substantial cup is wanted.

## PRICE LIST.

Number.....	0	1	1½	2	3	4	5	6
Extreme Outside Diameter of Cup (lever included) inches	2 <sup>1</sup> / <sub>16</sub>	2 <sup>1</sup> / <sub>8</sub>	2 <sup>5</sup> / <sub>16</sub>	3 <sup>1</sup> / <sub>4</sub>	3 <sup>3</sup> / <sub>4</sub>	4	4 <sup>1</sup> / <sub>8</sub>	5 <sup>1</sup> / <sub>4</sub>
Extreme Height of Cup, over all, inches.....	4 <sup>1</sup> / <sub>2</sub>	5 <sup>3</sup> / <sub>8</sub>	5 <sup>5</sup> / <sub>8</sub>	6	6 <sup>9</sup> / <sub>16</sub>	7 <sup>7</sup> / <sub>16</sub>	8 <sup>1</sup> / <sub>4</sub>	8 <sup>7</sup> / <sub>8</sub>
Outside Diameter of Glass, inches.....	1 <sup>1</sup> / <sub>4</sub>	1 <sup>1</sup> / <sub>2</sub>	1 <sup>3</sup> / <sub>4</sub>	2	2 <sup>1</sup> / <sub>4</sub>	2 <sup>1</sup> / <sub>2</sub>	3	3 <sup>1</sup> / <sub>2</sub>
Height of Glass, inches.....	1 <sup>1</sup> / <sub>8</sub>	1 <sup>3</sup> / <sub>8</sub>	1 <sup>5</sup> / <sub>8</sub>	1 <sup>7</sup> / <sub>8</sub>	2 <sup>1</sup> / <sub>8</sub>	2 <sup>3</sup> / <sub>8</sub>	3	4
Capacity, ounces.....	<sup>5</sup> / <sub>8</sub>	1	1 <sup>1</sup> / <sub>2</sub>	2 <sup>1</sup> / <sub>2</sub>	4	5	10	18
Shank Pipe Thread, inch.....	<sup>1</sup> / <sub>8</sub>	<sup>1</sup> / <sub>4</sub>	<sup>1</sup> / <sub>4</sub>	<sup>3</sup> / <sub>8</sub>	<sup>3</sup> / <sub>8</sub>	<sup>3</sup> / <sub>8</sub>	<sup>1</sup> / <sub>2</sub>	<sup>1</sup> / <sub>2</sub>
Finished Brass, each.....	\$1.25	\$1.50	\$1.75	\$2.10	\$2.55	\$3.15	\$3.90	\$4.80
Nickel-Plated, each.....	1.40	1.70	2.00	2.35	2.85	3.50	4.30	5.30



LUNKENHEIMER'S "ROYAL" SIGHT-FEED GLASS OIL CUP. 449




FIG. 517 L.

Lunkenheimer's "Royal " Sight-Feed Glass Oil Cup will be found an excellent cup for engine and dynamo use. It is simple and practical, and so constructed that, when the desired feed is once set, it can be stopped and started at will without resetting, the spring acting as a lock and indicator when engaging the flattened side of the thumb-nut.

Directions to set Feed.—Regulate the feed by turning the milled cover, so that when the flattened side of thumb-nut engages the spring the desired feed is obtained. When the feed is once established, it can instantly be shut off or put on by turning the milled thumb-nut, *i. e.*, to the right, feed off ; to the left, feed on.

PRICE LIST.

Number.....	000	00	0	1	1½	2	3	4	5	6
Extreme Outside Diameter of Cup, Inches.....	1⅜	1⅞	1⅝	1⅞	2⅛	2⅜	2⅞	2⅞	3⅞	3⅞
Extreme Height of Cup, (over all) Inches.....	3	3⅞	3⅞	4⅞	4⅞	4⅞	5⅞	6	6⅞	7⅞
Outside Diameter of Glass, Inches.....	1	1⅞	1¼	1½	1¾	2	2¼	2½	3	3½
Height of Glass, Inches.....	⅞	1	1⅞	1⅞	1⅝	1⅞	2⅞	2⅞	3	4
Capacity, Ounces .....	¼	½	⅞	1	1½	2½	4	5	10	18
Shank Pipe Thread, Inch.....	⅞	⅞	⅞	¼	¼	⅞	⅞	⅞	½	½
Finished Brass, each.....	\$0.95	\$1.10	\$1.25	\$1.50	\$1.75	\$2.10	\$2.55	\$3.15	\$3.90	\$4.80
Nickel-Plated, each .....	1.05	1.20	1.40	1.70	2.00	2.35	2.85	3.50	4.30	5.30

To avoid mistakes, when ordering glasses and cork washers, specify name and number of cup as stamped on same.

# LUNKENHEIMER'S "SENTINEL" SNAP LEVER SIGHT-FEED GLASS OIL CUP.

UNEQUALED FOR DYNAMO AND  
ENGINE USE.



FIG 546 L. LEVER UP, CUP FEEDING.




FIG. 546 L. LEVER DOWN, FEED STOPPED.

Lunkenheimer's "Sentinel" Snap Lever Sight-Feed Glass Oil Cup, as will be seen from the illustrations above, is handsome and ornamental in appearance, and thoroughly strong and substantial in construction. It is simple in operation, compact, well made and not liable to get out of order, as is the case with other makes. We have dispensed with complicated lock-nut feed regulating devices and use a simple arrangement by means of which the feed is easily and securely adjusted. Owing to its construction, the cup will not shake to pieces when placed on jarring machinery; neither will the feed unset when either raising or lowering lever, as the curved spring which presses against the milled regulating nut prevents it from turning.

Another advantage it has is that when set to feed a given amount of oil, it will hold up its rate of feed until cup is entirely emptied. Great care is taken in the manufacture of these cups, and we warrant them to be first-class in every particular and unequalled for durability, efficiency and reliability.

**Directions to set Feed.**—Raise the lever and turn the milled thumb-nut until the desired feed is obtained. The feed can be shut off by lowering the lever. When the lever is set at an angle of 45 degrees it raises the feed stem clear off its seat and cup flushes.

## PRICE LIST.

Number .....	0	1	1½	2	3	4	5	6
Extreme Outside Diameter of Cup, inches.....	1 5/8	2 1/4	2 3/8	2 3/4	2 1/2	2 1/2	3 5/8	3 1/2
Extreme Height of Cup over all (lever up), inches.....	5 1/8	5 3/8	5 1/2	6 1/4	6 3/4	7 1/8	8 1/8	9 1/8
Outside Diameter of Glass, inches.....	1 1/4	1 1/2	1 3/4	2	2 1/4	2 1/2	3	3 1/2
Height of Glass, inches .....	1 1/8	1 3/8	1 5/8	1 7/8	2 1/8	2 3/8	3	4
Capacity, ounces.....	5/8	1	1 1/2	2 1/2	4	5	10	18
Shank Pipe Thread, inch.....	1/8	1/4	1/2	3/8	3/4	5/8	1 1/2	1 1/2
Finished Brass, each.....	\$3.00	\$3.25	\$3.50	\$3.75	\$4.25	\$5.25	\$7.25	\$9.25
Nickel-Plated, each.....	3.50	3.75	4.00	4.25	4.75	5.75	8.00	10.25

To avoid mistakes, when ordering glasses and cork washers, specify name and number of cup, as stamped on same.

# LUNKENHEIMER'S "CHAMPION" ROD OIL CUP.

451

SUITABLE FOR ALL MOVABLE BEARINGS.

## PRICE LIST.

Number.....	1	2	3	4
Finished Brass, each.....	\$1.40	\$2.00	\$2.60	\$4.00
Nickel Plated, each.....	1.50	2.20	2.80	4.40
Capacity, ounces.....	1 $\frac{1}{4}$	2 $\frac{1}{2}$	5	12
Outside Diameter, inches.....	2	2 $\frac{1}{2}$	3	4
Height of Cup (closed), inches.....	3 $\frac{1}{4}$	3 $\frac{7}{8}$	4 $\frac{5}{8}$	5 $\frac{3}{4}$
Height of Cup (open to fill), inches.....	4 $\frac{1}{4}$	4 $\frac{7}{8}$	5 $\frac{7}{8}$	7 $\frac{1}{4}$
Width, inches.....	1 $\frac{5}{8}$	1 $\frac{11}{16}$	2 $\frac{1}{4}$	3 $\frac{11}{16}$
Shank Pipe Thread, inch.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$
Glasses, each.....	\$0.05	\$0.08	\$0.10	\$0.15
Corks, per dozen.....	.20	.30	.40	.60



FIG. 591 L. EXTERIOR VIEW.  
Showing Plug Raised for Filling.




FIG. 591 L. SECTIONAL VIEW.  
Showing Interior Construction.

# LUNKENHEIMER'S AUTOMATIC ROD CUPS.

FOR ENGINE CRANK PINS.

## PRICE LIST.

Number.....	0	1	1 $\frac{1}{2}$	2	3	4
Extreme Outside Diameter of Cup, inches.....	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2	2 $\frac{1}{4}$	2 $\frac{3}{4}$	2 $\frac{11}{16}$
Extreme Height of Cup (plug raised, open to fill), in..	3 $\frac{1}{16}$	4 $\frac{3}{16}$	4 $\frac{11}{16}$	5 $\frac{1}{8}$	5 $\frac{13}{16}$	6 $\frac{1}{8}$
Outside Diameter of Glass, Inches.....	1 $\frac{1}{4}$	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2	2 $\frac{1}{4}$	2 $\frac{1}{2}$
Height of Glass, inches.....	1 $\frac{1}{8}$	1 $\frac{3}{8}$	1 $\frac{5}{8}$	1 $\frac{7}{8}$	2 $\frac{1}{8}$	2 $\frac{3}{8}$
Capacity, ounces.....	$\frac{5}{8}$	1	1 $\frac{1}{2}$	2 $\frac{1}{2}$	4	5
Shank Pipe Thread, inch.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$
Finished Brass, each.....	\$1.10	\$1.50	\$2.00	\$2.50	\$3.00	\$4.00
Nickel Plated, each.....	1.25	1.70	2.25	2.75	3.30	4.35




FIG. 523 L.  
SCREW FEED.




FIG. 524 L.  
NEEDLE VALVE FEED.



## LUNKENHEIMER'S SHAFT OILERS.



FIG. 533 L. SHAFT OILER.



FIG. 534 L. SHAFT OILER  
WITH LOOSE WIRE AND WOOD PLUG.

FIG. 533 L. SECTIONAL.

**Directions for Using Lunkenheimer's Shaft Oilers.**—Fill the Oiler (full) with oil, screw on the socket air-tight, and then screw the stem tightly into the oil hole in bearing. When the Cup needs refilling, unscrew the stem out of the hole, take the oiler apart and proceed as before. See that the hole through stem is always clear of any obstruction before putting the oiler in its place.

See that the glass globe is always tight in its socket.

**To Regulate.**—The Oilers are shipped set for a *moderate* feed. The oil-hole in the stem is drilled parallel with the slot in head of the set-screw. By turning the regulating screw a *quarter turn backward* the supply of oil is entirely cut off. Between these two positions of the screw any desired amount of feed may be had.

## PRICE LIST.

Number .....	1	2	3
Capacity, ounces .....	1	1 $\frac{5}{8}$	2 $\frac{3}{4}$
Diameter, inches .....	1 $\frac{3}{4}$	2	2 $\frac{1}{2}$
Height, Inches.....	2 $\frac{3}{8}$	3	3 $\frac{1}{2}$
Finished Brass, each.....	\$0.50	\$0.55	\$0.60
Extra Glasses, each .....	.08	.08	.08
Extra Cork Washers, per dozen.....	.15	.15	.15

Shanks are threaded  $\frac{3}{8}$  inch on point, 16 threads to the inch.

Shaft Oilers with loose wire and wood plug are furnished at same price as regular pattern.

# LUNKENHEIMER'S PLAIN GLASS ENGINE OILER.

453

This Oil Cup has been upon the market for many years and many are in use. It is an air-tight cup and feeds only when the machinery is in motion.

## PRICE LIST.

Number.....	7	8	9
Extreme Height of Cup (plug raised to fill) inches.....	3 $\frac{3}{4}$	4 $\frac{3}{8}$	4 $\frac{3}{4}$
Height of Glass, inches.....	1 $\frac{1}{2}$	1 $\frac{7}{8}$	2 $\frac{1}{4}$
Diameter of Glass, inches.....	1 $\frac{3}{8}$	1 $\frac{7}{8}$	2 $\frac{1}{8}$
Capacity, ounces.....	$\frac{3}{4}$	1 $\frac{3}{8}$	2 $\frac{1}{2}$
Finished Brass, each.....	\$0.70	\$0.90	\$1.05
Extra Glasses, each.....	.08	.08	.08
Extra Cork Washers, per dozen.....	.15	.15	.15

All sizes of these cups have  $\frac{1}{4}$ -inch pipe thread on shanks.

They can be furnished with loose wire feed at same price as regular pattern, when so ordered.




Fig. 599 L.

# LUNKENHEIMER'S BRASS LOOSE PULLEY OILER.

This Oiler must be attached to hub of pulley, is easily filled and regulated, will not throw or waste oil, and a trial will convince users that it is a simple and satisfactory oiler for loose pulleys. It is guaranteed to give satisfaction, one filling lasting from two to four weeks, and feeding only when pulley is in motion.

## PRICE LIST.

Number.....	0	1	2	3	4
Height of Cup, (plug raised to fill), inches.....	1 $\frac{1}{8}$	2 $\frac{7}{16}$	2 $\frac{5}{8}$	3	3 $\frac{1}{8}$
Length of Cup, inches.....	1 $\frac{3}{4}$	2 $\frac{1}{16}$	2 $\frac{5}{16}$	2 $\frac{1}{2}$	2 $\frac{13}{16}$
Diameter of Body, inches.....	1	1 $\frac{1}{4}$	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2
Capacity, ounces.....	$\frac{1}{4}$	$\frac{1}{2}$	$\frac{3}{4}$	1 $\frac{1}{4}$	1 $\frac{3}{4}$
Rough Brass, Bronzed, each.....	\$0.25	.30	.40	.50	.65

Shanks on Nos. 0, 1 and 2 are threaded  $\frac{3}{8}$ -inch on point, 16 threads to the inch. Shanks on Nos. 3 and 4 are threaded  $\frac{1}{4}$ -inch pipe thread.



Fig. 537 L.

## LUNKENHEIMER'S OIL GAUGES.

WITH REVOLUBLE SHIELD.

(Patented.)




FIG. 528 L. PLAIN.




FIG. 529 L. WITH DRAIN COCK.

The oil gauges heretofore used on dynamos and other machinery having self-oiling journal boxes, possess several serious objections, which have been entirely overcome in the "Lunkenheimer" Improved Gauge, and on account of its advantages and low price is rapidly superseding them. All users of oil gauges are aware that with those heretofore used it is impossible to clean the glass tube, which soon becomes so covered with dust and dirt collecting in the slots of the shield that the oil cannot be seen. Besides, the slots or windows of the gauge are not always in proper position as regards the light to enable one to see the oil, and the shield being fixed can not be turned to suit. Then, owing to the construction of these oil gauges, they are unnecessarily clumsy and expensive. The Lunkenheimer Oil Gauge will be found perfect in all these particulars, it is simple and practical in construction, can be easily taken apart, is handsome in appearance and inexpensive. The glass protecting shield is a slotted tube, which permits being revolved around the glass tube, thus it can easily be kept clean and the shield set in proper position as regards the light, so that the oil is plainly visible. The entire gauge is held together by a thin wire rod, which is screwed into the bottom fitting, passes through the center of glass tube and has a nut fastened to it on the upper side of top cover. To clean the Glass Tube, hold a piece of waste to the tube, and revolve it with the shield around the glass until properly cleaned, then turn the shield to its former position.

## PRICE LIST.

Size, Shank Pipe Thread, Inch.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$
Height from center of square to top of Gauge, inches.....	$2\frac{9}{16}$	$3\frac{1}{8}$	$3\frac{3}{4}$	$4\frac{7}{8}$
Length of Shank from center of square, inches.....	$1\frac{5}{8}$	$1\frac{3}{4}$	$2\frac{9}{16}$	$4\frac{1}{16}$
Length of Glass, Inches.....	2	$2\frac{1}{2}$	3	4
Finished Brass without Drain Cock, each.....	\$0.40	\$0.50	\$0.65	\$1.00
Nickel-Plated without Drain Cock, each.....	.55	.65	.80	1.20
Finished Brass with Drain Cock, each.....	.80	.90	1.05	1.40
Nickel-Plated with Drain Cock, each.....	1.00	1.10	1.25	1.65

In ordering Oil Gauges always state whether wanted with or without Drain Cock, and if Finished Brass or Nickel-Plated. When not specified, Gauges will be sent Finished Brass with Drain Cock.

When Gauges are ordered, whose dimensions are different from the above an extra charge will be made, same varying according to number of Gauges ordered, and amount of difference from our standard of dimensions. Orders stating simply Oil Gauges will be filled with the above.



# LUNKENHEIMER'S CYLINDRICAL AND URN-SHAPED GLASSES.

455



Fig. 526 L.



Fig. 527 L.

These Glasses are clear, strong and uniform in size, and interchangeable with all styles of glass cups made by us.

## PRICE LIST.

Number.....	000	00	0	1	1½	2	3	4	5	6	8
Outside Diameter of Cylindrical Glasses, inches.....	1	1⅛	1¼	1½	1¾	2	2¼	2½	3	3½	4¼
Height of Cylindrical Glasses, inches.....	¾	1	1⅛	1¾	1⅝	1⅞	2¼	2¾	3	4	5
Outside Diameter at upper end of Urn-shaped Glasses, Inches.....		1⅛	1¼	1½	1¾	2	2¼	2½	3	3½	.....
Height of Urn-shaped Glasses, Inches.....		1½	1⅝	2	2¼	2½	2¾	3¼	3⅝	4½	.....
Cylindrical or Urn-shaped Glasses, each.....	\$0.05	\$0.06	\$0.08	\$0.10	\$0.10	\$0.12	\$0.15	\$0.25	\$0.35	\$0.65	\$1.50
Cork Washers, per dozen.....	.15	.18	.24	.30	.36	.40	.45	.50	.60	.75	1.50

In ordering Glasses always specify whether Cylindrical or Urn-shaped are wanted.


## BRASS STEAM COCKS.




TEE HANDLE.



FLAT OR SQUARE HEAD.



THREE-WAY, WITH CHECK, SQUARE HEAD.



FLANGED.

## TEE HANDLE.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$
Each.....	\$0.85	\$0.85	\$1.00
With Check, each.....	1.00	1.00	1.15

## FLAT OR SQUARE HEAD.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each.....	\$0.85	\$1.00	\$1.25	\$1.70	\$2.35	\$3.70	\$4.85	\$7.30	\$14.50	\$22.50
With Check, each.....	1.00	1.15	1.40	1.90	2.55	3.95	5.15	7.65	15.00	23.25
Extra Heavy, each.....	1.30	1.50	2.00	2.85	4.00	6.75	8.50	13.50	25.00	37.00

## THREE-WAY, WITH CHECK.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each.....	\$2.50	3.00	3.75	5.75	7.15	11.00	18.75	26.00

## FLANGED.

Size, Inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Square or Flat Head, each.....	\$7.30	\$9.70	\$11.75	\$18.00	\$27.50	\$43.00
Extra Heavy, each.....	10.00	14.25	17.25	27.00	41.00	63.00

## MALLEABLE-IRON WRENCHES.



## FOR GAS AND STEAM COCKS.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each.....	\$0.07	.07	.07	.09	.14	.19	.25	.44	.56	1.00

# GAS SERVICE COCKS.


457



TEE HANDLE.




FLAT HEAD.



SQUARE HEAD.



HEAVY ROUND WAY  
SQUARE HEAD.



HEAVY ROUND WAY  
FLAT HEAD.

## TEE HANDLE.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$
Each.....	\$0.75	\$0.85
Each, with Check.....	.90	1.00

## FLAT HEAD.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each .....	\$0.75	\$0.85	\$0.95	\$1.15	\$1.50	\$2.25	\$3.10	\$5.00	\$11.00	\$16.00
Extra Heavy.....	.85	.95	1.05	1.30	1.70	2.60	3.60	6.50	12.00	18.00

## SQUARE HEAD.


Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Each.....	\$0.75	\$0.85	\$0.95	\$1.15	\$1.50	\$2.25	\$3.10	\$5.00	\$11.00	\$16.00
Extra Heavy .....	.85	.95	1.05	1.30	1.70	2.60	3.60	6.50	12.00	18.00

## HEAVY ROUNDWAY.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Each .....	\$1.05	\$1.30	\$1.70	\$2.60	\$3.60	\$6.50
With Check, each .....	1.45	1.75	2.50	3.25	4.75	7.50




## BRASS COCKS.




METER COCK.

## GAS METER COCKS, FLAT HEAD.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Meter, each .....	\$1.30	\$1.40	\$1.95	\$3.00	\$4.25	\$6.00
Union Meter, each...	1.40	1.55	2.20	3.40	5.00	7.00




UNION METER COCK.



LOCK METER COCK.




LOCK SERVICE COCK.



LOCK UNION METER COCK.

## LOCK METER COCKS.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Meter, each.....	\$1.40	\$1.75	\$2.30	\$3.85	\$5.50	\$7.75
Union Meter, Flatway, each.....	1.50	1.80	2.50	4.00	5.50	8.00
Union Meter, Roundway, each.....	2.25	2.70	3.75	6.00	8.25	12.00



GAS STOVE COCK.

## LOCK GAS SERVICE COCKS, FLAT HEAD.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Each .....	\$1.30	1.60	2.10	3.50	5.00	7.00

## GAS STOVES COCK, ROUNDWAY.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1
Without Check, each.....	\$1.25	\$2.00	\$3.00
With Check, each.....	1.35	2.15	3.25

# ALL IRON COCKS.


459



SCREWED.



FLANGED.



THREE-WAY.

## SCREWED.

Size, Inches .....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
All Iron, each.....	\$0.85	\$0.90	\$1.05	\$1.30	\$1.60	\$1.95	\$2.70	\$4.40	\$6.75	\$12.00	\$15.50	\$32.00	\$45.00
All Iron, Three-way.....			1.65	1.80	2.05	2.65	3.65	5.35	7.50	14.00	19.00		

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
With Brass Washer, each.....	\$1.00	\$1.20	\$1.55	\$1.95	\$2.35	\$3.20	\$5.15	\$7.75	\$14.00	\$19.00	\$38.00	\$53.00
With Brass Washer, Three-way.....		1.80	2.05	2.40	3.05	4.15	6.10	8.50	16.00	22.50		

Size, Inches .....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
With Brass Plug, each.....	\$1.25	\$1.30	\$1.60	\$1.90	\$2.65	\$3.75	\$5.25	\$8.75	\$13.00	\$27.50	\$36.50	\$67.00	\$94.00
With Brass Plug, Three-way.....			2.20	2.40	3.10	4.50	6.25	9.75	13.75	30.00	40.00		

## FLANGED.

Size, Inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
All Iron.....	\$2.25	\$2.75	\$3.25	\$4.25	\$6.25	\$9.50	\$15.00	\$19.00	\$36.00	\$50.00
With Brass Washer.....	2.50	3.10	3.65	4.75	7.00	10.50	17.00	22.50	42.00	58.00
With Brass Plug.....	3.00	3.75	5.00	7.00	10.50	15.75	30.00	40.00	70.00	100.00

These Flanged Cocks are made to order only, at a special discount.


## AIR COCKS.



TEE HANDLE.




LEVER HANDLE.




TEE HANDLE, MALE THREADS.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$
Tee Handle, each.....	\$0.40	\$0.40	\$0.50	\$0.60
Lever Handle, each.....	.55	.55	.65	.75
Tee Handle, Male Threads, each.....	.55	.55	.65	.90



LEVER HANDLE, MALE THREADS.



TEE HANDLE, FEMALE THREADS.



LEVER HANDLE, FEMALE THREADS.

Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$
Lever Handle, Male Threads, each.....	\$0.60	\$0.70	\$0.85	\$1.00
Tee Handle, Female Threads, each.....	.70	.70	.90	.....
Lever Handle, Female Threads, each.....	.80	.80	.95	.....



TEE HANDLE.



LEVER HANDLE.



LEVER HANDLE WITH THREAD ON NOSE.


Size, Inches.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$
Tee Handle, each.....	\$0.70	\$0.70	\$0.80	\$0.90
Lever Handle, each.....	.80	.80	.90	1.00
Tee Handle, with Thread on Nose, each.....	.80	1.00	1.10	1.35
Lever Handle, with Thread on Nose, each.....	.95	1.15	1.25	1.50





STEAM GAUGE COCK.

Size,  $\frac{1}{4}$ -inch, each..... \$0.75



STEAM GAUGE COCK, WITH UNION.

Size,  $\frac{1}{4}$ -inch, each..... \$1.75




WITH BIBB.



WITH BIBB.

CYLINDER COCKS.




WITH COUPLING.

Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$
Tee Handle, each.....	\$1.00	\$1.15	\$1.60	\$2.35
Lever Handle, each.....	1.15	1.30	1.85	2.60
Tee Handle, with Thread on Nose, each.....	1.10	1.35	1.85	2.45
Lever Handle, with Thread on Nose, each.....	1.25	1.50	2.10	2.70
Lever Handle, with Coupling.....		2.00	2.50	3.75



WITHOUT STUFFING-BOX.



WITH STUFFING-BOX.

GAUGE COCKS.




REGISTER GAUGE COCK.

Size, Inches.....	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$
Wood Handle, each.....	\$1.10	\$1.20	\$1.35
Wood Handle, with Stuffing-Box, each.....	1.35	1.50	1.70
Register Gauge Cock, each.....	1.00	1.00	1.00


## ENGINE AND BOILER TRIMMINGS.



WITH ADJUSTABLE LEVER.



WHISTLE CHIMES.



PLAIN.

## WHISTLES.

Diameter of Bell, Inches..	1	1¼	1½	2	2½	3	3½	4	5	6	8	10
Size Pipe, Inches.....	½	½	½	¾	¾	1	1	1¼	1½	2	2½	2½
With Valve, each.....	\$3.10	\$3.75	\$4.00	\$5.50	\$6.50	\$8.50	\$11.50	\$15.00	\$22.50	\$33.00	\$95.00	\$210.00
Plain, each .....	2.20	2.75	3.00	4.35	5.25	7.25	9.50	12.00	19.00	24.00	70.00	150.00

Steam Whistle Chimes made to order of any desired combination. Write for prices.



PLAIN.



WHISTLE VALVE.



WITH REVERSIBLE LEVER.

## SINGLE BELL CHIME STEAM WHISTLES.

Diameter of Bell, Inches.....	2	3	4	5	6	8	10	12
Size Pipe, Inches.....	½	¾	1	1¼	1½	2	2½	3
Plain, each .....	\$5.00	\$8.00	\$14.00	\$22.00	\$38.00	\$85.00	\$150.00	\$260.00
With Valve each.....	7.00	11.00	18.00	28.00	42.00	100.00	180.00	300.00

## WHISTLE VALVES.


Size, Inches....	½	¾	1	1¼	1½	2	2½	3
Each.....	\$2.50	3.00	3.50	5.00	6.00	9.00	18.00	27.00

# WATER GAUGES.

463




Nos. 1 and 3.  
FINISHED BODY,  
With Two Guards.



Nos. 2 and 4.  
FINISHED BODY,  
With Four Guards.



No. 5.  
FINISHED BODY,  
With Iron Wheel.



No. 6.  
FINISHED BODY,  
With Wood Wheel.



No. 7.  
ROUGH BODY.  
Bronzed.



No. 8.  
ROUGH BODY.  
Bronzed.



No. 9.  
ROUGH BODY.  
Bronzed.

No. 1 with Wood Wheels, Glass  $\frac{3}{4}$  x 16 inch, Screwed for  $\frac{3}{4}$ -inch Pipe, each..... \$8.00

No. 2, with Wood Wheels, Glass  $\frac{3}{4}$  x 16 inch, Screwed for  $\frac{3}{4}$ -inch Pipe, each ..... \$10.00

No. 2 is so constructed that by removing top cap a new glass can be put in while under steam pressure.

No. 3, with Wood Wheels, Glass  $\frac{5}{8}$  x 12 inch, Screw for  $\frac{1}{2}$ -inch Pipe, each..... \$6 50

No. 4, with Wood Wheels, Glass  $\frac{5}{8}$  x 12 inch, Screwed for  $\frac{1}{2}$ -inch Pipe, each..... \$7.00

No. 5, with Iron Wheels, Glass  $\frac{5}{8}$  x 12 inch, Screwed for  $\frac{1}{2}$ -inch Pipe, each..... \$5.50

No. 6, with Wood Wheels, Glass  $\frac{5}{8}$  x 12 inch, Screwed for  $\frac{1}{2}$ -inch Pipe, each..... \$5.75

No. 7, with Iron Wheels, Glass  $\frac{5}{8}$  x 12 inch, Screwed for  $\frac{1}{2}$ -inch Pipe, each..... \$3.25

No. 8, with Iron Wheels, Glass  $\frac{5}{8}$  x 12 inch, Screwed for  $\frac{1}{2}$ -inch Pipe, each..... \$4.00


No. 9, with Iron Wheels, Glass  $\frac{1}{2}$  x 12 inch, Screwed for  $\frac{3}{8}$ -inch Pipe, each..... \$3.00

NOTE.—The bottom part of the No. 8 Gauge is so constructed that by removing drip cock, glass can be inserted.



## COMBINATION WATER AND STEAM GAUGES.

## DIMENSIONS OF COMBINATION BODIES.




Number.....	1	2	3	4
Center to centre of Boiler Connections, inches .....	10	12½	14	18
Center to centre of Water Gauge Connections inches.....	10	12½	14	18
Center to center of Gauge Cocks, inches.....	3⅜	3¾	4½	4
Extreme Length, inches.....	13	16½	18¾	22½
Tapped for Boiler Connections, inches.....	½	¾	¾	1¼
Tapped for Water Gauge Connections, inches.....	½	½	¾	¾
Tapped for Gauge Cocks, inches.....	⅜	½	½	¾
Top and bottom tapped, inches.....	½	½	¾	1¼
Price, Bodies only, painted and tapped, each.....	\$2.75	\$4.00	\$6.00	\$8.00
Price, Combination Gauges complete, with trimmings, as below, each.....	25.00	40.00	50.00	60.00
Gauge Cocks required.....	2	3	3	3
Size Chased Iron Pipe, inches.....	⅜	½	½	¾
One Water Gauge, No.....	7	3	1	1
One Iron Steam Gauge, original Bourdon Spring, size, inches.....	5	5	6	6
One Nipple, size, inches.....	½	½	¾	¾
One Globe Valve size, inches.....	½	½	¾	¾
One Syphon, size, inches.....	¼	¼	¼	¼
One Bushing, size, inches.....	½ x ¼	½ x ¼	¾ x ¼	1¼ x ¾

# ENGINE GOVERNORS.

465

## THE GARDNER GOVERNOR.



STANDARD. CLASS A.



STANDARD. CLASS B.

### PRICE LIST OF CLASS "A" AND "B" STANDARD GOVERNORS.

Size of Governor— Diameter of Opening....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{4}$	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10
Price Class B, Plain.....	\$16.00	18.00	21.00	25.00	30.00	35.00	40.00	50.00	60.00	71.00	83.00	94.00	122.00	150.00	185.00	215.00	240.00
Price Class B, Finished.....	18.00	20.00	24.00	29.00	34.00	40.00	45.00	58.00	69.00	81.00	94.00	106.00	136.00	166.00	202.00	235.00	260.00
Price Class A, Plain.....				29.50	36.00	42.00	48.00	59.00	71.00	83.00	96.00	109.00	140.00	170.00	210.00	241.00	270.00
Price, Class A, Finished.....				33.50	40.00	47.00	53.00	67.00	80.00	93.00	107.00	121.00	154.00	186.00	227.00	261.00	290.00

Class B is without Automatic Stop and Class A with Automatic Stop.


Prices on Sizes from 12 to 16 inches inclusive will be sent on application.

### TABLE OF DIMENSIONS OF CLASS "A" AND "B" STANDARD GOVERNORS.


Size of Governor—Diam. of Opening	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{4}$	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10
Diameter of Base Flange.....	Scr'd	Scr'd	Scr'd	$5\frac{1}{2}$	7	7	8	9	9	10	10	12	14	15	17	18	19
Diameter of Side Flange.....	Scr'd	Scr'd	Scr'd	Scr'd	Scr'd	7	7	8	9	10	10	11	13	14	15	16	17
Largest Radius of Balls.....	4	4	5	5	6	6	$6\frac{1}{2}$	$7\frac{1}{2}$	$7\frac{1}{2}$	$8\frac{1}{2}$	$8\frac{1}{2}$	10	11	12	12	15	15
From Center to Side Flange.....	$2\frac{1}{4}$	$2\frac{1}{2}$	3	$3\frac{1}{2}$	5	5	$5\frac{1}{2}$	6	$6\frac{1}{2}$	$6\frac{1}{2}$	7	$7\frac{1}{2}$	$8\frac{1}{2}$	9	10	11	14
From Base to Center of Inlet.....	$2\frac{1}{4}$	$2\frac{1}{2}$	3	4	5	$5\frac{1}{2}$	$5\frac{3}{4}$	6	$6\frac{1}{2}$	$6\frac{1}{2}$	7	8	$8\frac{1}{2}$	$9\frac{1}{2}$	$10\frac{1}{2}$	11	15
Extreme Height.....	15	15	20	21	25	26	28	32	34	37	38	43	44	51	53	62	67
From Center to End of Shaft.....	9	9	11	11	13	13	15	15	17	17	17	21	21	25	25	28	28
Diameter of Pulley.....	2	2	3	3	5	5	5	$5\frac{1}{2}$	$5\frac{1}{2}$	6	6	7	7	10	11	12	12
Width of Belt.....	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{1}{2}$	2	2	2	2	2	$2\frac{1}{2}$	$2\frac{1}{2}$	3	3	3	3	3	3
Number of Revolutions.....	300	300	250	250	200	200	200	170	170	160	160	150	150	130	130	130	115
Diameter Cylinder—300 ft. Piston Speed.	4	5	6	7	9	10	12	14	16	18	20	22	26	31	36	40	45
" " 400 " "	3	4	5	6	8	9	10	12	14	16	18	20	23	27	31	35	39
" " 500 " "		$3\frac{1}{2}$	$4\frac{1}{2}$	5	7	8	9	10	12	14	16	18	21	24	28	31	35
" " 600 " "			4	$4\frac{1}{2}$	6	7	8	9	11	13	15	16	19	22	25	28	32

## ENGINE GOVERNORS.

## THE GARDNER GOVERNOR.



SPRING. CLASS A.



SPRING. CLASS B.

## PRICE LIST OF CLASS "A" AND "B" SPRING GOVERNORS.


Size of Governor— Diameter of Opening....	½	¾	1	1¼	1½	2	2¼	2½	3	3½	4	4½	5	6	7
Price Class B, Plain.....	\$14.00	\$16.00	\$18.00	\$21.00	\$25.00	\$30.00	\$35.00	\$40.00	\$50.00	\$60.00	\$71.00	\$83.00	\$94.00	\$122.00	\$150.00
Price Class B, Finished ....	16.00	18.00	20.00	24.00	29.00	34.00	40.00	45.00	58.00	69.00	81.00	94.00	106.00	136.00	166.00
Price Class A, Plain.....			21.00	24.50	29.50	36.00	42.00	48.00	59.00	71.00	83.00	96.00	109.00	140.00	170.00
Price Class A, Finished.....			23.00	27.50	33.50	40.00	47.00	53.00	67.00	80.00	93.00	107.00	121.00	154.00	186.00

Class B is without Automatic Stop and Class A with Automatic Stop.


## TABLE OF DIMENSIONS OF CLASS "A" AND "B" SPRING GOVERNORS.

Size of Governor.....	½	¾	1	1¼	1½	2	2¼	2½	3	3½	4	4½	5
Diameter of Base Flange.....	Sc'd	Sc'd	Sc'd	Sc'd	5½	7	7	8	9	9	10	10	12
Diameter of Side Flange.....	Sc'd	Sc'd	Sc'd	Sc'd	Sc'd	Sc'd	Sc'd	7	8	9	10	10	11
Height, inches.....	12	13	13½	17½	22	23	24	27	29	30	35	36	37
Radius of Balls.....	2½	2½	2½	3½	4	4	4	5	5	5	5½	6	6
Length of Shaft.....	8	8	8	11	11	13	13	15	15	15	16	16	18
Diameter of Pulley.....	1½	1½	1½	2	2½	2½	2½	3½	3½	3½	4½	4½	4½
Width of Belt.....	1	1	1	1¼	1½	1½	1½	2	2	2	2½	2½	2½
Center to Side of Chamber.....	1¾	2¼	2¼	3	3½	5	5	5½	6	6	6½	7	7½
Base to Center of Chamber.....	1¾	2¼	2¼	3	3½	5	5½	6	6	6	6½	7	8
Number of Revolutions.....	600	600	600	450	400	400	400	350	350	350	275	275	275





DETROIT IMPROVED  
LUBRICATOR.



SINGLE CONNECTION.

Capacity .....	$\frac{1}{8}$ Pint.	$\frac{1}{2}$ Pint.	1 Pint.	1 Quart.	$\frac{1}{2}$ Gallon.	1 Gallon.
Size for Cylinder.....	Under 10-Inch.	10 to 12-Inch.	12 to 18-Inch.	18 to 30-Inch.	30-Inch and over.	.....
Polished Brass, each .....	\$17.00	\$22.00	\$30.00	\$45.00	\$60.00	\$75.00
Nickel-Plated, each.....	20.00	25.00	35.00	50.00	65.00	80.00

## WOOD WHEEL LUBRICATORS.

Diam. of Body, In.	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{4}$	$2\frac{1}{2}$	3
Pipe Thread.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{3}{4}$	$\frac{3}{4}$
Each .....	\$2.00	\$2.20	\$2.40	\$2.60	\$2.90	\$3.25	\$3.75	\$4.75
With Air Cock, each..	3.00	3.20	3.40	3.60	3.90	4.25	4.75	5.75

## ZERO (COLD WEATHER) LUBRICATORS.

SINGLE AND DOUBLE CONNECTION.

### FOR TRACTION, STATIONARY, HOISTING, PORTABLE ENGINES AND STEAM PUMPS.


We make two styles of Double Connection Zero Lubricators—Style “A” and Style “C.”

The Style “A” Double Connection Zero should be attached with both connections on same side of throttle, either above or below, as circumstances will permit.


The Style “C” Double Connection Zero has spray feed feature, and should take steam above the throttle and deliver the oil below the throttle, either into steam pipe or top of steam chest.

In ordering Double Connection Zero Lubricators, please say whether Style “A” or Style “C” is wanted.

The Single Connection Zero Lubricator may be attached to the steam pipe on either side of the throttle or to the steam chest direct.



PLAIN LUBRICATOR.



DOUBLE CONNECTION.


## DETROIT ZERO LUBRICATORS.

Capacity .....	$\frac{1}{4}$ Pint.	$\frac{1}{8}$ Pint.	$\frac{1}{2}$ Pint.	1 Pint.	1 Quart.
Bronze Body, Finished Trimminas, each.....	\$15.00	\$17.00	\$20.00	\$28.00	\$42.00
Nickel-Plated all over, each.....	18.00	20.00	23.00	32.00	47.00


# THE "SWIFT" SIGHT-FEED LUBRICATOR.



CLASS F. SINGLE  
CONNECTION.



CLASS F. DOUBLE  
CONNECTION.



CLASS G. SINGLE  
CONNECTION.

## CLASS F. SINGLE AND DOUBLE.

Capacity .....	$\frac{1}{4}$ Pint.	$\frac{1}{3}$ Pint.	$\frac{1}{2}$ Pint.	1 Pint.	1 Quart.
Size of Shank, inches.....	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{1}{2}$
Brass Finish.....	\$10.00	\$12.00	\$16.00	\$22.00	\$34.00
Nickel-Plated.....	12.00	14.00	20.00	26.00	40.00

## CLASS G.


Capacity, pints.....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{1}{3}$	$\frac{1}{2}$
Size of Shank, inches.....	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{3}{8}$
Brass Finish.....	\$2.50	\$3.00	\$3.75	\$4.50
Nickel-Plated.....	3.00	3.50	4.25	5.00

No. 2 Glasses fit  $\frac{1}{8}$ ,  $\frac{1}{4}$ ,  $\frac{1}{3}$ ,  $\frac{1}{2}$ -pint of all styles.

No. 3 Glasses fit 1 pint and 1 quart of all styles.

# FELTHOUSEN'S HAND CYLINDER OIL PUMPS.


469



NOS. 03 AND 6.

TO GO ON TOP OF CYLINDER OR  
STEAM PIPE.

Description.	Size.	With Screw Top.	With Strainer Top.	Extra Strainer Tops.
Price, No. 03, Finished, each...	2 x 2	\$3.50	\$3.65	\$0.40
Price, No. 6, Finished, each...	2 3/4 x 2 3/4	5.00	5.25	.60




NOS. 3, 04, 4 AND 5.

TO GO ON SIDE OF CYLINDER OR  
STEAM PIPE.

Description.	Size.	With Screw Top.	With Strainer Top.	Extra Strainer Tops.
Price, No. 3, Finished, each...	2 x 2	\$3.50	\$3.65	\$0.40
Price, No. 04, Finished, each...	2 3/4 x 2 3/4	5.00	5.25	.60
Price, No. 4, Finished, each...	3 1/2 x 3 1/2	7.50	7.80	.75
Price, No. 5, Finished, each...	7 x 4 1/2	12.00	12.00	.....

## LEVER HANDLE OIL PUMP.



Price, each...\$20.00



No. 1. PLAIN.



No. 2. HINGED LID.




No. 3. ELBOW SHANK.



No. 4. LEVER HANDLE.

Dia. of Body, In.	5/8	3/4	7/8	1	1 1/8	1 1/4	1 1/2	1 3/4	1 3/4	1 7/8	2	2	2 1/4	2 1/2	2 1/2	3
Pipe Thread, In....	1/8	1/8	1/8	1/4	1/2	1/4	3/8	3/8	1/2	1/2	3/4	1/2	1/2	1/2	3/4	3/4
No. 1, each.....	\$0.25	\$0.30	\$0.35	\$0.40	\$0.50	\$0.60	\$0.90	\$1.25	\$1.25	\$1.60	\$1.75	\$1.75	\$2.25	\$2.75	\$2.75	\$4.50
No. 2, each.....	.....	.....	.....	1.00	.....	1.40	1.85	.....	.....	.....	3.10	.....	.....	.....	.....	.....
No. 3, each.....	.....	.....	.....	.70	.....	1.00	1.40	.....	.....	.....	2.30	.....	.....	.....	.....	.....
No. 4, each.....	.....	.....	.....	1.35	.....	1.60	2.20	.....	.....	.....	.....	3.25	4.00	.....	.....	.....

## FUSIBLE PLUGS.



Size, Inches.....	1/2	3/4	1	1 1/4	1 1/2	2
Price, each.....	\$0.60	0.75	1.00	1.50	2.00	3.00

## BRASS OIL CUPS.

## MISSISSIPPI GAUGE COCKS.




Size, Chased Iron Pipe, Inches.....	3/8	1/2	1/2	3/4
Blank Shank, Inches.....	5/8	3/4	7/8	1
Price, each.....	\$0.90	1.20	1.50	1.80



# STEAM AND WATER GAUGES.

## BALANCE WATER GAUGE.



Size.	Iron Case, Japanned.	Brass Case.	N. P. Case.
12 inch Dial, each.....	\$60.00	\$80.00	\$84.00
10 " " " ".....	40.00	50.00	53.00
8 1/2 " " " ".....	30.00	40.00	42.50
6 3/4 " " " ".....	20.00	25.00	27.00
6 " " " ".....	16.00	20.00	21.50
5 1/2 " " " ".....	14.00	16.00	17.25
4 1/2 " " " ".....	12.00	14.00	15.00
3 1/2 " " " ".....	10.00	12.00	12.75


This Gauge is constructed to show the actual amount of water in tank, using the entire space on dial to show a few feet of water, according to capacity of tank. In ordering, please state the height of water column and depth of tank.

## ALTITUDE GAUGE.



Size.	Iron Case, Japanned.	Iron Case, N. P. Ring.	Brass Case.	N. P. Case.
12 inch Dial.....	\$60.00	\$61.50	\$80.00	\$84.00
10 " " " ".....	40.00	41.00	50.00	53.00
8 1/2 " " " ".....	30.00	30.75	40.00	42.50
6 3/4 " " " ".....	20.00	20.60	25.00	27.00
6 " " " ".....	16.00	16.50	20.00	21.50
5 1/2 " " " ".....	14.00	14.25	16.00	17.25
5 " " " ".....	12.00	12.20	15.00	16.00
4 1/2 " " " ".....	12.00	12.20	14.00	15.00
4 " " " ".....	12.00	12.20	14.00	15.00
3 1/2 " " " ".....	10.00	10.18	12.00	12.75

## BOURDON DOUBLE SPRING GAUGES FOR TRACTION ENGINES.



Size.	Iron Case, Japanned.	Iron Case, N. P. Ring.	Brass Case.	N. P. Case.
12 inch Dial, each.....	\$55.00	\$56.50	\$80.00	\$84.00
10 " " " ".....	37.00	38.00	45.00	48.00
8 1/2 " " " ".....	25.00	25.75	34.00	36.50
6 3/4 " " " ".....	18.00	18.60	22.00	24.00
6 " " " ".....	15.00	15.50	18.00	19.50
5 1/2 " " " ".....	12.00	12.25	14.00	15.25
5 " " " ".....	11.00	11.20	13.00	14.00
4 1/2 " " " ".....	10.00	10.20	12.00	13.00

Not warranted unless Syphon is used.

# PRESSURE AND VACUUM GAUGES.

471



## STEAM GAUGES.

BOURDON SINGLE SPRING.



Diameter of Dial, Inches.....	3 or less	3½	4 and 4½	5	5½	6	6¾	8½	10	12
Brass Case, Lacquered, each.....	\$8.00	\$9.00	\$10.00	\$11.00	\$12.00	\$16.00	\$20.00	\$30.00	\$40.00	\$75.00
Nickel-Plated Case, each.....	8.60	9.75	11.00	12.00	13.25	17.50	22.00	32.50	43.00	79.00
Iron Case with Brass Ring, each.....	6.00	7.00	8.00	8.00	10.00	13.00	16.00	22.00	32.00	50.00
Iron Case with N. P. Ring, each.....	6.15	7.18	8.20	8.20	10.25	13.50	16.60	22.75	33.00	51.50



## COMBINATION WATER PRESSURE GAUGES.

FOR INDICATING PRESSURE OF WATER IN POUNDS  
PER SQUARE INCH AND CORRESPONDING  
HEIGHT OF WATER COLUMN.

## COMPOUND PRESSURE AND VACUUM GAUGES.

FOR INDICATING EITHER PRESSURE OR VACUUM.



COMBINATION WATER PRES-  
SURE GAUGE.

COMPOUND PRESSURE AND  
VACUUM GAUGE.

These Gauges are graduated for Pressure in pounds per square inch, and for Vacuum in inches of mercury column or pounds per square inch as may be desired, fifteen pounds of pressure being equal to thirty inches of vacuum. If a pressure exceeding fifteen pounds is required it should be stated in ordering.

## COMBINATION W. P. GAUGES.

Size.	Iron Case, Japanned.	Brass Case.	N. P. Case.
12 inch Dial, each.....	\$60.00	\$80.00	\$84.00
10 " " " ".....	40.00	50.00	53.00
8½ " " " ".....	30.00	40.00	42.50
6¾ " " " ".....	20.00	25.00	27.00
6 " " " ".....	16.00	20.00	21.50
5½ " " " ".....	14.00	16.00	17.25

## COMPOUND P. AND V. GAUGES.


Size.	Iron Case, Japanned.	Brass Case.	N. P. Case.
12 inch Dial, each.....	\$60.00	\$80.00	\$84.00
10 " " " ".....	40.00	50.00	53.00
8½ " " " ".....	30.00	40.00	42.50
6¾ " " " ".....	20.00	25.00	27.00
6 " " " ".....	16.00	20.00	21.50
5½ " " " ".....	14.00	16.00	17.25
4½ " " " ".....	12.00	14.00	15.00
3½ " " " ".....	10.00	12.00	12.75

No Syphon is needed for these Gauges.

A Syphon must be used with these Gauges.



## PRESSURE RECORDERS.



CROSBY PRESSURE RECORDER.

### CROSBY PRESSURE RECORDER. IN FINE COMPOSITION CASE.

Size Dial, Inches.....	6 $\frac{3}{4}$	8 $\frac{1}{2}$	10	12
Price, each, in Shallow Case.....	\$40.00	50.00	65.00	85.00

Prices of Recorders, with deep cases, on application.  
With every instrument is furnished one year's supply of  
paper dials, bottle of ink and filler.



CROSBY PRESSURE RECORDER AND GAUGE

### CROSBY PRESSURE RECORDER AND GAUGE.

IN FINE COMPOSITION CASE.

Size Dial, Inches.....	8 $\frac{1}{2}$	10	12
Price, each, in Deep Case.....	\$60.00	75.00	100.00

With every instrument is furnished one year's supply  
of paper dials, bottle of ink and filler.

## COLUMBIA PRESSURE RECORDING GAUGES.

These Gauges are adapted for recording the pressure of  
steam, water, gas or air, and may be placed near the boiler  
or at any distance therefrom; for instance, in the office;  
always giving a true record of the fluctuations of pressure  
taking place in boiler, water and gas pipes, etc. They are  
made for all pressures.


Gauges and charts for the following pressures are kept  
in stock:

For steam, gas and air: 25, 50, 75, 150, 200 pounds per  
square inch.

For water: 100, 200, 300 feet of water column.

### PRICES.


"Columbia" Recording Gauge, in highly-japanned or nickered-iron case, with hinged brass cover and lock, including 100 charts.....	\$50.00
Solid Brass Case, highly finished.....	60.00
Electric Arm Attachment, for either of above Gauges.....	10.00
Additional Charts, per hundred.....	.75
Recording Ink, per bottle.....	.25





# SCOTCH GLASS TUBES. FOR WATER GAUGES.

473



Length, inches.....	10	11	12	13	14	15	16	17	18	19	20	22	24	30	36
$\frac{5}{8}$ -inch, per dozen.....	\$3.00	\$3.24	\$3.60	\$3.84	\$4.20	\$4.44	\$4.80	\$5.04	\$5.40	\$5.64	\$6.00	\$6.60	\$7.20	\$9.00	\$10.80
$\frac{3}{4}$ -inch, per dozen.....	3.60	3.96	4.32	4.80	5.16	5.52	5.88	6.24	6.60	7.08	7.44	8.16	8.88	11.16	13.44

$\frac{1}{2}$ -inch Glass Tubes same list as  $\frac{5}{8}$ -inch. Sizes over 24 inches special discount.

## RED-REFLECTING GAUGE GLASS.

Showing through the water a broad line of a rich red color, thus rendering it very distinct.

Length, inches.....	10	11	12	13	14	15	16	17	18
$\frac{5}{8}$ -inch, per dozen.....	\$4.80	\$4.80	\$5.40	\$5.40	\$6.00	\$6.60	\$7.20	\$7.80	\$8.40
$\frac{3}{4}$ -inch, per dozen.....	6.60	6.60	6.60	6.60	7.20	7.20	7.80	8.40	9.00

## CHESTERTON'S GLASS TUBE CUTTER.



One arm has a scale in inches and fractions of an inch, a slide stop with set screw and a rotary cutter at the end. This arm is inserted in the end of the glass tube to the required distance, against the slide stop or gauge, the outside of the glass tube resting in the circled end of the other arm. With a slight pressure of thumb and finger on the lever, and a rotation of the glass with the other hand, the rotary cutter makes an even cut around the inside of the tube and a very little pressure breaks it off.

Price, Tube Cutter complete, each.....	\$2.50
Price, extra Cutter Wheels, each, net.....	.15

## EXTRA BRASS GUARDS. FOR WATER GAUGES.

18 Inches Long, each, net.....	\$0.15
16 Inches Long, each, net.....	.12
14 Inches Long, each, net.....	.08
12 inches Long, each, net.....	.07

Longer Guards to order.

## RUBBER WASHERS. FOR WATER GAUGES.

Price, per dozen, net.....	\$0.12
----------------------------	--------

# REVOLUTION COUNTERS.

## ROUND CASE.



These counters are used in connection with engines and pumps and are made with either six or eight disks. The diameter of the disks of the 12-inch counters is 3 inches, of the 8½ and 10-inch counters 2½ inches, and of the 6¾-inch counters, 2 inches.

The movements are positive gear movements, without springs, and are accurate in action.


For use under a variable length of stroke, an attachment is provided whereby the shaft is released each time the counter registers a stroke.

## PRICES. ROUND CASES.

Size.	Brass Case.	N. P., O. G. or Oct. Ring.
12 in. Dial, 8 Wheels.....	\$110.00	\$114.00
10 " 8 " .....	95.00	98.00
8½ " 8 " .....	80.00	82.50
12 " 6 " .....	100.00	104.00
10 " 6 " .....	85.00	88.00
8½ " 6 " .....	70.00	72.50
6¾ " 6 " .....	60.00	62.00
6 " 6 " .....	50.00	52.00

## SQUARE CASE.

FOR ENGINES, PUMPS, GRAIN SCALES, ETC.



## PRICES. COUNTERS IN SQUARE METAL CASES.

### LARGE SIZE.

4 figs., counting	10,000, in cases	7 x 2½ inches.....	\$20.00
5 " "	100,000, "	8 x 2½ " .....	24.00
6 " "	1,000,000, "	9 x 2½ " .....	28.00
7 " "	10,000,000, "	10 x 2½ " .....	32.00

### SMALL SIZE.


4 figs., counting	10,000, in cases,	4½ x 1¾ inches.....	\$13.50
5 " "	100,000, "	5 x 1¾ " .....	16.00
6 " "	1,000,000, "	5½ x 1¾ " .....	20.00
7 " "	10,000,000, "	6 x 1¾ " .....	24.00

The same with re-setting attachment, each, extra, \$4.00.

# BLAKESLEE'S STEAM JET PUMP.

475

Size of Pump.	Suction Pipe.	Discharge Pipe.	Steam Pipe.	Steam Opening.	Capacity per Minute.	Price.
$\frac{3}{4}$ inch	$\frac{3}{4}$ inch	$\frac{1}{2}$ inch	$\frac{3}{8}$ inch	$\frac{3}{16}$	8 gallons	\$8.00
1 "	1 "	$\frac{3}{4}$ "	$\frac{1}{2}$ "	$\frac{1}{8}$	15 "	10.00
$1\frac{1}{4}$ "	$1\frac{1}{4}$ "	1 "	$\frac{1}{2}$ "	$\frac{5}{16}$	20 "	12.00
$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	$1\frac{1}{4}$ "	$\frac{3}{4}$ "	$\frac{6}{16}$	30 "	14.00
2 "	2 "	$1\frac{1}{2}$ "	$\frac{3}{4}$ "	$\frac{7}{16}$	40 "	16.00
$2\frac{1}{2}$ "	$2\frac{1}{2}$ "	2 "	1 "	$\frac{8}{16}$	50 "	20.00
3 "	3 "	$2\frac{1}{2}$ "	1 "	$\frac{9}{16}$	60 "	24.00



## PRICE LIST PARTS OF BLAKESLEE JET PUMP.

Size, Inches .....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Nuts, each.....	\$0.50	\$0.50	\$0.50	\$0.75	\$0.75	\$1.00	\$1.50	\$1.50
Malleable Nipples, each.....	.25	.25	.25	.35	.35	.60	.75	1.00
Combining Pipes (Loose Tube), each .....		.75	.75	.75	1.00	1.00	1.50	1.50
Steam Tubes (Tight Tube), each .....		.25	.50	.50	.60	.60	.75	.75

N. B.—Size of Nipples determined by inside diameter. Size of Nut determined by size Nipple it will take.

## STEAM GAUGE SYPHONS.



Fig. 1.




Fig. 2.




Fig. 3.




Fig. 4.




Fig. 5.


Figure.....	1	2	3	4	5
Each .....	\$1.00	1 25	1.50	1.50	.50



# AUTOMATIC INJECTORS AND EJECTORS.



AUTOMATIC INJECTOR.



AUTO-POSITIVE INJECTOR.

## PENBERTHY AUTOMATIC INJECTOR.

Size.....	OO	A	AA	B	BB	C	CC	D	DD	E
Price, each.....	\$16.00	\$18.00	\$20.00	\$25.00	\$30.00	\$40.00	\$45.00	\$55.00	\$60.00	\$75.00
Horse Power.....	4 to 8	8 to 10	10 to 15	15 to 25	25 to 35	35 to 50	50 to 60	60 to 95	95 to 120	120 to 165
Pipe Connections, inches.....	$\frac{3}{4}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{3}{4}$	1	1	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{2}$
Gallons per Hour, 1 to 3 Ft. Lift { Max... 50 to 75 Lbs. Pressure..... { Min ...	80 55	120 70	165 90	250 135	340 165	475 300	575 350	750 400	920 500	1300 700

Working Range: Start low, 18 to 22 pounds steam on 4 foot lift. Work high on, 150 to 160 pounds steam on 4 foot lift. Lift water 20 to 21 feet on 60 to 80 pounds steam. Handle hot water 120° to 125° at 60 to 80 pounds steam. 112° to 115° at 100 pounds steam. 95° to 100° at 125 pounds steam.

## PENBERTHY AUTO-POSITIVE INJECTOR.

Size.....	112	113	115	117	119	121	123
Price, each.....	\$18.00	20.00	30.00	45.00	60.00	90.00	125.00
Pipe, Con.—Steam, Suction, Delivery.....	$\frac{3}{4}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Capacity, gal. per hour, 60 to 80 lbs. Steam, { Max..... 3 ft. Lift..... { Min .....	120 40	200 60	400 130	675 225	1125 375	2000 700	3000 1000
H. P. Allowing 8 gallons per H. P. per hour.....	5 to 15	7 to 23	16 to 50	28 to 84	47 to 140	87 to 250	125 to 375

Working Range: Start low, 15 to 18 pounds steam on 3 foot lift. Work high, 225 to 235 pounds steam on 3 foot lift. Lift water 20 to 22 feet on 60 to 100 pounds steam. Handle hot water when flowing to Injector as follows: 143° to 145° and under, with 75 to 100 pounds steam. 133° to 135° and under, with 50 to 120 pounds steam: 118° to 120° and under, with 25 to 150 pounds steam. 95° to 100° and under, with 18 to 175 pounds steam.



## XL 96 EJECTOR OR JET PUMP.

LIFTS 20 FEET ON 25 POUNDS STEAM. ELEVATES 50 TO 75 FEET.

Number.....	1	2	3	4	5	6	7	8	9	10
Pipe Connection { Steam ..... Suction and Delivery.....	$\frac{3}{8}$ $\frac{1}{2}$	$\frac{1}{2}$ $\frac{3}{4}$	$\frac{3}{4}$ 1	1 $1\frac{1}{4}$	1 $1\frac{1}{2}$	$1\frac{1}{4}$ 2	$1\frac{1}{2}$ $2\frac{1}{2}$	2 3	2 $3\frac{1}{2}$	$2\frac{1}{2}$ 4
Capacity { 40 to 65 Lbs., Steam, 3 ft. lift..... 20 to 40 Lbs., and 65 to 100 Lbs..... 50 Ft. Elevation, 40 to 65 Lbs., 1 Ft. Lift... 25 Ft. Elevation, 40 to 65 Lbs., 1 Ft. Lift...	240 235 120 180	500 450 250 375	840 700 420 625	1350 1300 650 950	1950 1850 975 1450	3500 3000 1750 2600	5700 4350 2500 3750	9500 8160 4750 7200	13600 12400 6800 10200	18400 17100 9200 13800
Vertical Lift { 25 to 40 Lbs., and 75 to 100 Lbs., Feet... 40 to 75 Lbs., Feet.....	20 23	22 25	22 25	$21\frac{1}{2}$ 24	$21\frac{1}{2}$ 26	$21\frac{1}{2}$ 26	22 26	20 25	21 25	21 25
Price, each.....	\$8.00	10.00	15.00	20.00	25.00	35.00	40.00	50.00	70.00	95.00

Nos. 7, 8, 9 and 10 are all iron except Jets. These sizes made in all brass to order. Prices on application.

# AUTOMATIC INJECTORS.

477

## THE CHIEF.

Is guaranteed equal to any Automatic Injector made, and because of its simplicity can be sold for less than any other machine.

Number.	Pipe Connections.	Capacity per Hour. 1 to 6 Ft. Lift, 45 to 75 Lbs. Steam Pressure.	Horse Power.	Price.
2½	¾	80	4 to 8	\$16.00
3	1½	120	8 to 15	18.00
3½	1½	165	15 to 20	20.00
4	¾	250	20 to 30	25.00
4½	¾	340	30 to 40	30.00
5	1	475	40 to 60	40.00
5½	1	575	60 to 72	45.00
6	1¼	750	72 to 93	55.00
6½	1¼	920	93 to 120	60.00
7	1½	1,300	120 to 160	75.00
7½	1½	1,740	160 to 220	90.00
8	2	2,270	220 to 290	110.00
8½	2	2,800	290 to 350	125.00




THE CHIEF.

## THE METROPOLITAN.

OPERATED ENTIRELY BY ONE HANDLE.


Number.	Size of Pipe Connections.	Gallons per Hour, 65 Lbs. Pressure.	Horse Power.	Price.
2	¾	40	1 to 4	\$15.50
3	¾	60	4 to 8	16.00
3½	1½	90	8 to 12	18.00
4	1½	120	12 to 16	20.00
5	¾	220	16 to 28	25.00
6	¾	300	28 to 40	30.00
7	1	420	40 to 57	40.00
8	1	540	57 to 72	45.00
9	1¼	720	72 to 93	55.00
10	1¼	900	93 to 120	60.00
11	1½	1,260	120 to 168	75.00
12	1½	1,740	168 to 232	90.00
13	2	2,240	232 to 298	110.00
14	2	2,820	298 to 382	125.00
15	2½	3,480	382 to 466	150.00



THE METROPOLITAN.

# U. S. AUTOMATIC INJECTOR.


The most reliable and economical of all Boiler Feeders for Traction, Portable and Stationary Engines.



Size.	All Pipe Connections.	Capacity. Gallons per Hour.		Horse Power.	Price.
		Max.	Min.		
00	1/4 in.	36	15	1 to 4	\$13.00
0	3/8 "	65	28	3 to 8	14.00
1	3/8 "	90	40	6 to 10	16.00
2	1/2 "	125	60	8 to 15	18.00
3	1/2 "	170	75	15 to 20	20.00
4	3/4 "	250	125	20 to 30	25.00
5	3/4 "	340	140	30 to 40	30.00
6	1 "	475	250	40 to 60	40.00
7	1 "	575	300	60 to 70	45.00
8	1 1/4 "	750	350	70 to 95	55.00
9	1 1/4 "	920	450	85 to 120	60.00
10	1 1/2 "	1350	675	120 to 165	75.00
11	1 1/2 "	1750	850	165 to 230	90.00
12	2 "	2275	1000	230 to 295	110.00
13	2 "	2820	1300	295 to 375	125.00
14	2 "	3400	1700	375 to 460	150.00
15	2 1/2 "	3650	1800	460 to 500	175.00
16	2 1/2 "	4000	1950	500 to 600	200.00

## THE WORLD INJECTOR.

Every Injector guaranteed positive in its action.



Size.	Size of Connections, Suction and Delivery.	Size of Steam Connection.	80 Pounds Steam Pressure.		Price.
			Gallons per Hour.	Horse Power.	
30	1/2 in.	3/8 in.	120	10 to 15	\$20.00
40	3/4 "	1/2 "	220	15 to 25	25.00
50	3/4 "	1/2 "	300	25 to 35	30.00
60	1 "	3/4 "	420	35 to 50	40.00
70	1 "	3/4 "	540	45 to 60	45.00
80	1 1/4 "	1 "	720	60 to 95	55.00
90	1 1/4 "	1 "	900	85 to 120	60.00
100	1 1/2 "	1 1/4 "	1260	120 to 165	75.00
110	1 1/2 "	1 1/4 "	1740	165 to 230	90.00
120	2 "	1 1/2 "	2230	230 to 295	110.00
130	2 "	1 1/2 "	2820	295 to 375	125.00
140	2 "	1 1/2 "	3480	375 to 460	150.00
150	2 1/2 "	2 "	3600	460 to 500	175.00
160	2 1/2 "	2 "	4000	500 to 600	200.00



# THE HANCOCK INSPIRATOR.


479

Number of Inspirator.	SIZE OF CONNECTIONS.		Gallons per Hour, 60 Lbs. Pressure.	Horse Power.	Price.
	Suction and Feed.	Steam.			
7½	⅜	⅜	60	6 to 8	\$16.00
8¾	½	⅜	85	8 to 10	18.00
10	½	⅜	120	10 to 15	20.00
12½	¾	½	220	18 to 25	25.00
15	¾	½	300	25 to 35	30.00
17½	1	¾	430	35 to 50	40.00
20	1	¾	540	45 to 60	45.00
22½	1¼	1	700	60 to 90	55.00
25	1¼	1	900	75 to 100	60.00
30	1½	1¼	1,260	100 to 150	75.00
35	1½	1¼	1,740	140 to 210	90.00
40	2	1½	2,230	190 to 275	110.00
45	2	1½	2,820	240 to 350	125.00
50	2½	2	3,480	290 to 430	150.00




## H-D EJECTOR.

Size.	PIPE CONNECTIONS.		Capacity per Hour.	Price, Each.	Strainers.
	Steam.	Suction and Delivery.			
No. 1, Brass	⅜	½	250 gals.	\$8.00	\$0.50
" 2, "	½	¾	500 "	10.00	.75
" 3, "	¾	1	960 "	15.00	1.00
" 4, "	1	1¼	1,300 "	20.00	1.25
" 5, "	1¼	1½	2,000 "	25.00	1.50
" 6, Iron	1¼	2	4,000 "	35.00	1.75
" 7, "	1½	2½	8,000 "	40.00	.....
" 8, "	2	3	11,000 "	50.00	.....
" 9, "	2½	4	15,000 "	65.00	.....




# SCREW PLATES. MALLEABLE IRON. WITH SOLID DIES.





No.	Threads.	Dimensions of Dies.	Die Plates Complete.	Without Dies.	Extra Dies.	Extra Bushings.	Extra Die Frames.
0	$\frac{1}{8}$ to $\frac{1}{2}$	2 x 2 x $\frac{1}{2}$	\$9.50	\$3.50	\$1.50	\$0.25	.....
1	$\frac{1}{4}$ to 1	$2\frac{1}{2}$ x $2\frac{1}{2}$ x $\frac{3}{4}$	15.00	5.00	2.00	.35	\$0.30
$1\frac{1}{2}$	$\frac{3}{4}$ to $1\frac{1}{4}$	3 x 3 x $\frac{3}{4}$	13.50	6.00	2.50	.45	.40
$1\frac{3}{4}$	1 to $1\frac{1}{2}$	3 x 3 x $\frac{3}{4}$	13.50	6.00	2.50	.45	.40
2	$1\frac{1}{4}$ , $1\frac{1}{2}$ and 2	4 x 4 x $\frac{7}{8}$	20.00	9.50	3.50	.60	.50
3	$2\frac{1}{2}$ and 3	5 x 5 x $1\frac{1}{4}$	43.00	25.00	9.00	1.00	.60
4	$2\frac{1}{2}$ and 3	5 x 5 x $1\frac{1}{4}$	51.00	33.00	9.00	1.00	.60

## MILLER'S REVERSIBLE RATCHET STOCK.



No.	Threads.	Dimensions of Dies.	Die Plates Complete.	Without Dies.	Extra Dies.	Extra Bushings.	Extra Die Frames.
A	$\frac{1}{8}$ to $\frac{3}{4}$	2 x 2 x $\frac{1}{2}$	\$13.00	\$7.50	\$1.10	\$0.20	.....
B	$\frac{1}{4}$ to 1	$2\frac{1}{2}$ x $2\frac{1}{2}$ x $\frac{3}{4}$	15.00	8.50	1.50	.25	\$0.22
C	1 to $1\frac{1}{2}$	3 x 3 x $\frac{3}{4}$	18.50	13.00	1.80	.35	.30
D	$1\frac{1}{4}$ to 2	4 x 4 x $\frac{7}{8}$	20.00	13.50	2.50	.45	.38
E	$2\frac{1}{2}$ and 3	5 x 5 x $1\frac{1}{4}$	43.00	29.00	7.00	.75	.45



Size Number.	Cuts Iron Pipe Sizes.	Price, without Cut-off.	Price, with Cut-off.	Extra Dies, per Single Set.	Extra Lock Nuts.	Extra Cam Plates.
1	$\frac{1}{8}$ , $\frac{1}{4}$ , $\frac{3}{8}$ , $\frac{1}{2}$ , $\frac{3}{4}$	\$13.00	\$16.00	\$1.50	\$0.75	\$1.25
2	$\frac{1}{4}$ , $\frac{3}{8}$ , $\frac{1}{2}$ , $\frac{3}{4}$ , 1, $1\frac{1}{4}$	17.00	20.00	1.75	1.00	1.50
3	1, $1\frac{1}{4}$ , $1\frac{1}{2}$ , 2	22.00	25.00	2.00	1.25	2.00
$3\frac{1}{2}$	$\frac{1}{2}$ , $\frac{3}{4}$ , 1, $1\frac{1}{4}$ , $1\frac{1}{2}$ , 2	25.00	28.00	2.00	1.25	2.00
4	$1\frac{1}{2}$ , 2, $2\frac{1}{2}$ , 3	40.00	45.00	3.50	1.50	2.50
5	$2\frac{1}{2}$ , 3, $3\frac{1}{2}$ , 4	55.00	60.00	4.00	1.75	3.00


## JARECKI SCREW PLATES.

No.....	1	2	3	$3\frac{1}{2}$	4a	4b	5	5a
Cuts and Threads.....	$\frac{1}{4}$ to $\frac{3}{4}$	$\frac{1}{2}$ to $1\frac{1}{4}$	1 to 2	$\frac{1}{2}$ to 2	$1\frac{1}{2}$ to 3	$2\frac{1}{2}$ to 4	$4\frac{1}{2}$ to 6	6 to 8
Each .....	\$14.00	\$16.00	\$20.00	\$22.50 2 Sets. 4.00	\$35.00	\$50.00	\$75.00	\$125.00
Extra Dies, per Set.....	2.00	2.00	2.00	4.00	3.00	3.00	6.00	6.00
Extra Knives, each .....	.40	.40	.40	.40	.50	.50	.60	.60


Nos. 4a and 4b have four handles. Nos. 5 and  $5\frac{1}{2}$  have five handles.



# OSTER PATENT ADJUSTABLE DIE STOCK.



OSTER PATENT RATCHET DIE STOCK.



Number of Tool.....	0	1	1½	2	3	4	4½	5	6
Sizes of Pipe, each Tool will Thread and Cut.....	1/8 1/4-3/8 1/2	1/8 1/4-3/8 1/2-3/4	1/4-3/8 1/2-3/4 1	1/4-3/8 1/2-3/4 1-1/4	1-1/4 1½-2	1½-3/4 1-1/4 1½-2	3/8 1/2-3/4 1-1/4 1½-2	1½-2 2½-3	2½-3 3½-4
Without Cut-Off, each.....	\$12.00	\$13.00	\$14.00	\$17.00	\$22.00	\$25.00	\$28.00	\$40.00	\$55.00
With Cut-Off, each.....	15.00	16.00	17.00	20.00	25.00	28.00	31.00	45.00	60.00

All the above tools have two handles, as illustrated, except Nos. 5 and 6, which have four solid steel handles. The dies can be sharpened on a grindstone, like edged tools. Instantly adjusted, and released from the work without running back over the finished threads.

Number of Tool.....	7	8	9	9½	10
Threads Pipe Sizes.....	1, 1¼, 1½, 2	2½, 3, 3½, 4	3, 3½, 4, 4½	3½, 4, 4½, 5	2½, 3, 3½, 4, 4½, 5
Without Cut-Off, each.....	\$25.00	\$60.00	\$70.00	\$70.00	\$75.00
With Cut-Off, each.....	28.00	65.00	75.00	75.00	80.00

## EXTRA DIES AND CUT-OFF BLADES.


Number of Tool.....	0	1	1½	2	3	4	4½	5	6	7	8	9	9½	10
Per Set (4 Pieces), Right or Left.....	\$1.25	\$1.50	\$1.50	\$1.75	\$2.00	\$2.00	\$2.50	\$3.00	\$3.50	\$2.50	\$3.50	\$4.50	\$4.50	\$4.50
Number of Sets to each Tool.....	3	3	3	3	2	3	4	2	2	2	2	2	2	3
Cut-Off Blades, each.....	\$0.30	\$0.30	\$0.30	\$0.30	\$0.30	\$0.30	\$0.40	\$0.40	\$0.40	\$0.75	\$0.85	1.15	1.15	1.15

## "LITTLE GIANT" SCREW PLATE FOR PIPE.

### A SOLID DIE, YET ADJUSTABLE.

The guides are interchangeable throughout the set, for convenience in cutting nipples. Sure to cut the thread straight. The dies can be re-sharpened. Dies are adjustable to overcome variation of fittings or pipe. Dies and guides can be changed quickly. It is light, yet strong and durable. Dies are held by bevel. No screws to break or get out of order.

### PRICE LIST.



No. 1 Plate. Cutting ¼, ⅜, ½, ¾, 1 inch.....	\$9.00
Price of Stock, when sold alone.....	2.00
Price of Dies, when sold alone, each size.....	1.25
Price of Guides, when sold alone, each size.....	.50
No. 2 Plate. Cutting 1¼, 1½, 2 inches.....	15.00
Price of Stock, when sold alone.....	5.25
Price of Dies, when sold alone.....	3.00
Price of Guides, when sold alone.....	.75

This plate is packed same as shown above. L. H. Dies furnished at same prices. Plates cutting English Pipe Threads furnished at same list prices.

# ARMSTRONG'S ADJUSTABLE STOCK AND DIES.

483

## PRICE LIST.



No.	Threads.	Com- plete.	Stock Only.	Extra Dies.	Extra Bushings.	Extra Wrenches.
No. 1, 4 Dies, Single End.....	$\frac{1}{8}$ to $\frac{1}{2}$	\$9.00	\$3.25	\$1.25	\$0.20	\$0.25
No. 2, 5 Dies, Single End.....	$\frac{1}{4}$ to 1	12.00	4.00	1.50	.25	.25
No. 2½, 4 Dies, Double End.....	$\frac{1}{2}$ to 1¼	12.00	4.50	3.25	.40	.25
No. 3, 3 Dies, Single End.....	1¼ to 2	20.00	7.00	4.00	.50	.50
No. 4, 3 Square Dies.....	1¼ to 2	18.00	7.00	3.00	.50	.....
No. 5, 2 Dies, Double End.....	2½ and 3	40.00	25.00	15.00	1.00	.50
No. 7, 8 Dies, Double End.....	2½ to 4	60.00	30.00	16.00	1.50	.75

Prices for Dies mean per set of two pieces.

NOTE.—No. 4 Stock is a sectional stock. Nos. 2½, 6 and 7 Stocks are fitted with double-ended dies. Nos. 1 and 2 Stocks are packed in cases, as shown. Nos. 6 and 7 have four arms.

## PUMP ROD SCREW PLATES AND TAPS.

No. 12.—2 pair Dies, cutting $\frac{3}{8}$ , 14 threads; $\frac{7}{16}$ , 12 threads, complete, each.....	\$3.00
No. 13.—3 pair Dies, cutting $\frac{3}{8}$ , 14 threads; $\frac{7}{16}$ , 12 threads; $\frac{1}{2}$ , 12 threads, complete, each.....	3.50



PUMP PLATE.



LIGHTNING PUMP STOCK.




LIGHTNING PUMP STOCK.

Double Stock, with two Dies, $\frac{3}{8}$ x 14 and $\frac{7}{16}$ x 12, complete, each.....	\$3.00
Dies only, $\frac{3}{8}$ x 14, each.....	1.00
Dies only, $\frac{7}{16}$ x 12, each.....	1.15

In ordering Dies separately say for double stock.

Single Stock, with one Die, $\frac{3}{8}$ x 14, complete, each.....	\$1.70
" " " " " " $\frac{7}{16}$ x 12, " ".....	1.90
" " " " " " $\frac{1}{2}$ x 12, " ".....	2.20
Dies only, $\frac{3}{8}$ x 14.....	1.15
" " $\frac{7}{16}$ x 12.....	1.30
" " $\frac{1}{2}$ x 12.....	1.50



BIT BRACE TAP.



LIGHTNING DIE WITH HOLDER.



LIGHTNING DIES.

Sizes.	Price Each.	No. of Threads.	Sizes.	Price Each.	No. of Threads.
$\frac{3}{16}$	\$0.50	24	$\frac{3}{8}$	\$0.60	14-16
$\frac{1}{4}$	.50	16-18-20	$\frac{7}{16}$	.70	12-14
$\frac{5}{16}$	.55	16-18	$\frac{1}{2}$	.80	12-13

Dies and Guides, $\frac{3}{8}$ or $\frac{7}{16}$ , price, each.....	\$1.20
Holders for $\frac{3}{8}$ or $\frac{7}{16}$ Dies price, each.....	.75
Guides, price, each.....	.20

All Pump Rod Dies and Taps will be sent  $\frac{1}{32}$  oversize, unless otherwise ordered.



## TAPS, REAMERS AND DRILLS.



PLUG.



TAPER.



BOTTOMING.

## MACHINISTS' HAND TAPS.

				PRICES.		
Size.	Whole Length.	Length Thread.	No. Threads to Inch.	Each.	Per Set of 3 Taps.	
3 Taps to Set— Taper, Plug and Bottoming.	1 1/4.....	2 11/16	1 1/8	16, 18 and 20	\$0.45	\$1.35
	1 5/16.....	2 7/8	1 1/4	16 " 18	.50	1.50
	1 3/8.....	3 1/8	1 1/4	14, 16 " 18	.55	1.65
	1 1/2.....	3 5/8	1 3/8	14 " 16	.60	1.80
	1 5/8.....	4 1/8	1 3/8	12, 13 " 14	.70	2.10
	1 3/4.....	4 1/2	1 7/8	12 " 14	.80	2.40
	1 7/8.....	4 3/4	2	10, 11 " 12	.90	2.70
	2.....	5 1/4	2 1/8	11 " 12	1.05	3.15
	2 1/8.....	5 1/2	2 1/4	10, 11 " 12	1.20	3.60
	2 1/4.....	5 5/8	2 3/8	10 " 10	1.40	4.20
	2 3/8.....	6	2 1/2	9 " 10	1.60	4.80
	2 1/2.....	6 1/8	2 3/4	9 " 9	1.80	5.40
	2 5/8.....	6 1/4	2 7/8	8 " 8	2.00	6.00
	2 3/4.....	6 5/8	3	7 " 8	2.25	6.75
	2 7/8.....	6 7/8	3 1/4	7 " 7	2.60	7.80
	3.....	7 1/4	3 1/2	6 " 6	3.00	9.00
	3 1/8.....	7 5/8	3 3/4	5 " 6	3.50	10.50
	3 1/4.....	8 1/8	3 1/2	5 " 5 1/2	4.20	12.60
	3 3/8.....	8 1/4	4 1/8	5 " 5	5.00	15.00
	3 1/2.....	8 3/4	4 1/4	4 1/2 " 5	5.80	17.40
	3 3/4.....	9 1/8	4 1/2	4 1/2 " 4 1/2	6.70	20.10



PIPE TAP.



PIPE REAMER.

Size, Inches.....	1/8	1/4	3/8	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3
Taps, Right or Left, each	\$1.12	\$1.25	\$1.50	\$1.87	\$2.50	\$3.12	\$3.75	\$4.65	\$6.25	\$10.50	\$15.00
Reamers each.....	1.12	1.25	1.50	1.87	2.50	3.12	3.75	4.65	6.25	10.50	15.00



COMBINED TAP, REAMER AND DRILL.

## COMBINED TAP, REAMER AND DRILL.

Size, Inches..	1/4	3/8	1/2	3/4	1	1 1/4	1 1/2	2
Price, each.....	\$2.50	2.50	3.00	4.50	6.00	7.25	8.50	10.75



FLAT OR PIPE DRILL FOR PACKER RATCHET.

## FLAT DRILLS.

Size, Inches..	3/8	1/2	5/8	3/4	7/8	1	1 1/4	1 1/2	1 3/4	1 1/2
Price each.....	\$0.50	.50	.50	.55	.60	.60	.60	.65	.75	.85

## PIPE DRILLS.

Size, for Iron Pipe, Inches.....	1/4	3/8	1/2	3/4	1	1 1/4	1 1/2	2
Price, each.....	\$0.90	1.00	1.25	1.50	1.75	2.00	2.50	3.00

Flat Drills will be sent actual size, unless Pipe Drills are specified.




# PIPE VISES.

485

## PARKER COMBINATION VISE.

### PRICE LIST.

No.....	1	2	3	4
Holds Pipe from, inches.....	$\frac{1}{8}$ to 2	$\frac{1}{8}$ to 3	$\frac{1}{8}$ to 4	$\frac{1}{8}$ to 6
Weight, pounds .....	41	59	94	141
Each .....	\$16.00	\$20.00	\$28.00	\$35.00
Pipe Jaws, net, each.....	1.75	2.00	2.50	3.00
Plain Jaws, net, each.....	.50	.50	.50	.75




PARKER COMBINATION VISE.

## SMITH COMBINATION VISE.

### PRICE LIST.

No.....	1	2	3	4
Holds Pipe from, inches.....	$\frac{1}{8}$ to 2	$\frac{1}{8}$ to 3	$\frac{1}{8}$ to 4	$\frac{1}{8}$ to 6
Weight, pounds .....	41	59	94	141
Each.....	\$16.00	\$20.00	\$28.00	\$35.00
Pipe Jaws, net, each .....	1.75	2.00	2.50	3.00
Plain Jaws, net, each.....	.50	.50	.50	.75




SMITH COMBINATION VISE.

## BENCH VISE.


### PRICE LIST.

5-inch Jaw, each.....	\$20.00
-----------------------	---------



BENCH VISE.


## PIPE VISES.



NOS. 1 AND 2.


## MALLEABLE IRON HINGED PIPE VISES.

No.....	1	2
Holds Pipe, Inches.....	$\frac{1}{8}$ to 2	$\frac{1}{4}$ to 3
Each .....	\$10.00	\$14.00
Extra Jaws, per Set of Three.....	1.00	1.50




## REED'S SECTIONAL JAW PIPE VISE.

No.....	1	2	3
Holds .....	$\frac{1}{8}$ Pipe to 2-Inch Coupling.	$\frac{1}{8}$ Pipe to 3-Inch Coupling.	$\frac{1}{8}$ Pipe to 4-Inch Coupling.
Each .....	\$10.00	14.00	20.00



## PHOENIX VISE.

No.....	5	10
Holds Pipe, Inches.....	$\frac{1}{8}$ to 2½	$\frac{1}{2}$ to 4
Each .....	\$10.00	18.00



## ENTERPRISE IMPROVED PIPE VISE.

Capacity from $\frac{3}{8}$ Rod to 2-Inch Pipe.	
Each .....	\$4.00

# PIPE TONGS.

487



COMMON TONGS.

Size, Inches .....	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Each.....	\$0.60	.65	.70	.75	.90	1.10	1.30	1.50	1.90	2.50	4.25	5.25	6.25

COMMON TONGS.

BROWN'S ADJUSTABLE TONGS.



BROWN'S ADJUSTABLE TONGS.

No.....	1	$1\frac{1}{2}$	2	3	4	5	6	7
For Pipe, inches.....	$\frac{1}{8}$ to $\frac{3}{4}$	$\frac{3}{8}$ to 1	$\frac{1}{2}$ to $1\frac{1}{4}$	1 to 2	$1\frac{1}{2}$ to 3	$2\frac{1}{2}$ to 4	3 to 5	4 to 7
Each.....	\$1.30	1.65	2.00	3.00	6.00	11.00	25.00	35.00



WITH CABLE CHAIN.



WITH FLAT-LINK CHAIN.

THE VULCAN PATENT DROP-FORGED CHAIN PIPE WRENCHES.

No.....	10	11	12	13	$13\frac{1}{2}$	14	15
For Pipe, inches.....	$\frac{1}{4}$ to $\frac{3}{4}$	$\frac{1}{8}$ to $1\frac{1}{2}$	$\frac{1}{4}$ to $2\frac{1}{2}$	$\frac{3}{4}$ to 4	1 to 6	$1\frac{1}{2}$ to 8	2 to 12
With Cable Chain, each.....	\$2.25	\$3.25	\$4.50	\$6.25	\$7.75	\$9.50	\$16.00
With Flat-Link Chain, each.....	2.50	3.50	5.00	7.00	9.00	11.00	18.00
Extra Cable Chain, each.....	.50	.75	1.00	1.75	2.00	2.50	4.00
Extra Flat-Link Chain, each.....	.75	1.00	1.50	2.50	3.25	4.00	6.00
Extra Jaws, pair.....	1.00	1.75	2.75	4.00	4.75	5.50	7.50
Length Over All, inches.....	$13\frac{3}{4}$	20	27	37	$44\frac{1}{2}$	$50\frac{1}{2}$	$64\frac{1}{2}$

The Vulcan Wrench is sold with either cable or flat-link chain and is the only Wrench adapted for either. When ordering, say which chain is desired. This Wrench is equally efficient on fittings and straight pipe; in corners, against walls, between floors, in ditches or for overhead work. Each fits a range of sizes equal to six pairs of common tongs and will outwear several pairs of any kind. These tools are fully guaranteed and are recommended as the most efficient and economical Chain Pipe Wrenches made. Nothing is spared in their manufacture that adds to their working and wearing qualities. All parts are interchangeable; repairs can always be had.




ROBBINS' CHAIN TONGS.

ROBBINS' CHAIN TONGS.


No.....	2	3	4	5	6	7
Length of Lever, inches.....	27	36	48	60	72	84
Weight, pounds.....	7	12	24	33	50	100
For Pipe, inches.....	1 to 2	$1\frac{1}{4}$ to 4	2 to 6	$2\frac{1}{2}$ to 8	4 to 10	4 to 16
Each.....	\$5.50	6.25	9.00	12.50	16.00	30.00



## PIPE AND BOLT WRENCHES.



ENGINEER'S WRENCH.



COE'S WRENCH.


## ENGINEER'S AND GENUINE COE'S WRENCHES.

Size, Inches .....	6	8	10	12	15	18	21
Engineer's Wrenches, Black, per dozen...	\$9.00	\$10.00	\$12.00	\$14.00	\$24.00	\$30.00	\$36.00
Coe's Wrenches, Black, per dozen.....	9.00	10.00	12.00	14.00	24.00	30.00	36.00

## ALLIGATOR WRENCHES.



No. 1.



No. 2.

Number.....	1	2	3	4	5
Length, Inches.....	5 3/4	10	16	22	27
Takes Pipe.....	1/8 to 3/8	3/8 to 3/4	1/2 to 1 1/4	1 1/4 to 2	2 to 3
Price, each.....	\$0.33	1.00	2.00	3.00	4.50



DOUBLE.

Length.	For Pipe.	For Rod.	Price, each.
10 in.	1/8 to 3/4	1/4 to 1	\$1.50

## "THE ELGIN" ADJUSTABLE WRENCH.




Weight, Ounces.	Length, Inches.	List Price, per doz.
9 1/2	7	\$12.00

Will hold Round Pipe, Nipples, Collars, Rods, Square, Hexagon or Round Nuts.

## BEMIS &amp; CALL COMBINATION WRENCH.

Inches .....	10	12	15
Takes Pipe, Inches.....	1/2 to 1	1/2 to 1 1/2	1/2 to 2
Long Nut, per dozen.....	\$25.25	\$28.50	\$40.50
Short Nut, per dozen.....	23.00	26.00	37.00
Extra Grips, each .....	.25	.30	.35



"ALWAYS READY" WRENCH.

## "ALWAYS READY" WRENCHES.

Number.....	1	2	2 1/2	3
Takes Nut or Round Iron.....	1/4 to 3/4	1/4 to 1 1/4	1/4 to 1 3/4	3/4 to 2
Price, per dozen .....	\$5.00	6.75	10.50	16.00

# PIPE TOOLS.

489

## REED PIPE WRENCH.



Take without adjustment any size of pipe within their capacity. All parts are interchangeable. Facings and jaws are of best tool steel, drop forged.



Numbers Shows Length in Inches.	No. 6.	No. 8.	No. 11.	No. 16.	No. 20.	No. 30.	No. 40.
Takes from.....	0 to ½-in. Pipe.	⅛-in. Wire to ¾-in. Pipe.	¼-in. Pipe to 1-in. Pipe.	⅜-in. Pipe to 1½-in. Pipe.	1-in. Pipe to 2-in. Pipe.	1¼-in. Pipe to 3-in. Pipe.	2-in. Pipe to 4-in. Pipe.
Price, each.....	\$2.00	\$2.00	\$2.25	\$3.00	\$4.00	\$9.00	\$12.00
Extra Jaw including Rod.....	.67	.67	.75	1.00	1.35	3.00	4.00
Facing including Screws and Dowel Pin	.40	.40	.45	.60	.80	1.50	2.00
Spring.....	.10	.10	.10	.15	.20	.40	.50
Price, Nickel-Plated.....	2.50	2.50	3.00	4.00	5.00	12.00	15.00

No. 20 R. R. FOR RAILROAD AND CAR SHOP USE. Length, 20 inches, capacity, ⅜-inch pipe to 1½-inch pipe. Price \$4.00. Price of parts same as No. 20 Standard.

## ENTERPRISE IMPROVED RATCHET DIE STOCK AND REAMER.



### PRICE LIST.

Size.	Threads Pipe.	Reams Pipe.	Bushings.	Will Take Die.	Price Without Dies.
No. 1, Single.....	¼ to 1½	.....	¼ to 1¼	3 x 3	\$10.00
No. 1, Combined.....	¼ to 1½	¼ to 1½	¼ to 1¼	3 x 3	14.00
No. 2, Single.....	½ to 2	.....	½ to 1½	4 x 4	15.00
No. 2, Combined.....	½ to 2	½ to 2	½ to 1½	4 x 4	20.00
Dies 2 x 2 for ¼, ⅜ and ½-inch Pipe, each.....					\$1.50
Dies 3 x 3 for ½, ¾, 1, 1¼ and 1½-inch Pipe, each.....					2.50
Dies 4 x 4 for 1, 1¼, 1½ and 2-inch Pipe, each.....					3.50

## REEDS' SPECIAL WRENCH FOR STEEL ROD.



These Wrenches take without adjustment any size of Rod within their capacity. Capacity ¼ inch to 1 inch Rod. Length, 11 inches. Price, \$2.25.

## NEVER SLIP ROD TONGS.




This tool will hold Pump Rods without slipping.

Adjustable ⅛ to ½ inch, each..... \$1.50

## SHEFFY PIPE WRENCH.

Number.....	0	1	2	3	4
Length, inches.....	7	9	12	15	18
Takes Pipe, inches.....	¼ to ½	½ to ¾	¾ to 1	1 to 1½	1½ to 2
Price, each.....	\$2.00	\$2.00	\$2.25	\$3.00	\$4.00
Handles, each.....	.50	.50	.60	.70	.80
Jaw, each.....	.70	.70	.80	.90	1.00
Dogs, each.....	.60	.60	.70	.80	.90



This Wrench is self-adjusting. Disengages immediately by reversing the handle.

## PIPE WRENCHES.



STILLSON WRENCH. 6 TO 18 INCHES.



STILLSON WRENCH. 18 TO 48 INCHES.



JAW.



FRAME.



HANDLE.



NUT.

## STILLSON WRENCHES.

Length When Open, Inches.....	6	8	10	14	18	24	36	48
Grips, inches.....	$\frac{1}{8}$ wire to $\frac{1}{2}$ pipe	$\frac{1}{2}$ wire to $\frac{3}{4}$ pipe	$\frac{1}{8}$ wire to 1 pipe	$\frac{1}{4}$ wire to $1\frac{1}{2}$ pipe	$\frac{1}{4}$ wire to 2 pipe	$\frac{1}{4}$ wire to $2\frac{1}{2}$ pipe	$\frac{1}{4}$ pipe to $3\frac{1}{2}$ pipe	1 pipe to 5 pipe
Each .....	\$2.00	\$2.00	\$2.25	\$3.00	\$4.00	\$6.00	\$12.00	\$18.00

## REPAIRS FOR STILLSON WRENCHES.

Size, Inches.....	6	8	10	14	18	24	36	48
Jaws, each.....	\$0.67	\$0.67	\$0.75	\$1.00	\$1.33	\$2.00	\$4.00	\$6.00
Frames, each.....	.25	.25	.33	.45	.55	.65	.75	1.00
Handles, each.....	.15	.15	.20	.25	.30			
Nuts, each.....	.20	.20	.27	.35	.42	.50	.65	.80



TRIMO PIPE WRENCH.



REPAIRS FOR TRIMO WRENCH.

## TRIMO WRENCHES.

Length When Open, Inches.....	6	8	10	14	18	24	36	48
Grips, each.....	$\frac{1}{8}$ wire to $\frac{1}{2}$ pipe	$\frac{1}{2}$ wire to $\frac{3}{4}$ pipe	$\frac{1}{8}$ wire to 1 pipe	$\frac{1}{4}$ wire to $1\frac{1}{2}$ pipe	$\frac{1}{4}$ wire to 2 pipe	$\frac{1}{4}$ wire to $2\frac{1}{2}$ pipe	$\frac{1}{4}$ pipe to $3\frac{1}{2}$ pipe	1 pipe to 5 pipe
Each .....	\$2.00	\$2.00	\$2.25	\$3.00	\$4.00	\$6.00	\$12.00	\$18.00

## REPAIRS FOR TRIMO WRENCHES.

Size, Inches.....	6	8	10	14	18	24	36	48
Jaws, each.....	\$0.67	\$0.67	\$0.75	\$1.00	\$1.33	\$2.00	\$4.00	\$6.00
Nuts, each.....	.20	.20	.27	.35	.42	.50	.65	.80
Inserted Jaws, each.....	.25	.25	.33	.50	.55	.65	1.00	1.25
Frames, each.....	.25	.25	.33	.45	.55	.65	.75	1.00



# PIPE CUTTERS.


491



STANWOOD IMPROVED CUTTER.

## STANWOOD IMPROVED PIPE CUTTERS.

Number.....	1	2	3
Cuts Pipe. inches.....	$\frac{1}{4}$ to 1	$\frac{3}{4}$ to 2	2 to 3
Each.....	\$1.50	\$2.25	\$7.00
Extra Blocks and Wheels, each.....	.45	.60	1.25
Extra Wheels, each.....	.12	.18	.25
Pins, each.....	.05	.05	.08



SAUNDERS PIPE CUTTER.

## SAUNDERS PIPE CUTTERS.



BARNES PIPE CUTTER.

Number.....	1	2	3
Cuts Pipe. inches.....	$\frac{1}{4}$ to 1	1 to 2	2 to 3
Each.....	\$3.00	\$4.50	\$14.00
Extra Blocks and Wheels, each.....	1.25	1.75	3.25
Extra Wheels, each.....	.24	.32	.60
Extra Rollers, each.....	.24	.32	.50

## BARNES 3-WHEEL PIPE CUTTERS.

Number.....	1	2	3	4	5	6	7
Cuts Pipe, inches.....	$\frac{1}{4}$ to 1	$\frac{1}{2}$ to 2	$1\frac{1}{2}$ to 3	$2\frac{1}{2}$ to 4	4 to 6	6 to 8	9 to 12
Each.....	\$4.50	\$6.00	\$10.00	\$20.00	\$30.00	\$40.00	\$50.00
Extra Wheels, each.....	.25	.30	.40	.50	.75	.75	.75
Extra Wheel Pins, per dozen.....	1.00	1.00	1.00	2.00	2.00	2.00	2.00

No.  $6\frac{1}{2}$  (special size) cuts pipe 8 to 10 inches. Each, \$45.00.




MILLER'S RATCHET PIPE CUTTER.

## MILLER'S REVERSIBLE RATCHET PIPE CUTTERS.

Number.....	0	1	$1\frac{1}{2}$	2	3
Cuts Pipe inches.....	$\frac{1}{4}$ to $\frac{3}{4}$	$\frac{1}{2}$ to 1	1 to $1\frac{1}{2}$	$1\frac{1}{4}$ to 2	$2\frac{1}{2}$ to 3
Each.....	\$6.75	\$8.50	\$10.00	\$11.00	\$16.00
Extra Wheels, each.....	.12	.18	.18	.25	.40

# PLIERS AND CUTTING NIPPERS.



FLAT NOSE PLIERS.



ROUND NOSE PLIERS.

## FLAT AND ROUND NOSE PLIERS.

Length, inches.....	3 to 4½	5	5½	6	6½	7	8
Stubs', each.....	\$0.55	\$0.60	\$0.70	\$0.90	\$1.20	\$1.40	\$2.00
German, each.....	.35	.40	.50	.55	.70	.85	1.00



## GAS PLIERS




BURNER PLIERS.

## GAS AND BURNER PLIERS.

Length, Inches .....	5	6	7	8	9	10	12	14
Gas Pliers, Polished, per dozen.....			\$7.40	\$8.25	\$9.25	\$10.70	\$13.00	\$17.00
Burner " " " .....	\$4.80	\$6.50	10.00					

Burner Pliers, 5 and 6-inch, one hole; 7-inch, 2 holes.



## ADJUSTABLE PLIERS.

**GAS PLIERS, WIRE CUTTERS, WRENCH AND SCREW-DRIVER COMBINED.**

Length, Inches.....	6	10
Price, Black, per dozen.....	\$13.50	\$18.00
"    Nickel-Plated, per dozen.....	15.00	21.00




## BUTTON'S WIRE CUTTING PLIERS.

Length, Inches.....	4½	6	8	10
Price, each.....	\$0.90	\$1.00	\$1.25	\$2.00

# STANDARD TWIST DRILLS.

493



TWIST DRILL WITH SHANK  $\frac{1}{2}$  INCH DIAMETER.



TWIST DRILL WITH SHANK  $\frac{11}{64}$  INCH DIAMETER.

Shanks are  $2\frac{1}{4}$  inches long ;  $\frac{1}{4}$ -inch and larger Drills are 6 inches long over all.

## SIZES AND PRICES.

Size, Inches.....	$\frac{1}{8}$	$\frac{5}{32}$	$\frac{3}{16}$	$\frac{7}{32}$	$\frac{1}{4}$	$\frac{9}{32}$	$\frac{5}{16}$	$\frac{11}{32}$	$\frac{3}{8}$	$\frac{13}{32}$	$\frac{7}{16}$	$\frac{15}{32}$	$\frac{1}{2}$	$\frac{17}{32}$	$\frac{9}{16}$	$\frac{19}{32}$	$\frac{5}{8}$	$\frac{21}{32}$
Price each, $\frac{1}{2}$ inch Shank.....	\$0.45	\$0.48	\$0.50	\$0.55	\$0.60	\$0.65	\$0.70	\$0.73	\$0.75	\$0.78	\$0.80	\$0.83	\$0.85	\$0.88	\$0.90	\$0.95	\$1.05	\$1.10
Price each, $\frac{11}{64}$ inch Shank.....	.55	.58	.60	.65	.70	.73	.75	.80	.85	.88	.90	.93	.95	.98	1.00	1.03	1.05	1.10
Size, Inches.....	$\frac{1}{16}$	$\frac{3}{32}$	$\frac{3}{4}$	$\frac{3}{32}$	$\frac{1}{8}$	$\frac{27}{32}$	$\frac{7}{8}$	$\frac{3}{2}$	$\frac{15}{16}$	$\frac{31}{32}$	1	$1\frac{1}{16}$	$1\frac{1}{8}$	$1\frac{3}{16}$	$1\frac{1}{4}$	$1\frac{5}{16}$	$1\frac{3}{8}$	$1\frac{1}{2}$
Price each, $\frac{1}{2}$ inch Shank.....	\$1.15	\$1.20	\$1.25	\$1.30	\$1.35	\$1.40	\$1.45	\$1.50	\$1.60	\$1.70	\$1.80	\$2.00	\$2.20	\$2.30	\$2.40	\$2.60	\$2.80	\$3.20
Price each, $\frac{11}{64}$ inch Shank.....	1.15	1.20	1.25	1.30	1.35	1.40	1.45	1.55	1.60	1.70	1.80	2.00	2.20	2.30	2.40	2.60	2.80	3.20

## STRAIGHT SHANK TWIST DRILLS.



## SIZES AND PRICES.

Diameter.....	$\frac{1}{16}$	$\frac{5}{64}$	$\frac{3}{32}$	$\frac{7}{64}$	$\frac{1}{8}$	$\frac{9}{64}$	$\frac{5}{32}$	$\frac{11}{64}$	$\frac{3}{16}$	$\frac{13}{64}$	$\frac{7}{32}$	$\frac{15}{64}$	$\frac{1}{4}$	$\frac{17}{64}$	$\frac{9}{32}$
Length.....	$2\frac{1}{2}$	$2\frac{3}{8}$	$2\frac{1}{4}$	$2\frac{7}{8}$	3	$3\frac{1}{8}$	$3\frac{1}{4}$	$3\frac{3}{8}$	$3\frac{1}{2}$	$3\frac{3}{4}$	$3\frac{3}{4}$	$3\frac{7}{8}$	4	$4\frac{1}{8}$	$4\frac{1}{4}$
Price, each.....	\$0.09	.10	.11	.12	.13	.15	.16	.18	.20	.21	.23	.26	.28	.30	.32
Diameter.....	$\frac{13}{64}$	$\frac{1}{8}$	$\frac{21}{64}$	$\frac{11}{32}$	$\frac{23}{64}$	$\frac{3}{8}$	$\frac{25}{64}$	$\frac{13}{32}$	$\frac{27}{64}$	$\frac{7}{16}$	$\frac{29}{64}$	$\frac{15}{32}$	$\frac{31}{64}$	$\frac{1}{2}$	
Length.....	$4\frac{3}{8}$	$4\frac{1}{2}$	$4\frac{5}{8}$	$4\frac{3}{4}$	$4\frac{7}{8}$	5	$5\frac{1}{8}$	$5\frac{1}{4}$	$5\frac{3}{8}$	$5\frac{1}{2}$	$5\frac{5}{8}$	$5\frac{3}{4}$	$5\frac{7}{8}$	6	.....
Price, each.....	\$0.35	.37	.40	.42	.45	.48	.50	.53	.55	.59	.63	.65	.67	.70	.....

# MACHINISTS' HAMMERS.

BALL PANE. SOLID CAST STEEL.



Numbers .....	00	0	1	2	3	4	5	6
Price, each.....	\$1.00	1.20	1.30	1.50	1.65	1.90	2.05	2.20
Weight, each, pounds.....	1	1.25	1.50	1.87	2.18	2.50	2.75	3.00


Straight and Cross Pane same list as above. Copper Hammers made to order.



## BOILER MAKERS' TOOLS.




PROSSER FLUE EXPANDER.



ROLLER TUBE EXPANDER.

## SIZES AND PRICES.

Size O. D. of Tube, Inches.....	1	1¼	1½	1¾	2	2¼	2½	2¾	3	3¼	3½	4	4½	5	6
Prosser Expander, each.....	\$8.00	\$8.00	\$9.00	\$11.00	\$12.00	\$13.00	\$15.00	\$18.00	\$22.00	\$26.00	\$30.00	\$33.00	\$37.00	\$42.00	\$60.00
Roller Expander, each.....	10.00	10.00	10.00	10.00	10.00	12.00	14.00	16.00	18.00	20.00	23.00	30.00	40.00	50.00	60.00



CONICAL RIVET SET.

Sizes ½, 5⁄8, ¾, 7⁄8 in., each \$1.50



BEADING TOOL.

Price, each.....\$1.00

## CAULKING TOOLS.



FINE POINT.


Price, each..... \$0.80



THICK POINT.

Price, each..... \$0.80


## PACKER RATCHETS.



BOILER MAKERS RACHETS.

## SIZES AND PRICES.

Number.....	1	2
Length of Handle, Inches.....	10	12
Each.....	\$9.00	10.50



SLEEVE RATCHETS.


## SIZES AND PRICES.

Size, Inches.....	¼	¾	½	¾	1	1¼	1½	2
Price, each.....	\$0.30	.30	.35	.45	.60	.75	1.00	1.25

Number.....	1	2	3	4	5
Length of Handles, inches.....	10	12	16	18	20
Each.....	\$10.50	13.50	16.00	18.00	23.00

# BOILER FLUE CLEANERS.

495




## RED JACKET STEAM FLUE BLOWERS.

No. of Blower.....	0	1	2	3	4	5	6
Size of Tubes, O. D.....	1¼ to 1¾	2 to 2¼	2½ to 2¾	3 to 3¼	3½ to 3¾	4 to 4½	5 to 6
Price, each.....	\$5.00	5.00	6.25	7.50	8.75	10.00	12.50

Standard sizes for Horizontal Boilers are furnished with 18 inches of pipe between the conical head and valve. Prices do not include hose or globe valves.



ENGINEERS' FLUE SCRAPER.



DUPLEX FLUE SCRAPER.


Outside Diameter Tube, in.....	1¾	2	2¼	2½	2¾	3
Price, each.....	\$2.00	2.00	2.25	2.50	2.75	3.00
Outside Diameter Tube, in.....	3¼	3½	3¾	4	5	6
Price, each.....	\$3.25	3.50	3.75	4.00	5.00	6.00

Outside Diam. Tube, in.....	1¾	2	2¼	2½	2¾
Price, each.....	\$2.00	2.00	2.25	2.50	2.75
Outside Diam. Tube, in.....	3	3¼	3½	3¾	4
Price, each.....	\$3.00	3.25	3.50	3.75	4.00



SPIRAL FLAT STEEL WIRE BRUSH.

Price, per inch.....\$1.00



EXPANSION BRUSH.

Price, per inch.....\$1.00

Sizes smaller than 2-inch at same list as 2-inch.

## OILERS AND FILLERS



## MALLEABLE IRON OILER.



BRASS OR COPPERIZED STEEL.




CHACE ZINC OILER.

## STEEL AND BRASS OILERS.

Capacity, Ounces.....	3	5	5	5	10	10	14	14	14
Length of Nozzle, Inches.....	2 $\frac{1}{2}$	3	5	9	3	5	3	5	9
Diameter of Dome, Inches.....	2 $\frac{3}{4}$	3 $\frac{3}{8}$	3 $\frac{3}{8}$	3 $\frac{3}{8}$	3 $\frac{3}{4}$	3 $\frac{3}{4}$	4 $\frac{1}{8}$	4 $\frac{1}{8}$	4 $\frac{1}{8}$
Copperized Steel } Number.....	12	13	13A	14	14A	14AA	15	15A	16
Price, per dozen.....	\$4.50	5.50	6.00	6.50	7.50	8.00	9.25	9.75	10.50
Brass } Number.....	120	130	.....	140	.....	.....	150	.....	160
Price, per dozen.....	\$6.50	8.00	.....	9.20	.....	.....	12.00	.....	14.00

## MALLEABLE IRON AND CHACE ZINC OILERS.

Number .....	0	1	2	3	4	5	6
Malleable Iron Oilers, per dozen.....		\$3.60	\$4.00	\$4.40			
Chace Zinc Oilers, with Tin Bottoms, per dozen.....	\$1.25	1.50	2.00	2.25	\$2.75	\$3.50	\$4.50
Chace Zinc Oilers, with Brass Bottoms, per doz.....	1.50	1.75	2.50	3.00	3.50	4.50	5.50



ENGINEERS' SETS.



STEEL OIL FILLER.

No.	Capacity	Diam. Inches.	Height In.	Per Dozen.
19	1 pt.	4 $\frac{1}{8}$	3 $\frac{1}{2}$	\$ 14.00
19A	1 $\frac{1}{2}$ "	4 $\frac{3}{4}$	4	17.00
210	1 qt.	5	5	20.00
211	2 "	6	6	24.00

BRASS OR COPPERIZED STEEL, WITH ROUND TRAY

No. 30.	Copperized Steel, Five Pieces, (including Tray) per Set.....	\$5.00
No. 40.	Copperized Steel, Six " " " " .....	7.00
No. 30.	Brass, Five " " " " .....	6.00
No. 40.	Brass, Six " " " " .....	9.00



COPPER PLATED  
STEEL  
RAILROAD OILERS.


No. 10. 1 pint Railroad Oiler, 3 $\frac{3}{4}$  in. diameter, 5 in. high, 12 in. Nozzle.....per dozen, \$14.00

No. 11. 1 quart Railroad Oiler, 4 $\frac{1}{2}$  in. diameter, 6 in. high, 18 in. Nozzle.....per dozen, \$18.00




# STAR HACK SAWS.

497



- No. 0. Steel Extension Frame, for 10, 11 and 12-in. blades, each, \$1.25  
 No. 1. Steel Extension Frame, for 6, 7, 8 or 9-in. blades, each..... 1.00  
 No. 2. Steel Solid Frame For 8-in. blade only, each..... .80


These frames are all made of steel, and, as seen in the cut, are adjustable, so as to face the blade in four different directions. The Extension Frames will hold different lengths of blades. The Solid Frames only hold the 8-inch blades, this being the length most in use. They all have patent staple-shaped pins to hold the blades in the frame, which are so arranged that they cannot fall out.



No.	For Blades, Inches.	Frame	Price, Each.
6	6 to 12	Steel, Nickel-plated.	\$1.00


## STAR HACK SAW BLADES.

Length, Inches.....	6	7	8	9	10	11	12
Price, per dozen.....	\$0.55	.60	.65	.70	.85	.95	1.05



This No. 4 is a patent cast-iron frame, constructed so as to face in four different directions. The pins which hold the blade are fast in the frames and cannot drop out. It is a very stiff and desirable frame.

- No. 4A. For 8-in. blade, each..... \$0.50  
 No. 4B. For 9-in. blade, each..... .50




No.	For Blades, Inches.	Frame.	Price, Each.
11	6 to 12	Steel, Nickel-plated.	\$1.15

## SUPERIOR HACK SAW BLADES.

Length, Inches.....	6	7	8	9	10	11	12
Price, per dozen.....	\$0.65	.70	.75	.80	.90	.95	1.00

## SPEED INDICATORS.


## DOUBLE SPEED INDICATOR.



Counts up to 1,000, either right or left.

Price, each..... \$1.50

## THE TABOR SPEED INDICATOR.




This Indicator has a good, simple stop-motion whereby the point turns freely until the operator is ready to begin to count. A slight extra pressure then causes the point to engage with worm shaft by a clutch, and the registry begins; the dials continue to revolve until pressure on shaft is relieved. It will make a continuous count up to 4,900 revolutions. Full directions accompany each tool.

Price, each..... \$1.00

## LIGHTNING SPEED INDICATOR.

FOR SHAFTING.




It registers as high as 1,000. Has a rubber tip on the spindle, a silver-plated dial and the face covered with a watch crystal.

Will stand over 10,000 rotations per minute.


Price..... \$2.00

## IMPROVED SPEED INDICATOR.



Price, without Cap..... \$1.00  
Price, with Cap..... 1.25

## COTTON WASTE.



XXXX White.  
XXX White.  
XX White.  
XXXX Colored.  
XXX Colored.  
XX Colored.

In 100 and 500 lb. Bales.

## OIL WASTE CAN.

499



4-Gallon Waste Can, each..... \$1.50

This Can conforms to the requirements of the  
Fire Underwriters' Association.  
Any size made to order.


## CRANE'S STEAMFITTERS' CEMENT.



This Cement will give pipe threads  
proper lubrication to secure tight screwed  
joints, even when pipe is used against  
great pressure.

1 Pound Can, each..... \$0.25

## DIXON'S LUBRICATING GRAPHITE.



In 1, 5 and 10 lb. Cans and 25 lb. Boxes.

Price, per lb.....\$0.25

## GAS FITTER'S CEMENT.


Price per Pound..... \$0.20

## OAKUM.

Price per Bale (50 lbs.)..... \$5.00

## MANILA ROPE.

All sizes carried in stock. Hawser laid Manila Rope for oil and artesian well use. Tallow laid Manila Rope laid up  
in three and four strands. We guarantee our Manila Rope to be made out of pure Manila hemp of the best quality.  
Full coils contain 1,000 feet of rope; half coils, 500 feet.



Size in Diameter, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{7}{8}$	1	1 $\frac{1}{8}$	1 $\frac{1}{4}$	1 $\frac{3}{8}$
Weight of 100 feet, pounds.....	3	4	5 $\frac{1}{2}$	7	8	11	15	17	21
Strength of New Rope, pounds.....	450	750	900	1250	1700	2300	3000	4000	5000

Size in Diameter, inches.....	$\frac{7}{8}$	1	1 $\frac{1}{8}$	1 $\frac{1}{4}$	1 $\frac{3}{8}$	1 $\frac{7}{8}$	1 $\frac{1}{2}$	1 $\frac{5}{8}$	
Weight of 100 feet, pounds.....	25	33	36	42	46	54	62	67	84
Strength of New Rope, pounds.....	5,800	7,000	8,000	9,200	11,000	13,500	15,500	17,000	19,900

Size in Diameter, inches.....	1 $\frac{3}{4}$	2	2 $\frac{1}{4}$	2 $\frac{3}{8}$	2 $\frac{1}{2}$	2 $\frac{3}{4}$	2 $\frac{7}{8}$	3	3 $\frac{1}{2}$
Weight of 100 feet, pounds.....	100	120	142	170	192	217	243	276	350
Strength of New Rope, pounds.....	23,500	29,300	37,000	42,000	48,000	54,000	61,000	67,000	96,000



## STANDARD HOISTING ROPE.

SIX STRANDS, WITH 19 WIRES TO THE STRAND.

\* SWEDISH IRON.

† CAST-STEEL.



Trade Number.	Price in Cents per Foot	Diameter in Inches.	Approximate Circumference in Inches.	Weight per Foot in Pounds.	Approximate Breaking Strain in Tons of 2,000 Lbs.	Allowable Work'g Strain in Tons of 2,000 Lbs.	Minimum Size of Drum or Sheave in Feet.
.....	\$1.70	2 3/4	8 5/8	11.95	114	22.8	16
1	1.40	2 1/2	7 7/8	9.85	95	18.9	15
2	1.17	2 1/4	7 1/8	8.00	78	15.60	13
3	.92	2	6 1/4	6.30	62	12.40	12
4	.80	1 3/4	5 1/4	4.85	48	9.60	10
5	.63	1 1/2	5	4.15	42	8.40	8 1/2
5 1/2	.57	1 1/4	4 3/4	3.55	36	7.20	7 1/2
6	.48	1 1/8	4 1/4	3.00	31	6.20	7
7	.40	1 1/4	4	2.45	25	5.00	6 1/2
8	.33	1 1/8	3 1/2	2.00	21	4.20	6
9	.26	1	3	1.58	17	3.40	5 1/4
10	.20	7/8	2 3/4	1.20	13	2.60	4 1/2
10 1/4	.16	5/8	2 1/4	.89	9.7	1.94	4
10 1/2	.12	3/4	2	.62	6.8	1.36	3 1/2
10 3/4	.10	1 1/8	1 3/4	.50	5.5	1.10	2 3/4
10 a	.08	1 1/4	1 1/2	.39	4.4	.88	2 1/4
10 b	.07 1/2	1 1/2	1 1/4	.30	3.4	.68	2
10 c	.07	1 3/8	1 1/8	.22	2.5	.50	1 1/2
10 d	.06 3/4	1 1/2	1	.15	1.7	.34	1
	.06 1/2	3/4	3/4	.10	1.2	.24	3/4

\* NOTE.—Siemens-Martin Steel Rope, same price as Iron Rope. † When the Iron or Steel Rope named above is Galvanized or Tinned, add 10 per cent. to list price per foot. When made with Wire center, add 10 per cent. to list price per foot.

## TRANSMISSION AND STANDARD ROPE.

SIX STRANDS, WITH 7 WIRES TO THE STRAND.

\* SWEDISH IRON.

† CAST-STEEL.



Trade Number.	Price in Cents per Foot	Diameter in Inches.	Approximate Circumference in Inches.	Weight per Foot in Pounds.	Approximate Breaking Strain in Tons of 2,000 Lbs.	Allowable Work'g Strain in Tons of 2,000 Lbs.	Minimum Size of Drum or Sheave in Feet.
11	\$0.51	1 1/2	4 3/4	3.55	34	6.80	13
12	.43	1 1/4	4 1/4	3.00	29	5.80	12
13	.36	1 1/4	4	2.45	24	4.80	10 3/4
14	.29	1 1/8	3 3/4	2.00	20	4.00	10
15	.23	1	3	1.58	16	3.20	8 1/2
16	.17 1/2	7/8	2 3/4	1.20	12	2.40	7 1/2
17	.14	5/8	2 1/4	.89	9.3	1.86	6 3/4
18	.12	1 1/8	2 1/4	.75	7.9	1.58	6
19	.10	1 1/4	2	.62	6.6	1.32	5 1/4
20	.08	1 1/8	1 3/4	.50	5.3	1.06	4 1/2
21	.06 1/2	1 1/2	1 1/2	.39	4.2	.84	4
22	.05 1/2	1 1/4	1 1/4	.30	3.3	.66	3 1/4
23	.04	1 1/8	1 1/8	.22	2.4	.48	3
24	.03 3/4	1 1/4	1	.15	1.7	.34	2 1/2
25	.03 1/4	3/4	3/4	.125	1.4	.28	2 1/4

\* NOTE.—Siemens-Martin Steel Rope, same price as Iron Rope. † When the Iron or Steel Rope named above is Galvanized or Tinned, add 10 per cent. to list price per foot. When made with Wire center, add 10 per cent. to list price per foot.




CLASP CLOSED.

# WOOD SNATCH BLOCKS, ETC.

501

## IMPROVED IRON-STRAPPED SELF-LOCKING LINK SNATCH BLOCK.

SWIVEL HOOK AND CROSS-BOLTED.



CLASP OPENED.

### SIZES AND PRICES.

Size Sheave.	Diameter Rope.	Size Shell.	Iron Bushed, Each.	Self-Adjusting 5-Roller Bushed, Each	Self-Lubricating Metaline-Bushed, Ea.
3 X 1 1/8 X 1 1/8	7/8 inch	6 inches	\$4.00	\$4.65	\$5.25
3 1/2 X 1 1/8 X 1 1/8	1 1/8 "	7 "	4.75	5.50	6.00
4 1/2 X 1 3/8 X 1 3/8	1 1/4 "	8 "	5.75	6.60	7.25
5 X 1 3/8 X 1 3/8	1 1/2 "	9 "	6.75	7.75	8.50
5 3/4 X 1 7/8 X 1 7/8	1 3/4 "	10 "	8.50	10.00	11.00
6 3/4 X 2 1/8 X 2 1/8	1 1/2 "	12 "	10.00	11.50	13.00
8 X 2 1/4 X 2 1/4	1 3/4 "	14 "	13.00	15.00	16.50
9 X 2 3/8 X 2 3/8	2 "	16 "	17.00	20.00	22.00
10 X 3 X 3	2 1/4 "	18 "	25.00	28.50	31.00
11 X 3 1/2 X 3 1/2	2 1/2 "	20 "	38.00	43.00	46.00
11 3/4 X 4 1/4 X 4 1/4	3 "	22 "	55.00	63.00	68.00
12 1/2 X 4 1/2 X 4 1/2	3 1/2 "	24 "	70.00	78.00	86.00

## IMPROVED MALLEABLE IRON BLOCKS.

LIGHT, STRONG AND DURABLE.

### SIZES AND PRICES.

DIMENSIONS.		IRON BUSHED.			SELF-ADJUSTING ROLLER BUSHED.			SELF-LUBRICATING METALINE BUSHED.		
Length, Shell.	Diameter Rope.	Single, Each.	Double, Each.	Triple, Each.	Single, Each.	Double, Each.	Triple, Each.	Single, Each.	Double, Each.	Triple, Each.
3 inch	3/8 inch	\$0.70	\$1.30	\$1.75	\$1.10	\$2.00	\$2.90			
3 1/2 "	3/8 "	.75	1.45	2.00	1.15	2.20	3.15	\$1.50	\$2.90	\$4.15
4 "	1/2 "	.85	1.60	2.15	1.20	2.25	3.25			
5 "	5/8 "	.90	1.75	2.25	1.25	2.35	3.50	1.75	3.35	4.75
6 "	3/4 "	1.10	2.00	2.90	1.50	2.85	4.40	2.20	4.00	5.80
7 "	7/8 "	1.30	2.40	3.50	1.70	3.35	5.00	2.50	4.50	6.70
8 "	1 "	1.65	2.85	4.25	2.25	4.15	6.00	3.25	5.70	8.50
9 "	1 1/8 "	1.85	3.40	4.75	2.50	4.70	7.25	3.70	6.75	10.00
10 "	1 1/8 "	2.75	4.50	6.25	3.50	6.00	8.50	4.75	8.50	12.50
11 "	1 1/4 "	4.45	7.50	10.65	5.30	9.20	13.20	6.75	12.50	18.50
12 "	1 1/4 "	4.45	7.00	10.65	5.30	9.20	13.20	6.75	12.50	18.50
13 "	1 1/4 "	7.00	10.50	15.00	8.15	12.80	18.45	9.75	17.00	25.00
14 "	1 1/2 "	7.00	10.50	15.00	8.15	12.80	18.45	9.75	17.00	25.00
15 "	1 1/2 "	8.00	13.00	18.00	9.25	15.50	21.75	11.00	19.50	28.00
16 "	1 3/4 "	10.00	15.00	22.00	11.50	18.00	26.50			





# REGULAR INSIDE IRON STRAPPED BLOCKS.

WITH HARCOURT'S PATENT STRAPS, LIGNUM-VITÆ OR  
IRON SHEAVES, AND LOOSE HOOKS.



LOOSE HOOK AND BECKET.



LOOSE HOOK.



LOOSE HOOK AND BECKET.

DIMENSIONS.				IRON BUSHED.			SELF-ADJUSTING ROLLER BUSHED.		
Size Sheave.	For Diam. Rope.	Size.	Mortise.	Single, Each.	Double, Each.	Triple, Each.	Single, Each.	Double, Each.	Triple, Each.
1 3/4 x 1 1/2 x 3/8	3/8	3	9/16	\$0.70	\$1.30	\$1.75	\$1.10	\$2.00	\$2.90
2 x 1 1/2 x 3/8	3/8	3 1/2	1 1/8	.75	1.45	2.00	1.15	2.20	3.15
2 1/4 x 1 1/2 x 3/8	1/2	4	1 1/8	.85	1.60	2.15	1.20	2.25	3.25
3 x 1 1/2 x 3/8	5/8	5	1 1/8	.90	1.75	2.25	1.25	2.35	3.50
3 1/2 x 1 1/2 x 3/8	3/4	6	1 1/2	1.10	2.00	2.90	1.50	2.85	4.40
4 1/4 x 1 1/2 x 3/8	7/8	7	1 1/8	1.30	2.40	3.50	1.70	3.35	5.00
4 3/4 x 1 1/2 x 3/8	1	8	1 1/4	1.65	2.85	4.25	2.25	4.15	6.00
5 1/2 x 1 1/2 x 3/8	1	9	1 1/4	1.85	3.40	4.75	2.50	4.70	7.25
6 1/4 x 1 1/2 x 3/8	1 1/8	10	1 3/8	2.75	4.50	6.25	3.50	6.00	8.50
7 1/4 x 1 1/2 x 3/8	1 1/8	11	1 3/8	4.45	7.50	10.65	5.30	9.20	13.20
8 x 1 1/2 x 3/8	1 1/4	12	1 1/2						
9 x 1 1/2 x 3/8	1 1/4	13	1 1/2	7.00	10.50	15.00	8.15	12.80	18.45
9 1/2 x 1 1/2 x 3/8	1 3/8	14	1 3/4						
10 x 1 1/2 x 3/8	1 1/2	15	1 3/4	8.00	13.00	18.00	9.25	15.50	21.75
11 x 1 1/2 x 3/8	1 5/8	16	1 7/8	10.00	15.00	22.00	11.50	18.00	26.50

## HARCOURT'S PATENT HEAVY TACKLE BLOCKS.

Thick mortise, double-cross bolted, with extra heavy straps and hooks. Loose hooks, rings or shackles, lignum-vitæ or iron sheaves.

DIMENSIONS.			IRON BUSHED.			IMP. SELF-ADJUSTING FIVE ROLL STEEL ROLLER BUSHED.		
Size Sheave.	For Diameter Rope.	Size Shell.	Single, Each.	Double, Each.	Triple, Each.	Single, Each.	Double, Each.	Triple, Each.
4 1/4 x 1 1/8 x 1/2	1	7 inches	\$2.25	\$4.00	\$5.50	\$3.00	\$5.50	\$7.75
4 3/4 x 1 3/8 x 5/8	1 1/8	8 "	2.75	4.50	6.30	3.50	6.00	8.55
5 1/8 x 1 3/8 x 5/8	1 1/8	9 "	3.15	5.25	7.25	4.00	6.95	9.80
6 1/4 x 1 1/2 x 3/4	1 1/2	10 "	4.00	6.50	8.50	5.25	9.00	12.25
7 x 1 1/2 x 3/4	1 1/4	11 "	5.25	8.50	12.50	6.50	11.00	16.25
8 x 1 1/2 x 3/4	1 1/2	12 "						
9 x 1 3/4 x 7/8	1 3/4	13 "	8.00	13.00	17.00	9.75	16.50	22.25
9 1/2 x 1 7/8 x 1	1 3/4	14 "						
10 x 1 7/8 x 1	1 5/8	15 "	9.00	15.00	20.00	11.00	19.00	26.00
11 x 2 1/8 x 1	2	16 "	11.50	18.00	28.00	14.00	23.00	35.50

Our thick Mortise Blocks are especially well adapted for railroad, mining, bridge building and contractors' work. Our improved self-adjusting five-roll steel roller-bushed Blocks will give twice the purchase over the common bushed, on account of their superiority and ease in hoisting, and are the strongest roller-bushed Blocks in the world.




# COMPLETE REVISED PRICE LIST OF WOOD SPLIT PULLEYS. 503


## DOUBLE BELT CAPACITY.

(March 1, 1897.)

Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	
3	2	\$1.80	6	5	\$2.55	9	9	\$4.00	12	3	\$3.15	14	8	\$5.10	
	3	1.90		6	2.75		10	4.30		4	3.40		9	5.55	
	4	2.00		7	3.00		11	4.65		5	3.65		10	6.00	
	5	2.10		8	3.25		12	5.00		6	3.90		11	6.45	
	6	2.25		9	3.50		13	5.40		7	4.20		12	6.90	
	7	2.40		10	3.75		14	5.80		8	4.55		13	7.40	
	8	2.60		11	4.00		15	6.20		9	4.90		14	7.90	
	9	2.85		12	4.30		16	6.60		10	5.30		15	8.50	
	10	3.10		13	4.65		17	7.00		11	5.70		16	9.10	
	11	3.35		14	5.00		18	7.50		12	6.10		17	9.70	
	12	3.60		15	5.35		19	8.00		13	6.50		18	10.40	
	13	3.85		16	5.70		20	8.50		14	6.90		19	11.10	
	14	4.10								15	7.40		20	11.80	
	15	4.40								16	7.90		21	12.60	
	16	4.75								17	8.50		22	13.40	
			7	2	2.20					18	9.10		23	14.20	
				3	2.30		10	3	2.80	19	9.70		24	15.00	
				4	2.45			4	3.00	20	10.40				
4	2	1.90		5	2.65			5	3.25	21	11.10	15	3	3.60	
	3	2.00		6	2.85			6	3.50	22	11.80		4	3.90	
	4	2.10		7	3.10			7	3.75	23	12.60		5	4.25	
	5	2.20		8	3.35			8	4.00	24	13.40		6	4.60	
	6	2.40		9	3.60			9	4.30				7	5.00	
	7	2.60		10	3.85			10	4.65				8	5.45	
	8	2.85		11	4.15			11	5.00				9	5.90	
	9	3.10		12	4.50			12	5.40				10	6.35	
	10	3.35		13	4.85			13	5.80	13	3	3.30	11	6.80	
	11	3.60		14	5.20			14	6.20		4	3.55	12	7.30	
	12	3.85		15	5.55			15	6.60		5	3.80	13	7.80	
	13	4.10		16	5.90			16	7.00		6	4.10	14	8.40	
	14	4.40						17	7.50		7	4.45	15	9.00	
	15	4.75						18	8.00		8	4.80	16	9.60	
	16	5.10						19	8.60		9	5.20	17	10.30	
			8	2	2.35			20	9.20		10	5.60	18	11.00	
				3	2.45						11	6.00	19	11.80	
				4	2.60						12	6.40	20	12.60	
5	2	2.00		5	2.80						13	6.80	21	13.40	
	3	2.10		6	3.00						14	7.30	22	14.20	
	4	2.20		7	3.25		11	3	3.00		15	7.80	23	15.10	
	5	2.40		8	3.50			4	3.25		16	8.40	24	16.00	
	6	2.60		9	3.75			5	3.50		17	9.00	25	16.90	
	7	2.85		10	4.00			6	3.75		18	9.60	26	17.80	
	8	3.10		11	4.30			7	4.00		19	10.30	28	19.80	
	9	3.35		12	4.65			8	4.30		20	11.00	30	21.80	
	10	3.60		13	5.00			9	4.65		21	11.70			
	11	3.85		14	5.40			10	5.00		22	12.50			
	12	4.10		15	5.80			11	5.40		23	13.30			
	13	4.40		16	6.20			12	5.80		24	14.10			
	14	4.75						13	6.20				16	3	3.80
	15	5.10						14	6.60					4	4.15
	16	5.45						15	7.00					5	4.50
			9	3	2.60			16	7.50	14	3	3.45		6	5.00
				4	2.80			17	8.00		4	3.70		7	5.50
				5	3.00			18	8.60		5	4.00		8	6.00
6	2	2.10		6	3.25			19	9.20		6	4.35		9	6.50
	3	2.20		7	3.50			20	9.80		7	4.70		10	7.00
	4	2.35		8	3.75									11	7.50



## WOOD BUSHINGS.



## PRICE LIST OF EXTRA WOOD BUSHING.

30 cents per foot (4 pieces), subject to same discount as Pulleys.

All stock Pulleys are bored for 3½-inch shaft.

Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.
16	12	\$8.00	18	12	\$9.00	20	12	\$10.40	22	12	\$11.70	24	12	\$13.00	26	3	\$6.20
	13	8.50		13	9.60		13	11.20		13	12.60		13	14.10		4	7.00
	14	9.00		14	10.30		14	12.00		14	13.50		14	15.20		5	7.80
	15	9.60		15	11.10		15	12.90		15	14.50		15	16.50		6	8.60
	16	10.30		16	11.90		16	13.80		16	15.50		16	17.70		7	9.50
	17	11.00		17	12.70		17	14.70		17	16.60		17	18.90		8	10.50
	18	11.80		18	13.50		18	15.60		18	17.70		18	20.20		9	11.50
	19	12.60		19	14.30		19	16.50		19	18.80		19	21.50		10	12.60
	20	13.40		20	15.20		20	17.50		20	20.00		20	22.80		11	13.75
	21	14.20		21	16.10		21	18.50		21	21.20		21	24.10		12	15.00
	22	15.10		22	17.00		22	19.60		22	22.40		22	25.40		13	16.30
	23	16.00		23	17.90		23	20.70		23	23.60		23	26.80		14	17.60
	24	16.90		24	19.00		24	21.80		24	24.80		24	28.20		15	19.00
	25	17.80		25	20.10		25	22.90		25	26.00		25	29.60		16	20.40
	26	18.80		26	21.20		26	24.00		26	27.20		26	31.00		17	21.80
	28	20.80		28	23.50		28	26.30		28	29.70		28	34.00		18	23.30
	30	23.00		30	26.00		30	29.00		30	32.50		30	38.50		19	24.80
													32	45.00		20	26.30
17	3	4.00	19	3	4.40	21	3	4.80	23	3	5.20		34	50.00		21	27.90
	4	4.40		4	4.90		4	5.40		4	5.80		36	56.00		22	29.50
	5	4.90		5	5.40		5	6.00		5	6.50		38	63.00		23	31.10
	6	5.40		6	5.90		6	6.60		6	7.20		40	70.00		24	32.70
	7	5.90		7	6.50		7	7.30		7	8.00					25	34.30
	8	6.40		8	7.10		8	8.00		8	8.80	25	3	5.90		26	35.90
	9	6.90		9	7.70		9	8.70		9	9.70		4	6.60		28	39.10
	10	7.40		10	8.30		10	9.40		10	10.60		5	7.30		30	42.50
	11	7.90		11	8.90		11	10.20		11	11.50		6	8.10		32	48.00
	12	8.40		12	9.50		12	11.00		12	12.50		7	9.00		34	54.00
	13	8.90		13	10.20		13	11.80		13	13.60		8	10.00		36	60.00
	14	9.50		14	11.00		14	12.70		14	14.70		9	11.00		38	67.00
	15	10.20		15	11.80		15	13.60		15	15.80		10	12.00		40	75.00
	16	11.00		16	12.60		16	14.50		16	17.00		11	13.00			
	17	11.80		17	13.40		17	15.50		17	18.20		12	14.00	27	3	6.60
	18	12.60		18	14.30		18	16.50		18	19.40		13	15.20		4	7.40
	19	13.40		19	15.20		19	17.50		19	20.60		14	16.40		5	8.20
	20	14.20		20	16.10		20	18.60		20	21.80		15	17.70		6	9.00
	21	15.10		21	17.00		21	19.70		21	23.00		16	19.00		7	10.00
	22	16.00		22	17.90		22	20.80		22	24.30		17	20.40		8	11.10
	23	16.90		23	19.00		23	22.00		23	25.60		18	21.80		9	12.20
	24	17.80		24	20.10		24	23.20		24	26.90		19	23.20		10	13.40
	25	18.80		25	21.20		25	24.40		25	28.20		20	24.60		11	14.60
	26	19.90		26	22.30		26	25.60		26	29.60		21	26.00		12	15.80
	28	22.10		28	24.80		28	28.00		28	32.50		22	27.50		13	17.10
	30	24.50		30	27.50		30	30.70		30	36.00		23	29.00		14	18.50
													24	30.50		15	20.00
18	3	4.20	20	3	4.60	22	3	5.00	24	3	5.50		25	32.00		16	21.50
	4	4.70		4	5.20		4	5.60		4	6.20		26	33.50		17	23.00
	5	5.20		5	5.80		5	6.30		5	7.00		28	36.50		18	24.50
	6	5.70		6	6.40		6	7.00		6	7.80		30	41.00		19	26.10
	7	6.20		7	7.00		7	7.70		7	8.60		32	46.00		20	27.70
	8	6.70		8	7.60		8	8.40		8	9.40		34	52.00		21	29.30
	9	7.20		9	8.30		9	9.20		9	10.30		36	58.00		22	30.90
	10	7.80		10	9.00		10	10.00		10	11.20		38	65.00		23	32.50
	11	8.40		11	9.70		11	10.80		11	12.10		40	72.00		24	34.10

### PRICE LIST—WOOD SPLIT PULLEYS.—Continued.

505

Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	
27	25	\$35.70	29	15	\$22.10	31	5	\$10.00	32	28	\$51.00	34	17	\$31.70	36	7	\$16.10	
	26	37.30		16	23.70		6	11.10		30	55.00		18	33.60		8	17.70	
	28	41.00		17	25.30		7	12.35		32	61.00		19	35.70		9	19.30	
	30	45.00		18	27.00		8	13.60		34	67.00		20	37.80		10	21.00	
	32	50.00		19	28.70		9	15.00		36	74.00		21	40.00		11	22.00	
	34	56.00		20	30.40		10	16.50		38	82.00		22	42.20		12	24.00	
	36	62.00		21	32.10		11	18.00		40	91.00		23	44.40		13	26.00	
	38	70.00		22	33.80		12	19.60					24	46.80		14	28.00	
	40	78.00		23	35.50		13	21.20		33	3		9.00	25		49.20	15	30.00
				24	37.20		14	22.80			4		10.00	26		51.60	16	32.00
28	3	7.00	25	38.90	15	24.60	5	11.15	28		56.40	17	34.00					
	4	7.80	26	40.60	16	26.40	6	12.35	30		61.40	18	36.00					
	5	8.60	28	44.50	17	28.20	7	13.65	32		68.20	19	38.00					
	6	9.50	30	49.00	18	30.00	8	15.00	34		75.00	20	40.00					
	7	10.50	32	55.00	19	31.80	9	16.45	36		82.60	21	43.00					
	8	11.60	34	61.00	20	33.60	10	18.00	38		91.00	22	45.00					
	9	12.80	36	68.00	21	35.40	11	19.65	40		100.00	23	47.00					
	10	14.00	38	76.00	22	37.20	12	21.40				24	50.00					
	11	15.20	40	84.00	23	39.00	13	23.10	35	3	9.85	25	53.00					
	12	16.50			24	40.80	14	24.95		4	11.15	26	56.00					
13	17.90	30	3	7.70	25	42.60	15	26.75		5	12.45	28	61.00					
14	19.40		4	8.60	26	44.50	16	28.60		6	13.85	30	67.00					
15	20.90		5	9.50	28	48.75	17	30.40		7	15.25	32	75.00					
16	22.40		6	10.60	30	53.00	18	32.30		8	16.80	34	83.00					
17	24.00		7	11.80	32	59.00	19	34.35		9	18.35	36	91.00					
18	25.60		8	13.00	34	65.00	20	36.40		10	20.00	38	100.00					
19	27.20		9	14.30	36	72.00	21	38.50		11	21.70	40	110.00					
20	28.80		10	15.60	38	80.00	22	40.60		12	23.50							
21	30.40		11	17.00	40	88.00	23	42.70	13	25.30	38	4	12.80					
22	32.00		12	18.50			24	44.90	14	27.20		5	14.40					
23	33.60	13	20.00	32	3	8.50	25	47.10	15	29.10		6	16.00					
24	35.30	14	21.50		4	9.50	26	49.30	16	31.00		7	17.70					
25	37.00	15	23.25		5	10.50	28	53.70	17	32.90		8	19.50					
26	38.70	16	25.00		6	11.60	30	58.20	18	34.90		9	21.20					
28	42.50	17	26.75		7	12.85	32	64.60	19	37.00		10	23.00					
30	47.50	18	28.50		8	14.10	34	71.00	20	39.20		11	24.50					
32	53.00	19	30.25		9	15.50	36	78.30	21	41.50		12	26.00					
34	59.00	20	32.00		10	17.00	38	86.50	22	43.80		13	28.00					
36	65.00	21	33.75		11	18.60	40	95.70	23	46.10	14	30.00						
38	73.00	22	35.50		12	20.30			24	48.70	15	32.00						
40	81.00	23	37.25	13	22.00	34	3	9.40	25	51.30	16	34.00						
29	3	7.30	24	39.00	14		23.80	4	10.60	26	53.90	17	36.00					
	4	8.20	25	40.75	15		25.60	5	11.80	28	59.10	18	38.00					
	5	9.10	26	42.50	16		27.40	6	13.10	30	64.60	19	41.00					
	6	10.00	28	46.50	17		29.20	7	14.45	32	71.80	20	43.00					
	7	11.10	30	51.00	18		31.00	8	15.90	34	79.00	21	46.00					
	8	12.30	32	57.00	19		33.00	9	17.40	36	86.90	22	48.00					
	9	13.50	34	63.00	20		35.00	10	19.00	38	95.50	23	51.00					
	10	14.75	36	70.00	21		37.00	11	20.70	40	105.00	24	54.00					
	11	16.00	38	78.00	22		39.00	12	22.50			25	57.00					
	12	17.50	40	86.00	23	41.00	13	24.20	36	3	10.30	26	60.00					
13	19.00	31	3	8.00	24	43.00	14	26.10		4	11.70	28	67.00					
14	20.50		4	9.00	25	45.00	15	27.90		5	13.10	30	74.00					
					26	47.00	16	29.80		6	14.60	32	82.00					



Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.
38	34	\$91.00	42	18	\$44.00	44	48	\$201.00	48	21	\$65.00	52	7	\$32.00	54	28	\$118.00
	36	99.00		19	46.00					22	70.00		8	34.00		30	130.00
	38	109.00		20	49.00	46	4	19.00		23	74.00		9	36.00		32	142.00
	40	119.00		21	52.00		5	21.00		24	78.00		10	38.50		34	155.00
				22	55.00		6	23.00		25	83.00		11	41.00		36	168.00
40	4	13.90		23	58.00		7	25.00		26	88.00		12	43.50		38	181.00
	5	15.70		24	62.00		8	27.00		28	98.00		13	46.00		40	194.00
	6	17.50		25	66.00		9	29.00		30	109.00		14	49.00		42	211.00
	7	19.30		26	70.00		10	31.00		32	120.00		15	52.00		44	228.00
	8	21.25		28	78.00		11	33.00		34	131.00		16	55.00		46	247.00
	9	23.10		30	87.00		12	36.00		36	142.00		17	58.00		48	266.00
	10	25.00		32	97.00		13	38.00		38	154.00		18	62.00			
	11	26.50		34	107.00		14	40.00		40	165.00		19	66.00	56	6	35.00
	12	28.00		36	117.00		15	43.00		42	180.00		20	70.00		7	37.00
	13	30.00		38	127.00		16	45.00		44	195.00		21	75.00		8	39.00
	14	32.00		40	138.00		17	48.00		46	211.00		22	80.00		9	41.00
	15	34.00		42	150.00		18	51.00		48	227.00		23	85.00		10	43.00
	16	36.00		44	162.00		19	54.00					24	90.00		11	46.00
	17	39.00		46	175.00		20	57.00	50	5	25.00		25	95.00		12	49.00
	18	41.00		48	188.00		21	61.00		6	27.00		26	100.00		13	52.00
	19	43.00					22	65.00		7	29.00		28	112.00		14	55.00
	20	46.00	44	4	17.00		23	68.00		8	31.00		30	124.00		15	59.00
	21	49.00		5	19.00		24	73.00		9	33.70		32	136.00		16	63.00
	22	51.00		6	21.00		25	77.00		10	36.20		34	148.00		17	66.00
	23	54.00		7	23.00		26	82.00		11	38.60		36	160.00		18	71.00
	24	58.00		8	25.00		28	91.00		12	41.00		38	172.00		19	75.00
	25	61.00		9	27.00		30	101.00		13	43.00		40	184.00		20	80.00
	26	65.00		10	29.00		32	112.00		14	46.00		42	200.00		21	85.00
	28	72.00		11	31.00		34	123.00		15	49.00		44	217.00		22	90.00
	30	80.00		12	33.00		36	134.00		16	51.00		46	235.00		23	95.00
	32	89.00		13	35.00		38	145.00		17	54.00		48	253.00		24	101.00
	34	99.00		14	37.00		40	156.00		18	58.00					25	106.00
	36	108.00		15	40.00		42	170.00		19	62.00	54	5	30.00		26	112.00
	38	118.00		16	42.00		44	184.00		20	65.00		6	32.00		28	124.00
	40	128.00		17	44.00		46	199.00		21	70.00		7	34.00		30	136.00
	42	139.00		18	47.00		48	214.00		22	75.00		8	36.00		32	149.00
	44	151.00		19	50.00					23	79.00		9	38.50		34	163.00
	46	163.00		20	53.00	48	4	21.00		24	84.00		10	41.20		36	176.00
	48	175.00		21	56.00		5	23.00		25	89.00		11	43.80		38	190.00
				22	60.00		6	25.00		26	94.00		12	46.00		40	204.00
42	4	15.00		23	63.00		7	27.00		28	105.00		13	49.00		42	222.00
	5	17.00		24	67.00		8	29.00		30	116.00		14	52.00		44	240.00
	6	19.00		25	71.00		9	31.50		32	128.00		15	55.00		46	259.00
	7	21.00		26	76.00		10	33.90		34	139.00		16	59.00		48	279.00
	8	23.00		28	84.00		11	36.20		36	151.00		17	62.00			
	9	25.00		30	94.00		12	38.50		38	163.00		18	66.00	58	6	38.00
	10	27.00		32	104.00		13	40.00		40	174.00		19	70.00		7	40.00
	11	29.00		34	115.00		14	43.00		42	191.00		20	75.00		8	42.00
	12	31.00		36	125.00		15	46.00		44	207.00		21	80.00		9	44.00
	13	33.00		38	136.00		16	48.00		46	223.00		22	85.00		10	46.00
	14	35.00		40	147.00		17	51.00		48	240.00		23	90.00		11	49.00
	15	37.00		42	161.00		18	54.00					24	95.00		12	52.00
	16	39.00		44	174.00		19	58.00	52	5	28.00		25	100.00		13	55.00
	17	41.00		46	187.00		20	61.00		6	30.00		26	106.00		14	59.00


PRICE LIST—WOOD SPLIT PULLEYS.—Continued.

507

Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.
58	15	\$62.00	60	46	\$285.00	64	24	\$123.00	68	12	\$68.00	70	40	\$279.00	74	21	\$128.00
	16	67.00		48	305.00		25	130.00		13	72.00		42	302.00		22	135.00
	17	71.00					26	136.00		14	77.00		44	324.00		23	143.00
	18	75.00	62	6	44.00		28	150.00		15	82.00		46	347.00		24	152.00
	19	80.00		7	46.00		30	164.00		16	87.00		48	370.00		25	161.00
	20	85.00		8	48.00		32	179.00		17	92.00					26	170.00
	21	90.00		9	50.00		34	196.00		18	97.00	72	6	54.00		28	188.00
	22	95.00		10	52.00		36	212.00		19	102.00		7	56.00		30	207.00
	23	101.00		11	55.00		38	229.00		20	108.00		8	58.00		32	225.00
	24	106.00		12	58.00		40	246.00		21	113.00		9	62.00		34	244.00
	25	112.00		13	62.00		42	267.00		22	120.00		10	66.00		36	263.00
	26	118.00		14	66.00		44	288.00		23	127.00		11	70.00		38	282.00
	28	130.00		15	70.00		46	309.00		24	134.00		12	75.00		40	301.00
	30	143.00		16	75.00		48	331.00		25	142.00		13	80.00		42	324.00
	32	156.00		17	80.00					26	150.00		14	85.00		44	348.00
	34	170.00		18	85.00	66	6	48.00		28	166.00		15	90.00		46	372.00
	36	185.00		19	90.00		7	50.00		30	182.00		16	95.00		48	396.00
	38	200.00		20	95.00		8	52.00		32	198.00		17	100.00			
	40	215.00		21	100.00		9	54.00		34	216.00		18	105.00	76	6	62.00
	42	234.00		22	106.00		10	57.00		36	233.00		19	111.00		7	64.00
	44	253.00		23	112.00		11	61.00		38	250.00		20	117.00		8	66.00
	46	272.00		24	118.00		12	64.00		40	268.00		21	123.00		9	71.00
	48	292.00		25	124.00		13	69.00		42	290.00		22	130.00		10	75.00
				26	130.00		14	73.00		44	312.00		23	138.00		11	80.00
60	6	41.00		28	142.00		15	78.00		46	334.00		24	146.00		12	85.00
	7	43.00		30	156.00		16	83.00		48	357.00		25	155.00		13	90.00
	8	45.00		32	170.00		17	88.00					26	164.00		14	95.00
	9	47.00		34	186.00		18	93.00	70	6	52.00		28	182.00		15	100.00
	10	49.00		36	202.00		19	98.00		7	54.00		30	200.00		16	105.00
	11	52.00		38	219.00		20	103.00		8	56.00		32	218.00		17	110.00
	12	55.00		40	236.00		21	109.00		9	59.00		34	236.00		18	116.00
	13	58.00		42	256.00		22	115.00		10	63.00		36	254.00		19	122.00
	14	62.00		44	276.00		23	122.00		11	67.00		38	272.00		20	128.00
	15	66.00		46	297.00		24	129.00		12	71.00		40	290.00		21	134.00
	16	71.00		48	318.00		25	136.00		13	76.00		42	312.00		22	141.00
	17	75.00					26	143.00		14	81.00		44	325.00		23	149.00
	18	80.00	64	6	46.00		28	158.00		15	86.00		46	349.00		24	158.00
	19	85.00		7	48.00		30	173.00		16	91.00		48	383.00		25	167.00
	20	90.00		8	50.00		32	189.00		17	96.00					26	176.00
	21	95.00		9	52.00		34	206.00		18	101.00	74	6	58.00		28	195.00
	22	100.00		10	55.00		36	222.00		19	106.00		7	60.00		30	214.00
	23	106.00		11	58.00		38	240.00		20	112.00		8	62.00		32	233.00
	24	112.00		12	61.00		40	257.00		21	118.00		9	66.00		34	253.00
	25	118.00		13	65.00		42	278.00		22	125.00		10	70.00		36	272.00
	26	124.00		14	69.00		44	300.00		23	132.00		11	75.00		38	292.00
	28	136.00		15	74.00		46	322.00		24	140.00		12	80.00		40	312.00
	30	149.00		16	79.00		48	344.00		25	148.00		13	85.00		42	336.00
	32	163.00		17	84.00					26	157.00		14	90.00		44	360.00
	34	178.00		18	89.00	68	6	50.00		28	174.00		15	95.00		46	384.00
	36	193.00		19	94.00		7	52.00		30	191.00		16	100.00		48	409.00
	38	209.00		20	99.00		8	54.00		32	208.00		17	105.00			
	40	225.00		21	104.00		9	56.00		34	226.00		18	110.00	78	8	71.00
	42	245.00		22	110.00		10	60.00		36	243.00		19	116.00		9	75.00
	44	265.00		23	117.00		11	64.00		38	261.00		20	122.00		10	80.00

Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.	Diameter, Inches.	Face.	Price.
78	11	\$85.00	80	42	\$359.00	84	26	\$207.00	88	18	\$163.00	92	10	\$120.00	94	40	\$426.00
	12	90.00		44	384.00		28	227.00		19	170.00		11	127.00		42	455.00
	13	95.00		46	409.00		30	248.00		20	178.00		12	135.00		44	483.00
	14	100.00		48	435.00		32	270.00		21	186.00		13	142.00		46	511.00
	15	105.00					34	292.00		22	194.00		14	150.00		48	540.00
	16	110.00	82	8	80.00		36	314.00		23	203.00		15	157.00			
	17	116.00		9	85.00		38	336.00		24	212.00		16	166.00	96	8	115.00
	18	121.00		10	90.00		40	358.00		25	222.00		17	174.00		9	123.00
	19	127.00		11	95.00		42	385.00		26	232.00		18	183.00		10	132.00
	20	133.00		12	100.00		44	411.00		28	253.00		19	191.00		11	140.00
	21	140.00		13	105.00		46	438.00		30	274.00		20	200.00		12	149.00
	22	147.00		14	110.00		48	465.00		32	296.00		21	209.00		13	157.00
	23	155.00		15	115.00	86	8	90.00		34	318.00		22	218.00		14	166.00
	24	164.00		16	121.00		9	96.00		36	340.00		23	227.00		15	174.00
	25	173.00		17	127.00		10	102.00		38	363.00		24	237.00		16	184.00
	26	182.00		18	133.00		11	108.00		40	385.00		25	247.00		17	193.00
	28	201.00		19	139.00		12	114.00		42	412.00		26	258.00		18	203.00
	30	221.00		20	145.00		13	120.00		44	439.00		28	279.00		19	212.00
	32	241.00		21	152.00		14	126.00		46	467.00		30	300.00		20	222.00
	34	261.00		22	159.00		15	132.00		48	495.00		32	322.00		21	231.00
	36	282.00		23	167.00		16	139.00	90	8	100.00		34	345.00		22	241.00
	38	302.00		24	176.00		17	146.00		9	107.00		36	367.00		23	251.00
	40	323.00		25	185.00		18	153.00		10	114.00		38	390.00		24	262.00
	42	347.00		26	195.00		19	160.00		11	121.00		40	412.00		25	272.00
	44	372.00		28	215.00		20	167.00		12	128.00		42	441.00		26	283.00
	46	397.00		30	235.00		21	174.00		13	135.00		44	469.00		28	304.00
	48	422.00		32	257.00		22	182.00		14	142.00		46	497.00		30	326.00
80	8	75.00		34	279.00		23	191.00		15	149.00		48	525.00		32	348.00
	9	80.00		36	301.00		24	200.00		16	157.00	94	8	110.00		34	371.00
	10	85.00		38	323.00		25	210.00		17	165.00		9	118.00		36	394.00
	11	90.00		40	345.00		26	220.00		18	173.00		10	126.00		38	416.00
	12	95.00		42	372.00		28	240.00		19	181.00		11	134.00		40	439.00
	13	100.00		44	398.00		30	261.00		20	189.00		12	142.00		42	470.00
	14	105.00		46	424.00		32	283.00		21	197.00		13	150.00		44	498.00
	15	110.00		48	450.00		34	305.00		22	206.00		14	158.00		46	526.00
	16	115.00	84	8	85.00		36	327.00		23	215.00		15	166.00		48	555.00
	17	121.00		9	90.00		38	349.00		24	225.00		16	175.00	98	8	120.00
	18	127.00		10	96.00		40	372.00		25	235.00		17	184.00		9	129.00
	19	133.00		11	101.00		42	399.00		26	245.00		18	193.00		10	138.00
	20	139.00		12	107.00		44	426.00		28	266.00		19	202.00		11	147.00
	21	146.00		13	112.00		46	453.00		30	287.00		20	211.00		12	156.00
	22	153.00		14	118.00		48	480.00		32	309.00		21	220.00		13	165.00
	23	161.00		15	123.00	88	8	95.00		34	331.00		22	229.00		14	174.00
	24	170.00		16	130.00		9	101.00		36	354.00		23	239.00		15	183.00
	25	179.00		17	136.00		10	108.00		38	376.00		24	249.00		16	193.00
	26	188.00		18	143.00		11	114.00		40	399.00		25	260.00		17	203.00
	28	208.00		19	149.00		12	121.00		42	426.00		26	270.00		18	213.00
	30	228.00		20	156.00		13	127.00		44	454.00		28	291.00		19	223.00
	32	249.00		21	163.00		14	134.00		46	482.00		30	313.00		20	233.00
	34	270.00		22	170.00		15	140.00		48	510.00		32	335.00		21	243.00
	36	291.00		23	179.00		16	148.00	92	8	105.00		34	358.00		22	253.00
	38	312.00		24	188.00		17	155.00		9	112.00		36	380.00		23	263.00
	40	334.00		25	197.00								38	403.00		24	274.00





## STANDARD PULLEY LIST.

Our Pulleys are all turned and bored in the lathe, are balanced, painted and provided with set screws or key seats, as may be desired. Additional Price to be added to List Price for Finished Split Pulleys.

Diameter, Inches.	Face, Inches.	Price.	Diameter, Inches.	Face, Inches.	Price.
8 to 10	2 to 3	\$1.30	24 to 30	21 to 30	\$14.00
	4 to 6	1.75	31 to 36	3 to 4	4.50
	7 to 10	2.15		5 to 6	5.60
	11 to 14	3.10		7 to 10	6.75
	15 to 20	4.00		11 to 14	9.80
11 to 18	2 to 3	1.50		15 to 20	13.00
	4 to 6	2.20		21 to 30	19.00
	7 to 10	2.85	37 to 47	3 to 4	6.50
	11 to 14	4.00		5 to 6	7.50
	15 to 20	5.25		7 to 10	9.90
19 to 23	3 to 4	2.65		11 to 14	13.50
	5 to 6	3.40		15 to 20	18.00
	7 to 10	4.05		21 to 30	27.00
	11 to 14	5.60		31 to 40	37.00
	15 to 20	7.30	48 to 60	5 to 6	10.00
	21 to 30	11.00		7 to 10	13.00
24 to 30	3 to 4	3.60		11 to 14	18.00
	5 to 6	4.40		15 to 20	25.00
	7 to 10	5.40		21 to 30	34.50
	11 to 14	7.25		31 to 40	48.00
	15 to 20	10.00			

Additional Price to be added to the List Price for Tight and Loose Pulleys, per pair, and Finished Flange Pulleys each.

Diameter, Inches.	Price Tight and Loose Pulleys.	Price Flanged Pulleys.	Diameter, Inches.	Price Tight and Loose Pulleys.	Price Flanged Pulleys.
6 to 8	\$1.60	\$4.65	27 to 28	\$5.10	\$13.75
9 to 10	1.95	5.20	29 to 30	5.45	15.40
11 to 12	2.30	5.75	31 to 32	5.80	17.05
13 to 14	2.65	6.30	33 to 34	6.15	18.70
15 to 16	3.00	7.15	35 to 36	6.50	20.35
17 to 18	3.30	8.00	37 to 40	7.20	23.10
19 to 20	3.70	8.80	41 to 44	7.90	26.40
21 to 22	4.05	9.90	45 to 48	8.60	29.70
23 to 24	4.40	11.00	49 to 52	9.30	33.00
25 to 26	4.75	12.10			

[illegible]



## 511

Diameter.	Face.	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Single Belt.	Double Belt.	Double Arm, Double Belt.	
24	20	\$23.75	\$31.70	\$36.45	27	6	\$9.05	\$12.50	.....	29	18	\$26.80	\$37.00	.....	32	5	\$10.45	\$14.10	.....	
22	26.55	35.40	40.70	.....	7	10.00	14.10	.....	.....	20	30.10	41.40	\$47.60	.....	34	16	\$29.45	\$40.70	.....	
24	29.50	39.00	44.95	.....	8	11.10	15.65	.....	.....	22	33.40	45.80	52.65	.....	18	33.10	45.90	.....	.....	
26	32.30	42.70	49.10	.....	9	12.20	17.25	.....	.....	24	36.70	50.15	57.70	.....	20	36.95	51.65	.....	\$59.40	
28	35.10	46.60	53.60	.....	10	13.35	18.90	.....	.....	26	40.05	54.00	62.80	.....	22	41.05	56.20	.....	64.60	
30	38.00	50.70	58.35	.....	11	14.60	20.60	.....	.....	28	43.35	59.00	67.85	.....	24	44.50	61.30	.....	70.50	
					12	15.90	22.20	.....	.....	30	46.55	63.45	73.00	.....	26	48.35	66.50	.....	76.45	
					14	18.60	25.80	.....	.....						28	52.20	71.80	.....	82.55	
					16	21.45	29.60	.....	.....						30	56.05	76.70	.....	88.20	
25	3	5.70	7.40	.....	18	24.50	33.55	.....	.....	30	3	7.60	9.60	.....	16	27.05	37.45	.....	.....	
4	6.50	8.65	.....	.....	20	27.55	37.50	\$43.10	.....	4	8.55	11.10	.....	18	30.55	42.30	.....	.....	.....	
5	7.25	9.90	.....	.....	22	30.70	41.70	47.95	.....	5	9.45	12.70	.....	20	34.15	47.45	\$54.50	.....	.....	
6	8.10	11.25	.....	.....	24	33.85	45.70	52.55	.....	6	10.55	14.55	.....	22	38.40	52.00	59.80	.....	.....	
7	8.95	12.70	.....	.....	26	36.95	50.75	58.35	.....	7	11.75	16.20	.....	24	41.35	56.85	65.35	.....	.....	
8	9.90	14.15	.....	.....	28	40.05	54.00	62.10	.....	8	13.00	18.00	.....	26	44.95	61.70	70.90	.....	.....	
9	10.85	15.60	.....	.....	30	43.10	58.40	67.20	.....	9	14.30	19.80	.....	28	48.60	66.65	76.65	.....	.....	
10	11.85	17.10	.....	.....						10	15.75	21.60	.....	30	52.25	70.90	81.85	.....	.....	
11	12.90	18.60	.....	.....						11	17.15	23.50	.....					.....	.....	
12	14.05	20.05	.....	.....	28	3	6.75	8.70	.....	12	18.60	25.50	.....					.....	.....	
14	16.65	23.25	.....	.....	5	7.70	10.10	.....	.....	14	21.55	29.70	.....					.....	.....	
16	19.35	26.60	.....	.....	6	8.50	11.55	.....	.....	16	24.70	34.20	.....	33	3	8.90	11.00	.....	.....	
18	22.15	30.10	.....	.....	8	11.70	16.40	.....	.....	18	28.00	38.70	.....	4	9.90	12.80	.....	.....	.....	
20	25.00	33.60	38.65	.....	9	12.90	18.05	.....	.....	20	31.40	43.25	49.75	5	11.00	14.80	.....	.....	.....	
22	28.05	37.45	43.05	.....	10	13.10	19.80	.....	.....	22	34.80	47.80	54.95	6	12.25	16.80	.....	.....	.....	
24	30.95	41.20	47.40	.....	11	15.45	21.60	.....	.....	24	38.20	52.40	60.25	7	13.60	18.80	.....	.....	.....	
26	33.85	45.05	51.80	.....	12	16.85	23.30	.....	.....	26	41.60	56.95	65.45	8	15.05	20.80	.....	.....	.....	
28	37.75	49.10	56.95	.....	14	19.55	27.10	.....	.....	28	45.00	61.50	70.70	9	16.70	22.85	.....	.....	.....	
30	39.70	53.25	61.10	.....	16	22.50	31.10	.....	.....	30	48.45	66.10	76.00	10	18.25	24.95	.....	.....	.....	
					18	25.65	35.25	.....	.....					11	19.90	27.10	.....	.....	.....	
					20	28.80	39.45	45.35	.....					12	21.50	29.25	.....	.....	.....	
					22	32.00	43.75	50.30	.....	31	3	8.05	10.00	.....	14	24.80	34.10	.....	.....	.....
					24	35.25	47.90	55.10	.....	4	8.95	11.65	.....	16	28.25	39.05	.....	.....	.....	
					26	38.50	52.15	60.00	.....	5	9.95	13.40	.....	18	31.80	44.10	.....	.....	.....	
					28	41.70	56.50	65.00	.....	6	11.10	15.30	.....	20	35.50	49.55	56.95	.....	.....	
					30	44.85	60.90	70.05	.....	7	12.35	17.10	.....	22	39.70	54.10	62.30	.....	.....	
										8	13.70	19.00	.....	24	42.90	59.05	67.90	.....	.....	
										9	15.10	21.50	.....	26	46.65	64.10	73.70	.....	.....	
										10	16.55	22.70	.....	28	50.40	69.20	79.60	.....	.....	
										11	18.05	24.70	.....	30	54.15	73.80	84.85	.....	.....	
										12	19.55	26.75	.....					.....	.....	
										14	22.60	31.15	.....					.....	.....	
										16	25.85	35.80	.....					.....	.....	
										18	29.25	40.50	.....	34	3	9.40	11.60	.....	.....	
										20	32.75	45.35	52.15	4	10.40	13.50	.....	.....	.....	
										22	36.10	49.90	57.40	5	11.50	15.50	.....	.....	.....	
										24	39.75	54.60	62.80	6	12.90	17.60	.....	.....	.....	
										26	43.25	59.30	68.20	7	14.35	19.70	.....	.....	.....	
										28	46.80	64.05	73.65	8	15.85	21.75	.....	.....	.....	
										30	50.35	68.00	78.20	9	17.55	23.85	.....	.....	.....	
														10	19.10	26.10	.....	.....	.....	
														11	20.85	28.30	.....	.....	.....	
														12	22.50	30.50	.....	.....	.....	
														14	25.90	35.60	.....	.....	.....	
27	3	6.35	8.25	.....	29	3	7.25	9.15	.....										.....	
4	7.30	9.60	.....	.....	4	8.10	10.60	.....	.....										.....	
5	8.15	11.00	.....	.....	5	9.00	12.15	.....	.....										.....	
					6	10.00	13.85	.....	.....										.....	
					7	11.15	15.50	.....	.....										.....	
					8	12.35	17.15	.....	.....										.....	
					9	13.60	18.85	.....	.....										.....	
					10	14.90	20.70	.....	.....										.....	
					11	16.30	22.60	.....	.....										.....	
					12	17.70	24.40	.....	.....										.....	
					14	20.55	28.40	.....	.....										.....	
					16	23.60	32.60	.....	.....										.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	
																			.....	



Diameter.	Face	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face	Single Belt.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face	Single Belt.	Double Belt.	Double Arm, Double Belt.	
38	4	\$12.55	\$16.25		42	6	\$18.60	\$24.80		46	7	\$24.05	\$32.00		50	8	\$30.25	\$40.30		54	10	\$53.60			
	5	13.95	17.15			7	20.55	27.55			8	26.35	35.15			9	32.80	43.85			11	57.55			
	6	15.60	21.05			8	22.55	30.30			9	28.60	38.35			10	35.45	47.45			12	61.50			
	7	17.95	23.45			9	24.60	33.05			10	30.95	41.55			11	38.10	51.15			14	70.25			
	8	19.05	25.90			10	26.70	35.85			11	33.40	44.90			12	40.80	54.80			16	79.25			
	9	20.90	28.35			11	28.85	38.75			12	35.80	48.20			14	46.20	62.70			18	88.50			
	10	22.80	30.80			12	31.00	41.60			14	40.60	55.30			16	52.00	70.85			20	97.70	\$112.35		
	11	24.75	33.35			14	35.30	47.95			16	45.70	62.60			18	57.95	79.15			22	107.00	123.05		
	12	26.65	35.95			16	39.70	54.40			18	50.90	70.00			20	64.00	87.40	\$100.50		24	116.50	133.95		
	14	30.50	41.65			18	44.20	61.00			20	56.30	77.40	\$89.00		22	70.40	95.70	110.50		26	126.00	144.90		
	16	34.45	49.15			20	49.00	67.60	\$77.75		22	62.00	84.80	97.50		24	76.85	104.10	119.70		28	135.60	155.95		
	18	38.50	53.50			22	54.00	74.30	85.45		24	67.60	92.30	106.15		26	83.20	112.60	129.50		30	145.30	167.10		
	20	42.80	59.80	\$68.75		24	59.00	81.00	93.15		26	73.30	99.90	114.90		28	89.60	121.25	139.45		32	155.00	178.25		
	22	47.10	65.05	74.80		26	64.00	87.70	100.85		28	79.00	107.55	123.70		30	96.00	129.90	149.40		34	167.00	189.40		
	24	51.45	70.85	81.45		28	69.00	92.45	108.60		30	84.60	115.20	132.50		32	102.50	138.60	158.80		36	174.50	200.60		
	26	55.80	76.75	88.25		30	74.00	101.20	116.40		32	90.30	123.00	141.45		34	.....	147.40	169.50		38	184.30	212.95		
	28	60.20	82.75	95.15		32	79.00	108.00	124.20		34	.....	130.70	150.30		36	.....	156.10	179.50		40	194.20	223.35		
	30	64.55	88.75	102.05		34	.....	114.75	131.95		36	.....	138.40	159.15		38	.....	164.90	189.65						
	32	68.95	94.80	109.00		36	.....	121.50	139.70		38	.....	146.20	168.10		40	.....	173.80	199.85						
	34	.....	100.85	115.95		38	.....	128.25	147.50		40	.....	154.00	177.00											
	36	.....	106.95	123.00		40	.....	135.00	155.28																
	38	.....	113.10	130.05																					
	40	.....	119.20	137.10																					
					44	4	16.25	21.00		48	4	19.00	24.50		52	5	.....	31.85			56	6	40.65		
						5	18.20	23.90			5	21.20	27.70			6	.....	35.65				7	44.50		
						6	20.25	26.85			6	23.50	31.00			7	.....	39.30				8	48.50		
						7	22.30	29.75			7	25.85	34.30			8	.....	43.00				9	52.55		
						8	24.45	32.70			8	28.25	37.65			9	.....	46.75				10	56.60		
						9	26.60	35.65			9	30.65	41.05			10	.....	50.50				11	60.75		
						10	28.80	38.65			10	33.15	44.45			11	.....	54.35				12	65.00		
						11	31.10	41.80			11	35.70	48.00			12	.....	58.15				14	74.35		
						12	33.40	44.90			12	38.20	51.50			14	.....	66.45				16	83.55		
						14	37.90	51.60			14	43.30	59.00			16	.....	75.05				18	93.50		
						16	42.70	58.50			16	48.70	66.70			18	.....	83.80				20	103.25	119.75	
						18	47.55	65.50			18	54.20	74.50			20	.....	92.50	106.40			22	113.10	130.05	
						20	52.60	72.60	83.45		20	60.00	82.30	94.65		22	.....	101.30	116.50			24	123.15	141.60	
						22	58.00	79.50	91.40		22	66.00	90.10	103.60		24	.....	110.30	126.85			26	133.20	153.20	
						24	63.30	86.65	99.65		24	72.00	98.00	112.70		26	.....	119.30	137.20			28	143.20	164.70	
						26	68.60	93.80	107.85		26	78.00	106.00	121.90		28	.....	128.40	147.65			30	153.50	176.50	
						28	74.00	100.95	115.10		28	84.00	114.15	131.25		30	.....	137.65	158.20			32	163.70	188.25	
						30	79.30	108.20	124.45		30	90.00	122.30	140.65		32	.....	146.80	168.80			34	173.80	199.85	
						32	84.70	115.50	132.80		32	96.00	130.50	150.05		34	.....	156.10	179.50			36	184.00	211.60	
						34	.....	122.70	141.10		34	.....	138.70	159.50		36	.....	165.30	190.10			38	194.30	233.45	
						36	.....	129.90	149.40		36	.....	146.90	168.95		38	.....	174.70	200.90			40	204.60	235.30	
						38	.....	137.20	157.80		38	.....	155.10	178.35		40	.....	184.10	211.70						
						40	.....	144.50	166.15		40	.....	163.30	187.80											
					46	4	17.65	22.75		50	5	22.80	29.75		54	5	.....	33.95			58	6	43.25		
						5	19.70	25.80			6	25.30	33.30			6	.....	37.90				7	47.20		
						6	21.85	28.90			7	27.75	36.80			7	.....	41.80				8	51.30		
																8	.....	45.70				9	55.45		
																9	.....	49.65				10	59.65		
																						11	64.00		
																						12	68.50		
																						14	78.45		
42	4	14.90	19.30																						
	5	16.70	22.05																						
				</																					

PRICE LIST—FINISHED IRON PULLEYS.—Continued.

513

Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.
58	16	\$87.85	.....	62	26	\$155.15	\$178.40	66	36	\$234.10	\$269.20	72	8	\$72.55	.....	76	22	\$179.00	\$205.85
	18	98.50	.....		28	166.85	191.85		38	246.90	283.95		9	78.40	.....		24	194.50	223.70
	20	108.85	\$125.20		30	178.50	205.30		40	259.70	298.65		10	84.30	.....		26	209.85	241.30
	22	119.25	137.15		32	190.00	218.50						11	90.30	.....		28	225.35	259.15
	24	129.80	149.25		34	201.80	232.00						12	96.50	.....		30	240.80	276.90
	26	140.40	161.45		36	213.50	245.50	68	6	55.70	.....		14	109.45	.....		32	256.30	294.75
	28	150.90	173.55		38	225.10	258.55		7	60.95	.....		16	122.75	.....		34	271.80	312.55
	30	161.70	185.95		40	236.80	272.30		8	66.25	.....		18	136.50	.....		36	287.20	330.30
	32	172.40	198.25						9	71.60	.....		20	150.60	\$173.20		38	302.60	348.00
	34	182.90	210.35						10	77.10	.....		22	165.00	189.75		40	318.20	366.00
	36	193.50	222.50						11	82.55	.....		24	179.50	207.40				
	38	204.30	234.95						12	88.20	.....		26	193.85	222.90				
	40	215.00	247.25						14	100.25	.....		28	208.20	239.45				
				64	6	50.60	.....		16	112.55	.....		30	222.60	256.00				
					7	55.35	.....		18	125.10	.....		32	237.00	272.55	78	8	82.35	.....
					8	60.10	.....		20	138.35	159.10		34	251.40	289.10		9	89.10	.....
					9	64.95	.....		22	151.50	174.25		36	265.80	305.65		10	95.90	.....
					10	69.90	.....		24	165.00	189.75		38	280.20	322.25		11	102.85	.....
60	6	46.00	.....		11	74.90	.....		26	178.05	204.75		40	294.60	338.80		12	110.00	.....
	7	50.00	.....		12	80.00	.....		28	191.35	220.05						14	124.50	.....
	8	54.10	.....		14	91.35	.....		30	204.60	235.30						16	139.25	.....
	9	58.35	.....		16	102.35	.....		32	218.00	250.70						18	154.50	.....
	10	62.75	.....		18	113.85	.....		34	231.30	266.00	74	8	75.75	.....		20	170.30	195.85
	11	67.30	.....		20	126.25	145.20		36	244.60	281.30		9	81.90	.....		22	186.10	214.00
	12	72.00	.....		22	138.30	159.05		38	258.00	296.70		10	88.50	.....		24	202.00	232.30
	14	82.55	.....		24	150.90	173.55		40	271.30	312.00		11	94.80	.....		26	217.95	250.65
	16	92.15	.....		26	162.65	187.05						12	101.00	.....		28	233.95	269.05
	18	103.50	.....		28	174.90	201.15						14	114.45	.....		30	249.95	287.45
	20	114.45	131.60		30	187.10	215.20						16	128.25	.....		32	266.00	305.90
	22	125.45	144.25		32	199.00	228.55	70	6	58.40	.....		18	142.50	.....		34	282.00	324.30
	24	136.50	157.00		34	211.50	243.25		7	63.85	.....		20	157.10	180.65		36	298.00	342.70
	26	147.65	169.80		36	223.80	257.35		8	69.25	.....		22	172.00	197.80		38	314.00	361.10
	28	158.80	182.60		38	235.95	271.30		9	75.00	.....		24	187.00	215.05		40	330.00	379.50
	30	169.90	195.40		40	248.25	285.30		10	80.70	.....		26	201.85	232.10				
	32	181.00	208.15						11	86.40	.....		28	216.75	249.25				
	34	192.10	220.90						12	92.40	.....		30	231.70	266.45				
	36	203.20	233.60						14	104.85	.....		32	246.60	283.60				
	38	214.30	246.55						16	117.65	.....		34	261.60	300.85	80	8	85.95	.....
	40	225.40	259.20						18	130.80	.....		36	276.50	317.95		9	92.90	.....
				66	6	53.00	.....		20	144.55	166.25		38	291.40	335.10		10	99.85	.....
					7	58.05	.....		22	158.25	182.00		40	306.40	352.30		11	106.95	.....
					8	63.15	.....		24	172.50	198.40						12	114.30	.....
					9	68.30	.....		26	185.95	213.85						14	129.50	.....
					10	73.50	.....		28	199.75	239.70						16	144.95	.....
					11	78.75	.....		30	213.60	245.65						18	160.80	.....
					12	84.00	.....		32	227.50	261.60						20	177.10	203.65
					14	95.75	.....		34	241.30	277.50	76	8	79.05	.....		22	193.40	222.40
					16	107.55	.....		36	255.15	293.40		9	85.50	.....		24	210.00	241.50
					18	119.50	.....		38	269.10	309.45		10	92.70	.....		26	226.25	260.20
					20	132.15	152.05		40	282.90	325.35		11	99.30	.....		28	242.85	279.30
					22	144.80	166.50						12	105.50	.....		30	259.35	298.25
					24	157.50	181.10						14	119.45	.....		32	276.00	317.40
					26	170.20	195.70						16	133.75	.....		34	292.50	336.35
					28	182.95	210.40						18	148.45	.....		36	309.10	355.45
					30	195.70	225.05	72	6	61.00	.....		20	163.70	188.25				
					32	208.50	239.80		7	66.75	.....								
					34	221.30	254.50												
62	6	48.30	.....																
	7	52.65	.....																
	8	57.10	.....																
	9	61.65	.....																
	10	66.30	.....																
	11	71.10	.....																
	13	76.00	.....																
	14	86.95	.....																
	16	97.25	.....																
	18	108.70	.....																
	20	120.35	138.40																
	22	131.85	150.60																
	24	143.20	164.70																



Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.	Diameter.	Face.	Double Belt.	Double Arm, Double Belt.			
80	38	\$325.70	\$374.55	90	16	\$173.40	.....	102	34	\$417.10	\$479.65	120	12	\$221.00	.....			
	40	342.20	383.55		18	191.50	.....		36	440.20	506.25		14	246.10	.....			
					20	210.70	\$242.30		38	463.30	532.80		16	271.75	.....			
					22	230.05	264.55		40	486.40	559.35		18	298.00	.....			
82	8	89.55	.....		24	249.50	286.95						20	325.90	\$374.80			
	9	96.70	.....		26	268.95	309.30						22	353.80	406.90			
	10	103.85	.....		28	288.45	331.70	108	8	144.35	.....		24	382.50	439.90			
	11	111.15	.....		30	307.95	354.15			9	154.75	.....		26	410.80	473.40		
	12	118.65	.....		32	327.50	376.65			10	165.35	.....		28	439.20	505.10		
	14	134.50	.....		34	347.00	389.05			11	176.10	.....		30	467.60	537.75		
	16	150.65	.....		36	366.50	421.50			12	187.00	.....		32	496.00	575.40		
	18	167.10	.....		38	386.00	443.90			14	209.50	.....		34	524.40	603.10		
	20	183.90	211.48		40	405.50	466.30			16	232.50	.....		36	552.80	635.70		
	22	200.70	230.80							18	256.00	.....		38	581.20	668.40		
	24	218.00	250.70							20	280.20	.....		40	609.60	701.00		
	26	234.65	269.85							22	304.55	350.25						
	28	251.75	289.50	96	8	117.10	.....			24	329.00	378.35						
	30	268.80	309.10			9	125.85		.....		26	353.35	406.35	126	10	212.10	.....	
	32	286.00	328.90			10	134.75		.....		28	377.80	434.45			11	224.90	.....
	34	303.10	348.55			11	143.85		.....		30	402.35	462.70			12	238.00	.....
36	320.20	368.20			12	153.00	.....			32	427.00	491.05			14	264.30	.....	
38	337.40	388.00			14	172.10	.....			34	451.60	519.35			16	291.10	.....	
40	354.50	407.65			16	191.75	.....		36	476.20	547.65		18		319.00	.....		
					18	212.50	.....		38	500.80	575.90		20		349.00	401.30		
				20	233.00	267.95		40	525.40	604.20		22	380.30		437.80			
84	8	93.25	.....		22	254.50	292.70						24	409.25	470.60			
	9	100.50	.....		24	276.00	317.40						26	433.40	486.90			
	10	107.85	.....		26	297.00	341.50	114	8	159.45	.....		28	469.75	541.20			
	11	115.35	.....		28	318.00	365.70			9	170.75	.....		30	495.00	569.25		
	12	123.00	.....		30	339.50	390.45			10	182.10	.....		32	530.50	610.10		
	14	139.60	.....		32	361.00	415.15			11	193.50	.....		34	561.00	645.10		
	16	156.40	.....		34	382.30	439.65			12	205.00	.....		36	591.40	680.10		
	18	173.50	.....		36	403.60	464.15			14	228.40	.....		38	621.80	715.10		
	20	190.75	219.35		38	424.90	488.65			16	252.45	.....		40	652.30	750.10		
	22	208.10	239.30		40	446.25	513.15			18	277.00	.....						
	24	225.50	259.30							20	303.00	348.50						
	26	243.05	279.50							22	329.50	379.40						
	28	260.65	299.75	102	8	130.75	.....			24	356.00	409.40	132	10	227.60	.....		
	30	278.30	320.05			9	140.70		.....		26	382.30		439.60		11	241.10	.....
	32	296.00	340.40			10	150.75		.....		28	408.70		470.00		12	255.00	.....
	34	313.70	360.75			11	160.85		.....		30	435.30		500.60		14	282.50	.....
36	331.40	381.10			12	171.00	.....			32	462.00	531.30			16	310.50	.....	
38	349.10	401.45			14	192.00	.....			34	488.60	562.00			18	340.00	.....	
40	366.80	421.80			16	213.40	.....		36	515.20	592.50			20	372.00	427.80		
					18	233.50	.....		38	541.80	623.10			22	404.00	464.60		
90	8	104.75	.....		20	256.25	294.70		40	568.40	653.70		24	436.00	501.40			
	9	112.80	.....		22	279.05	320.90						26	468.00	538.20			
	10	121.00	.....		24	302.00	347.30	120	8	172.85	.....		28	500.30	575.30			
	11	129.40	.....		26	324.95	373.70			9	184.60	.....		30	532.50	612.50		
	12	138.00	.....		28	347.95	400.15			10	196.55	.....		32	565.00	649.75		
	14	155.60	.....		30	370.95	426.60			11	208.65	.....		34	597.50	687.10		
					32	394.00	453.10						36	630.00	724.50			




# "ECLIPSE" BALANCED CUT-OFF CLUTCH COUPLINGS. 515

MADE IN TWO, FOUR OR SIX ARMS.

## FOUR-ARM COUPLINGS.

*Diameter of Shaft.	Diameter of Clutch.	SPACE ON SHAFT.				H. P. for 100 Revolu- tions.	Approximate Shipping Weight.	Price.
		Z Clutch.	Y Socket.	X Hub.	Total.			
2	12	8 $\frac{3}{4}$	2 $\frac{3}{4}$	4	15 $\frac{1}{2}$	3	130	\$45.00
2 $\frac{1}{2}$	14	9 $\frac{3}{4}$	2 $\frac{3}{4}$	4 $\frac{1}{2}$	17	4	160	50.00
2 $\frac{1}{2}$	16	10 $\frac{3}{4}$	3	5	18 $\frac{3}{4}$	6	225	55.00
3 $\frac{1}{2}$	18	11 $\frac{1}{2}$	3 $\frac{1}{4}$	5 $\frac{1}{2}$	20 $\frac{1}{4}$	7	270	60.00
3 $\frac{1}{2}$	20	12	3 $\frac{1}{4}$	6	21 $\frac{1}{4}$	10	320	75.00
3 $\frac{1}{2}$	22	12 $\frac{1}{2}$	3 $\frac{1}{4}$	6 $\frac{1}{2}$	22 $\frac{1}{4}$	14	375	85.00
4 $\frac{1}{2}$	24	13 $\frac{1}{2}$	3 $\frac{1}{2}$	7	24	20	450	100.00
4 $\frac{1}{2}$	26	13 $\frac{3}{4}$	3 $\frac{3}{4}$	7 $\frac{1}{2}$	25	24	550	110.00
5 $\frac{1}{2}$	30	14 $\frac{3}{4}$	4	8 $\frac{1}{2}$	27 $\frac{1}{4}$	32	675	125.00
5 $\frac{1}{2}$	36	16 $\frac{1}{2}$	4 $\frac{1}{2}$	9	30	52	800	160.00
7	42	19 $\frac{3}{4}$	4 $\frac{3}{4}$	9 $\frac{1}{2}$	34	90	1100	225.00
7	48	20 $\frac{1}{2}$	5	10	35 $\frac{1}{2}$	100	1560	275.00
8 $\frac{1}{2}$	54	22	5 $\frac{1}{2}$	10 $\frac{1}{2}$	38	174	2300	325.00
8 $\frac{1}{2}$	60	23 $\frac{1}{2}$	6	11	40 $\frac{1}{2}$	274	2800	445.00
9	72	25	7 $\frac{1}{4}$	12	44 $\frac{1}{4}$	410	4800	525.00

\* This diameter is largest that hubs will bore regular. May be as much smaller as desired.



TRANSMITTING 1000 TO 2000 H. P.

## SIX-ARM COUPLINGS.

*Diameter of Shaft.	Diameter of Clutch.	SPACE ON SHAFT.				H. P. for 100 Revolu- tions.	Approximate Shipping Weight.	Price.
		Z Clutch.	Y Socket.	X Hub.	Total.			
5 $\frac{1}{2}$	30	14 $\frac{3}{4}$	4	8 $\frac{1}{2}$	27 $\frac{1}{4}$	48	850	\$185.00
5 $\frac{1}{2}$	36	16 $\frac{1}{2}$	4 $\frac{1}{2}$	9	30	78	1200	210.00
7	42	19 $\frac{3}{4}$	4 $\frac{3}{4}$	9 $\frac{1}{2}$	34	135	1800	270.00
7	48	20 $\frac{1}{2}$	5	10	35 $\frac{1}{2}$	150	2200	360.00
8 $\frac{1}{2}$	54	22	5 $\frac{1}{2}$	10 $\frac{1}{2}$	38	261	2700	460.00
8 $\frac{1}{2}$	60	23 $\frac{1}{2}$	6	11	40 $\frac{1}{2}$	411	4700	700.00
9	72	25	7 $\frac{1}{4}$	12	44 $\frac{1}{4}$	615	6000	850.00

\* This diameter is largest that hubs will bore regular. May be as much smaller as desired.


Price includes our wrought shifter straps, to which purchaser may attach wood or iron levers, as the location requires. Other shifting devices charged extra.

For splitting Clutch mechanism, add 10 per cent.

For splitting both Clutch mechanism and Friction Ring, add 20 per cent.

Like parts interchangeable. Every Clutch balanced and warranted.


# SPLIT FRICTION CLUTCH CUT-OFF COUPLINGS FOR SHAFTING.



Size of Clutch.	Size of Shaft Equal to Capacity of Clutch, in.	Horse Power of Shaft at 100 Revolutions.	Largest Size Clutch Will Bore. Inches.	Price of Coupling Complete.
10	1½	6	2½	\$49.00
12	1¾	10	3	56.00
14	2	15	3½	66.00
16	2¼	19	4½	82.00
18	2½	26	5	102.00
20	2¾	34	6	124.00
22	3	42	6	150.00
24	3¼	51	6½	172.00
26	3½	63	6½	190.00
28	3¾	78	7	213.00
30	4	90	7½	264.00
36	4½	126	8	339.00
40	4¾	150	10	382.00
48	5	210	12	495.00
54	6	295	12	641.00
60	6½	400	12	810.00

All Clutches above 48 inches in diameter have three sets of levers, each with two points of contact for securing compression of the friction rings. The levers in all Clutches are accurately counter-balanced and will run satisfactorily at any speed.

## FLANGE OR PLATE COUPLINGS.



Size of Shaft.	Price per Pair.	Price for Fitting.	Size of Shaft.	Price per Pair.	Price for Fitting.
1 7/8	\$8.00	\$2.50	4 7/8	\$43.25	\$13.00
1 11/16	8.50	2.60	4 5/8	54.75	18.25
1 15/16	9.50	2.75	5 7/8	67.00	20.50
2 3/8	10.50	2.85	5 15/16	81.00	22.00
2 7/8	12.50	3.00	6 7/8	95.50	24.50
2 11/4	15.25	3.25	6 15/16	110.00	26.50
2 15/16	18.25	3.50	7 7/8	126.00	28.50
3 3/8	21.75	4.00	7 15/16	142.00	30.00
3 7/8	25.25	4.50	8 7/8	160.00	32.50
3 11/16	29.25	5.00	8 15/16	179.00	35.00
3 15/16	33.25	6.00	9 7/8	200.00	37.50

Reducing Couplings will be charged for at the rate of ten per cent. above the price for a pair for the larger size of shaft.

# SHAFTING AND COUPLINGS.

517

## SHAFTING.

Diam-eter.	Weight Per Foot.	Price Per Pound.	Diam-eter.	Weight Per Foot.	Price Per Pound.	Diam-eter.	Weight Per Foot.	Price Per Pound.
1-4	.167	13c.	1 5-8	7.04	5c.	3	24.06	5c.
5-16	.259	11c.	1 11-16	7.60		3 1-16	24.58	5 1/2 c.
3-8	.370	9c.	1 3-4	8.16		3 1-8	26.09	
7-16	.510		1 13-16	8.78		3 3-16	27.16	
1-2	.666		1 7-8	9.39		3 1-4	28.24	
9-16	.843		1 15-16	10.00		3 5-16	29.40	
5-8	1.05	7 3/4 c.	2	10.65		3 3-8	30.43	
11-16	1.25		2 1-16	11.15		3 7-16	31.50	
3-4	1.50		2 1-8	12.07		3 1-2	32.64	
13-16	1.757		2 3-16	12.79		3 9-16	33.84	
7-8	2.03	6 1/2 c.	2 1-4	13.40		3 5-8	35.20	
15-16	2.34		2 5-16	14.00		3 11-16	36.40	
1	2.64		2 3-8	14.07		3 3-4	37.45	
1 1-16	3.00		2 7-16	15.83		3 7-8	39.85	
1 1-8	3.33	5 1/2 c.	2 1-2	16.68		3 15-16	41.04	
1 3-16	3.74		2 9-16	17.55		4	42.50	
1 1-4	4.16		2 5-8	18.32		4 1-4	48.26	
1 5-16	4.61		2 11-16	19.31		4 7-16	52.62	
1 3-8	5.048	5c.	2 3-4	20.18		4 1-2	54.11	
1 7-16	5.50		2 13-16	21.15		4 3-4	60.88	
1 1-2	6.00		2 7-8	22.09		4 15-16	65.50	
1 9-16	6.52		2 15-16	22.96		5	67.50	

## EXTRAS FOR CUTTING SHORT AND LONG LENGTHS.

For shafts 6 inches to 11 3/4 inches long, 1/2 cent per pound, net, extra.

For shafts 3 inches to 5 3/4 inches long, 1 cent per pound, net, extra.

For shafts shorter than 3 inches a special price will be quoted upon application.

For shafts over 24 feet and less than 30 feet, 1 1/2 cent per pound extra.


For shafts 30 feet and less than 35 feet, 1 cent per pound extra.

For shafts 35 feet and less than 40 feet, 1 1/2 cent per pound extra.

For shafts 40 feet and less than 45 feet, 2 cents per pound extra.

For shafts 45 feet and over, 2 1/2 cents per pound extra.

## RIBBED COMPRESSION COUPLINGS.



## PLAIN SET COLLARS.



## PRICE LIST.

Dia. of Shaft in Inches.....	1	1 1/8	1 1/4	1 3/8	1 1/2	1 5/8	1 3/4	1 7/8	2
Price.....	\$0.50	.55	.55	.60	.70	.80	1.05	1.20	1.40
Dia. of Shaft in Inches.....	2 1/8	3 1/8	3 1/4	3 3/8	4 1/8	4 1/4	4 3/8	5 1/8	5 1/4
Price.....	\$1.65	1.90	2.25	2.85	4.05	5.40	6.00	6.90	7.60

Intermediate sizes, proportionate prices.

## PRICE LIST.

Size of Shaft.	Price.	Size of Shaft.	Price.
1 3-16	\$3.05	2 11-16	\$11.00
1 5-16	3.65	2 15-16	13.00
1 7-16	4.20	3 3-16	16.50
1 11-16	6.30	3 7-16	20.00
1 15-16	7.40	3 11-16	24.00
2 3-16	9.00	3 15-16	28.00
2 7-16	10.00	4 7-16	38.00

For price of reduction couplings, add 10 per cent. to price of coupling for the larger of the two shafts.

## SOLID SLEEVE COUPLINGS. FOR LIGHT SHAFTING.



Have Countersunk Set Screws, and are finished over entire surface.


## PRICE LIST.

Size.	Price.	Size.	Price.
15-16	\$3.00	1 7-16	\$4.00
1 3-16	3.50	1 11-16	4.50



# PILLOW BLOCKS.


## STANDARD RIGID PILLOW BLOCKS



PRICE LIST.

Size.	Price.	Size.	Price.
1 $\frac{5}{8}$	\$1.30	3 $\frac{7}{8}$	\$11.00
1 $\frac{3}{4}$	1.60	3 $\frac{11}{16}$	13.30
1 $\frac{7}{8}$	2.10	3 $\frac{13}{16}$	16.60
1 $\frac{15}{16}$	2.65	4 $\frac{7}{8}$	21.80
1 $\frac{1}{8}$	3.40	4 $\frac{15}{16}$	26.40
2 $\frac{1}{8}$	4.00	5 $\frac{1}{8}$	33.60
2 $\frac{1}{4}$	4.90	5 $\frac{15}{16}$	48.40
2 $\frac{3}{8}$	6.10	6 $\frac{1}{8}$	56.50
2 $\frac{1}{2}$	7.80	6 $\frac{3}{8}$	63.80
3 $\frac{1}{8}$	9.40	7 $\frac{1}{8}$	80.00

## BALL AND SOCKET PILLOW BLOCKS.



STANDARD TYPE.

PRICE LIST.

Size.	Price.	Size.	Price.
1 $\frac{5}{8}$	\$4.70	3 $\frac{1}{8}$	\$28.75
1 $\frac{3}{4}$	4.80	3 $\frac{15}{16}$	38.25
1 $\frac{7}{8}$	5.10	4 $\frac{1}{8}$	46.50
1 $\frac{15}{16}$	5.60	4 $\frac{15}{16}$	54.00
1 $\frac{1}{8}$	6.30	5 $\frac{1}{8}$	63.00
2 $\frac{1}{8}$	7.50	5 $\frac{15}{16}$	73.50
2 $\frac{1}{4}$	9.10	6 $\frac{1}{8}$	84.75
2 $\frac{3}{8}$	11.75	6 $\frac{3}{8}$	95.00
2 $\frac{1}{2}$	14.00	7 $\frac{1}{8}$	106.00
3 $\frac{1}{8}$	16.75	7 $\frac{15}{16}$	118.00
3 $\frac{1}{4}$	19.50	8 $\frac{1}{8}$	131.00



# ADJUSTABLE BALL AND SOCKET HANGERS WITH STANDARD BEARINGS.

519

SINGLE AND DOUBLE BRACE.


## PRICE LIST.

Size of Shaft.	Brace.	DROP IN INCHES.									
		8	10	12	14	16	18	20	24	30	36
$1\frac{3}{16}$ and $1\frac{1}{4}$	Single	\$4.00	\$4.15	\$4.35	\$4.60	\$4.70	\$5.10	\$5.55	.....	.....	.....
	Double	4.40	4.55	4.75	5.00	5.10	5.50	5.95	.....	.....	.....
$1\frac{7}{16}$ and $1\frac{1}{2}$	Single	4.55	4.70	4.90	5.15	5.25	5.65	6.10	.....	.....	.....
	Double	4.95	5.10	5.30	5.55	5.65	6.05	6.50	.....	.....	.....
$1\frac{11}{16}$ and $1\frac{3}{4}$	Single	4.65	4.80	5.00	5.25	5.35	5.75	6.20	.....	.....	.....
	Double	5.05	5.20	5.40	5.65	5.75	6.15	6.60	.....	.....	.....
$1\frac{5}{8}$ and 2	Single	6.35	6.85	7.00	7.30	7.75	7.80	8.30	\$9.15	.....	.....
	Double	6.85	7.35	7.50	7.80	8.25	8.30	8.80	9.65	.....	.....
$2\frac{3}{16}$ and $2\frac{1}{4}$	Single	8.15	8.50	8.65	9.15	9.75	10.20	11.10	12.80	\$15.15	.....
	Double	8.70	9.05	9.20	9.70	10.30	10.75	11.65	13.35	15.70	.....
$2\frac{7}{16}$ and $2\frac{1}{2}$	Single	8.80	9.10	9.30	9.80	10.40	10.85	11.75	13.45	15.80	.....
	Double	9.35	9.65	9.85	10.35	10.95	11.40	12.30	14.00	16.35	.....
$2\frac{11}{16}$ and $2\frac{3}{4}$	Single	10.05	10.55	11.15	11.25	12.55	13.65	14.70	16.95	19.00	\$19.75
	Double	10.85	11.35	11.95	12.05	13.35	14.45	15.50	17.75	19.80	20.55
$2\frac{5}{8}$ and 3	Single	12.00	12.50	13.10	13.20	14.50	15.60	16.65	18.90	20.95	21.70
	Double	12.80	13.30	13.90	14.00	15.30	16.40	17.45	19.70	21.75	22.50
$3\frac{3}{16}$ and $3\frac{1}{4}$	Single	.....	.....	15.90	16.65	17.15	18.55	20.45	23.65	26.75	28.65
	Double	.....	.....	16.95	17.70	18.20	19.60	21.50	24.70	27.80	29.70
$3\frac{7}{16}$ and $3\frac{1}{2}$	Single	.....	.....	16.35	17.10	17.60	19.00	20.90	24.10	27.20	29.10
	Double	.....	.....	17.40	18.15	18.65	20.05	21.95	25.15	28.25	30.15
$3\frac{11}{16}$ and $3\frac{3}{4}$	Single	.....	.....	22.20	24.70	24.85	25.60	27.50	32.75	36.20	40.75
	Double	.....	.....	23.40	25.90	26.05	26.80	28.70	33.95	37.40	41.95
$3\frac{5}{8}$ and 4	Single	.....	.....	25.45	25.95	28.10	28.85	30.75	36.00	39.45	44.00
	Double	.....	.....	26.65	27.15	29.30	30.05	31.95	37.20	40.60	45.20
$4\frac{3}{16}$ and $4\frac{1}{4}$	Single	.....	.....	.....	.....	31.15	33.40	35.65	40.90	43.70	49.65
	Double	.....	.....	.....	.....	32.70	34.95	37.20	42.45	45.25	51.20
$4\frac{7}{16}$ and $4\frac{1}{2}$	Single	.....	.....	.....	.....	32.40	34.65	36.90	42.15	44.95	50.90
	Double	.....	.....	.....	.....	33.95	36.20	38.45	43.70	46.50	52.45
$4\frac{11}{16}$ and $4\frac{3}{4}$	Single	.....	.....	.....	.....	37.40	41.10	43.35	46.95	51.15	59.25
	Double	.....	.....	.....	.....	39.35	43.05	45.30	48.90	53.10	61.20
$4\frac{5}{8}$ and 5	Single	.....	.....	.....	.....	40.45	44.15	46.40	50.00	54.20	62.30
	Double	.....	.....	.....	.....	42.40	46.10	48.35	51.95	56.15	64.25




# ADJUSTABLE BALL AND SOCKET POST HANGERS.

WITH STANDARD BEARINGS.



SINGLE BRACE.



DOUBLE BRACE

This Hanger is a combination of our standard frame with the Standard hanger box, which is four diameters of shaft in length, babbited, reamed and faced. With these boxes may be used either oil, grease or candles. A wide range of adjustment is secured.

## PRICE LIST.—SINGLE BRACE.

Size.	Price.	Size.	Price.	Size.	Price.	Size.	Price.
1 3-16	\$4.60	2 3-16	\$9.20	3 3-16	\$17.95	4 3-16	\$31.30
1 7-16	5.15	2 7-16	9.85	3 7-16	18.40	4 7-16	32.55
1 11-16	5.25	2 11-16	12.20	3 11-16	24.25	4 11-16	41.40
1 15-16	6.65	2 15-16	14.15	3 15-16	27.50	4 15-16	44.45

## PRICE LIST.—DOUBLE BRACE.

Size.	Price.	Size.	Price.	Size.	Price.	Size.	Price.
1 3-16	\$5.00	2 3-16	\$9.75	3 3-16	\$19.00	4 3-16	\$32.85
1 7-16	5.50	2 7-16	10.40	3 7-16	19.45	4 7-16	34.10
1 11-16	5.60	2 11-16	13.00	3 11-16	25.45	4 11-16	43.35
1 15-16	7.15	2 15-16	14.95	3 15-16	28.70	4 15-16	46.40



# ELEVATOR BUCKETS AND BOLTS.

521

## SALEM STEEL ELEVATOR BUCKETS.

Capacity, Bushel per Hour, 200 Feet per Minute, 12 Inches Apart.	SIZE OF BUCKET.		For Ordinary Mill and Elevator Work.		For Ear Corn and Heavy Substances.	
	Width.	Projection.	Gauge of Steel Used.	Price, Each.	Gauge of Steel Used.	Price, Each.
87	3	x 3 in.	23	\$0.07		
102	3½	x 3 "	23	.07		
116	4	x 3 "	23	.08		
159	4	x 3½ "	22	.09	18	\$0.21
179	4½	x 3½ "	22	.10	18	.22
229	5	x 4 "	22	.11	18	.24
251	5½	x 4 "	21	.12	18	.25
274	6	x 4 "	21	.12	18	.25
500	7	x 4½ "	20	.16	18	.35
670	8	x 5 "	19	.20	16	.43
754	9	x 5 "	19	.23	16	.44
973	10	x 5½ "	19	.29	16	.53
1342	11	x 6 "	18	.39	16	.57
1464	12	x 6 "	18	.40	16	.58
1708	14	x 6 "	18	.47	16	.67
1952	16	x 6 "	18	.48	16	.71
2196	18	x 6 "	18	.60	16	.74
2440	20	x 6 "	18	.65	16	.77



These Buckets are popular among millwrights. They empty clean and are unsurpassed for strength and durability.

## THE "ACME" STEEL ELEVATOR BUCKET.

Width.	Projection.	Gauge of Steel Used.	Price Plain, Each.	Width.	Projection.	Gauge of Steel Used.	Price Plain, Each.
3	x 3 in.	23	\$0.09	8	x 5 in.	19	\$0.27
3½	x 3 "	23	.10	9	x 5 "	19	.33
4	x 3 "	23	.11	10	x 5½ "	18	.40
4	x 3½ "	22	.12	11	x 6 "	17	.52
4½	x 3½ "	22	.13	12	x 6 "	17	.55
5	x 4 "	21	.15	14	x 6 "	17	.63
5½	x 4 "	21	.17	16	x 6 "	17	.65
6	x 4 "	21	.17	18	x 6 "	17	.75
7	x 4½ "	20	.21	20	x 6 "	17	.80



For ordinary Mill and Elevator work.

## PUNCHING.

Buckets punched for belt or chain, as wanted. If buckets are to replace others, or to go on belt already punched, send template. For belting, see page 523.

## ELEVATOR BUCKET BOLTS.—PRICE PER HUNDRED.

Key Heads ⅜ and ¼-inch Wrought Iron.	LARGE COUNTERSUNK HEADS. WROUGHT IRON.		
	⅜ and ¼-inch.	⅝-inch.	¾-inch.
¾ inch, \$1.50	¾ inch, \$2.20	1 inch, \$3.00	1 inch, \$4.00
⅝ " 1.60	⅝ " 2.30	1¼ " 3.20	1¼ " 4.30
1 " 1.60	1 " 2.30	1½ " 3.40	1½ " 4.60
1¼ " 1.80	1¼ " 2.40		



KEY HEAD.




COUNTERSUNK HEAD.

# BELTING, LACE LEATHER, ETC.

## RAW HIDE CUT LACE.

Size, Inches .....	$\frac{1}{4}$	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{7}{16}$
Per 100 Feet.....	\$1.00	1.25	1.50	1.75
Size, Inches.....	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Per 100 Feet.....	\$2.00	2.75	3.25	4.50



## CANVAS STITCHED BELTING.

Size, In.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
4-Ply, per ft.	\$0.18	\$0.23	\$0.27	\$0.32	\$0.36
6-Ply, per ft.	.....	.....	.36	.42	.48
Size, In.....	$4\frac{1}{2}$	5	6	7	8
4-Ply, per ft.	\$0.41	\$0.45	\$0.54	\$0.63	\$0.72
6-Ply, per ft.	.54	.60	.72	.84	.96
Size, In.....	9	10	12	14	
4-Ply, per ft.	\$0.81	\$0.90	\$1.08	.....	
6-Ply, per ft.	1.08	1.20	1.44	\$1.68	
8-Ply, per ft.	.....	.....	1.80	2.10	

We make Canvas Stitched Belting in all widths to 60-in.

## RUBBER BELTING.

Size, inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8
2-Ply, per foot.....	\$0.07	\$0.09	\$0.11	\$0.15	\$0.18	\$0.22	\$0.26	\$0.30	\$0.33	\$0.36	\$0.43	\$0.51	\$0.59
3-Ply, per foot.....	.17	.22	.26	.30	.34	.39	.43	.47	.52	.56	.60	.64	.70
4-Ply, per foot.....	.21	.26	.31	.37	.42	.47	.52	.57	.62	.67	.72	.77	.84
5-Ply, per foot.....	.26	.33	.39	.46	.53	.59	.65	.71	.78	.84	.91	.98	1.05
6-Ply, per foot.....	.31	.39	.47	.56	.63	.71	.78	.86	.93	1.00	1.10	1.20	1.26
Size, inches.....	9	10	11	12	13	14	15	16	18	20	22	24	26
2-Ply, per foot.....	\$0.67	\$0.75	\$0.83	\$0.91	\$1.00	\$1.08	\$1.16	\$1.25	\$1.41	\$1.58	\$1.76	\$1.96	\$2.18
3-Ply, per foot.....	.80	.90	1.00	1.08	1.18	1.28	1.38	1.50	1.70	1.90	2.12	2.36	2.60
4-Ply, per foot.....	.95	1.07	1.18	1.30	1.42	1.54	1.66	1.78	2.02	2.26	2.52	2.80	3.08
5-Ply, per foot.....	1.18	1.33	1.47	1.62	1.77	1.92	2.07	2.22	2.52	2.82	3.15	3.50	3.85
6-Ply, per foot.....	1.42	1.60	1.77	1.95	2.13	2.31	2.49	2.67	3.03	3.39	3.78	4.20	4.62

Endless Belts made to order, for which there will be three extra feet charged for splice.

## LEATHER BELT.

(Revised List Adopted November 15, 1899.)

Size, inches.....	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{4}$	$2\frac{1}{2}$	$2\frac{3}{4}$	3	$3\frac{1}{4}$	$3\frac{1}{2}$	$3\frac{3}{4}$	4	$4\frac{1}{2}$	5	$5\frac{1}{2}$	6	$6\frac{1}{2}$	7
Per foot.....	\$0.14	.19	.24	.29	.34	.39	.43	.48	.53	.58	.63	.67	.72	.82	.91	1.01	1.11	1.20	1.30
Size, inches.....	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
Per foot.....	\$1.48	1.67	1.85	2.04	2.22	2.41	2.59	2.78	2.96	3.15	3.33	3.52	3.70	3.89	4.07	4.26	4.44	4.63	4.81
Size, inches.....	27	28	30	32	34	36	40	44	48	52	56	60	64	68	72	78	84		
Per foot.....	\$5.00	5.18	5.55	5.92	6.29	6.66	7.40	8.14	8.88	9.62	10.36	11.10	11.84	12.58	13.32	14.43	15.54		

Full rolls contain about 400 feet.

Double Belts are twice the price of single.

# BELTING, ETC.

523

## SOLID COTTON BELTING.

This Belt is suitable for light work, and especially for elevating purposes.

Inches.	2-Ply.	3-Ply.	4-Ply.	5-Ply.	6-Ply.	8-Ply.
1.....	\$0.04					
1½.....	.05	\$0.06				
2.....	.06	.08	\$0.12			
2½.....	.06½	.10	.14			
3.....	.07	.12	.16			
3½.....	.08	.14	.18			
4.....	.09	.15	.21	\$0.34		
4½.....	.11	.17	.24	.36		
5.....	.13	.19	.26	.38		
5½.....	.15	.21	.28	.40		
6.....	.17	.23	.30	.42	\$0.46	\$0.75
7.....	.19	.27	.34	.45	.51	.83
8.....	.21	.31	.38	.50	.57	.91
9.....	.23	.35	.44	.56	.66	1.03
10.....	.26	.39	.50	.63	.75	1.15
12.....	.33	.48	.60	.75	.90	1.35
14.....	.41	.60	.75	.94	1.12	1.65
16.....	.49	.72	.90	1.12	1.35	1.95
18.....	.57	.82	1.00	1.28	1.50	2.13
20.....	.61	.90	1.15	1.44	1.72	2.33
22.....	.65	1.00	1.35	1.62	1.94	2.60
24.....	.69	1.10	1.55	1.80	2.16	2.85

In lacing cotton belt do not cut the fabric, but use a large awl for making the holes.


## RAWHIDE BELTING.

Width, Inches.	Price, per Foot.	Width, Inches.	Price, per Foot.	Width, Inches.	Price, per Foot.
1	\$0.10	5½	\$0.70	17	\$2.31
1¼	.13	6	.76	18	2.49
1½	.17	6½	.83	19	2.66
1¾	.20	7	.90	20	2.84
2	.23	8	1.02	21	3.02
2¼	.26	9	1.15	22	3.20
2½	.30	10	1.29	23	3.37
2¾	.33	11	1.42	24	3.54
3	.36	12	1.55	26	3.92
3½	.43	13	1.68	28	4.30
4	.50	14	1.82	30	4.64
4½	.56	15	1.98	32	5.00
5	.63	16	2.14		

## SEPARATOR STRAP BUCKLES.


### WROUGHT ROLLER.

Inches .....	2	2¼	2½	2¾
Per Gross, Japanned.....	\$6.50	7.00	7.80	9.00





# RUBBER WATER HOSE.



Internal Diameter, Inches.	2-PLY.	3-PLY.	4-PLY.	5-PLY.	6-PLY.
	Conducting, per Foot.	Hydrant, Per Foot.	Engine, Per Foot.	Engine, Per Foot.	Engine, Per Foot.
$\frac{1}{2}$	\$0.20	\$0.25	\$0.30	\$0.37	\$0.45
$\frac{3}{4}$	.25	.30	.37	.46	.55
1	.33	.40	.50	.62	.75
$1\frac{1}{4}$	.42	.50	.62	.77	.93
$1\frac{1}{2}$	.50	.60	.75	.93	1.12
2	.66	.80	1.00	1.25	1.50
$2\frac{1}{2}$	.83	1.00	1.25	1.56	1.87
3	.99	1.20	1.50	1.87	2.25
$3\frac{1}{2}$	1.15	1.40	1.75	2.18	2.62
4	1.32	1.60	2.00	2.50	3.00

## EXTRA FOR WINDING WATER HOSE WITH GALVANIZED STEEL WIRE.



	3-PLY.	4-PLY.	5-PLY.	6-PLY.
$\frac{1}{2}$ in., per foot.....	\$0.03	\$0.04	\$0.05	\$0.06
$\frac{3}{4}$ " " ".....	.04	.05	.06	.07
1 " " ".....	.05	.07	.08	.09
$1\frac{1}{4}$ " " ".....	.07	.08	.09	.10
$1\frac{1}{2}$ " " ".....	.08	.09	.10	.11
2 " " ".....	.10	.11	.12	.13
$2\frac{1}{2}$ " " ".....	.12	.13	.14	.15

# COTTON AND LINEN HOSE.



Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{4}$	$2\frac{1}{2}$	3
Cotton Hose, Rubber-lined .....	\$0.20	\$0.25	\$0.35	\$0.45	\$0.50	.....	\$0.60	\$0.65	\$0.70	.....
Linen Hose, Unlined.....	.....	.....	.16	.18	.20	\$0.23	.25	.27	.29	\$0.35
Linen Hose, Rubber-lined .....	.....	.....	.....	.40	.45	.....	.55	.60	.65	.....

In 50-foot lengths.


## COTTON MILL HOSE.—SEAMLESS WOVEN AND RUBBER LINED.

Internal Diameter, Inches.....	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Price per foot.....	\$0.45	.50	.60	.70	1.00



## COTTON FIRE HOSE.—SEAMLESS WOVEN AND RUBBER LINED.

Samples and prices furnished upon application.




FIRE HOSE.

# RUBBER SUCTION HOSE.

525

Internal Diameter, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
On Spiral Brass Wire, per foot.....	\$0.77	\$1.00	\$1.25	\$1.65	\$2.50
On Spiral Tinned Iron Wire, per foot.....	.70	.90	1.15	1.50	2.30



## LARGE RUBBER SUCTION HOSE.

Internal Diameter, Inches.....	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	8	10
On Spiral Tinned Iron, per foot.....	\$3.10	4.00	4.90	5.80	6.70	7.60	9.50	15.00	20.00



## "SMOOTH BORE" RUBBER SUCTION HOSE.

Internal Diameter, Inches.....	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	8	10
On Spiral Tinned Iron, per foot.....	\$2.60	3.50	4.50	5.50	6.50	7.50	8.50	10.50	16.50	22.50



## HARD RUBBER SUCTION HOSE.

Internal Diameter, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Price, per foot.....	\$0.55	0.65	0.75	0.93	1.13	1.50	1.88

## STEAM AND BREWERS' HOSE.

Internal Diameter, Inches .....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
3-Ply, per foot.....	\$0.43	\$0.51	\$0.67	\$0.85	\$1.02	\$1.34	\$1.66
4-Ply, per foot.....	.51	.67	.83	1.04	1.25	1.66	2.08
5-Ply, per foot.....	.63	.83	1.03	1.30	1.56	2.07	2.60
6-Ply, per foot.....	.76	1.00	1.24	1.56	1.87	2.49	3.12


Marlin Wound Steam Hose, 10 per cent. advance on list net.

## \*RUBBER TUBING.

Internal Diameter, Inches .....	$\frac{1}{8}$	$\frac{3}{16}$	$\frac{1}{4}$	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1
Plain, per foot.....	\$0.08	\$0.12	\$0.16	\$0.18	\$0.20	\$0.25	\$0.30	\$0.35	\$0.45
Cloth Inserted, per foot.....	.10	.14	.18	.20	.23	.28	.33	.38	.50


\* Made in 12-ft. lengths.

## HOSE REELS.




"THE DUDE REEL."

Finished in oil; one size only; capacity, 100 feet  $\frac{3}{4}$ -inch hose. It has 6-inch wheel; is made entirely of hard wood and is furnished with a hose-holder on top bar to hold nozzle in position when used as a fountain.



"FOUNTAIN REEL."


A stout Reel—stronger than the "Dude." Will carry 150 feet of  $\frac{3}{4}$ -inch hose.



"COLUMBIA REEL."

This is a new Reel, with drum and ratchet attachment; is painted vermillion color, striped and varnished; is a very fine looking Reel, stout and durable. Made entirely of hard wood.


## SWINGING HOSE RACKS.



SWINGING HOSE RACK.

No.		Price.
0	For 50 feet $1\frac{1}{2}$ or 2-inch, plain linen.....	\$7.00
00	For 50 feet $2\frac{1}{2}$ -inch, plain linen.....	7.00
1	For 100 feet $1\frac{1}{2}$ or 2-inch, plain linen.....	8.00
2	For 100 feet $2\frac{1}{2}$ -inch, plain linen.....	8.00
3	For 150 feet $1\frac{1}{2}$ or 2-inch, plain linen.....	9.00
4	For 150 feet $2\frac{1}{2}$ -inch, plain linen.....	9.00
3	For 50 feet $1\frac{1}{2}$ or 2-inch, lined linen or mill.....	9.00
4	For 50 feet $2\frac{1}{2}$ -inch, lined linen or mill.....	9.00
5	For 100 feet $1\frac{1}{2}$ or 2-inch, lined linen or mill.....	9.50
6	For 100 feet $2\frac{1}{2}$ -inch, lined linen or mill.....	10.00

Capacity, about 150 feet  $2\frac{1}{2}$ -inch linen hose, each..... \$10.00




PLAIN WALL HOSE REEL.



# HOSE NOZZLES.

527



No. 1.



No. 2.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Length, to Screw, inches.....	3	4	$4\frac{3}{4}$	$5\frac{3}{4}$	$6\frac{3}{4}$	$7\frac{1}{2}$
Length, to Wind, inches.....	$5\frac{1}{2}$	6	$6\frac{3}{4}$			
No. 1, Hose Pipe Threads, per dozen.....	\$4.00	\$5.00	\$12.00	\$18.00	\$26.40	\$37.00
No. 1, Iron Pipe Threads, per dozen.....	5.00	6.25	13.75	19.75	29.00	39.50
No. 2, to Wind, per dozen.....	4.00	5.00	12.00			

## HOSE PIPES.



PLAIN HOSE PIPE.



HOSE PIPE, SCREW TIP.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Length, inches.....	8	8	12	12	12	15
Per dozen.....	\$7.00	9.00	18.00	22.00	34.00	65.00

## WITH SCREW TIP.


Size, Inches.....	$\frac{3}{4}$	$\frac{3}{4}$	1	1	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{2}$	2	2	$2\frac{1}{2}$
Length, Inches.....	8	12	8	12	12	15	20	12	15	20	12	20	15
Per dozen.....	\$8.00	10.00	10.00	12.00	20.00	24.00	30.00	25.00	30.00	36.00	38.00	50.00	75.00

## COCK, LARGE END.




Size, Inches.....	$\frac{3}{4}$	$\frac{3}{4}$	$\frac{3}{4}$	$\frac{3}{4}$	1	1	1	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{2}$	2	2	$2\frac{1}{2}$	$2\frac{1}{2}$
Length, Inches.....	6	8	9	12	8	9	12	12	15	20	12	15	20	12	20	15	24
Per Dozen.....	\$11.00	13.00	18.00	18.00	15.00	20.00	20.00	40.00	45.00	55.00	55.00	60.00	80.00	80.00	110.00	150.00	200.00

## GEM NOZZLE.



SHOWING SPRAY.

Size, Inches.....	$\frac{3}{4}$	1
Per Dozen.....	\$10.00	15.00



SHOWING SOLID STREAM.

## BRASS HOSE COUPLINGS, ETC.



### COMMON HOSE COUPLING.



### STEAM HOSE COUPLING.

## COMMON HOSE COUPLINGS.

Size, inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3
Hose Pipe Thread, per dozen.....	\$2.40	\$2.40	\$4.40	\$10.00	\$14.00	\$24.00	\$48.00	\$75.00
Iron Pipe Thread, per dozen.....	2.65	2.65	4.65	10.50	15.00	26.00	50.00	76.00
Male or Female Half H. P. Thread, per dozen.....	1.80	1.80	3.00	7.20	9.60	16.20	31.80	50.00
Male or Female Half I. P. Thread, per dozen.....	1.80	1.80	3.25	7.80	10.80	17.40	32.80	52.00
Size, inches.....	$3\frac{1}{2}$	4	5	6	8			
Iron Pipe Thread, per dozen.....	\$120.00	150.00	250.00	350.00	504.00			

## STEAM HOSE COUPLINGS.

Size, inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Hose Pipe Thread, per dozen.....	\$15.00	\$15.00	\$18.00	\$24.00	\$30.00	\$42.00	\$72.00
Iron Pipe Thread, per dozen.....	15.50	15.50	19.00	25.50	32.00	44.00	75.00
Female Half Hose Pipe Thread, per dozen.....	10.00	10.00	12.00	16.00	20.00	28.00	48.00
" " Iron " " " " .....	10.35	10.35	12.75	17.00	21.50	30.00	50.00

## A. & W. WATER-TIGHT HOSE COUPLER.



**DISCONNECTED.**



CONNECTED.



No. 5.



No. 1.



No. 2.



No. 3



No. 4.

**DESCRIPTION.**

No. 1. For New Hose—With the use of No. 3, goes on end that attaches to either faucet or ground pipe. It is used with No. 2 for connecting two lengths of hose. No. 2. For New Hose—Used on nozzle end of hose, and can be connected with any nozzle by using the No. 4 as an intermediate. Used with No. 1 for connecting two lengths of hose. No. 3. For New and Old Hose—Screws on faucet, ground pipe or hose crook, on any of which it may be left permanently, and to it the hose is readily attached by the lever connections, Nos. 1 or 4. No. 4. For Old Hose—Screws into old style couplings on hose and attaches to Nos. 2 or 3. Used as an intermediate for connecting nozzle to Nos. 2 or 3.

## A. & W. HOSE COUPLERS AND CROOKS.


Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{2}$	2
Nos. 1 and 2, per dozen Sets.....	\$3.50	\$3.50	\$8.50	\$24.00	\$40.00
" 3 " 4, .....	3.50	3.50	8.50	24.00	40.00
No. 1, per dozen.....	2.40	2.40	5.00	16.50	28.00
" 2, .....	1.20	1.20	3.50	8.50	14.00
" 3, .....	1.20	1.20	3.50	8.50	14.00
" 4, .....	2.40	2.40	5.00	16.50	28.00
" 5, Hose Crook and Swivel, per dozen.....	4.00	4.00			

## HOSE NIPPLES.


529



MALE AND FEMALE.




Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Male, per dozen.....	\$3.50	3.50	5.00	9.00	10.00	14.00	28.00	40.00	50.00	75.00
Male and Female, per dozen...	\$3.50	3.50	5.00	9.00	10.00	14.00	28.00	40.00	50.00	75.00



MALE.

## HOSE REDUCERS AND HOSE BUSHINGS.

Size, Inches .....	$1 \times \frac{3}{4}$	$1\frac{1}{4} \times \frac{3}{4}$	$1\frac{1}{4} \times 1$	$1\frac{1}{2} \times 1\frac{1}{4}$	$2 \times 1\frac{1}{2}$	$2\frac{1}{2} \times \frac{3}{4}$	$2\frac{1}{2} \times 1$
Price, Hose Reducers, per dozen.....	\$6.50	\$10.00	\$10.00	\$12.00	\$18.00	\$30.00	\$30.00
Price, Hose Bushings, per dozen.....	6.50						



## HOSE CAPS.

Size, Inches.....	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Price, per dozen... ..	\$4.00	6.00	8.00	10.00	15.00	24.00	31.00	39.00	43.00



## GLOBE SUCTION BASKET, TO TIE ON.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Black .....	\$0.35	\$0.40	\$0.45	\$0.50	\$0.65	\$1.00	\$1.50
Galvanized Iron.....	.40	.45	.50	.60	.75	1.25	1.90
Brass.....	1.50	1.75	2.00	2.25	2.75	3.50	5.00




## HOSE PIPE SPRINKLERS.

Suitable for Hose Pipes, Inches ...	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
Price, per dozen.....	\$4.50	6.00	15.00	21.00	30.00
Diameter of Face, inches .....	2	2	3	$3\frac{1}{2}$	4



## SUCTION HOSE STRAINERS.

Size, Inches.....	2	$2\frac{1}{2}$	3	4	5	6
Price, Hose Thread, each.....	\$7.50	\$8.50	\$10.00			
Price, Iron Pipe Thread, each.....				\$19.00	\$31.00	\$46.00



## HOSE SPANNERS.


MALLEABLE IRON.

Size, Inches.....	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$
Price, each.....	\$0.12	.15	.20	.25





## HOSE GOODS.



HOSE STRAP.

## CALDWELL'S HOSE STRAPS.



FASTENER.

Number.....	2	4	6	8	10	12	14	16	18	20
Size Hose.....	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{3}{4}$	1	1	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{1}{2}$
Length, Inches.....	$3\frac{3}{8}$	$3\frac{3}{4}$	$4\frac{1}{8}$	$4\frac{1}{2}$	5	$5\frac{3}{8}$	6	$6\frac{3}{8}$	$6\frac{3}{4}$	$7\frac{1}{8}$
Price, per dozen.....	\$0.40	.40	.60	.60	.80	.80	1.00	1.00	1.20	1.20

## CALDWELL'S STRAP FASTENERS.


Number.....	1	2
Size.....	$\frac{1}{2}$ to 1 inch	$1\frac{1}{4}$ to $1\frac{1}{2}$ inches.
Price, each.....	\$0.50	.75

## HOSE CLAMPS.



COMMON HOSE CLAMP.

Size, Inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Common Hose Clamps, per dozen.....	\$1.50	\$1.50	\$2.00	\$2.50	\$3.00	\$4.00	\$7.00	\$10.00	\$24.00	\$30.00
Sherman Hose Clamps, per dozen.....	1.50	1.50	2.00	2.50	3.00	4.00	.....	.....	.....	.....



SHERMAN HOSE CLAMP.


## HOSE MENDERS OR SPLICES.



WOODEN.




MALLEABLE IRON.



SHERMAN SEAMLESS BRASS.

Size, Inches.....	$\frac{3}{4}$	1
Sherman Seamless Brass Menders, per dozen.....	\$1.20	.....
Wooden Hose Menders, per dozen.....	.40	.....
Malleable Iron Hose Menders, per dozen.....	.60	\$0.75

## UNDERWRITERS' HOSE PIPES.



UNDERWRITERS' HOSE PIPE

Size, Inches.....	2	$2\frac{1}{2}$	$2\frac{1}{2}$	$2\frac{1}{2}$
Length, inches.....	20	24	30	36
Wound and Painted, each.....	\$9.00	\$11.00	\$12.00	\$15.00
Plain Brass, each.....	7.50	9.50	11.00	13.50
Wound and Painted, without Handles, each.....	6.50	8.50	10.00	12.50
Rubber Tube, Swivel Handles, each.....	.....	.....	15.00	18.00
Leather Tubes, Swivel Handles, each.....	.....	.....	.....	18.00

# LAWN SPRINKLERS.


531



## FOUR AND EIGHT-ARM LAWN SPRINKLERS.

Description.	Single Head, Four Arms.	Double Head, Eight Arms.
N. P. Head, each.....	\$6.50	\$7.50
N. P. Head, each, with Basket and Ball.....	13.00	14.00


## "COMET" SPRINKLER.



Any spray nozzle can be used with it, which can be inclined at any angle, thus throwing spray or solid stream exactly as desired. The nozzle is not furnished.

Price, each.....\$1.50


## "CYCLONE" SPRINKLER.



It can be adjusted to throw a full or half circle, permitting lawn to be sprinkled without wetting sidewalk or passers-by. Will throw as much water on the half circle as on the full.


Price, each.....\$2.00

## "IMPROVED COLUMBIA" SPRINKLER.



Price, each.....\$2.25


## "NEPTUNE" SPRINKLER.



It will run with high or low pressure. Runs continuously, and will not get out of order. It distributes water evenly over a large circle.

Price, each.....\$2.00

## BLAKE SPRINKLER.



This Sprinkler has a  $\frac{3}{4}$ -inch thread cut on base so as to screw directly on to hose coupling.


Price, each.....\$0.50

## AMAZON SPRINKLER. TO ATTACH TO END OF NOZZLE.



Price, each.....\$0.50

## MERRILL SPRINKLER.



Price, each.....\$1.00





# SMITH'S PATENT BELT FASTENERS.

Are neatly packed in boxes of 100 each. Four sizes are made. The cuts show the exact sizes as regards the distances between rivets. Patented September 20, 1881; August 15, 1882; June 10, 1884. Patented in Canada, 1885.

They will successfully hold belts running on patent rolls in flour mills, under tighteners and on fastest motion pulleys. We do not ask our customers to put them in easy places, but warrant them to hold on any belt that can be run. We challenge any other fastener to hold as well, run as smoothly and be as easy on the belt.

## PRICE LIST.

No. 1, per box of 100.....	\$2.00
No. 2, per box of 100.....	1.75
No. 3, per box of 100, for thin and single belting.....	1.50
No. 3, per box of 100, for thick and double belting.....	1.50
No. 4, per box of 100, for thin and single belting.....	1.25
No. 4, per box of 100, for thick and double belting.....	1.25
Patented Combination Punches each.....	1.25
Reamers.....	.35
"Uncle John's" Double Set and Shaper.....	.25



## CHICAGO BELT HOOKS.

Put up in boxes of 200 each, all sizes..... \$2.50 per 1,000


## BELT LACE HOLE PRO-TECTOR.



It saves time in lacing, strengthens the belting when laced.

Put up in boxes of one gross each, one size, per box..... \$0.50

## BRISTOL PATENT STEEL LACING.



Packed 100 inches in a box in assorted lengths.

## ELLIOTT'S "1880" LACE CUTTER.



Patented Sept. 3, 1878.

Improved May 1, 1880.

Price, each..... \$0.50

No.	Used For	Price per Box.
00	Split and extra light Leather Belts, 1-16 to 1/8-in. thick.....	\$1.00
0	Split Leather Belts, 1/8 to 3-16-in. thick.....	1.00
1	Single Leather Belts, 3-16 to 1/4 in. thick.....	1.50
2	Heavy Wide Single Leather Belts, 1/4 to 5-16-in. thick.....	2.00
3	Double Leather Belts, 5-16 to 3/8-in. thick.....	2.50
4	Heavy Double Leather Belts, 3/8 to 7-16-in. thick.....	3.00
5	Extra Heavy Double Leather Belts, 7-16 to 9-16-in. thick.....	3.50
100	Light Rubber and Cotton Belts, 1-16 to 1/8-in. thick.....	1.10
10	2-Ply Rubber and Cotton Belts, 1/8 to 3-16-in. thick.....	1.10
11	3-Ply Rubber and Cotton Belts, 3-16 to 1/4-in. thick.....	1.65
12	4-Ply Rubber and Cotton Belts, 1/4 to 5-16-in. thick.....	2.20
13	5-Ply Rubber and Cotton Belts, 5-16 to 3/8-in. thick.....	2.75
14	6-Ply Rubber and Cotton Belts, 3/8 to 7-16-in. thick.....	3.30
15	7 & 8-Ply Rubber and Cotton Belts, 7-16 to 9-16-in. thick.....	3.85

## LOTHROP'S PATENT BELT AWL.

A great convenience for lacing belts.



Price, each..... \$0.15



# STEAM PACKING.

533

## CLOTH INSERTION—CLOTH ON ONE OR BOTH SIDES.

There is one ply of cloth to every 1-16-inch thickness.

Three cents per pound additional will be charged for each extra ply of cloth.



The cloth, whether used as an insertion or on the outside, counts as one ply.

All cloth insertion or plain packing is made in rolls about one yard wide and twenty yards long.



Thickness, Inches.....	$\frac{1}{64}$	$\frac{1}{32}$	$\frac{1}{16}$	$\frac{3}{32}$	$\frac{1}{8}$	$\frac{3}{16}$	$\frac{1}{4}$
One-Ply, per pound.....	\$0.70	\$0.65	\$0.60				
Two-Ply, per pound.....			.63	\$0.58	\$0.55		
Three-Ply, per pound.....				.61	.58	\$0.55	
Four-Ply, per pound.....					.61	.58	\$0.55

## SQUARE AND ROUND DUCK PACKING.



Price, per pound.....\$0.85

Made in lengths of 12 and 20 feet.

## SQUARE DUCK PACKING, RUBBER BACK.



Price, per pound.....\$1.00

Made in lengths of 12 and 20 feet.

## SPECIAL FINE HARD PUMP PACKING.

This packing is made from a superior quality of fine duck and white rubber, for packing water pistons or plungers in steam pumps, and is highly recommended by all manufacturers of steam pumps.

Made in lengths of 12 feet.



Price, per pound..... \$1.00

## PURE SHEET RUBBER PACKING.

Thickness,  $\frac{1}{64}$ ,  $\frac{1}{32}$ ,  $\frac{1}{16}$ ,  $\frac{3}{32}$ ,  $\frac{1}{8}$ ,  $\frac{3}{16}$ ,  $\frac{1}{4}$  inch.

Price, per pound.....\$1.50

Pure Sheet Packing or Valve Gum is made 36 inches wide, of any thickness or length desired.

# PACKING.

## RAINBOW SHEET PACKING.

This Packing is especially adapted for very high pressure, and is not affected by any degree of steam heat. It will not harden under any degree of heat, or blow out under the highest pressure, and will make an air, steam, hot or cold water joint equally well. It is not affected by oils, ammonia liquors, steam, heat or alkalies.

Made in rolls, about 200 pounds each.  $\frac{1}{32}$ ,  $\frac{1}{16}$ ,  $\frac{3}{32}$ ,  $\frac{1}{8}$ ,  $\frac{5}{16}$ ,  $\frac{1}{4}$ ,  $\frac{3}{8}$ ,  $\frac{1}{2}$  inch.


Price, per lb..... \$0.80

## ECLIPSE SECTIONAL RAINBOW GASKET.

WILL FIT ANY HANDHOLE OR MANHOLE IN THE WORLD.

To form a Gasket, cut piece the length required, join the ends with the tube furnished, and wind the joint with tape to keep it in place, as shown in cut.

### LENGTH AND WEIGHT PER BOX.



$\frac{3}{8}$ inch diameter	36 feet	$3\frac{1}{4}$ lbs.
$\frac{1}{2}$ " "	36 "	$5\frac{1}{4}$ "
$\frac{5}{8}$ " "	24 "	6 "
$\frac{3}{4}$ " "	18 "	$5\frac{1}{4}$ "

$\frac{3}{8}$  in. for pipe unions,  $\frac{1}{2}$  in. for handhole plates,  $\frac{5}{8}$  and  $\frac{3}{4}$  in. for manhole plates.

Price, per lb..... \$1.00

## ITALIAN HEMP PACKING.

B Quality, per lb..... \$0.20  
A " " ..... .25

An excellent Packing for general use.

## HYDRAULIC PACKING.

Of pure rubber, made square, and in lengths of 12 feet.

Price, per lb..... \$1.50

## JUTE PACKING.

For caulking purposes, 100-lb. bales.

Price, per lb..... \$0.10

## JENKINS STANDARD 1896 PACKING.

Jenkins Standard Packing will pack a joint no matter how rough or uneven the surface is, as the packing vulcanizes in place, and is frequently called Jenkins Metal. 36-inch wide, cut in any length. Thickness,  $\frac{1}{32}$ ,  $\frac{1}{16}$ ,  $\frac{3}{32}$ ,  $\frac{1}{8}$ ,  $\frac{5}{16}$  inch.

Accept no Packing as Jenkins unless stamped with their trade mark.

Price, per lb..... \$0.80



## "PLUMBAGO" SHEET PACKING.

This Packing is similar to the Salamanda, possessing all its characteristics, but in a less degree. It is offered at a lower price, and is guaranteed to do good service. Directions for use, same as for Salamanda.

List Price, per lb..... \$0.65



## TUCKS ROUND PACKING.

Made of heavy frictioned cotton duck, wrapped around a rubber core or centre, and vulcanized solidly together. Made in 12 ft. lengths.

List Price, per lb..... \$0.85

## GARLOCK PACKINGS, FOR STEAM, GAS, WATER AND AMMONIA.

### GARLOCK'S ELASTIC RING PACKING.



(Patented.)

Elastic Ring Packing is made to order only in rings an exact fit to the rod and box, and is subjected to a perfect lubricating process. The elastic ring is made any size, from  $\frac{5}{8}$ -inch to 30 inches diameter.

Price, per pound.....\$1.20

### GARLOCK'S SECTIONAL RING PACKING.



(Patented.)

Sectional Ring Packing is especially adapted for rods out of line, cut rods, flat bottom stuffing boxes, ammonia, and places that are very difficult to keep tight. Made to order only.

We can only send the Sectional Packing when the rim of the packing ring is quite heavy.

Price, per pound.....\$1.20

### GARLOCK'S SPIRAL PACKING.



Garlock's Spiral Packing commends itself to the user because it is practically the same as Garlock's Ring Packing. It is manufactured of same material and with same process. In ordering Spiral Packing give only the exact space between rod and stuffing box. State the number of boxes wanted of each size. Each box contains 12 feet, and we only furnish full boxes. It is made in sizes from  $\frac{1}{8}$ -inch to 2 inches.

Price, per pound.....\$1.20

## GENUINE EMPIRE PACKING.

The original and only Genuine Empire Round Gum Core Packing. In all sizes, from  $\frac{1}{4}$  to  $1\frac{1}{2}$ -inch in diameter. In reels from 25 to 40 pounds. The Genuine Empire Packing has a yellow label attached to the packing. All other so-called Empire Packings are cheap imitations, of which beware.



Price, per pound.....\$0.50

## EUREKA PISTON PACKING.

Eureka Oblong Gum Core Packing, made in all sizes, from  $\frac{1}{4}$  to  $1\frac{1}{2}$  inches diameter.

In boxes of 5 pounds each. Bales 30 to 50 pounds.



Price, per pound .....\$0.75

## SQUARE BRAIDED FLAX PACKING.

Warranted best quality of Pure Irish Flax, free from Hemp or Jute.

In all sizes, from  $\frac{1}{4}$  to  $1\frac{1}{2}$  inches.

In boxes from 5 to 15 pounds each, according to size of packing.




Price, per pound.....\$0.85



# CLOTH INSERTION GASKETS AND RINGS.

These Gaskets are made under improved method and are superior to all others.

## STOCK SIZES.



Inside Measure.	Flange	Thick-ness.	Inside Measure.	Flange	Thick-ness.	Inside Measure.	Flange	Thick-ness.	Inside Measure.	Flange	Thick-ness.
12 1/2 x 16	1 1/4	1/4	10 1/2 x 15	1 1/4	1/4	9 x 12	1 1/4	1/4	3 1/2 x 6	3/4	3-16
12 1/2 x 15	1 1/4	1/4	10 1/2 x 14 1/2	1 1/4	1/4	8 x 14	1 1/4	1/4	3 1/2 x 5 1/2	3/4	3-16
12 x 16	1 1/4	1/4	10 1/2 x 14	1 1/4	1/4	8 x 11 1/2	1 1/4	1/4	3 1/2 x 5	3/4	3-16
12 x 15 1/2	1 1/4	1/4	10 x 16	1 1/4	1/4	8 x 11	1 1/4	1/4	3 1/2 x 4 1/2	3/4	3-16
12 x 15	1 1/4	1/4	10 x 15	1 1/4	1/4	7 x 9	1	3-16	3 1/2 x 4	3/4	3-16
11 1/2 x 16	1 1/4	1/4	10 x 15 1/2	1 1/4	1/4	6 1/2 x 7 1/2	1	3-16	3 1/2 x 5 1/2	3/4	3-16
11 1/2 x 15 1/2	1 1/4	1/4	10 x 14 1/2	1 1/4	1/4	6 1/2 x 7	1	3-16	3 x 5	3/4	3-16
11 1/2 x 15	1 1/4	1/4	10 x 14	1 1/4	1/4	6 x 10	1	3-16	3 x 4 1/2	3/4	3-16
11 1/2 x 14	1 1/4	1/4	9 1/2 x 15 1/2	1 1/4	1/4	6 x 8	1	3-16	3 x 4	3/4	3-16
11 1/2 x 14 1/2	1 1/4	1/4	9 1/2 x 14	1 1/4	1/4	6 x 7 1/2	1	3-16	2 1/2 x 4 1/2	5/8	3-16
11 x 16	1 1/4	1/4	9 1/2 x 12 1/2	1 1/4	1/4	5 x 7	1	3-16	2 1/2 x 4	5/8	3-16
11 x 15 1/2	1 1/4	1/4	9 1/2 x 15	1 1/4	1/4	4 1/2 x 6 1/2	1 7/8	3-16	2 1/2 x 3 1/2	5/8	3-16
11 x 15	1 1/4	1/4	9 1/2 x 14 1/2	1 1/4	1/4	4 1/2 x 6	1 7/8	3-16	2 1/2 x 3	5/8	3-16
11 x 14 1/2	1 1/4	1/4	9 x 15	1 1/4	1/4	4 1/2 x 5 1/2	1 7/8	3-16	2 x 3 1/2	5/8	3-16
11 x 14	1 1/4	1/4	9 x 14 1/2	1 1/4	1/4	4 x 6	1 3/4	3-16	2 x 3	5/8	3-16
10 1/2 x 16	1 1/4	1/4	9 x 14	1 1/4	1/4	4 x 5 1/2	1 3/4	3-16			3-16
10 1/2 x 15 1/2	1 1/4	1/4	9 x 12 1/2	1 1/4	1/4	4 x 5	1 3/4	3-16			3-16


Price, 1-16 or less in thickness, per pound.....

\$1.25

Price, 3-32 and upwards, per pound.....

1.00

There is one ply of Cloth to every 1-16 inch thickness. Five cents per pound additional will be charged for each extra ply of cloth. The cloth, whether used as an insertion or on the outside, counts as one ply. Orders for special size and pattern made up on short notice.



## PURE RUBBER GASKETS AND RINGS.

Price, per pound.....

\$1.50

## FIBROUS GASKETS AND RINGS.

Price, 1/8 inch or less, in thickness, per pound.....

\$0.90

Price, 5-32 inch and upwards, per pound.....

.80

## PURE RUBBER VALVES.



PURE RUBBER VALVES.


Diameter, Inches.....	2	2 1/2	3	3 1/2	4	4 1/2	5	5 1/2	6
Thickness, inches.....	1 1/2	1 1/2	1 1/2	1 1/2	5/8	5/8	5/8	5/8	3/4
Size of Hole, inches.....	1/2	1/2	1/2	1/2	5/8	5/8	5/8	5/8	5/8

We have in stock three grades: Hard, for hot water; Medium and Soft, for cold water. Special Valves made to order. Price, per pound, \$1.50.

# METAL AND MAN-HOLE GASKETS, ETC.

537

FOR UNIONS, FLANGE UNIONS,  
AND PLAIN FLANGE JOINTS.



FOR STEAM, AIR, GAS, OR WATER  
PIPE CONNECTIONS.

## CORRUGATED METAL GASKETS.


Size, Inches.....	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$
For Unions, each.....	\$0.02	\$0.02	\$0.02	\$0.02	\$0.03	\$0.04	\$0.05	\$0.06	\$0.06	\$0.11	\$0.13	\$0.18	.....
For Flange Unions, each.....				.03	.03	.05	.06	.08	.09	.12	.18	.19	\$0.27
For Flanged Fittings, each.....								.16	.23	.24	.25	.26	.29


Size, Inches .....	5	6	7	8	9	10	12	14	16	18	20	22	24
For Flange Unions, each.....	\$0.27	\$0.39	\$0.44	\$0.49	\$0.84	\$0.70	\$0.87						
For Flanged Fittings, each .....	.30	.33	.67	.74	.92	.94	\$1.37	\$1.51	\$1.79	\$1.93	\$2.10	\$2.36	\$2.55



OVAL



ROUND SHOULDER



EGG SHAPE


## METAL MAN-HOLE GASKETS.

In ordering Man-Hole Gaskets, specify shape desired, and where possible send template. We carry in stock Gaskets for all standard makes of boilers.


## METAL HAND-HOLE GASKETS.

Size, Inches.....	$2\frac{1}{2} \times 3\frac{1}{2}$	2 x 4	$3\frac{1}{2} \times 4\frac{1}{2}$	4 x 5	$4\frac{1}{2} \times 5\frac{1}{2}$	4 x 6	5 x 7
Each .....	\$0.15	.20	.25	.30	.40	.45	.50

For Babcock & Wilcox, 6 x 8, 50 cents; Campbell & Zell, 4 x 11, 30 cents; Standard, 4 x 11, 30 cents; Gill, 4 x 11, 30 cents; Edgemoor's Oval, 20 cents; Heine, 15 cents.



FULLER BALL.




BIBB WASHERS.

Boss Washers, for Compression Bibbs, $\frac{3}{8}$ , $\frac{1}{2}$ , $\frac{5}{8}$ , $\frac{3}{4}$ -inch, per 100 .....	\$0.75
Fiber Washers, for Compression Bibbs, $\frac{3}{8}$ to 1-inch, per 100.....	.75
Rubber Hose Washers, $\frac{3}{4}$ -inch, per 100.....	.75
Paper Boiler Coupling Washers, per 100.....	.75
Gauge Glass Washers, per dozen.....	.12

# PIPE COVERINGS, ETC.

## ASBESTOS AND HAIR-FELT SECTIONAL COVERING.

FOR PIPES, BOILERS, HEATERS, TANKS, ETC.



Made in sections 3 feet long to fit all size pipes. Anyone can apply it.


Inside Dia. of Pipe, In.	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Price, per Lineal Foot....	\$0.17	.18	.20	.21	.23	.26	.30	.33	.35	.39	.42	.47	.53	.58	.64	.70	.81

Special Covering made in sheets. Price, 25 cents per square foot. Fittings furnished for above.

## REED'S ASBESTOS AND WOOLEN-FELT SECTIONAL COVERING.

FOR STEAM AND WATER PIPES, BOILERS, HEATERS, TANKS, ETC.

### SIZES AND PRICE LIST PER LINEAL FOOT.



Made in sections 3 feet long to fit all size pipes. Anyone can apply it.

Ins. Dia. Pipe, In.	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	6	7	8	9	10	12
Price, per Lineal ft.	\$0.17	.19	.21	.23	.25	.27	.31	.35	.39	.41	.45	.50	.56	.65	.72	.78	.87	1.00
Price of Elbow Covers (Net).....		\$0.25	.25	.25	.25	.27	.30	.34	.38	.43	.47	.50	.56	.65	.72	.....	.....	.....
Price of Tee Covers (Net).....		\$0.25	.28	.30	.32	.35	.40	.46	.52	.58	.63	.68	.77	.88	.96	.....	.....	.....

Special prices on Covering, made in sheets, to fit boilers, heaters, etc.

## MINERAL WOOL.

Price, per Pound .....\$.....

## HAIR FELT.

IN ROLLS 50 FEET LONG AND 6 FEET WIDE.

$\frac{1}{2}$ Inch Thick, per square foot.....	\$0.08
$\frac{3}{4}$ Inch Thick, per square foot.....	.09 $\frac{1}{2}$
1 Inch Thick, per square foot.....	.11

## ASBESTOS WICK PACKING.

For packing small valves, pumps, etc. Put up in  $\frac{1}{4}$ ,  $\frac{1}{2}$  and 1-pound balls, and on 5 and 10-pound spools.

Price, per pound.....\$.....

## ASBESTOS STEAM ROPE PACKING.

For packing piston rods, valve stems, etc. On reels containing 15, 25 and 50 pounds each.

Price,  $\frac{1}{4}$  to 2 Inches Diameter, per pound.....\$.....

## ASBESTOS MILL BOARD.

Made in sheets 40 x 40 inches;  $\frac{1}{32}$  to  $\frac{1}{2}$  inch thick.

The approximate weights of sheets are as follows:

Thickness,  $\frac{1}{32}$ ,  $\frac{1}{16}$ ,  $\frac{1}{8}$ ,  $\frac{3}{16}$ ,  $\frac{1}{4}$ ,  $\frac{5}{16}$ ,  $\frac{1}{2}$  inch.

Weights,  $1\frac{1}{4}$ ,  $3\frac{1}{2}$ ,  $7\frac{1}{2}$ ,  $10\frac{1}{2}$ , 14, 21, 28 pounds.

Price, per pound.....\$.....

## ASBESTOS PAPER AND CEMENT.

Building Felt, in rolls about 75 lbs., weight 10 lbs. to 100 sq. ft., per lb. \$0.10

Sheathing, in rolls about 75 lbs., weight, 6 pounds to 100 sq. ft., per lb. .11

Hot Blast, in barrels or bags, each..... 4.00

Cement Felting, in barrels or bags, each..... 3.00

## CANDLE WICK.

IN 5-POUND BALES.

Price, per pound.....\$0.40



# ASBESTOS PIPE COVERING.

539

## ASBESTOS MAGNESIA MOULDED BLOCKS.

There are many large surfaces such as boilers, stills, domes, heaters, etc., that cannot be covered with the sectional covering and for this work we especially make moulded blocks, which are easily applied to the surface and can be securely and cheaply fastened by the use of a large mesh wire screen. To make a more presentable appearance this screen can be covered with a thin coat of our asbestos cement felting, thus giving the work a smooth finished appearance. Special sizes, shapes and thicknesses made to order. Made in blocks or slabs three or four inches wide, eighteen inches long and one or one and one-half inches thick. Straight or beveled edges.

Price per square foot, 1 inch thick .....	\$0.24
Price per square foot, 1½ inch thick .....	.32

## W. B. PIPE COVERING.



W. B. Pipe Covering is the perfection of insulating protection for steam pipes and all heated surfaces. There are no better non-conductors of heat known than asbestos and wool felt, and in W. B. Covering these have been combined, producing the best results, there being consecutive layers of asbestos (about one-eighth of an inch thick) about the pipe, outside of this the wool felt with a canvas cover or jacket. This covering is easily applied, is removable, and lasts as long as the pipes themselves. Will not crack, crumble or fall away from the pipes when necessary staples are used in applying.

## PRICE LIST "EUREKA" AND W. B. PIPE COVERING AND FITTINGS.

Size, Inches.	Covering per ft.	Ells.	Tees.	Valves.	Crosses.
1½	\$0.20	\$0.25	\$0.33	\$0.25	\$0.35
¾	.22	.25	.33	.25	.44
1	.23	.25	.33	.25	.44
1¼	.24	.25	.33	.25	.44
1½	.25	.25	.33	.25	.44
2	.27	.27	.36	.27	.50
2½	.31	.31	.41	.41	.54
3	.36	.36	.48	.48	.62
3½	.40	.40	.53	.53	.70
4	.44	.44	.59	.59	.80
4½	.47	.47	.63	.63	.85
5	.50	.50	.67	.67	.95
6	.58	.58	.77	.77	1.15
7	.70	.70	.90	.90	1.25
8	.77	.77	1.00	1.00	1.45
9	.84	.84	1.15	1.15	1.60
10	1.00	1.00	1.30	1.30	1.75
12	1.20	1.20	1.60	1.60	1.90

Use Asbestos Cement Felting for fittings larger than 12 inches, and for all flanged fittings.


Our Moulded Covering for high pressure is made extra thick for large pipes.

## "EUREKA" PIPE COVERING.

For all low pressure steam pipes and hot water pipes we consider this to be an excellent covering, filling all requirements. It is made of wool felt and asbestos. Sections three feet long, canvas covered, with fittings for ells, tees, valves, etc., of same material.

## ASBESTOS MOULDED COVERING.

This Covering is made of asbestos fibre and other light non-conductive materials. It is very strong; is absolutely fire-proof and is adapted for highest steam pressure. It will not crack, and is made to fit pipes of all diameters, from ½ inch upward. The fittings are furnished of the same materials and fit perfectly. It can be easily applied to hot or cold pipes by any practical man. We always send with this covering sufficient metal bands to securely fasten it to the pipes.



## PRICE LIST OF MOULDED COVERING.

Size, Inches.	Covering.	Ells.	Tees.	Valves.
1½ to 3¼	\$0.20	\$0.24	\$0.27	\$0.20
1 " 1¼	.21	.24	.30	.22
1½	.23	.24	.33	.24
2	.26	.27	.36	.27
2½	.29	.29	.39	.39
3	.32	.32	.45	.45
3½	.35	.35	.50	.50
4	.38	.38	.55	.55
4½	.43	.43	.61	.61
5	.49	.49	.67	.67
6	.56	.56	.73	.73
7	.64	.64	.82	.82
8	.70	.70	.91	.91
9	.77	.77	1.03	1.03
10	.85	.85	1.15	1.15
12	1.00	1.00	1.30	1.30

## EMERY WHEELS.



## SIZES AND PRICES.

Diameter in Inches.	THICKNESS OF WHEELS IN INCHES.														No. of Revolutions per Minute.
	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	
3	\$0.50	\$0.63	\$0.75	\$0.87	\$0.95	\$1.10	\$1.25	\$1.35	\$1.45	\$1.60	\$1.85	\$2.10	\$2.60	\$3.00	7,400
4	.80	.95	1.10	1.23	1.35	1.60	1.90	2.20	2.50	2.75	3.25	3.85	4.60	5.00	5,450
5	1.00	1.20	1.40	1.60	1.80	2.10	2.60	3.00	3.45	3.80	4.65	5.40	6.40	7.40	4,400
6	1.40	1.58	1.75	2.13	2.50	3.05	3.70	4.30	5.00	5.60	6.90	8.25	9.50	11.00	3,600
7	1.82	2.08	2.30	2.73	3.15	3.95	5.00	5.60	6.40	7.25	8.90	10.55	11.10	12.60	3,150
8	2.12	2.36	2.60	3.10	3.60	4.50	5.70	6.40	7.60	8.30	10.20	12.05	14.00	16.00	2,750
9	2.50	2.83	3.15	3.50	3.85	4.90	6.80	8.05	9.25	10.50	12.95	15.40	19.00	21.75	2,450
10	3.00	3.35	3.70	4.40	5.10	6.60	8.10	9.50	11.00	12.40	15.35	18.15	21.00	23.80	2,200
12	3.50	3.75	4.00	5.00	6.00	7.40	9.00	10.70	12.75	14.05	17.40	20.75	24.25	27.50	1,850
14	.....	.....	6.20	7.45	8.70	10.70	13.25	15.20	17.80	19.50	24.20	26.75	28.70	30.70	1,600
16	.....	.....	.....	.....	11.00	13.70	16.90	19.40	22.00	25.00	30.80	36.50	43.00	48.75	1,400
18	.....	.....	.....	.....	13.75	17.00	21.75	24.50	28.75	32.00	39.50	47.00	54.50	62.00	1,250
20	.....	.....	.....	.....	.....	20.00	25.00	29.00	34.00	38.00	47.00	56.00	66.00	75.00	1,100
22	.....	.....	.....	.....	.....	.....	29.87	35.50	41.12	46.75	58.80	69.25	80.50	91.75	1,000
24	.....	.....	.....	.....	.....	.....	.....	43.00	50.00	57.00	71.00	85.00	99.00	113.00	925
26	.....	.....	.....	.....	.....	.....	.....	51.00	59.00	67.00	83.00	99.00	115.00	131.00	775
30	.....	.....	.....	.....	.....	.....	.....	.....	.....	87.50	109.00	131.00	153.00	175.00	735
36	.....	.....	.....	.....	.....	.....	.....	.....	.....	127.00	157.00	188.00	219.00	250.00	550

## DIRECTIONS FOR ORDERING.

In ordering, state the substance the wheel is to cut and tell whether the work is rough, sharp points, thin edges or smooth surface; and whether the wheel is to be used on the side or face. Give also diameter, size, thickness of arbor and shape of wheel. Wheels should be mounted so as to run truly and steadily, with flanges of generous size, and always with rubber or leather washers between flanges and wheel. The wheel should fit arbor loosely, to allow for the expansion, and in no case should arbor be driven into spindle after the wheel has been tightly screwed upon same, as the liability to crack the wheel by a blow on end of arbor is very great. Better adjust the arbor to the spindle before putting on the wheel.

## EMERY WHEEL DRESSERS.



HUNTINGTON.


For truing, shaping, sharpening and removing glaze from solid Emery Wheels running at full speed.

## PRICES.

Patent Emery Wheel Dresser (2 sets of Cutters).....	\$2.50
Extra Cutters, per set.....	.40

# LOCOMOTIVE JACK SCREWS.

541



## PRICE LIST.

Diameter of Screw.	Height of Stand.	Price.	Diameter of Screw.	Height of Stand.	Price.
1 1/4 inches.	4 inches	\$2.90	2 inches	24 inches	\$13.50
1 1/4 "	6 "	3.10	2 1/4 "	6 "	7.00
1 1/4 "	8 "	3.40	2 1/4 "	8 "	7.50
1 1/4 "	10 "	3.80	2 1/4 "	10 "	8.25
1 1/4 "	12 "	4.20	2 1/4 "	12 "	9.00
1 1/4 "	14 "	4.60	2 1/4 "	14 "	10.00
1 1/2 "	4 "	3.25	2 1/4 "	16 "	11.00
1 1/2 "	5 "	3.50	2 1/4 "	18 "	12.00
1 1/2 "	6 "	3.75	2 1/4 "	20 "	13.25
1 1/2 "	8 "	4.25	2 1/4 "	22 "	14.50
1 1/2 "	10 "	4.75	2 1/4 "	24 "	15.75
1 1/2 "	12 "	5.25	2 1/2 "	6 "	7.75
1 1/2 "	14 "	6.00	2 1/2 "	6 1/2 "	8.00
1 1/2 "	6 "	6.75	2 1/2 "	8 "	8.75
1 3/4 "	6 "	4.50	2 1/2 "	10 "	9.75
1 3/4 "	8 "	5.00	2 1/2 "	12 "	10.75
1 3/4 "	10 "	5.75	2 1/2 "	14 "	12.00
1 3/4 "	12 "	6.25	2 1/2 "	16 "	13.25
1 3/4 "	14 "	6.75	2 1/2 "	18 "	14.50
1 3/4 "	16 "	7.50	2 1/2 "	20 "	15.75
1 3/4 "	18 "	8.50	2 1/2 "	22 "	17.00
2 "	5 "	5.00	2 1/2 "	24 "	18.25
2 "	6 "	5.25	2 1/2 "	28 "	22.00
2 "	8 "	6.00	2 1/2 "	32 "	26.00
2 "	10 "	6.75	3 "	14 "	19.50
2 "	12 "	7.50	3 "	16 "	20.75
2 "	14 "	8.25	3 "	18 "	22.00
2 "	16 "	9.25	3 "	20 "	23.25
2 "	18 "	10.25	3 "	22 "	24.50
2 "	20 "	11.50	3 "	24 "	25.75
2 "	22 "	12.50	3 "	30 "	30.00



LAG SCREWS.

PRICE PER HUNDRED.

(Adopted September 20, 1899, to take effect October 1, 1899.)




Length, Inches.	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$ and $\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1
$1\frac{1}{2}$	\$2.25	\$2.70	\$3.15	\$3.75				
2	2.45	2.96	3.47	4.11	\$5.00			
$2\frac{1}{2}$	2.65	3.22	3.79	4.47	5.50	\$7.90		
3	2.85	3.48	4.11	4.83	6.00	8.60		
$3\frac{1}{2}$	3.05	3.74	4.43	5.19	6.50	9.30	\$12.50	\$18.20
4	3.25	4.00	4.75	5.55	7.00	10.00	13.50	19.50
$4\frac{1}{2}$	3.45	4.26	5.07	5.91	7.50	10.70	15.50	20.80
5	3.65	4.52	5.39	6.27	8.00	11.40	16.50	22.10
$5\frac{1}{2}$	3.85	4.78	5.71	6.63	8.50	12.10	17.50	23.40
6	4.05	5.04	6.03	6.99	9.00	12.80	18.50	24.70
$6\frac{1}{2}$			6.35	7.35	9.50	13.50	19.50	26.00
7			6.67	7.71	10.00	14.20	20.50	27.30
$7\frac{1}{2}$			6.99	8.07	10.50	14.90	21.50	28.60
8			7.31	8.43	11.00	15.60	22.50	29.90
9			7.95	9.15	12.00	17.00	24.50	32.50
10				9.87	13.00	18.40	26.50	35.10
11				10.59	14.00	19.80	28.50	37.70
12				11.31	15.00	21.20	30.50	40.30

The following extras are to be understood as a part of the Coach and Lag Screw List: Hexagon and Tee Heads, 10 per cent. extra.

WROUGHT-IRON PUNCHED WASHERS.

MANUFACTURERS' STANDARD LIST.



Diameter.	Hole.	Thickness of Wire Gauge.	Bolt.	Price per Pound in 200-Pound Kegs.	Approximate No. in 100 Pounds.
9-16 inch.	$\frac{1}{4}$ inch.	No. 18	3-16 inch.	14 cts.	35,200
$\frac{3}{4}$ "	5-16 "	" 16	$\frac{1}{4}$ "	12.2 "	15,000
$\frac{7}{8}$ "	$\frac{3}{8}$ "	" 16	5-16 "	11.4 "	11,900
1 "	7-16 "	" 14	$\frac{3}{8}$ "	10.5 "	7,900
$1\frac{1}{4}$ "	$\frac{1}{2}$ "	" 14	7-16 "	9.7 "	4,500
$1\frac{3}{4}$ "	9-16 "	" 12	$\frac{1}{2}$ "	9.20 "	3,100
$1\frac{1}{2}$ "	$\frac{5}{8}$ "	" 12	9-16 "	9.10 "	2,156
$1\frac{3}{4}$ "	11-16 "	" 10	$\frac{5}{8}$ "	9 "	1,323
2 "	13-16 "	" 10	$\frac{3}{4}$ "		1,000
$2\frac{1}{4}$ "	15-16 "	" 9	$\frac{7}{8}$ "		825
$2\frac{1}{2}$ "	1 1-16 "	" 9	1 "	8.80 "	637
$2\frac{3}{4}$ "	$1\frac{1}{4}$ "	" 9	$1\frac{1}{8}$ "		637
3 "	$1\frac{3}{8}$ "	" 9	$1\frac{1}{4}$ "		299
$3\frac{1}{4}$ "	$1\frac{1}{2}$ "	" 8	$1\frac{3}{8}$ "	9 "	294
$3\frac{1}{2}$ "	$1\frac{3}{4}$ "	" 8	$1\frac{1}{2}$ "		243
$3\frac{3}{4}$ "	$1\frac{7}{8}$ "	" 8	$1\frac{5}{8}$ "	9.20 "	240
4 "	2 "	" 8	$1\frac{3}{4}$ "		229
$4\frac{1}{4}$ "	$2\frac{1}{8}$ "	" 8	$1\frac{7}{8}$ "	9.50 "	
$4\frac{1}{2}$ "	$2\frac{1}{4}$ "	" 8	2 "		82

# MACHINE BOLTS.



## PRICE PER HUNDRED.

(Adopted September 20, 1899, to take effect October 1, 1899.)

Length Inches.	1/4	5/16	3/8	7/16	1/2	9/16 & 5/8	3/4	7/8	1
1 1/2	\$1.70	\$2.00	\$2.40	\$2.80	\$3.60	\$5.20	\$7.20	\$10.50	\$15.10
2	1.78	2.12	2.56	3.00	3.86	5.58	7.70	11.20	16.00
2 1/2	1.86	2.24	2.72	3.20	4.12	5.96	8.20	11.90	16.90
3	1.94	2.36	2.88	3.40	4.38	6.34	8.70	12.60	17.80
3 1/2	2.02	2.48	3.04	3.60	4.64	6.72	9.20	13.30	18.70
4	2.10	2.60	3.20	3.80	4.90	7.10	9.70	14.00	19.60
4 1/2	2.18	2.72	3.36	4.00	5.16	7.48	10.20	14.70	20.50
5	2.26	2.84	3.52	4.20	5.42	7.86	10.70	15.40	21.40
5 1/2	2.34	2.96	3.68	4.40	5.68	8.24	11.20	16.10	22.30
6	2.42	3.08	3.84	4.60	5.94	8.62	11.70	16.80	23.20
6 1/2	2.50	3.20	4.00	4.80	6.20	9.00	12.20	17.50	24.10
7	2.58	3.32	4.16	5.00	6.46	9.38	12.70	18.20	25.00
7 1/2	2.66	3.44	4.32	5.20	6.72	9.76	13.20	18.90	25.90
8	2.74	3.56	4.48	5.40	6.98	10.14	13.70	19.60	26.80
9	2.90	3.80	4.80	5.80	7.50	10.90	14.70	21.00	28.60
10	3.06	4.04	5.12	6.20	8.02	11.66	15.70	22.40	30.40
11	3.22	4.28	5.44	6.60	8.54	12.42	16.70	23.80	32.20
12	3.38	4.52	5.76	7.00	9.06	13.18	17.70	25.20	34.00
13	.....	.....	6.08	7.40	9.58	13.94	18.70	26.60	35.80
14	.....	.....	6.40	7.80	10.10	14.70	19.70	28.00	37.60
15	.....	.....	6.72	8.20	10.62	15.46	20.70	29.40	39.40
16	.....	.....	7.04	8.60	11.14	16.22	21.70	30.80	41.20
17	.....	.....	.....	.....	11.66	16.98	22.70	32.20	43.00
18	.....	.....	.....	.....	12.18	17.74	23.70	33.60	44.80
19	.....	.....	.....	.....	12.70	18.50	24.70	35.00	46.60
20	.....	.....	.....	.....	13.22	19.26	25.70	36.40	48.40
21	.....	.....	.....	.....	.....	.....	26.70	37.80	50.20
22	.....	.....	.....	.....	.....	.....	27.70	39.20	52.00
23	.....	.....	.....	.....	.....	.....	28.70	40.60	53.80
24	.....	.....	.....	.....	.....	.....	29.70	42.00	55.60
25	.....	.....	.....	.....	.....	.....	30.70	43.40	57.40
26	.....	.....	.....	.....	.....	.....	31.70	44.80	59.20
27	.....	.....	.....	.....	.....	.....	32.70	46.20	61.00
28	.....	.....	.....	.....	.....	.....	33.70	47.60	62.80
29	.....	.....	.....	.....	.....	.....	34.70	49.00	64.60
30	.....	.....	.....	.....	.....	.....	35.70	50.40	66.40

The following extras are to be understood as a part of the machine bolt list:


Bolts with Hexagon Heads or Hexagon Nuts, 10 per cent extra.

If both Hexagon Heads and Hexagon Nuts, 20 per cent extra.

Joint Bolts with Oblong Nuts, Bolts with Tee Heads, Askew Heads and Eccentric Heads, 10 per cent extra.

Special Bolts with irregular Threads and unusual dimensions of Heads or nuts will be charged extra at the discretion of the manufacturer.

# COMMON CARRIAGE BOLTS. 543




## PRICE PER HUNDRED.

(Adopted January 30 1895, to take effect February 14, 1895.)

Length.	1/4	5/16	3/8	7/16	1/2	9/16 & 5/8	3/4
1 1/2	\$1.00	\$1.20	.....	.....	.....	.....	.....
1 3/4	1.04	1.25	.....	.....	.....	.....	.....
2	1.08	1.30	\$1.50	\$2.20	.....	.....	.....
2 1/4	1.12	1.35	1.57	2.28	.....	.....	.....
2 1/2	1.16	1.40	1.64	2.36	.....	.....	.....
2 3/4	1.20	1.45	1.71	2.44	.....	.....	.....
3	1.24	1.50	1.78	2.52	\$3.00	\$5.00	\$7.20
3 1/4	1.28	1.55	1.85	2.60	3.10	5.15	7.40
3 1/2	1.32	1.60	1.92	2.68	3.20	5.30	7.60
3 3/4	1.36	1.65	1.99	2.76	3.30	5.45	7.80
4	1.40	1.70	2.06	2.84	3.40	5.60	8.00
4 1/4	1.44	1.75	2.13	2.92	3.50	5.75	8.20
4 1/2	1.48	1.80	2.20	3.00	3.60	5.90	8.40
4 3/4	1.52	1.85	2.27	3.08	3.70	6.05	8.60
5	1.56	1.90	2.34	3.16	3.80	6.20	8.80
5 1/2	1.64	2.00	2.48	3.32	4.00	6.50	9.20
6	1.72	2.10	2.62	3.48	4.20	6.80	9.60
6 1/2	1.80	2.20	2.76	3.64	4.40	7.10	10.00
7	1.88	2.30	2.90	3.80	4.60	7.40	10.40
7 1/2	1.96	2.40	3.04	3.96	4.80	7.70	10.80
8	2.04	2.50	3.18	4.12	5.00	8.00	11.20
8 1/2	2.12	2.60	3.32	4.28	5.20	8.30	11.60
9	2.20	2.70	3.46	4.44	5.40	8.60	12.00
9 1/2	2.28	2.80	3.60	4.60	5.60	8.90	12.40
10	2.36	2.90	3.74	4.76	5.80	9.20	12.80
11	2.52	3.10	4.02	5.08	6.20	9.80	13.60
12	2.68	3.30	4.30	5.40	6.60	10.40	14.40
13	2.84	3.50	4.58	5.72	7.00	11.00	15.20
14	3.00	3.70	4.86	6.04	7.40	11.60	16.00
15	3.16	3.90	5.14	6.36	7.80	12.20	16.80
16	3.32	4.10	5.42	6.68	8.20	12.80	17.60
17	3.48	4.30	5.70	7.00	8.60	13.40	18.40
18	3.64	4.50	5.98	7.32	9.00	14.00	19.20
19	3.80	4.70	6.26	7.64	9.40	14.60	20.00
20	3.96	4.90	6.54	7.96	9.80	15.20	20.80
Advance per inch....	\$0.20	.30	.40	.50	.64	1.00	1.40

## THE IMPROVED FEED COOKER.

This Cooker is made in the most substantial manner. The material used in its construction is the best boiler plate steel, 60,000 pounds tensile strength, hand riveted, tested to 100 pounds hydrostatic pressure, securing perfect safety and ample capacity to users. The fire door is of ample size, and the grate so designed that any kind of fuel may be used. The boiler is the tubular type, the flues passing through the water, giving unusually large heating surface, and as durable and as efficient as any engine boiler of same dimensions.




### SIZES AND PRICES.

Size No.	Diameter of Shell, Inches.	Height of Shell, Inches.	No. of 2-in. Flues.	Length of Boiler, In.	Shipping Weight, Lbs.	Price.
1	19	40	9	54	325	\$40.00
2	19	44	13	58	370	45.00

The following fittings and trimmings are furnished with each Cooker: One Safety Valve, Two Gauge Cocks, One Pump, Two Valves, Sufficient Pipe Connections and Two Feet of Hose. It is fitted with connections for one tank or barrel, but may be used with two or three, with additional pipe and fittings.

## NO. 3 VERTICAL BOILER.



Diameter in Inches.....	19
Height " " .....	44
Fire Box Diameter.....	16
" " Height.....	17
No. 2 Flues.....	13

This cut represents a Water Leg Surrounding Fire Pot. By this construction the Boiler is very economical. Tested at 160 pounds hydrostatic pressure, and has sufficient capacity to run 1½ horse power engine.

The boiler can be fitted up to cook from one to four barrels at the same time. Complete with Steam and Water Gauge.

Price.....	\$64.00
------------	---------



The outfit here represented is one of the simplest, most compact and strongest in the market. The crank shaft, connecting rod, piston rod, valve stem, and pins of the engine are made of steel. The main frame of the engine and the slides, as well as the bearings for the crank shaft, are made in one piece, so that it is impossible for the working parts of the engine to get out of line or change their relation to each other.

The construction of the engine is such that the action of the piston rod is exactly central, and all overhanging strains are avoided.


These outfits do not require any masonry foundation, or extra care in setting. They will stand upon any ordinary floor and do perfect work. Every engine is adjusted, and run for several hours before leaving the shop, and is in complete order when sent out.

A vertical engine has many features which recommend it to those wanting power. It occupies but little space, is convenient to work around, and is solid and substantial. Should it be necessary to move it at any time the boiler can be taken off the base by simply unscrewing the steam and exhaust pipes.

A valuable feature of this form of portable boiler and engine is, that it can be taken apart and carried up or down stairs, or into localities where it would be difficult and expensive to carry the same power engines and boilers if all fastened together.

The apparently higher price at which the boilers and engines come when listed on combined base, than the same boilers and engines on single base, is due to the fact that the price on combined base connected together includes Improved Boiler Feeder and pipes and fittings, not included in the price when the boiler and engines are sold separately.

Prices for boiler and engine, with all connections and fittings, and improved boiler feeder attached, as follows :




No.	Cipher.									Price.
276	Sack	2	Horse-Power	Engine	and	4	Horse-Power	Vertical	Boiler.....	\$210.00
277	Safe	4	"	"	"	4	"	"	" .....	265.00
278	Sage	4	"	"	"	6	"	"	" .....	285.00
279	Sago	4	"	"	"	8	"	"	" .....	310.00
280	Sail	4	"	"	"	10	"	"	" .....	325.00
281	Same	6	"	"	"	6	"	"	" .....	325.00
282	Samp	6	"	"	"	8	"	"	" .....	350.00
283	Sand	6	"	"	"	10	"	"	" .....	370.00
284	Sang	8	"	"	"	10	"	"	" .....	425.00
285	Sash	10	"	"	"	12	"	"	" .....	475.00

We furnish with each boiler a certificate of inspection showing that the boiler has been tested to a high pressure, and that it is safe for high working pressure, and is properly built, of good quality and weight of material.

Every engine we send out has been tested and run for hours with steam, before leaving our shop, under, as nearly as possible, the conditions of actual service. We know each one to be in complete running order when shipped. They require no further adjustment of valves or boxes before starting.

## "LITTLE GIANT" ENGINE AND BOILER.




THIS CUT REPRESENTS OUR "LITTLE GIANT" ENGINE.

It is unique in design throughout, compact and a model of simplicity, and is especially adapted for use in running Creamery Separators, Ice Cream machinery and light printing Presses.

When run at 400 revolutions per minute, will develop its full rated horse power. With each engine we furnish governor, governor pulley and belt, oil cups, throttle valve, cylinder lubricator, belt and balance wheel, complete.

### RATED HORSE POWER.

Cylinder.....	{ Bore.....	2½ inches
	{ Stroke.....	3 "
Revolutions per Minute.....		400
Belt Pulley.....	{ Diameter .....	6 "
	{ Face.....	3¼ "
Fly Wheel.....	{ Diameter.....	13 "
	{ Face .....	3½ "
	{ Weight.....	35 pounds
Governor.....		¾ inch
Exhaust.....		½ inch
Floor Space.....		14 x 26 inches
Height to Top of Cylinder.....		30 "
Weight, complete.....		170 pounds



"LITTLE GIANT" ENGINE AND BOILER.


This outfit is complete in every detail, and is extensively used where light power is needed. Boiler is made of the best quality of steel and tested at 150 pounds pressure before leaving the works.

Boiler Trimmings comprise the steam gauge, water gauge, gauge cocks, safety valve, check and blow-off valves and injector.

Furnished on combined or independent bases, as desired.

### SPECIFICATIONS OF LITTLE GIANT BOILERS.

Horse Power.....	1½	Length of tubes, in inches.....	18
Telegraphic Cipher.....	Red	No. of 2-inch tubes.....	16
Diameter of Boiler, in inches.....	20	Weight of boiler without trimmings or fixtures.....	325
Height above base, in inches.....	36	Floor space diameter, in inches.....	30
Diameter of furnace, in inches.....	16	Weight of boiler, complete.....	475
Height of furnace, in inches.....	18	Outside diameter of stack opening, in inches	8½
Thickness of steel in shell.....	3-16	Height from floor to top of hood.....	4 ft. 2 in.
Thickness of steel in heads.....	¼		
Thickness of steel in fire box.....	¼		



## SPECIFICATIONS OF PLAIN VERTICAL BOILERS.

Horse Power.....	1½	2	3	4	5	6	8	10	12	14	16
Telegraphic Cipher.....	Red	Green	Yellow	Blue	Indigo	Violet	White	Black	Orange	Maroon	Purple
Diameter of Boiler, in inches.....	20	20	20	24	24	26	30	30	36	36	36
Height above base, in inches.....	36	43	49	50	60	60	60	72	72	84	96
Diameter of furnace, in inches.....	16	16	16	21	21	22	25	25	30	30	30
Height of furnace, in inches.....	18	18	18	18	18	22	24	24	24	28	32
Thickness of steel in shell.....	3-16	¼	¼	¼	¼	¼	¼	¼	¼	¼	¼
Thickness of steel in heads.....	¼	5-16	5-16	5-16	5-16	5-16	5-16	¾	¾	¾	¾
Thickness of steel in fire box.....	¼	¼	¼	¼	¼	¼	¼	¼	5-16	5-16	5-16
Length of tubes, in inches.....	18	25	31	32	40	38	36	48	48	56	64
Number of 2-inch tubes.....	16	19	19	31	31	37	43	43	55	55	55
Weight of Boiler without trimmings or fixtures ..	325	430	530	640	750	840	1010	1180	1520	1800	2280
Weight of Boiler complete.....	475	560	620	890	1060	1300	1550	1650	2350	2540	3000
Outside diameter of stack opening, inches. ....	8½	8½	8½	10	10	11	12½	12½	16	16	16
Height from floor to top of hood, inches.....	50	54	60	66	76	76	76	94	98	108	120


**Cast Fixtures.**—Base, hood, fire door and grates.

**Trimmings.**—Injector fitted with pipe and valves, steam gauge, water gauge, gauge cocks, safety valve and blow-off.

All Boilers above 26 inches in diameter have vertical seams double riveted. They are made of flange steel 60,000 pounds T. S., and are tested to 160 pounds, hydraulic pressure.



## VERTICAL ENGINE.



## DIMENSIONS OF VERTICAL ENGINES

Rated Horse Power.....	1	2	3	4	5	6	8	10	12	15
Telegraphic Cipher.....	Celery.	Carrot.	Turnip.	Parsnip.	Radish.	Cabbage.	Squash.	Lettuce.	Beans.	Peas.
Cylinder { Bore, inches.....	2½	3	3½	4	4½	5	6	7½	7½	7½
Stroke, inches.....	3	5	5	5	5	7½	7½	8	9	10
Steam Pipe, inches.....	¾	1½	1½	¾	¾	1	1¼	1½	1½	1½
Exhaust Pipe, inches.....	¾	¾	¾	1	1	1¼	1½	2	2	2
Revolutions per Minute.....	400	350	350	300	300	250	200	200	180	180
Belt Pulley { Diameter, inches..	6	10	10	12	12	14	14	16	18	18
Face, inches.....	3¼	4½	4½	5	5	6½	6½	7½	8½	8½
Governor Pulley { Diameter, in...	3	4	4	4½	4½	5½	6½	9	9	9
Face, inches..	1¼	1½	1½	1½	1½	1¾	1¾	2	2	2
Floor Space, inches.....	14 x 26	18 x 20	18 x 20	18 x 20	18 x 20	20 x 22	20 x 22	22 x 24	22 x 24	22 x 24
Height to Top of Cylinder.....	30 in.	3 ft. 6 in.	3 ft. 6 in.	3 ft. 6 in.	3 ft. 8 in.	4 ft. 8 in.	4 ft. 10 in.	5 ft. 2 in.	5 ft. 3 in.	5 ft. 4 in.
Weight, pounds.....	170	275	300	425	500	700	850	1,250	1,400	1,500
Balance Wheel { Dia. inches.....	13	15	15	17	17	24	24	30	30	35
Face, inches...	3½	4	4	4½	4½	6	6	6¾	6¾	7¼
Weight, lbs.....	35	45	45	65	100	170	170	180	180	350
Diameter of Shaft, inches.....	1½	1½	1½	1½	1½	1 15-16	1 15-16	2¾	2¾	2¾

**Trimmings.**—The above prices include governor, governor pulley and belt, throttle valve, oil cuts, cylinder lubricator, belt wheel, balance wheel and air cock.

# THE "ECONOMIC."

549

## RETURN TUBULAR PORTABLE BOILER.


All Smoke Stacks up to and including 28-inch diameter are made of No. 16 gauge, larger sizes of No. 14; if heavier is required a proportionate charge will be made.

If so desired, these boilers will be built with Domes or Drums, at the regular additional cost.

### FIXTURES.

With a boiler ordered "complete," the following fixtures are furnished:


Grates, Steam Gauge, Water Gauge fitted with Stand Pipe, Gauge Cocks, Whistle and Pipe, Safety Valve, Blow-off Valve, Check Valve, Stop Valve, Smoke Stack and Guys.




## SPECIFICATIONS OF "ECONOMIC" BOILERS.

Number of Size.....	2	3	4	5	6	7	7½	8	9	10	11	12	13	14
Horse-Power, as usually rated.....	10	12	15	20	25	30	35	40	50	60	70	80	90	100
Diameter of Boiler in inches .....	28	28	30	30	36	36	40	40	44	50	54	54	60	60
Length of Grate in inches.....	36	36	36	42	42	42	48	48	48	60	60	60	60	66
Number of 3-inch Tubes.....	16	16	21	21	30	30	38	38	52	64	78	78	88	88
Length of 3-inch Tubes used in feet..	6	7	7	8½	8	9	9	10	9½	9½	9	10	9½	11
Number of 4-inch Tubes.....	10	10	12	12	18	18	20	20	26	32	42	42	46	46
Length of 4-in. Tubes used in inches	34	46	43	55	49	61	52	64	58	54	48	60	54	66
Thickness of Shell in inches .....	No. 4	No. 4	¼	¼	¼	¼	⅜	⅜	⅝	⅝	⅝	⅝	¾	¾
Thickness of Tube Sheets in inches...	⅜	⅜	⅜	⅜	⅜	⅜	⅜	⅜	⅜	⅜	⅜	⅜	⅞	⅞
Diameter of Stack in inches.....	12	12	14	14	18	18	20	20	22	24	28	28	30	30
Length of Stack in feet.....	30	35	35	40	40	45	45	50	50	50	45	50	50	60
Length of Boiler, over all, in ft. about..	9½	10½	10½	12	11½	12½	13	14	13½	13½	13	13½	13½	15½
Width of Boiler, over all, in ft. about ...	4	4	4	4	4½	4½	5	5	5½	6	6½	6½	7	7
Height of Boiler, over all, in ft. about...	6	6	6½	6½	6¾	6¾	7	7	8	8	10½	10½	11	11
Weight of Boiler about.....	4,500	4,750	6,000	6,450	7,800	8,400	9,200	10,300	11,800	14,100	17,000	17,900	20,800	22,500
Weight of Fixtures about.....	700	750	750	1,000	1,100	1,200	1,500	1,700	1,900	2,100	2,300	2,400	2,700	3,000
Weight of Boiler and Fixtures about..	5,200	5,500	6,750	7,450	8,900	9,600	10,700	12,000	13,700	16,200	19,300	20,300	23,500	25,500

550 STANDARD TUBULAR BOILER, WITH FULL "C" FRONT.



STANDARD TUBULAR BOILER, WITH HALF FRONT.





# STANDARD TUBULAR BOILERS.

## SPECIFICATIONS.

551



Number of Size.....	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
Horse power, as usually rated	10	12	15	20	25	30	35	40	45	50	60	70	80	90	100	125	150	175	200
Diam. of Boiler, in.....	30	30	36	42	42	44	44	48	48	54	60	60	60	66	66	72	72	78	84
Length of tubes used, ft.....	7	8	8	8	10	10	12	12	14	12	12	14	16	15	16	16	18	18	18
No. of Tubes 3-in. diam.....	20	20	28	38	38	46	46	52	52	64	82	82	82	98	98	120	84	88	108
Sq. ft. heating surface, about	151	185	220	305	376	440	526	591	687	708	885	1028	1172	1296	1377	1660	4" Tbs	4" Tbs	4" Tbs
Length of grates, in.....	36	36	36	36	42	42	48	48	54	48	48	54	54	54	54	54	60	60	60
Diam. of dome, in.....	18	18	20	22	22	22	22	26	26	30	32	32	32	36	36	36	36	36	36
Height of dome, in.....	20	20	22	24	24	24	24	28	28	34	36	36	36	40	40	40	40	40	40
Thickness of shell, in.....	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{1}{4}$	9-32	9-32	9-32	9-32	5-16	5-16	5-16	11-32	11-32	11-32	$\frac{3}{8}$	$\frac{3}{8}$	7-16	7-16	7-16	7-16
Thickness of main heads, in.	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	7-16	7-16	7-16	7-16	7-16	7-16	7-16	7-16	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$
Thickness of dome shell, in.	9-32	9-32	9-32	9-32	9-32	9-32	9-32	5-16	5-16	5-16	5-16	5-16	5-16	5-16	5-16	5-16	5-16	5-16	5-16
Thickness of dome head, in.	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$
Diam. of smoke stack, in....	14	14	16	20	20	22	22	24	24	26	28	28	28	30	30	34	36	40	44
Length of smoke stack, ft....	28	28	28	28	35	35	40	40	50	40	40	50	60	60	60	60	60	60	60
Wt. Boiler & Britchen, about	1900	2300	2600	3500	4000	4300	4900	6000	6800	7000	9000	9900	11000	12700	13000	16000	17300	21000	25000
Wt. Boiler fixtures, about....	1500	1600	1700	2200	2500	2600	2700	3400	3500	3600	4000	4500	5000	5000	5000	6000	6200	7000	8000
Wt. Boiler & fixtures, about.	3400	3900	4300	5700	6500	6900	7600	9400	10300	10600	13000	14400	16000	17700	18000	22000	23500	28000	33000
Wt. Flush-ended Boiler, { four wall brackets, about }	1800	2200	2500	3300	3900	4300	5000	5700	6500	7000	8600	9700	10500	12000	13000	16000	17400	21000	24700
Wt. with full front and fix- tures, about.....	4400	4900	5300	7000	7700	8400	9000	10200	11500	12000	14500	16000	17000	19000	20000	24000	25000	30000	35000

## PROPER NUMBER OF 3, 3½, 4 AND 6-INCH TUBES FOR STATIONARY BOILERS.

Number of Size.....	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
No. of 3-in. tubes, with hand-hole in each head below tubes, regular list....	20	20	28	38	38	46	46	52	52	64	82	82	82	98	98	120	.....	.....	.....
“ 3 “ “ man-hole in front “ “ no hand-hole. ....	.....	.....	20	30	30	40	40	46	46	58	78	78	78	94	94	116	.....	.....	.....
“ 3½ “ “ hand-hole in each “ “ .....	16	16	22	30	30	36	36	42	42	50	64	64	64	78	78	96	96	.....	.....
“ 3½ “ “ man-hole in front “ “ no hand-hole. ....	.....	.....	18	26	26	32	32	38	38	46	60	60	60	76	76	94	94	.....	.....
“ 4 “ “ hand-hole in each “ “ .....	12	12	18	24	24	30	30	34	34	42	54	54	54	64	64	84	84	.....	.....
“ 4 “ “ man-hole in front “ “ no hand-hole. ....	.....	.....	14	20	20	26	26	30	30	38	52	52	52	58	58	80	80	88	108
“ 6 “ “ man-hole in front “ “ no hand-hole. ....	.....	.....	6	10	10	10	10	14	14	18	22	22	22	30	30	36	36	40	44

These boilers are all tested and inspected before shipment by a responsible Steam Boiler Inspection and Insurance Company, at 150 pounds hydrostatic pressure per square inch, and the purchaser can have a certificate of inspection and a policy of insurance for one year issued by the Insurance Company. This policy is payable to the purchaser and will be in force and valid wherever the boiler is located.

# “JEWEL” AUTOMATIC ENGINES.



## DIMENSIONS AND POWERS OF THE “JEWEL” AUTOMATIC CUT-OFF ENGINES.

Based on 80 pounds Initial Pressure, Cut-Off at  $\frac{1}{4}$  Stroke.

**Trimming.**—We ship with each Engine a complete set of glass oilers, sight-feed lubricator, one throttle valve and two cylinder cocks. On crank pin we use center oilers on numbers 1, 2 and 3.


On numbers 4, 5, 6, 7, 8, 9 we use wipe oilers.

Engine Number.....	1		2		3		4		5		6		7		8		9	
Telegraphic Cipher. ....	Diamond.		Ruby.		Emerald.		Pearl.		Opal.		Garnet.		Amethyst.		Sapphire.		Topaz.	
Horse Power Rating.....	6 to 8		8 to 10		10 to 12		15 to 18		20 to 25		30 to 35		40 to 45		50 to 55		60 to 65	
	at	at	at	at	at	at	at	at	at	at	at	at	at	at	at	at	at	at
Revolutions per Minute.....	260	380	230	320	230	300	220	280	220	260	220	260	180	200	200	220	200	220
Cylinder. .... { Bore, in .....	4½		5		6		7½		8		9¼		10		11		12	
..... { Stroke. in .....	6		7½		7½		8		10		10		15		15		15	
Steam Pipe, in.....	1¼		1¼		1½		2		2		2		3		3½		4	
Exhaust Pipe, in .....	1½		1½		2		2½		2½		2½		4		4½		5	
Fly Wheel..... { Diameter, in... ..	20		30		30		35		42		42		42		42		48	
..... { Face, in .....	5½		6¾		6¾		7½		9¾		9¾		10		10		12	
..... { Weight, lbs. ....	135		200		340		435		660		660		1,000		1,000		1,500	
Belt Pulley..... { Diameter, in... ..	14		16		18		20		20		24		24		30		30	
..... { Face, in.....	6½		7½		8½		10⅓		12		12		12		12½		12½	
Diameter of Shaft, in.....	1⅞		2¼		2¼		2⅝		3½		3½		3⅞		4⅞		4⅞	
Floor Space.....	52 x 36		64 x 38		64 x 38		69½ x 46½		73 x 54		73 x 54							
Weight Complete, lbs... ..	700		1,050		1,275		1,850		2,850		2,950							

# MEDIUM SPEED, SINGLE VALVE, AUTOMATIC ENGINE.

553

"CLASS CC."




## SPECIFICATIONS OF MEDIUM SPEED SINGLE-VALVE AUTOMATIC ENGINES.

Number of Size.....	1	2	3	4	5	6	7	8	9	10	11	12
Rated Horse power (at 40 lbs. M. E. P. and $\frac{1}{4}$ cut-off).....	12	15	20	25	30	35	45	55	70	85	100	130
Revolutions per minute.....	240	210	210	210	200	200	200	200	200	200	200	180
Diameter of cylinder by Length of Stroke, in inches.....	6x9	7x10	8x10	8x12	9x12	10x12	10x15	11x15	12x16	13x16	14x16	16x18
Diameter of Steam pipe, in inches..	1½	2	2½	2½	3	3	3	3½	4	4	4½	5
Diameter of Exhaust Pipe, in inches	2	2½	3	3	4	4	4	4½	5	5	6	6
Size of Balance Wheel Pulleys, in...	44x7½	48x8½	48x8½	48x10½	54x10½	54x10½	54x12½	54x12½	60x14½	60x14½	66x16½	78x20½
Size of Governor Wheel, in inches..	30x8½	34x8½	34x8½	36x8½	36x8½	42x10½	42x10½	42x10½	48x10½	48x10½	54x12½	54x12½
Diameter of Crank Shaft, in inches..	2¾	2¾	2¾	3	3¾	3¾	3¾	4¾	4¾	4¾	5¾	5¾
Length of Journals, in inches.....	5½	6	6	7	7½	8½	8½	9	10	10	12	14
Diameter of Crank Pin, in inches...	2¼	2½	2¾	2¾	3¼	3½	3¾	4¼	4¾	4¾	5¾	5¾
Weight, complete, in pounds, about	1,800	2,300	2,500	3,150	3,900	4,900	5,500	6,000	7,100	7,300	9,900	13,000



# 554 MEDIUM SPEED, SINGLE VALVE, AUTOMATIC ENGINE.

"CLASS B."



## SPECIFICATIONS OF MEDIUM SPEED SINGLE-VALVE AUTOMATIC ENGINES.

Number of Size.....	1	2	3	4	5	6	7	8	9
Rated Horse Power (at 40 lbs. M. E. P. and $\frac{1}{4}$ cut-off).....	45	55	70	85	100	130	180	225	300
Revolutions per minute.....	200	200	200	200	180	180	160	150	140
Diameter of Cylinder by Length of Stroke, in inches.....	10 x 15	11 x 15	12 x 16	13 x 16	14 x 18	16 x 18	18 x 22	20 x 24	22 x 28
Diameter of Steam Pipe, in inches.....	3	3 $\frac{1}{2}$	4	4	4 $\frac{1}{2}$	5	6	6	7
Diameter of Exhaust Pipe, in inches.....	4	4 $\frac{1}{2}$	5	5	5	6	7	7	8
Diameter of Balance Wheel Pulley, in inches.....	54	54	60	60	72	78	84	96	108
Face of Balance Wheel Pulley, in inches.....	12 $\frac{1}{2}$	12 $\frac{1}{2}$	14 $\frac{1}{2}$	14 $\frac{1}{2}$	16 $\frac{1}{2}$	20 $\frac{1}{2}$	24 $\frac{1}{2}$	30 $\frac{1}{2}$	36 $\frac{1}{2}$
Diameter of Shaft, in inches.....	4 $\frac{7}{8}$	5 $\frac{1}{4}$	5 $\frac{3}{4}$	6 $\frac{3}{8}$	6 $\frac{7}{8}$	7 $\frac{1}{2}$	8 $\frac{1}{2}$	10	11
Diameter of Crank Pin, in inches.....	2 $\frac{1}{2}$	2 $\frac{3}{4}$	3	3 $\frac{1}{4}$	3 $\frac{1}{2}$	4	4 $\frac{1}{2}$	5	5 $\frac{1}{2}$
Length of Shaft from Center of Engine, in feet.....	6	6	7	7	7 $\frac{1}{2}$	8	8 $\frac{1}{2}$	9 $\frac{1}{2}$	10
Length of Engine Bed, in feet.....	7 $\frac{1}{4}$	7 $\frac{1}{4}$	8	8	8 $\frac{3}{4}$	9	10 $\frac{1}{2}$	12	13 $\frac{1}{2}$
Width of Engine Bed, in inches.....	29 $\frac{3}{4}$	29 $\frac{3}{4}$	35 $\frac{1}{2}$	35 $\frac{1}{2}$	38	40 $\frac{1}{2}$	55	56	58
Length of Journals, in inches.....	11	11	13	13	14	15 $\frac{1}{2}$	18	20	22
Shipping Weight, about in pounds.....	5,500	5,900	7,400	7,700	9,700	12,600	19,200	32,000	35,000


## FIXTURES.

With an engine ordered "complete," the following fixtures are furnished:


Pulleys, per specifications,  
Throttle Valve,  
Sight-Feed Lubricator,

Automatic Oiling Device for Crank Pin and Crosshead,  
Set of Glass Oil Cups,  
Cylinder Drip Valves.

Steam, Water and Exhaust Connections and Foundation Bolts are extras, and an additional charge will be made for them.



1899 MODEL THREE-QUARTER HORSE POWER.



MADE IN THREE SIZES, 2, 3 AND 4 H. P.

The above cuts show our Gasoline Engines of the smaller sizes. The  $\frac{3}{4}$  H. P. engine is of the horizontal type and is complete and self-contained.

The 2, 3 and 4 H. P. engines are of the vertical type and can be used wherever small powers are wanted.

The engines are of very simple and durable construction and are positively reliable.


There are no cams, gear wheels or rocker arms to get out of order.

These engines can be used for pumping, feed cutting and grinding, cider presses, cream separators, churns, ice cream freezers, ventilating fans and printing offices

## SIZES, ETC.

Actual Horse Power.	Stroke.	Pulley.	Revolutions.	Shipping Weight.	Price.
$\frac{3}{4}$	4 inches	5 x 5	400	225 pounds	\$100.00
2	6 "	8 x 6	300	575 "	200.00
3	7 $\frac{1}{2}$ "	8 x 6	300	775 "	275.00
4	8 "	10 x 8	275	975 "	325.00

## GASOLINE ENGINES.



## SIZES, DIMENSIONS, ETC.


	Actual Horse Power.	Floor Space.	Pulley on Engine Shaft.		Speed of Engine.	Shipping Weight Complete.
Horizontal	4	67 in. x 38½ in.	12 x 8	Single Belt.	300	2,660
	6	68½ in. x 39 in.	16 x 10		275	2,950
	8	85 in. x 51 in.	18 x 12		250	4,400
	12	85½ in. x 53 in.	24 x 14		225	4,800
	16	103½ in. x 65½ in.	28 x 14	Double Belt.	185	7,950
	22	106 in. x 66 in.	32 x 16		185	8,700
	28	110½ in. x 78 in.	36 x 18		185	10,000
	34	114 in. x 81 in.	38 x 20		185	11,700
	44	117 in. x 89 in.	72 x 12½		175	17,000
	54	123 in. x 94 in.	72 x 14½		175	18,500

Pulleys are made with straight faces for shifting belts, except on 44 and 54 H. P.

Fitted with Patent Electric and Tube Ignitors, also Patent Self Starting Device, as furnished only with this make of engine.


Electric Ignitor dispenses with all flame and handling of gasoline in building, and expense of gasoline for heating tube.





DIRECT CURRENT STATIONARY MOTOR.  
TYPE CE.

CLASSIFICATION.							Weight.	Pulley.		
Type.	Poles.	H. P.	Speed.					Diameter.	Face.	
			110 V.	125 V.	220 V.	250 V.				500 V.
CA.....	2	1 <sup>1</sup> / <sub>2</sub>	1400	.....	.....	.....	25	2	3 <sup>3</sup> / <sub>4</sub>	
CA.....	2	2	1650	.....	1650	.....	1800	95	3 <sup>3</sup> / <sub>4</sub>	
CA.....	2	3 <sup>1</sup> / <sub>4</sub>	1200	.....	1400	.....	1600	120	3 <sup>3</sup> / <sub>4</sub>	
CA.....	2	3 <sup>1</sup> / <sub>2</sub>	1800	.....	1800	.....	2000	120	3 <sup>3</sup> / <sub>4</sub>	
CA.....	2	1	1000	.....	1000	.....	1200	200	4 <sup>1</sup> / <sub>2</sub>	
CA.....	2	2	1800	.....	1800	.....	2000	200	4 <sup>1</sup> / <sub>2</sub>	
CE.....	2	2	960	1070	960	1070	1200	335	5	
CE.....	2	3	1630	1820	1630	1820	1800	335	5	
CE.....	4	3	960	1070	960	1070	1200	465	5	
CE.....	4	5	1630	1820	1630	1820	1800	465	5	
CE.....	4	5	960	1070	960	1070	1200	540	5	
CE.....	4	7.5	1440	1600	1440	1600	1650	540	5	
CE.....	4	7.5	850	900	850	900	1000	800	7 <sup>3</sup> / <sub>4</sub>	
CE.....	4	10	1300	1400	1300	1400	1400	800	7 <sup>3</sup> / <sub>4</sub>	
CE.....	4	10	600	675	600	675	800	1150	9 <sup>3</sup> / <sub>4</sub>	
CE.....	4	15	1025	1100	1125	1200	1200	1150	9 <sup>3</sup> / <sub>4</sub>	



FORM H, SLOW-SPEED MOTOR.  
15 HORSE POWER.

CLASSIFICATION.								Weight.	Pulley.	
Type.	Poles.	H. P.	Speed.						Diameter.	Face.
			110 V.	125 V	220 V.	250 V.	500 V.			
MP.....	4	15	745	800	745	800	800	1900	9½	9½
MP.....	4	20	650	700	650	700	700	2665	11	10
MP.....	4	20	1025	1100	1025	1100	1100	1900	10½	9¼
MP.....	4	25	610	650	610	650	650	3350	11¾	11¾
MP.....	4	30	975	1050	975	1050	1050	2665	11	10
MP.....	4	35	560	600	560	600	600	4935	17¼	12¾
MP.....	4	35	910	975	910	975	975	3350	11¾	11¼
MP.....	4	50	515	550	515	550	550	5690	18¾	17¼
MP.....	4	50	840	900	840	900	900	4935	14¾	13¼
MP.....	4	60	515	550	515	550	550	7140	18¾	20
MP.....	4	65	790	850	790	850	850	5690	15¾	16¾
MP.....	4	75	745	800	745	800	800	7140	16¾	18¾
MP.....	4	85	470	500	470	500	500	8800	20¾	24
MP.....	4	95	655	700	655	700	700	8800	19¼	23

Prices and estimates furnished upon application.

## WOOD PUMPS AND TUBING.

## WOOD PUMPS.

NO. "OO," EXTRA STOCK. EIGHT INCHES  
SQUARE. FIVE INCH BORE.

	Plain.	Porcelain lined.
6 feet long.....	\$8.50	\$10.50
7   “   “ .....	9.50	11.50
8   “   “ .....	10.50	12.50
10   “   “ .....	12.50	14.50

NO. "O," STOCK PUMP. SEVEN INCHES  
SQUARE. FOUR INCH BORE.

	Plain.	Porcelain lined.
6 feet long—in one piece.....	\$7.00	\$8.75
7   “   “   “   “   “   “ .....	7.75	9.50
8   “   “   “   “   “   “ .....	8.50	10.00
10   “   “   “   “   “   “ .....	9.50	11.25
12   “   “   “   “   “   “ .....	10.75	12.50
14   “   “   “   “   “   “ .....		14.10
16   “   “   “   “   “   “ .....		15.50

NO. 1, HOUSE PUMP. SIX INCHES SQUARE.  
THREE AND ONE-HALF INCH BORE.

	Plain.	Porcelain Lined.
6 feet long in one piece.....	\$5.50	\$7.00
7 " " " " .....	6.00	7.50
8 " " " " .....	6.50	8.00
10 " " " " .....	7.50	9.00
12 " " " " .....	8.50	10.00
14 " " " " .....	9.75	11.25
16 " " " " .....	11.00	12.50

NO. 1, HOUSE PUMP SIX INCHES SQUARE,  
WITH DRIVE WELL ATTACHMENT FOR  
1¼, 1½ AND 2 INCH IRON PIPE.

	Iron Cylinder.
6 feet long complete.....	\$7.50
7 " " " " .....	8.00
8 " " " " .....	8.50
10 " " " " .....	9.50

NO. 2, CISTERN PUMP, FIVE INCHES  
SQUARE, THREE INCH BORE.



	Iron Cylinder.	Porcelain Cylinder.
6 feet in one piece.....	\$4.50	\$6.00
7 " " " " .....	4.75	6.25
8 " " " " .....	5.00	6.50



## WOOD TUBING.

	12 ft. and Under.	Over 12 ft.
"00," 5x5 square, 2½ in. bore, p. ft.	\$0.27	\$0.30
"0," 4½x4½ " 2 " " " "	.22	.24
"1," 4x4 " 1½ " " " "	.17	.19
"2," 3½x3½ " 1½ " " " "	.13	.14
Extension, 6x6 " 3¼ " " " "	.40	.40

**EXTRAS.**

Couplings for No. "00,"	\$0.60
"    "    "0,"	.60
"    "    No. 1	.50
"    "    No. 2	.40
Iron Spout and Collar, each	.40
Wood Spout, each	.15
Wood Spout Brace, each	.15
Handle Links, each	.25
Splice Straps with Bolts, per pair	.25
Iron Pipe Connections. each	.75
Iron Bands, each	.10
Brackets, Nos. 35 and 36, each	.40
Brackets, No. 37, closed	.50
Handles, each	.30
Frost Faucets, complete	.25
"    Plugs only	.15
"    Rods only	.10
Plungers, No. "00," 5 in.	1.25
"    "    "0," 4 in.	1.00
"    "    No. 1, 3½ in.	.80
"  No. 2, 3 in.	.65
"    "    Drive Wells, No. 1. 3 in.	.80
"    "    Wood, per dozen	3.00
"  Leathers, per dozen	3.50
"    "    Rod, per 100 feet	3.00
Check Valves, per dozen	1.50
Pump Caps, each	.15
"    Ornaments, each	.15
Wood Pump Connections for Iron Pipe	.25


## PUMPS RECOMMENDED FOR DEEP WELLS.

For Wells	20 feet and under.....	use	6 foot pump
66	20 to 25 feet.....	7	66
66	25 to 28 "	8	66
66	28 to 30 "	10	66
66	30 to 32 "	12	66
66	32 to 36 "	16	66
66	36 to 40 "	20	66
66	40 to 44 "	24	66
66	44 to 47 "	28	66
66	47 to 50 "	32	66
66	50 to 54 "	36	66
66	54 to 58 "	40	66
66	58 to 62 "	44	66
66	62 to 65 "	48	66

# DRAG SCRAPERS.

559

## THE "COLUMBUS" SOLID STEEL SCRAPER. THE ONLY PERFECT ALL-STEEL SCOOP.



(Patented Nov. 4, 1879, and March 24, 1885.)


CUT OF NOS. 1 AND 2 SCRAPER, WITH RUNNERS.

We ship always without Runners, unless otherwise directed.

- |        |  |          |
|--------|--|----------|
| No. 1. | Carries 7 feet of earth. Used for long haul or down grade. Size of bowl: Top of back to cutting edge, 33½ inches; width 32 inches; depth, 11½ inches. Weight, 102 pounds. Price .....                    | \$ ..... |
| No. 2. | Carries 5 feet of earth. For all ordinary grading, farm, road, or township work. Size of bowl: Top of back to cutting edge, 31½ inches; width, 29 inches; depth, 11½ inches. Weight, 94 lbs. Price ..... | .....    |
|        | With Runners, weight, 8 lbs., extra per Scraper.....   | .....    |
|        | With Double Bottoms, weight, 15 lbs., extra per Scraper.....   | .....    |

The Bails are of Steel and of improved pattern, with strong and perfect working swivels. The most economical tool made for making and mending roads. Awarded First Premium everywhere over all competitors.

## "COLUMBUS" SOLID STEEL DITCHING SCRAPER.



(Patented Nov. 4, 1879, and March 24, 1885.)

No. 3. Capacity, 3 cubic feet. Intended for work on narrow ditch with one horse. Size of bowl: Top of back to nose, 32 inches; width, 25 inches; greatest depth, 10¾ inches. Weight, 70 lbs. The entire bowl of the Scraper is made of one sheet of heavy steel, and is the only one so made, and has greater capacity than any other one-horse Scraper in the market.



# DRAG SCRAPERS.

## THE "CRESCENT" SOLID STEEL DRAG SCRAPER.



Nos. 1 AND 2 SCRAPER WITHOUT RUNNERS.

(Patented November 4, 1879, and March 24, 1885.)



Nos. 1 AND 2 SCRAPER WITH RUNNERS.

## BEST AND CHEAPEST SCRAPER IN THE MARKET.

These Scrapers are made from heavy plates, of specially hardened steel, and are stamped from one sheet without joint seam or rivet. They are superior to any other Drag Scraper upon the market, the "Columbus" Solid Steel Scraper alone excepted. The bowl being made of thicker and harder steel, enables it to scour where no other Scraper will; and owing to, the sharp, rounded nose, it will enter the ground more readily than any other make of Scraper. The bails are steel, with perfect working swivels, and handles of hard wood.

No. 1. Capacity, 7 cubic feet; weight, 90 lbs.: each.....	\$.....
No. 2. Capacity, 5 cubic feet; weight, 80 lbs.: each.....	.....
With Steel Runners, extra weight, 8 lbs.: each extra. ....	.....
With Steel Bottom Plate, extra weight, 15 lbs.: each extra.....	.....

## "CRESCENT" SOLID STEEL DITCHING SCRAPER.

No. 3. Capacity three cubic feet. We also make this Scraper with Handle Sockets on the side of the bowl, and the bail attached same as the "Crescent" Scrapers, the size and thickness of bowl being the same as in the "Columbus" Ditching Scraper. Weight, 67 pounds.

Both the "Crescent" and the "Columbus" Ditching Scrapers are furnished, when so ordered, with Steel Shoes or Runners, or with extra Steel Bottom Plate. The Runners weigh eight pounds and Bottom Plates twelve pounds per Scraper.


# DRAG AND TONGUE SCRAPERS.

561

## "STAR" DRAG SCRAPER.

The "Star" Drag Scraper is very much superior to any riveted Scraper upon the market. It is made of one sheet of steel, cut in the back, with a plate securely riveted thereto, leaving a perfectly smooth interior surface. This Scraper is made of very high grade material, has a strong and substantial bail, with perfect swivels, hardwood handles, and for the price, is exceptionally strong and substantial and everywhere gives the very best satisfaction.

MADE IN THREE SIZES.



No. 1, capacity 7 cubic feet, each.....	\$.....
No. 2, " 5 " " .....	
No. 3, " 3 " " .....	
With runners, per Scraper, extra.....	
With double bottoms, per Scraper, extra.....	

## TONGUE SCRAPER AND IRRIGATION DITCHER.


The driver fills and dumps his own load with ease.

This Scraper and Ditcher is designed for making and leveling roads, cutting and cleaning irrigation and other large ditches, and is well adapted for moving earth short distances at minimum cost to users.

The steel blade is of extra quality; size 48 inches long by 4 inches wide by  $\frac{1}{4}$  inch thick, and a sharp cutting edge.


The shoes are best *wrought steel* or *malleable iron*, as ordered; and draw bars of steel, strong and durable. The scraper box and handles are made of well-seasoned lumber and thoroughly bolted together.

There is an extra iron plate under the wood bottom 31 inches long by 4 inches long by  $\frac{1}{8}$  inch thick. Scraper has the "Flipper Trigger" and jaw of malleable iron. A malleable wrench and draw pin combined, accompanies each scraper.




No 1 Scraper and Ditcher, 48 in. wide, weight 123 lbs., list price.....	\$14.00
No. 2 " " 36 " " 113 " " .....	13.00

562 THE "K. & J." No. 1 PRESSED BOWL WHEEL SCRAPER.  
WITH K. & J. IMPROVED WHEELS.



CUT OF PRESSED BOWL SCRAPER IN CARRYING POSITION. WEIGHT, 381 LBS.



WITH END GATE IN CARRYING POSITION.

"K. & J." Heavy Hardened Iron Hub Wheels, 34 inches in diameter; tire, 3 inches wide.

This Wheel Scraper has our new Patent Automatic Lock Hooks, Independent Steel Axle, Bifurcated Compound Lever, Steel Bowl, and Improved "K. & J." Iron Hub Wheels.


The Bowl, which is the hardest and best steel, is 34 inches long by 34 inches wide by 11½ inches deep. Capacity, 9 cubic feet level full, but will carry an average load of 10 cubic feet. Gauge of track, 4 feet 2 inches.

We furnish either Pressed Bowls or Square Boxes, as ordered.

Square Bowl Scraper weighs 390 lbs.

"K. & J." PRESSED BOWL WHEEL SCRAPERS.

WITH K. & J. IMPROVED SAND PROOF HUB WHEELS.



The largest sized Scraper is easily operated by one man. No strain on horses' necks.

No. 2. Capacity, 13 cubic feet; wheels, 40 inches in diameter; tire, 3 x ¼ inches. Size of bowl: Length, 36 inches; width, 38 inches; depth, 13½ inches—all inside measurement. Tracks, 4 feet 7 inches. Weight, 600 pounds.

No. 3. Capacity, 17 cubic feet; wheels, 46 inches in diameter; tire, 3 x ¼ inches. Size of bowl: Length, 42 inches; width, 42 inches; depth, 16 inches—all inside measurement. Tracks, 5 feet 2 inches. Weight, 744 pounds.

No. 3 has draft-rod. No. 2 sent with draft-rod only when specially ordered.

Whiffletrees and neck-yokes are never furnished with Wheel Scrapers, unless specially ordered, and are always charged extra.



## K. & J. BOLTED RAILROAD OR CANAL BARROWS.

Diameter of wheel, 17 in.; tire  $\frac{3}{8}$  x  $1\frac{1}{8}$  in.; spokes,  $\frac{7}{8}$  x 1 in.;  $\frac{1}{2}$  in. axle bolt.

Full sized Bent Tray, planed, cleated and strapped together. Bolted securely to frame. The legs extend upward, serving as a brace to the bowl, to which they are bolted. They are also bolted to handles.

This Barrow has the Jacobs' Patent Wheel, superior to any wood wheel manufactured.

The Barrow for Railroad Contractors. Will out-wear any other made. **WITH JACOBS' PATENT No. 2 WOOD WHEEL—PAINTED**  
Knocks down completely for shipping, and is easily set up. Weight, 50 lbs.



WITH STEEL SPOKE WHEEL.



WITH STEEL SPOKE WHEEL.

Best R. R. Barrow manufactured.

With Lewis or Jacobs' Patent Steel Wheel, as ordered.

Diameter of wheel,  $16\frac{1}{2}$  inches; wrought-iron tire,  $1\frac{3}{8}$  inches wide,  $\frac{3}{8}$  inch thick; steel spokes, in Lewis' wheel  $\frac{3}{8}$  inch round, in Jacobs' wheel  $\frac{5}{8}$  x  $\frac{1}{4}$ ; hub, 6 inches long,  $\frac{1}{2}$ -inch bore Weight, 55 lbs.


## "SCIOTO" RAILROAD OR CANAL BARROW.

A thoroughly first-class bolted Barrow.

Diameter of wheel, 17 inches; tire,  $\frac{3}{8}$  x  $1\frac{1}{8}$  inches; spokes,  $\frac{7}{8}$  x 1 inch;  $\frac{1}{2}$  inch axle bolt. Unpainted.

Knocks down completely for shipping, and is easily set up. Weight, per dozen, 576 lbs.

Also furnished with No. 13-X Lewis Steel Spoke Wheel. Diameter of Wheel,  $16\frac{1}{2}$  inches; spokes,  $\frac{3}{8}$  inch round; tire,  $1\frac{3}{8}$  x  $\frac{3}{8}$  inch;  $\frac{1}{2}$  inch axle bolt. Painted black. Weight, per dozen, 594 lbs.




WITH JACOBS' PATENT No. 2 WOOD WHEEL—UNPAINTED.

## WHEELBARROWS.

## FOLDING GARDEN OR FARM BARROW.

WITH JACOBS' PATENT WHEEL, REMOVABLE SIDEBOARDS, DOUBLE FRAMES.



No. 3-C. SET UP FOR USE.



FOLDED FOR SHIPPING.

These Barrows are made of thoroughly seasoned wood, with Double Frames, firmly bolted together, iron braced, and so constructed that, by simply removing one bolt (the axle) and two nuts, they can be folded flat down (see cut), and shipped at lowest rate of freight. But a moment's time is required to set up for use.

No. 2. Wheel,  $16\frac{1}{2}$  inches diameter; tire,  $1\frac{1}{8} \times \frac{3}{16}$  inches; spokes,  $\frac{7}{8} \times 1$  inch.

No. 3-C. " 19 " " " "  $1\frac{3}{8} \times \frac{3}{16}$  " " 1 x 1 "

No. 4-C. " 21 " " " "  $1\frac{3}{4} \times \frac{3}{16}$  " " 1 x  $1\frac{1}{4}$  "

No. 5-C. " 21 " " " "  $1\frac{3}{4} \times \frac{3}{16}$  " " 1 x  $1\frac{1}{4}$  "

Axle bolts on Nos. 2 and 3-C are  $\frac{1}{2}$ -inch; Nos. 4-C and 5-C,  $\frac{5}{8}$  inch.

No. 2 is small size, No. 3-C medium, No. 4-C large, and No. 5-C extra large.

No.	Dimensions of Bed.	Capacity.	Length of Handle.	Weight.	Price, Dozen.
2	11 x 20 x 25 inches.	3 cubic feet.	48 inches.	45 lbs.	\$.....
3-C	12 x 22 x 25 "	4 " "	52 "	52 "	.....
4-C	14 x 24 x 28 "	6 " "	54 "	59 "	.....
5-C	21 x 26 x 31 "	9 " "	54 "	80 "	.....

Painted Green and Varnished.



## WITH LEWIS OR JACOBS' PATENT STEEL-SPOKE WHEEL.

Nos. 2 and 3-C. Wheel,  $16\frac{1}{2}$  inches diameter; tire,  $1\frac{3}{8} \times \frac{3}{8}$  inches.

Nos. 4-C and 5-C. " 19 " " " "  $1\frac{3}{4} \times \frac{3}{8}$  "

# "COLUMBUS" TUBULAR STEEL WHEELBARROWS.

565

WITH WHEEL GUARD.

## STEEL DIRT BARROWS.



CUT OF NO. 4 STEEL DIRT BARROWS WITH NO. 18 LEWIS ROUND STEEL SPOKE WHEEL.

The No. 14 Lewis Steel Wheels used with these Barrows are 16½ inches in diameter, with iron tire 1½x3⁄8 inches, and steel spokes ½ inch round.

- No. 4. Tray made of No. 15 Steel. Capacity 3 cubic feet of earth. Suitable for light work, as carrying loose earth, sand, etc. Weight of Barrow, 70 pounds. Price, each..... \$10.75
- No. 4½. Tray made of No. 14 Steel. Capacity 3 cubic feet of earth. Weight of Barrow, 75 pounds. Price, each..... 11.50
- No. 5. Tray made of No. 14 steel. Capacity, 4 cubic feet of earth. Weight of Barrow, 78 pounds. Price, each..... 13.50

These Barrows are intended for moving earth, sand, gravel, mortar, etc. For the heaviest work in mines, quarries, etc., we recommend our Tubular Mining or General Purpose Steel Barrows.

## MEMORANDUM OF ONE DOZEN NO. 4 BARROWS PACKED FOR EXPORT.

Number of Packages.	Contents of Each Package.	Dimension in Inches.	Net Weight Each.	Total Weight	Cubic Feet.
One Crate.	12 Frames and Wheels	27x30x70	589	681	33
One Crate.	12 Trays .....	14x32x35	274	320	9

## STEEL MINING AND GENERAL PURPOSE BARROWS.

The No. 15 Lewis Steel Wheels, with which these Barrows are furnished are 16½ inches in diameter, with iron tire 1¾x3⁄8 inches, and steel spoke ½ inch round, and extra heavy malleable iron hubs.

These Barrows have extra heavy leg braces, are intended for hard usage, and are the best general purpose all-metal Barrows manufactured.

- No. 6. Tray made of No. 14 steel. Size of Tray, same as No. 4 Dirt Barrow. Weight of Barrow, 83 pounds. Price, each..... \$12.25
- No. 7. Tray made of No. 14 steel. Size of Tray, same as No. 5 Dirt Barrow. Also suitable for small Coal Barrow. Weight of Barrow, 88 pounds. Price, each..... 14 25

## STEEL FOUNDRY BARROWS.



CUT OF NO. 9 STEEL FOUNDRY BARROW WITH NO. 15 LEWIS ROUND STEEL SPOKE WHEEL.


Wheels and leg braces on these Barrows are same as Nos 6 and 7, described above. Intended for wheeling castings, hot iron, etc., and for general foundry and furnace use.

- No. 8. Tray made of No. 12 steel. Size of Tray same as Nos. 4 and 6. Weight of Barrow, 95 pounds. Price, each..... \$14.00
- No. 9. Tray made of No. 12 steel. Size of Tray, same as Nos. 5 and 7. Weight of Barrow, 98 pounds. Price, each..... 16.00



## CORN SHELLERS.

### THE "GOULD" ONE-HOLE CORN SHELLER.




This is a very popular machine, because it is strong, durable, efficient and easy to operate. The frame is made of hard wood, the shafting of steel. All parts are properly proportioned and the entire machine is built and finished in a workman-like manner. The balance wheel is large in diameter and very heavy. Has an adjustable rag-iron so that it may be adapted to large or small ears of corn.

The machine will shell any kind of corn and clean it nicely. Furnished with or without fan and feed table, as may be desired.


### THE "HANDY" CORN SHELLER.

FOR HAND POWER ONLY.



A sheller that is portable, and can be used winter evenings near the kitchen fire, to shell pop corn, seed corn, corn for poultry, and for other purposes. Is in demand even by those who own a large-sized sheller. It is very simple, and there is nothing about the machine to get out of order. Simple, strong, convenient and cheap.

## THE "GOULD" TWO-HOLE CORN SHELLER.



FOR HAND OR POWER.


This Machine is suitable for farm, warehouse or custom mill use. It has large capacity, is thoroughly well made and nicely finished. The frame is made of hardwood, the shafting of steel, and it is fitted with a heavy balance wheel.

The rag-irons are adjustable and may be set so as to shell either large or small ears of corn, and the machine will shell and clean corn perfectly.

Each machine is fitted with feed-table, fan, cob-carrier, crank and pulley.

The pulley is 8-inch diameter by 4-inch face, and when run by power should make 300 to 400 revolutions per minute.

## THE "DEWEY" DOUBLE AUTOMATIC STOCK WATERER.



AA, double drinking cup; BB, valve and float compartment; C, brass float; D, valve; E, screen—remove for pipe attachment; F, division and shield broken away to show outlet for water; H, barrel or tank space.

Valve, 8 inches in water; governed by water closet; brass float which cannot rust, freeze nor allow mud to collect under it.

Attachable to tank, barrel or pipe instantly by the most inexperienced.

Waters 150 to 300 hogs a day; also sheep, calves, chickens and ducks.

## CHURCH AND FIRE BELLS.



The Meneely Bells have been known to the public since 1826. Unequaled for Sonorousness, Power, Musical Qualities, Purity and Beauty of Tone. Production over 30,000 Bells.

Genuine Bell Metal Bells are sold by the pound, the price being determined by the prices of copper and tin. The mountings are an additional charge.

Ranging in weight from 100 to 6,000 pounds and upwards, and mounted with Patent Conical Rotary Yoke, Wheel, Frame, Standards and Tolling hammer. Spring Steel clapper springs are attached to all sizes. Friction Rollers are furnished with all large Bells; and special mountings are constructed when necessary.

The line of Bells in this department embraces over one hundred patterns, extending from the smaller Bells adapted to the belfry of the wayside chapel, to the large and deep-toned Bells that resound from massive towers. Bells can be furnished of any desired pattern weight.

The tone in properly proportioned Bells depends entirely upon the weight of metal employed. With increase of weight is obtained a deeper and more melodious tone and a greater volume of sound.

These Bells are used for churches, schools, fire-alarms, court houses, with tower-clocks, etc. We are Western Agents for these Bells and can furnish promptly and at factory prices. These Bells are guaranteed for five years. Send for circulars and prices.

BELL.			MOUNTINGS.		
Weight.	Medium Tone.	Diameter.	Size of Frame Outside.	Diameter of Wheel.	Price of Mountings.
100 lbs.	.....	17 in.	2 ft. 5 in. x 2 ft. 8 in.	.....	\$13.00
125 "	.....	18½ "	2 " 6 " x 2 " 8 "	.....	13.00
150 "	.....	19½ "	2 " 6 " x 2 " 8 "	.....	15.00
175 "	.....	20½ "	2 " 8 " x 3 " 1 "	.....	20.00
200 "	.....	21¼ "	2 " 8 " x 3 " 1 "	.....	20.00
225 "	.....	22 "	2 " 8 " x 3 " 1 "	.....	20.00
250 "	.....	23 "	3 " 0 " x 3 " 2 "	.....	23.00
300 "	.....	24½ "	3 " 1 " x 3 " 4 "	.....	25.00
350 "	.....	26 "	3 " 1 " x 3 " 4 "	.....	27.00
375 "	.....	27 "	3 " 1 " x 3 " 4 "	.....	27.00
400 "	D	27 "	3 " 6 " x 3 " 5 "	4 ft.	30.00
450 "	D	28 "	3 " 6 " x 3 " 5 "	4 "	30.00
500 "	D	29 "	3 " 6 " x 3 " 9 "	4 " 4 in.	35.00
550 "	D	30 "	3 " 6 " x 3 " 9 "	4 " 4 "	35.00
600 "	C	31 "	3 " 6 " x 3 " 9 "	4 " 4 "	35.00
650 "	C	32 "	3 " 6 " x 3 " 9 "	4 " 4 "	35.00
700 "	B	33 "	4 " 5 " x 4 " 1 "	5 " 6 "	40.00
750 "	B	33 "	4 " 5 " x 4 " 1 "	5 " 6 "	40.00
800 "	B	34 "	4 " 5 " x 4 " 1 "	5 " 6 "	40.00
900 "	B	36 "	4 " 5 " x 4 " 5 "	5 " 6 "	45.00
1,000 "	A	37 "	4 " 5 " x 4 " 5 "	5 " 6 "	45.00
1,100 "	A	38 "	4 " 5 " x 4 " 5 "	5 " 6 "	45.00
1,200 "	A	39 "	4 " 10 " x 4 " 9 "	6 " 3 "	55.00
1,300 "	A	40 "	4 " 10 " x 4 " 9 "	6 " 3 "	55.00
1,400 "	G	41 "	5 " 3 " x 5 " 0 "	6 " 3 "	70.00
1,500 "	G	42 "	5 " 3 " x 5 " 0 "	6 " 3 "	70.00
1,600 "	G	43 "	5 " 3 " x 5 " 0 "	6 " 3 "	70.00
1,700 "	F	44 "	5 " 8 " x 5 " 5 "	7 "	90.00
1,800 "	F	45 "	5 " 8 " x 5 " 5 "	7 "	90.00
2,000 "	F	46 "	5 " 8 " x 5 " 5 "	7 "	90.00
2,100 "	F	47 "	5 " 8 " x 5 " 5 "	7 "	90.00
2,300 "	E	49 "	5 " 8 " x 5 " 7 "	7 " 6 "	115.00
2,500 "	E	50 "	5 " 8 " x 5 " 7 "	7 " 6 "	115.00
2,800 "	E	52 "	6 " 6 " x 6 " 3 "	8 "	130.00
3,000 "	E	53 "	6 " 6 " x 6 " 3 "	8 "	130.00
3,200 "	D	54 "	6 " 6 " x 6 " 3 "	8 "	140.00
3,500 "	D	56 "	6 " 6 " x 6 " 3 "	8 "	140.00
4,000 "	D	59 "	6 " 6 " x 6 " 3 "	8 "	140.00
4,500 "	D	62 "	6 " 9 " x 6 " 6 "	8 " 6 "	150.00
5,000 "	C	64 "	7 " 8 " x 7 " 4 "	9 "	165.00
6,000 "	B	67 "	7 " 8 " x 7 " 4 "	9 "	190.00



Doubling the diameter of a pipe increases its capacity four times. Friction of liquids in pipes increases as the square of the velocity.

The mean pressure of the atmosphere at tide level is usually estimated at 14.7 lbs. per square inch, so that with a perfect vacuum it will sustain a column of mercury 29.9 inches, or column of water 33.9 feet high. In ordinary practice we recommend Pumps be placed not over twenty feet above water supply, and even nearer, where possible.

*To find the capacity of any single-acting cylinder*, square the diameter (in inches of the cylinder), multiply this by .7854, and the result (which is the area of the circle of cylinder) by the length of stroke in inches. This gives the capacity in cubic inches per stroke. Multiply this by the number of strokes per minute and divide the product by 231 (the number of cubic inches in a gallon of water). The result will be capacity or gallons of water the cylinder will discharge per minute.

A two-cylinder or double-acting cylinder has double the capacity of a single-acting cylinder.

*To find the pressure in pounds per square inch* of a column of water, multiply the height of the column in feet by .434. Approximately, we say that every foot elevation is equal to  $\frac{1}{2}$ -lb. pressure per square inch ; this allows for ordinary friction.

*To find the horse power* necessary to elevate water to a given height, multiply the number of gallons per minute by total number of feet water is raised (that is, from surface of the water to the highest point to which the water is raised), and divide by 4,000 and you have the horse power. One horse power is equal to about five men. To the theoretical power a liberal allowance for friction, etc., always should be added.

## WEIGHT AND CAPACITY OF DIFFERENT STANDARD GALLONS OF WATER.

	Cubic Inches in a Gallon.	Weight of a Gallon in Pounds.	Gallons in a Cubic Foot.	Weight of a Cubic Foot of Water, English Standard, Lbs. Avoirdupois.
Imperial, or English.....	277.274	10.00	6.232102	62.321
United States.....	231	8.33111	7.470519	

## BAROMETRIC PRESSURES AT DIFFERENT ALTITUDES.

WITH EQUIVALENT HEAD OF WATER AND THE VERTICAL SUCTION LIFT OF PUMPS.

Altitude.	Barometric Pressure.	Equivalent Head of Water.	Practical Suction Lift of Pump.	Altitude.
Sea Level.....	14.70 lbs. per sq. in.	33.95 ft.	25 ft.	Sea Level.....
$\frac{1}{4}$ mile (1320 ft.) above sea level	14.02 " "	32.38 "	24 "	$\frac{1}{4}$ mile (1320) ft. above sea level
$\frac{1}{2}$ " (2640 ft.) " " "	13.33 " "	30.79 "	23 "	$\frac{1}{2}$ " (2640) ft. " " "
$\frac{3}{4}$ " (3960 ft.) " " "	12.66 " "	29.24 "	21 "	$\frac{3}{4}$ " (3960) ft. " " "
1 " (5280 ft.) " " "	12.02 " "	27.76 "	20 "	1 " (5280) ft. " " "
$1\frac{1}{4}$ " (6600 ft.) " " "	11.42 " "	26.38 "	19 "	$1\frac{1}{4}$ " (6600) ft. " " "
$1\frac{1}{2}$ " (7920 ft.) " " "	10.88 " "	25.13 "	18 "	$1\frac{1}{2}$ " (7920) ft. " " "
2 " (10560 ft.) " " "	9.88 " "	22.82 "	17 "	2 " (10560) ft. " " "

## TABLE OF CAPACITY OF PUMPS.

Dia. of Cyl. Ins.	Area, Square Inches.	LENGTH OF STROKE IN INCHES.															Dia. of Cyl. Ins.	
		2	3	4	5	6	7	8	9	10	12	14	15	16	18	20		24
		Capacity per Stroke in Gallons, or Decimal Parts Thereof.																
1 1/8	.196	.002	.003	.003	.004	.005	.006	.007	.008	.009	.01	.012	.013	.014	.015	.017	.02	1 1/8
1 1/4	.307	.003	.004	.005	.007	.008	.009	.011	.012	.013	.016	.019	.021	.021	.024	.027	.032	1 1/4
1 1/2	.442	.004	.006	.008	.01	.011	.013	.015	.017	.019	.023	.027	.029	.031	.034	.038	.046	1 1/2
1 3/4	.601	.005	.008	.01	.013	.016	.018	.021	.023	.026	.031	.036	.039	.042	.047	.052	.062	1 3/4
2	.785	.007	.01	.014	.017	.02	.024	.027	.031	.034	.041	.048	.051	.054	.061	.068	.082	2
2 1/8	.994	.009	.013	.017	.022	.026	.03	.034	.039	.043	.052	.06	.065	.069	.077	.086	.103	2 1/8
2 1/4	1.227	.011	.016	.021	.027	.032	.037	.043	.048	.053	.064	.074	.08	.085	.096	.106	.127	2 1/4
2 1/2	1.485	.013	.019	.026	.032	.039	.044	.051	.058	.064	.077	.089	.096	.103	.116	.128	.154	2 1/2
2 3/4	1.767	.015	.023	.031	.038	.046	.054	.061	.069	.077	.092	.107	.115	.122	.138	.153	.184	2 3/4
3	2.405	.021	.031	.042	.052	.063	.073	.083	.094	.104	.125	.146	.156	.167	.187	.208	.25	3
3 1/8	3.142	.027	.041	.054	.068	.082	.095	.109	.122	.136	.163	.19	.204	.218	.245	.272	.326	3 1/8
3 1/4	3.976	.034	.052	.069	.086	.103	.121	.138	.155	.172	.206	.241	.258	.275	.31	.344	.413	3 1/4
3 1/2	4.909	.043	.064	.085	.106	.128	.149	.17	.191	.213	.255	.298	.319	.34	.383	.425	.51	3 1/2
3 3/4	5.94	.051	.077	.103	.129	.154	.18	.206	.231	.257	.309	.36	.386	.411	.463	.514	.617	3 3/4
4	7.069	.061	.092	.122	.153	.184	.214	.245	.275	.306	.367	.428	.459	.49	.551	.612	.734	4
4 1/8	8.296	.072	.108	.144	.18	.215	.251	.287	.323	.359	.431	.503	.539	.575	.647	.718	.862	4 1/8
4 1/4	9.621	.083	.125	.167	.208	.25	.292	.333	.375	.417	.5	.583	.625	.666	.75	.833	1.	4 1/4
4 1/2	11.045	.095	.143	.191	.239	.287	.335	.382	.43	.478	.574	.669	.717	.765	.861	.956	1.147	4 1/2
4 3/4	12.566	.109	.163	.218	.272	.326	.381	.435	.49	.544	.653	.762	.816	.87	.979	1.088	1.306	4 3/4
5	14.186	.123	.184	.246	.307	.368	.43	.491	.553	.614	.737	.86	.921	.982	1.105	1.228	1.473	5
5 1/8	15.904	.138	.207	.275	.344	.413	.482	.551	.62	.689	.826	.964	1.033	1.102	1.239	1.377	1.652	5 1/8
5 1/4	17.721	.153	.23	.307	.384	.46	.537	.614	.69	.767	.92	1.073	1.15	1.227	1.38	1.534	1.84	5 1/4
5 1/2	19.635	.17	.255	.34	.425	.51	.595	.68	.765	.85	1.02	1.19	1.275	1.36	1.53	1.7	2.04	5 1/2
5 3/4	21.648	.187	.281	.375	.469	.562	.656	.75	.843	.937	1.124	1.311	1.405	1.499	1.686	1.874	2.248	5 3/4
6	23.758	.206	.309	.411	.514	.617	.72	.823	.926	1.029	1.234	1.44	1.543	1.646	1.851	2.057	2.468	6
6 1/8	25.967	.225	.337	.45	.562	.674	.787	.899	1.011	1.124	1.348	1.573	1.686	1.798	2.022	2.248	2.696	6 1/8
6 1/4	28.274	.245	.367	.49	.612	.734	.857	.979	1.102	1.224	1.469	1.714	1.836	1.958	2.203	2.448	2.938	6 1/4
6 1/2	30.68	.266	.398	.531	.664	.797	.93	1.062	1.195	1.328	1.593	1.859	1.992	2.124	2.39	2.656	3.186	6 1/2
6 3/4	33.183	.287	.431	.574	.718	.861	1.005	1.149	1.293	1.436	1.796	2.011	2.155	2.298	2.589	2.873	3.447	6 3/4
7	35.785	.309	.465	.62	.775	.929	1.084	1.239	1.394	1.549	1.858	2.168	2.323	2.479	2.788	3.098	3.716	7
7 1/8	38.485	.333	.5	.666	.833	1.	1.166	1.333	1.499	1.666	1.999	2.332	2.499	2.666	2.999	3.332	3.998	7 1/8
7 1/4	44.179	.383	.574	.765	.956	1.148	1.339	1.53	1.721	1.913	2.295	2.678	2.869	3.06	3.443	3.825	4.59	7 1/4
7 1/2	47.173	.408	.613	.817	1.021	1.225	1.429	1.633	1.837	2.042	2.45	2.858	3.063	3.266	3.674	4.084	4.9	7 1/2
7 3/4	50.266	.435	.653	.87	1.088	1.306	1.523	1.741	1.958	2.176	2.611	3.046	3.264	3.482	3.917	4.352	5.222	7 3/4
8	56.745	.49	.735	.98	1.225	1.47	1.715	1.96	2.205	2.45	2.94	3.43	3.675	3.92	4.41	4.9	5.88	8
8 1/8	60.132	.52	.78	1.04	1.3	1.56	1.82	2.08	2.34	2.6	3.12	3.64	3.9	4.16	4.68	5.2	6.24	8 1/8
8 1/4	63.617	.551	.826	1.101	1.377	1.652	1.928	2.203	2.479	2.754	3.305	3.856	4.131	4.406	5.057	5.508	6.61	8 1/4
8 1/2	70.882	.612	.918	1.224	1.53	1.83	2.142	2.448	2.754	3.06	3.672	4.284	4.59	4.896	5.51	6.12	7.344	8 1/2
8 3/4	74.662	.646	.97	1.293	1.616	1.939	2.262	2.586	2.908	3.232	3.878	4.525	4.848	5.171	5.818	6.464	7.757	8 3/4
9	78.54	.68	1.02	1.36	1.7	2.04	2.38	2.72	3.06	3.4	4.08	4.76	5.1	5.44	6.12	6.8	8.16	9
9 1/8	95.033	.823	1.234	1.645	2.057	2.464	2.879	3.291	3.726	4.114	4.937	5.76	6.171	6.582	7.405	8.228	9.874	9 1/8
9 1/4	103.869	.90	1.351	1.80	2.252	2.701	3.15	3.60	4.05	4.505	5.406	6.30	6.75	7.2	8.1	9.	10.8	9 1/4
9 1/2	113.098	.979	1.468	1.958	2.448	2.938	3.422	3.917	4.406	4.896	5.875	6.854	7.344	7.833	8.813	9.792	11.75	9 1/2
9 3/4	132.733	1.149	1.723	2.297	2.872	3.445	4.022	4.596	5.17	5.745	6.894	8.042	8.616	9.192	10.34	11.49	13.78	9 3/4
10	153.938	1.332	1.998	2.665	3.331	3.997	4.664	5.33	5.996	6.663	7.994	9.328	9.993	10.66	11.99	13.32	15.98	10
10 1/8	165.13	1.43	2.142	2.856	3.574	4.284	5.0	5.718	6.426	7.148	8.578	10.0	10.71	11.424	12.852	14.28	17.136	10 1/8
10 1/4	176.715	1.529	2.294	3.059	3.824	4.589	5.354	6.119	6.884	7.649	9.178	10.7	11.47	12.23	13.76	15.29	18.35	10 1/4
10 1/2	201.062	1.74	2.61	3.48	4.35	5.22	6.09	6.96	7.83	8.703	10.44	12.18	13.05	13.92	15.66	17.40	20.88	10 1/2
11	254.47	2.202	3.303	4.404	5.505	6.606	7.707	8.808	9.909	11.01	13.21	15.41	16.51	17.61	19.81	22.02	26.42	11
11 1/8	314.16	2.720	4.08	5.44	6.8	8.16	9.52	10.88	12.24	13.6	16.32	19.04	20.4	21.76	24.48	27.2	32.64	11 1/8



## 571

Gallons per Minute.	SIZES OF PIPES.—INSIDE DIAMETER.													
	$\frac{3}{4}$ In.	1 In.	$1\frac{1}{4}$ In.	$1\frac{1}{2}$ In.	2 In.	$2\frac{1}{2}$ In.	3 In.	4 In.	5 In.	6 In.	7 In.	8 In.	10 In.	12 In.
5	3.3	0.84	0.31	0.12	0.03									
10	13.0	3.16	1.05	0.47	0.12	0.03								
15	28.7	6.98	2.38	0.97	0.27	0.06								
20	50.4	12.3	4.07	1.66	0.42	0.13	0.03							
25	78.0	19.0	6.40	2.62	0.67	0.21	0.10							
30		27.5	9.15	3.75	0.91	0.30	0.12	0.03						
35		37.0	12.4	5.05	1.26	0.42	0.14	0.05						
40		48.0	16.1	6.52	1.60	0.51	0.17							
45			20.2	8.15	2.01	0.62	0.27	0.07						
50			24.9	10.0	2.44	0.81	0.35	0.09	0.03					
75			56.1	22.4	5.32	1.80	0.74	0.21	0.06	0.03				
100				39.0	9.46	3.20	1.31	0.33	0.12	0.05				
125					14.9	4.89	1.99	0.51	0.17	0.07				
150					21.2	7.0	2.85	0.69	0.25	0.10		0.02		
175					28.1	9.46	3.85	0.95	0.34	0.14		0.03		
200					37.5	12.47	5.02	1.22	0.42	0.17	0.08	0.05	0.01	
250						19.66	7.76	1.89	0.65	0.26	0.13	0.07	0.03	.01
300						28.06	11.2	2.66	0.93	0.37	0.18	0.09	0.04	

Gallons.	3 In.	4 In.	5 In.	6 In.	7 In.	8 In.	10 In.	12 In.	14 In.	16 In.	18 In.	20 In.	24 In.	30 In.
350	15.2	3.65	1.28	.50	.25	.12	.05	.02						
400	19.5	4.73	1.68	.65	.32	.16	.06							
450	25.	6.01	2.10	.81	.42	.20	.07	.03						
500	30.8	7.43	2.70	.96	.49	.25	.09	.04	.017	.009	.005			
600		10.6	3.45	1.72	.86	.348	.13	.05	.024					
750			5.40	2.21	1.11	.53	.18	.08	.038					
1000			9.60	3.88	1.91	.94	.32	.13	.062	.036	.02			
1250						1.46	.49	.20						
1500						2.09	.70	.29	.135	.071				
1750							.95	.38						
2000							1.23	.49	.234	.123				
2500								.77	.362	.188	.107			
3000								1.11	.515	.267	.15	.09		
3500									.697	.365	.204	.124		
4000									.91	.47	.264	.158	.067	.022
4500										.593	.33	.20	.08	.027
5000										.73	.41	.244	.102	.035

PRESSURE PER SQUARE INCH INTO FEET HEAD OF WATER.

Feet Head.	Pounds per Sq. In.	Feet Head.	Pounds per Sq. In.	Feet Head.	Pounds per Sq. In.	Pounds per Sq. in.	Feet Head.	Pounds per Sq. In.	Feet Head.	Pounds per Sq. In.	Feet Head.
1	.43	60	25.99	200	86.62	1	2.31	40	92.36	170	392.52
2	.87	70	30.32	225	97.45	2	4.62	50	115.45	180	415.61
3	1.30	80	34.65	250	108.27	3	6.93	60	138.54	190	438.90
4	1.73	90	38.98	275	119.10	4	9.24	70	161.63	200	461.78
5	2.17	100	43.31	300	129.93	5	11.54	80	184.72	225	519.51
6	2.60	110	47.64	325	140.75	6	13.85	90	207.81	250	577.24
7	3.03	120	51.97	350	151.58	7	16.16	100	230.90	275	643.03
8	3.40	130	56.30	400	173.24	8	18.47	110	253.98	300	692.69
9	3.90	140	60.63	500	216.55	9	20.78	120	277.07	325	750.41
10	4.33	150	64.96	600	259.85	10	23.09	125	288.62	350	808.13
20	8.66	160	69.29	700	303.16	15	34.63	130	300.16	375	865.89
30	12.99	170	73.63	800	346.47	20	46.18	140	323.25	400	922.58
40	17.32	180	77.96	900	389.78	25	57.72	150	346.34	500	1154.48
50	21.65	190	82.29	1,000	433.09	30	69.27	160	369.43	1,000	2308



The driving pulley is called the Driver, and the driven pulley the Driven.

If the number of *teeth in gears* are used instead of diameter, in these calculations, number of teeth must be substituted wherever diameter occurs.

To find the diameter of Driver, the diameter of the Driven and its revolutions, and also revolutions of Driver being given: Multiply the diameter of Driven by its revolutions, and divide the product by the revolutions of the Driver; the quotient will give the diameter of the Driver. To find the diameter of Driven, the revolutions of the Driven, also diameter and revolutions of the Driver being given: Multiply the diameter of Driver by its revolutions, and divide the product by the revolutions of the Driven; the quotient will give the diameter of the Driven. To find the revolutions of the Driver, the diameter and revolutions of the Driven, also diameter of the Driver being given: Multiply the diameter of Driven by its revolutions, and divide the product by the diameter of Driver; the quotient will give the revolutions of Driver. To find the revolutions of the Driven, the diameter and revolutions of the Driver, also diameter of the Driven being given: Multiply the diameter of Driver by its revolutions, and divide the product by the diameter of Driven; the quotient will give the revolutions of Driven.

### HORSE POWER BELTING WILL TRANSMIT.

Width of Belt in Inches.	HORSE POWER PER 100 FT. VELOCITY OF BELT.		Width of Belt in Inches.	HORSE POWER PER 100 FT. VELOCITY OF BELT.	
	Single Belt.	Double Belt.		Single Belt.	Double Belt.
1	.09	.18	12	1.09	2.18
2	.18	.36	14	1.27	2.55
3	.27	.55	16	1.45	2.91
4	.36	.73	18	1.64	3.27
5	.45	.91	20	1.82	3.64
6	.55	1.09	22	2.00	4.00
7	.64	1.27	24	2.18	4.36
8	.73	1.46	28	2.55	5.09
9	.82	1.64	32	2.91	5.82
10	.91	1.82	36	3.27	6.55
11	1.	2.	40	3.64	7.27

In the calculations for horse power in the above table, the belt is assumed to run about horizontally, the semi-circumference of smaller pulley has been considered as the ordinary arc contact of belt. Any reduction of this contact will make approximate proportional reduction of horse power.

### HORSE POWER SHAFTING WILL TRANSMIT.

Diameter of Shaft in Inches.	REVOLUTIONS PER MINUTE.									
	100	125	150	175	200	225	250	300	350	400
15-16	1.2 h. p.	1.4 h. p.	1.7 h. p.	2.1 h. p.	2.4 h. p.	2.6 h. p.	3.1 h. p.	3.6 h. p.	4.3 h. p.	5.0 h. p.
1 3-16	2.4 "	3.1 "	3.7 "	4.3 "	4.9 "	5.5 "	6.1 "	7.3 "	8.5 "	9.7 "
1 7-16	4.3 "	5.3 "	6.4 "	7.4 "	8.5 "	9.5 "	10.5 "	12.7 "	14.8 "	16.9 "
1 11-16	6.7 "	8.4 "	10.1 "	11.7 "	13.4 "	15.1 "	16.7 "	20.1 "	23.4 "	26.8 "
1 15-16	10.0 "	12.5 "	15.0 "	17.5 "	20.0 "	22.5 "	25.0 "	30.0 "	35.0 "	40.0 "
2 3-16	14.3 "	17.8 "	21.4 "	24.9 "	28.5 "	32.1 "	35.6 "	42.7 "	49.8 "	57.0 "
2 7-16	19.5 "	24.4 "	29.3 "	34.1 "	39.0 "	44.1 "	48.7 "	58.5 "	68.2 "	78.0 "
2 11-16	26.0 "	32.5 "	39.0 "	43.5 "	52.0 "	58.5 "	65.0 "	78.0 "	87.0 "	104.0 "
2 15-16	33.8 "	42.2 "	50.6 "	59.1 "	67.5 "	75.9 "	84.4 "	101.3 "	118.2 "	135.0 "
3 3-16	43.0 "	53.6 "	64.4 "	75.1 "	85.8 "	96.6 "	107.3 "	128.7 "	150.3 "	171.6 "
3 7-16	53.6 "	67.0 "	79.4 "	93.8 "	107.2 "	120.1 "	134.0 "	158.8 "	187.6 "	214.4 "
3 11-16	65.9 "	82.4 "	97.9 "	115.4 "	121.8 "	148.3 "	164.8 "	195.7 "	230.7 "	243.6 "
3 15-16	80.0 "	100.0 "	120.0 "	140.0 "	160.0 "	180.0 "	200.0 "	240.0 "	280.0 "	320.0 "
4 7-16	113.9 "	142.4 "	170.8 "	199.3 "	227.8 "	256.2 "	284.7 "	341.7 "	398.6 "	455.6 "
4 15-16	156.3 "	195.3 "	234.4 "	273.4 "	312.5 "	351.5 "	390.6 "	468.7 "	546.8 "	625.0 "

# TABLE FOR EQUALIZING PIPES.

573

The size of main pipe is given in the column at the left. The number of branches is given in the line on top, and the proper size of branches is given in the body of the table on the line of each main and beneath the desired number of branches.

In commercial sizes the nominal  $1\frac{1}{4}$ -inch pipe is generally over-size. Often as large as  $1\frac{3}{8}$ . It is safe to call it 1.3 inches, and it is so figured in the table. Exact sizes are given for branch pipes. The designer of the pipe system can thus better select the commercial sizes to be used.

Copied by permission from the Catalogue of the Norwalk Iron Works Co., South Norwalk, Conn.

Size of Main Pipe.	NUMBER OF BRANCHES.														
	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
1 in.	.758	.644	.574	.525	.488	.459	.435	.415	.398	.383	.370	.358	.348	.338	.330
$1\frac{1}{4}$ "	.985	.838	.747	.683	.635	.597	.556	.540	.518	.498	.482	.466	.452	.440	.428
$1\frac{1}{2}$ "	1.14	.967	.861	.788	.733	.689	.653	.623	.597	.575	.555	.538	.522	.508	.494
2 "	1.52	1.29	1.15	1.05	.977	.918	.870	.830	.796	.766	.740	.717	.696	.677	.660
$2\frac{1}{2}$ "	1.89	1.61	1.44	1.31	1.22	1.15	1.09	1.09	.995	.958	.925	.896	.870	.846	.825
3 "	2.27	1.92	1.72	1.58	1.47	1.38	1.31	1.25	1.19	1.15	1.11	1.08	1.04	1.02	.989
$3\frac{1}{2}$ "	2.65	2.26	2.01	1.84	1.71	1.61	1.52	1.45	1.39	1.34	1.30	1.25	1.22	1.18	1.15
4 "	3.03	2.58	2.30	2.10	1.95	1.84	1.74	1.66	1.59	1.53	1.48	1.43	1.39	1.35	1.32
$4\frac{1}{2}$ "	3.41	2.90	2.58	2.36	2.20	2.07	1.96	1.87	1.79	1.72	1.67	1.61	1.57	1.52	1.48
5 "	3.79	3.22	2.87	2.63	2.44	2.30	2.18	2.08	1.99	1.92	1.85	1.79	1.74	1.69	1.65
6 "	4.55	3.87	3.45	3.15	2.93	2.75	2.61	2.49	2.39	2.30	2.22	2.15	2.09	2.03	1.98
7 "	5.30	4.51	4.02	3.68	3.42	3.21	3.05	2.91	2.79	2.68	2.59	2.51	2.44	2.37	2.31
8 "	6.06	5.16	4.59	4.20	3.91	3.67	3.48	3.32	3.18	3.09	2.96	2.87	2.78	2.71	2.64
9 "	6.82	5.80	5.17	4.73	4.40	4.13	3.92	3.74	3.58	3.45	3.33	3.23	3.13	3.04	2.97
10 "	7.58	6.44	5.74	5.25	4.88	4.59	4.35	4.15	3.98	3.83	3.70	3.59	3.48	3.38	3.30
12 "	9.08	7.73	6.89	6.30	5.86	5.51	5.22	4.98	4.78	4.60	4.44	4.30	4.18	4.06	3.96

## WROUGHT-IRON WELDED PIPE.

## CAPACITY OF ROUND TANKS AND CISTERNS

IN U. S. GALLONS, PER FOOT IN HEIGHT.

DIMENSIONS, WEIGHTS, Etc., OF STANDARD SIZES FOR STEAM, GAS, WATER, OIL, Etc.

One and one-fourth inch and below are butt-welded, and proved to 300 pounds per square inch hydraulic pressure.

One and one-half inch and above are lap-welded, and proved to 500 pounds, per square inch hydraulic pressure.

Diameter Feet.	Gallons.	Diameter Feet.	Gallons.	Nominal Inside Diameter.	Actual Outside Diameter.	Internal Area.	Weight per Foot of Length.	Contents in Gallons per Foot.	Weight of Water per Foot of Length.
2	23.5	17	1,698	$\frac{1}{2}$ in.	.84 in.	.304 in.	.84 lbs.	.0102	.085 lbs.
3	52.9	18	1,903	$\frac{3}{4}$ "	1.05 "	.533 "	1.12 "	.0230	.190 "
4	94	19	2,121	1 "	1.31 "	.862 "	1.67 "	.0408	.349 "
5	147	20	2,350	$1\frac{1}{4}$ "	1.66 "	1.496 "	2.25 "	.0638	.527 "
6	212	22	2,844	$1\frac{1}{2}$ "	1.9 "	2.038 "	2.69 "	.0918	.760 "
7	288	24	3,384	2 "	2.37 "	3.355 "	3.66 "	.1632	1.356 "
8	376	26	3,971	$2\frac{1}{2}$ "	2.87 "	4.783 "	5.77 "	.2550	2.116 "
9	476	28	4,606	3 "	3.5 "	7.388 "	7.54 "	.3673	3.049 "
10	588	30	5,288	$3\frac{1}{2}$ "	4 "	9.837 "	9.05 "	.4998	4.155 "
11	711	32	6,016	4 "	4.5 "	12.730 "	10.72 "	.6528	5.405 "
12	846	36	7,617	$4\frac{1}{2}$ "	5 "	15.939 "	12.49 "	.8263	6.851 "
13	993	40	9,400	5 "	5.56 "	19.990 "	14.56 "	1.020	8.500 "
14	1,152	45	11,897	6 "	6.62 "	28.889 "	18.76 "	1.469	12.312 "
15	1,322	56	14,688						
16	1,504	60	21,151						

## IRRIGATION TABLE.

GIVING CAPACITY IN GALLONS PER HOUR AND EQUIVALENT IN MINERS' INCHES, POWER REQUIRED PER FOOT LIFT AND IRRIGATING ACREAGE.

Gallons per Hour.	Miners' Inches.	Approximate Horse Power Required per Foot Lift.	Number of Acres Will Cover 1 Inch Deep in 10 Hours.
500	42	.004	.18
1,000	84	.007	.37
1,500	125	.01	.55
2,000	167	.014	.74
2,500	217	.017	.92
3,000	250	.02	1.11
3,500	292	.024	1.28
4,000	333	.027	1.48
4,500	375	.03	1.66
5,000	417	.034	1.8
6,000	500	.04	2.2
7,000	583	.047	2.5
8,000	667	.054	3.
9,000	750	.06	3.3
10,000	833	.067	3.7
15,000	1,250	.1	5.5
20,000	1,666	.134	7.4
25,000	2,083	.167	9.2
30,000	2,500	.2	11.1

## NOTE.

Because of varying conditions of climate and soil, no exact rule can be made, yet, as basis for estimate, a supply of 2 to 3 gallons water per minute per acre through irrigating season is considered liberal. Example: 100 acres 200 to 300 gallons water per minute. In many sections one-half this quantity is sufficient.

NOTE—As stated, a miners' inch of water is considered in these tables as 12 U. S. gallons per minute. If considered as 9 U. S. gallons per minute, increase our estimate one-third. Our estimate of approximate horse power required per foot lift also makes an allowance of 50 per cent. for friction of water in pipes, etc. The efficiency of small engines or motors of any type cannot be safely accepted on as close estimates as larger powers.

TABLE OF DISCHARGE OF WATER OVER WEIRS ONE INCH WIDE, IN GALLONS PER MINUTE.

Depth, inches.....	$\frac{1}{2}$	1	2	3	4	5	6	7	8	9	10	12	18	24	30
Gallons.....	1.14	3.2	9.1	16.7	25.7	35.4	47.2	59.6	72.8	86.5	101.7	133.7	245.7	378.2	516.6

APPROXIMATE HEIGHTS PUMPS MAY BE WORKED BY PONY OR HORSE GEAR.

The pony or horse in each case being estimated to walk at the rate of three miles per hour.

Diameter of Working Barrel or Cylinder, inches...	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4	5	6
Single-Barrel Pump, worked by Pony Gear.....	260 ft.	175 ft.	135 ft.	100 ft.	64 ft.	44 ft.
Double-Barrel Pump, worked by Pony Gear.....	130 "	88 "	68 "	50 "	32 "	22 "
Single-Barrel Pump, worked by Horse Gear.....	520 "	350 "	270 "	200 "	128 "	88 "
Double-Barrel Pump, worked by Horse Gear.....	260 "	176 "	136 "	100 "	64 "	44 "

The above calculations are based upon strong, powerful horses or ponies being used. If inferior animals are substituted, the heights given will, of course, not be attained.



# WEIGHTS AND MEASURES.

575

METRIC SYSTEM.		U. S. STANDARD.		METRIC SYSTEM.		U. S. STANDARD.	
LENGTH.		LENGTH.		WEIGHT.		WEIGHT.	
1 millimeter =	.0394 inches.	1 inch =	2.5309 centimeters.	1 gram =	15.4323 grains.	1 lb. =	.4536 kilos.
1 centimeter =	.3937 inches.	1 foot =	30.4794 centimeters.	1 KILOGRAM =	2.2046 lbs.	1 cwt. =	50.8024 kilos.
1 METER =	39.3708 inches.	1 yard =	9143 meters.	1 tonneau =	2204.55 lbs.	1 ton =	1016.0483 kilos.
1 kilometer =	0.6214 miles.	1 mile =	1.6093 kilometers.				
SQUARE.		SQUARE.		DRY MEASURE.		DRY MEASURE.	
1 sq. centimeter =	.1549 sq. in.	1 sq. in. =	6.4513 sq. centimeters.	1 centiliter =	.0181 pints.	1 pint =	55.0661 centiliters.
1 sq. meter =	10.7631 sq. feet.	1 sq. ft. =	.0929 sq. meters.	1 LITER =	.908 quarts.	1 quart =	1.1013 liters.
1 ARE =	119.5894 sq. yds.	1 sq. yd. =	.8361 sq. meters.	1 hectoliter =	2.837 bushels.	1 bushel =	35.2416 liters.
1 hectare =	2.4711 acres.	1 acre =	.4047 hectares.				
CUBIC.		CUBIC.		LIQUID MEASURE.		LIQUID MEASURE.	
1 CUBIC METER =	35.3166 cu. feet.	1 cubic foot =	.02831 cubic meters.	1 centiliter =	.0211 pints.	1 pint =	47.3171 centiliters.
				1 LITER =	1.0567 quarts.	1 quart =	.9563 liters.
				1 hectoliter =	26.4176 gallons.	1 gallon =	3.7854 liters.

1 U. S. ton of shipping = 40 cubic feet = 32.143 U. S. bushels = 1.1326 cubic meters.

*Minimum freight charged on a SS. B | L is on 20 cubic feet.*

## ESTIMATE OF VALUES OF FOREIGN COINS.

Country.	Monetary Unit.	Value in Terms of U. S. Gold Dollar.	Country.	Monetary Unit.	Value in Terms of U. S. Gold Dollar.
Argentine Republic.....	Peso.....	\$0.96,5	France.....	Franc.....	\$ .19,3
Austria-Hungary.....	Crown.....	.20,3	German Empire.....	Mark.....	0.23,8
Belgium.....	Frank.....	.19,3	Great Britain.....	Pound Sterling.....	4.86,6½
Bolivia.....	Boliviano.....	.44,3	Greece.....	Drachma.....	.19,3
Brazil.....	Milreis.....	.54,6	Haiti.....	Gourde.....	.96,5
British Possessions, N. A. ( <i>Except Newfoundland.</i> )	Dollar.....	1.00	India.....	Rupce.....	.210
Central American States:			Italy.....	Lira.....	.19,3
Costa Rica.....	Colon.....	.46,5	Japan.....	Yen, Gold.....	.49,8
Guatemala.....	Peso.....	.44,3	Liberia.....	Dollar.....	1.00
Honduras.....			Mexico.....	Dollar.....	.48,1
Nicaragua.....			Netherlands.....	Florin.....	.40,2
Salvator.....			Newfoundland.....	Dollar.....	1.01,4
Chili.....	Peso.....	.36,5	Norway.....	Crown.....	.26,8
China.....	Tael.....	.67,0	Peru.....	Sol.....	.44,3
		.75,3	Portugal.....	Milreis.....	1.08
		(Customs)	Russia.....	Ruble, Gold.....	.51,5
Colombia.....	Peso.....	.44,3	Spain.....	Peseta.....	.19,3
Cuba.....	Peso.....	.92,6	Sweden.....	Crown.....	.26,8
Denmark.....	Crown.....	.26,8	Switzerland.....	Franc.....	.19,3
Ecuador.....	Sucre.....	.44,3	Tripoli.....	Mahbub, 20 Piastres...	.41,3
Egypt.....	Pound (100 piastres).....	4.94,3	Turkey.....	Piastre.....	.04,4
Finland.....	Mark.....	.19,3	Venezuela.....	Bolivar.....	.19,3

## PUMP REPAIRS.

In the following Tables will be found a partial price list of Staple Pump Repairs. Repairs for Pumps not included in Tables will be quoted upon application.

GOULDS CISTERN PUMPS, FIGS. 198, 199, 200, 201, 202 1-2.

No.....	0	1	2	3	4	5	6	8
DIA. CYLINDER, INCHES	2	2¼	2½	2¾	3	3¼	3½	4
Lever or Handle.....	\$0.50	\$0.50	\$0.50	\$0.60	\$0.70	\$1.00	\$1.25	\$1.50
Fulcrum or Bearer Top....	.70	.70	.70	.75	.80	.90	1.10	1.50
Cylinder.....	1.45	1.60	1.80	1.90	2.25	2.40	3.00	4.00
Brass-Lined Cylinder.....	3.00	3.25	3.50	4.00	4.25	5.00	6.00	8.50
Brass Cylinder.....	5.00	5.50	6.00	6.50	7.00	8.00	10.00	13.50
Iron Top Section for B.C.								
Pump.....	1.00	1.00	1.15	1.25	1.50	2.00	2.50	3.50
Base, Figs. 198, 199, 200, 201	.75	.75	.75	.85	1.00	1.00	1.25	1.75
Bottom Cap, Fig. 202½.....	.50	.50	.50	.50	.50	.75	.75	1.00
Plunger with Rod.....	.70	.75	.80	.90	1.00	1.15	1.30	1.50
Plunger Rod only.....	.15	.15	.15	.15	.15	.15	.15	.15
Plunger Cage.....	.30	.35	.35	.40	.45	.50	.60	.70
Plunger Follower.....	.30	.35	.35	.40	.45	.50	.60	.70
Plunger Poppet Valve.....	.10	.10	.10	.10	.15	.15	.15	.15
Brass Plunger Poppet Valve, Fig. 199, etc.....	.20	.20	.20	.20	.30	.30	.30	.30
Brass Plunger with Rod..	1.40	1.50	1.60	1.80	2.00	2.30	2.60	3.00
Brass Plunger Cage.....	.60	.70	.70	.80	.90	1.00	1.20	1.40
Brass Plunger Follower... Plunger Leather.....	.60	.70	.70	.80	.90	1.00	1.20	1.40
Lower Valve complete....	.15	.15	.15	.15	.15	.20	.20	.20
Lower Valve Leather.....	.25	.25	.25	.25	.25	.35	.35	.35
Lower Valve Weight.....	.15	.15	.15	.15	.15	.20	.20	.20
Lower Valve Screw and Washer.....	.10	.10	.10	.10	.10	.15	.15	.15
Brass Valve Seat and Tube.....	.05	.05	.05	.05	.05	.05	.05	.05
Brass Tube for Iron or Lead Pipe.....	.75	.75	.75	.75	.75	1.00	1.25	1.75
Iron Pipe Nut.....	.50	.50	.50	.50	.50	.75	.75	1.00
Lead Pipe Nut.....	.35	.35	.35	.35	.35	.45	.45	.60
Base, Lever, Bearer Bolts and Set Screws.....	.25	.25	.25	.25	.25	.35	.35	.50
Leather Ring Packing ....	.08	.08	.08	.08	.08	.08	.08	.08
	.10	.10	.10	.10	.10	.10	.10	.10

GOULDS PITCHER PUMPS, FIGS. \*923, 205, 205½, 209, 208.

No.....	1	2	3	4	5	6
DIAMETER CYLINDER, INCHES	2½	3	3½	4	4½	5
Lever.....	\$0.60	\$0.60	\$0.60	\$0.60	\$0.75	\$1.00
Fulcrum or Bearer Top, Figs. 205, 209, 208, Open Top.....	.40	.40	.50	.50	.60	1.25
Fulcrum or Bearer Top, Figs. 205½, 209, 208, Closed Top.....	.60	.70	.85	.95	1.25	1.50
Cylinder .....	1.25	1.35	1.50	1.75	2.25	3.50
Brass-Lined or Porcelain-Lined Cylinder .....	2.50	3.00	3.50	4.00	5.00	7.50
Base, Figs. 205, 205½, 209.....	.75	.85	1.00	1.25	1.75	3.25
Same for Brass Valve Seat.....	.80	.90	1.00	1.15	1.50	3.00
Base, Fig. 208.....	1.60	1.75	2.00	.....	.....	.....
Plunger complete with Rod.....	.75	.80	.90	1.00	1.50	2.00
Plunger Rod.....	.10	.10	.10	.15	.15	.25
Plunger Cage.....	.35	.45	.60	.70	.80	1.00
Plunger Follower.....	.35	.45	.60	.70	.80	1.00
Plunger Poppet Valve.....	.10	.15	.15	.15	.20	.25
Plunger Leather.....	.15	.15	.20	.20	.20	.30
Lower Valve Complete.....	.25	.25	.35	.35	.35	.45

## GOULDS PITCHER PUMPS, FIGS. \*923, 205, 205½, 209, 208.—Continued.

No.....	1	2	3	4	5	6
DIAMETER CYLINDER, INCHES	2½	3	3½	4	4½	5
Lower Valve Leather.....	\$0.15	\$0.15	\$0.20	\$0.20	\$0.20	\$0.30
Lower Valve Weight.....	.10	.10	.15	.15	.15	.15
Lower Valve Screw and Washer.....	.05	.05	.05	.05	.05	.05
Brass Valve Seat and Tube.....	.75	.90	1.10	1.20	1.30	1.75
Iron Pipe Nut.....	.35	.35	.35	.45	.45	.75
Lead Pipe Nut.....	.25	.25	.25	.35	.35	.60
Brass Tube for Iron or Lead Pipe.....	.50	.50	.50	.75	.75	1.50
Brass Valve Plate.....	.50	.50	.50	.75	.75	1.00
Leather Ring Packing.....	.10	.10	.10	.15	.20	.25
Base, Set Screw and Lever Bolts.	.08	.08	.08	.08	.08	.08

\* Fig. 923, Repairs takes Lists of No. 1 Pumps.

GOULDS WELL PUMPS, FIGS. 1018, 1019, AND PUMP STANDARDS,  
FIGS. 1023 AND 1024.

Lever or Handle, Fig. 1018.....	\$1.00
“ “ “ 1019.....	1.25
Fulcrum or Bearer Top, Fig. 1018.....	.75
“ “ “ 1019.....	1.25
Stock or Standard only, Figs. 1018 and 1019.....	3.50
Bearer Link, Fig. 1019.....	.25
Crosshead, Fig. 1019.....	.50
Long Plunger Rod, Fig. 1018.....	.50
Long Polished Plunger Rod, Fig. 1019.....	.75
Brace, Figs. 1018 and 1019.....	.50
Extra Connecting Pipe and Rod, per foot.....	.50
Cylinder Repairs, see page 582.	

GOULDS "STAR" WELL PUMPS, FIGS. 550, 551, 553, 554, 847,  
848, 847 $\frac{1}{2}$ , 848 $\frac{1}{2}$ .

	ALL SIZES.
Level or Handle, Figs. 550.....	\$1.00
Level or Handle, Figs. 551, 553, 847, 848, 847½, 848½.....	1.25
Level or Handle Fig. 554.....	1.25
Fulcrum or Bearer Top, Figs. 550, 847½.....	.90
Fulcrum or Bearer Top, Figs. 551, 847.....	1.10
Fulcrum or Bearer Top, Fig. 553.....	1.25
Fulcrum or Bearer Top, Fig. 848½.....	1.15
Fulcrum or Bearer Top, Figs. 554, 848.....	1.35
Stock or Standard only, Figs. 550, 553, 847½, 848½.....	3.75
Stock or Standard only, Figs. 551, 554, 847, 848.....	4.25
Bearer Link, Figs. 553, 554.....	.50
Links, Figs. 848, 848½, per pair.....	.25
Crosshead, Figs. 848, 848½.....	.50
Long Connecting Rods, Figs. 550, 551, 847, 847½.....	.50
Long Flat Rod, Figs. 553, 554.....	.75
Long Polished Round Rod, Figs. 848, 848½.....	.75
Lever, Bearer, Brace Bolts and Set Screws.....	.08
Pin through Rod, Figs. 553, 554.....	.15
Brace.....	.50
Extra Connecting Pipe and Rod per foot.....	.50
Cylinder Repairs, see page 582.	



## WELL PUMP, FIG. 1039, AND WELL PUMP STANDARD, FIG. 1032.

	Fig. 1039, 6-in.	Fig. 1032, 6-in.	10-in.
STROKE.....			
Lever or Handle.....	\$1.00	\$1.00	\$1.25
Fulcrum or Bearer.....	1.25	1.25	1.50
Stock or Standard.....	3.50	3.50	3.50
Bearer Link.....	.25	.25	.50
Rod.....	.75	.50	.75
Pin of Malleable Iron.....	.10	.10	.10
Brace.....	.50	.50	.50
Rod Coupling.....	.20	.20	.20

Cylinder Repairs, see page 582.

## GOULDS "STAR" WELL PUMPS. FIGS. 206, 207, 212 AND PUMP STANDARD, FIG. 845.

No.	1	2	3	4	5
Lever or Handle.....	\$0.75	\$0.75	\$0.85	\$0.85	\$0.85
Fulcrum or Bearer Top.....	.75	.75	.80	.80	.85
Stock or Standard only.....	2.00	2.25	2.60	2.75	3.00
Base.....	.75	.75	.85	1.00	1.00
Brace.....	.50	.50	.50	.50	.50
Long Connecting Rod.....	.50	.50	.50	.50	.50
Leather Packing for Base.....	.15	.15	.15	.15	.20
Lever, Bearer, Base and Brace Bolts.....	.08	.08	.08	.08	.08
Extra Connecting Pipe and Rod, Fig. 207, per foot.....	.50	.50	.50	.50	.50
2 feet Cast Set Length, Fig. 206.....	1.75	1.75	1.75	1.75	1.75
3 feet Cast Set Length, Fig. 206.....	2.25	2.25	2.25	2.25	2.25
Set Lengths Complete.....		3.50		4.00	

Cylinder Repairs—See page 582.

## GOULDS WELL FORCE PUMP, FIG. 1153.

Air Chamber with Tube and Thumb-screw.....	\$2.50
Thumb-screw only.....	.15
Fulcrum and Clamp.....	1.50
Fulcrum Clamp only.....	.25
Lever.....	1.00
Link.....	.25
Cross Head.....	.25
Brass Gland.....	.50
Hose Tube Nut.....	.25
Hose Tube.....	.25
Plunger Rod.....	.75
Brace.....	.50
Adjustable Brace Ring.....	.50
Brace Ring Set Screw.....	.05
Adjustable Base with Set Screws.....	1.50
Base Set Screws (2) each.....	.05
Reducer.....	.25
Bearer, Lever Pins and Sundry Bolts, each.....	.08

Cylinder Repairs—See page 582.

## GOULDS WELL LIFT PUMP, FIG. 1252.

Top Section only.....	\$1.50
Fulcrum.....	.75
Lever.....	1.00
Plunger Rod.....	.75
Adjustable Base with Set Screws.....	1.00
Base Set Screws (2) each.....	.05
Brace.....	.50
Adjustable Brace Ring.....	.50
Brace Ring Set Screw.....	.05
Sundry Bolts.....	.08

Cylinder Repairs—See page 582.

GOULDS "STAR" WELL FORCE PUMPS AND STANDARDS,  
FIGS. 1244, 1245, 852 $\frac{1}{2}$ , 882 $\frac{1}{2}$ , 852, 882 ALL SIZES.  
FIGS. 853, 883 NOS. 0, 1, 2.

Lever or Handle.....	\$1.25
Fulcrum or Bearer Top.....	1.25
Stock or Standard only, Figs. 852, 882 and 853, 883 No. 2.....	5.25
Stock or Standard only, Figs. 852 $\frac{1}{2}$ , 882 $\frac{1}{2}$ and 853, 883 No. 1.....	4.75
Stock or Standard only, Figs. 1244, 1245 and 853, 883 No. 0.....	4.50
Links per pair.....	.25
Cross Head, including Set Screw.....	.50
Long Polished Round Rod, Figs. 1244, 1245, 852 $\frac{1}{2}$ , 882 $\frac{1}{2}$ , 852, 882 ...	.75
Short Polished Round Rod, Figs. 422, 423.....	.60
Brass Gland.....	.75
Air Chamber Inside Tube.....	.30
Spout, Figs. 852 and 852 $\frac{1}{2}$ , 1244 and 853.....	0.50
Cock Spout, Figs. 882 and 882 $\frac{1}{2}$ , 1245, 883.....	2.50
Iron Cock Body and Brass Valve Seat, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883...	1.00
Cock Body only, iron, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.80
Brass Valve Seat only, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.20
Brass Cap for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.50
Brass Packing Ring for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.15
Brass Valve Stem for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.60
Brass Valve Body for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.40
Valve Packing for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.05
Cap Packing for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.05
Small Brass Nut for Cock, Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.04
Hose Tube Nut for Cock., Figs. 882, 882 $\frac{1}{2}$ , 1245, 883.....	.25
Hose Tube.....	.25
Back Plug.....	.25
Brace.....	.50
Leather Spout Packing.....	.25
Leather Ring Packing.....	.10
Brass Thumb Screw.....	.25
Sundry Bolts.....	.08
Extra Connecting Pipe and Rod, per foot.....	.50

Cylinder Repairs, see page 582.

GOULDS "STAR" WIND MILL FORCE PUMPS AND STANDARDS,  
FIGS. 1247, 1248, 424, 426 AND 422, 423.

Lever or Handle.....	\$1.40
Fulcrum and Guide, Figs. 422, 423 No. 0, and Figs. 1247, 1248.....	1.50
Pat. Extension Stroke Guide, Figs. 422, 423 No. 0, and Figs. 1247, 1248.....	.25
Fulcrum 6-in. Stroke, Figs. 422, 423 Nos. 1 and 2, and Figs. 424 426.....	1.50
Fulcrum 10-in. Stroke, Figs. 422, 423 Nos. 1 and 2 and Figs. 424 426.....	1.75
Fulcrum Link, 6-in. Stroke.....	.50
Fulcrum Link, 10-in. Stroke.....	.75
Stock or Standard only, Figs. 422 and 423 No. 2.....	5.25
Stock or Standard only, Figs. 422, 423 No. 1 and 424, 426.....	4.75
Stock or Standard only, Figs. 422, 423 No. 0 and 1247, 1248.....	4.50
Short Flat Rod, Figs. 422, 423 Nos. 1 and 2 and 424, 426.....	.50
Rod Coupling and Set Screw, Figs. 422, 423 Nos. 1 and 2 and 424, 426.....	.25
Short Polished Round Rod, Figs. 422, 423 Nos. 1 and 2.....	.60
Long Round Plunger Rod Polished at Top, Figs. 424 and 426.....	.75
Short, Flat and Round Rod, Figs. 422, 423 No. 0.....	1.00
Long, Flat and Round Rod, Figs. 1247, 1248.....	1.25
Brass Gland.....	.75
Air Chamber Inside Tube.....	.30
Spout, Figs. 422, 424, 1247.....	.50
Cock Spout Complete, Figs. 423, 426, 1248.....	2.50
Iron Cock Body and Brass Valve Seat, Figs. 423, 426, 1248.....	1.00
Iron Cock Body only, Figs. 423, 426, 1248.....	.80
Brass Valve Seat only for Cock, Figs. 423, 426, 1248.....	.20
Brass Cap for Cock, Figs. 423, 426, 1248.....	.50



## GOULDS "STAR" WIND MILL FORCE PUMPS AND STANDARDS,

FIGS. 1247, 1248, 424, 426 AND 422, 423.

Brass Packing Ring for Cock, Figs. 423, 426, 1248.....	\$0.15
Brass Valve Stem for Cock, Figs. 423, 426, 1248.....	.60
Brass Valve Body for Cock, Figs. 423, 426, 1248.....	.40
Valve Packing for Cock, Figs. 423, 426, 1248.....	.05
Cap Packing for Cock, Figs. 423, 426, 1248.....	.05
Small Brass Nut for Cock, Figs. 423, 426, 1248.....	.04
Hose Tube Nut.....	.25
Hose Tube.....	.25
Back Plug.....	.25
Brass Thumb Screw.....	.25
Brace.....	.50
Wind Mill Slide.....	.50
Female Wood Rod Coupling.....	.25
Leather Spout Packing.....	.15
Leather Ring Packing.....	.10
Bearer, Lever, Spout, Hook and Brace Bolts.....	.08
Pin through Flat Rod.....	.15
Extra Connecting Pipe and Rod, per foot.....	.50
Cylinder Repairs, see page 582.	

## GOULDS WELL FORCE PUMP, FIG. 854 AND PUMP STANDARD,

FIG. 855.

## ALL SIZES.

Lever or Handle.....	\$1.40
Fulcrum or Bearer Top.....	1.25
Stock or Standard only.....	3.60
Links per pair.....	.25
Crosshead, including Nut and Set Screw.....	.50
Long Polished Round Rod.....	.75
Polished Round Rod, Fig. 855.....	.60
Brass Gland.....	.75
Air Chamber only.....	3.00
Air Chamber Cap.....	.45
Air Chamber Inside Tube.....	.30
Air Chamber Nut.....	.50
Spout.....	.25
Spout Hose Tube Nut.....	.25
Spout Hose Tube.....	.25
Brace.....	.50
Lever, Bearer, Flange and Brace Bolts.....	.08
Leather Packing for Air Chamber.....	.25
Leather Ring Packing.....	.10
Extra Connecting Pipe and Rod, per foot.....	.50
Cylinder Repairs, see page 582.	

## GOULDS "EMPIRE" DOUBLE-ACTING WELL FORCE PUMPS,

FIGS. 1025, 1026, 1027 AND 1028.

No.....	2	4
DIAMETER OF LOWER CYLINDER, INCHES.....	2½	3
Lever or Handle, Figs. 1025 and 1027.....	\$1.00	\$1.00
Lever or Handle, Figs. 1026 and 1028.....	1.25	1.25
Bearer Link, Figs. 1026 and 1028.....	.35	.35
Stock only, two sides, Figs. 1025 and 1027.....	4.00	4.00
Stock only, two sides, Figs. 1026 and 1028.....	4.50	4.50

## GOULDS "EMPIRE" DOUBLE-ACTING WELL FORCE PUMPS,

FIGS. 1025, 1026, 1027 AND 1028.—Continued.

No.....	2	4
DIAMETER OF LOWER CYLINDER, INCHES.....	2½	3
Spout.....	\$0.50	\$0.50
Spout Hose Tube.....	.25	.25
Spout Hose Tube Nut.....	.25	.25
Spout Swivel Nut.....	.25	.25
Spout Swivel Pipe Coupling.....	.25	.25
Crosshead, Figs. 1025 and 1027.....	.25	.25
Upper Plunger Rod, Figs. 1025 and 1027.....	.75	.75
Flat Wind Mill Rod, Figs. 1026 and 1028.....	.50	.50
Connecting Rod, Figs. 1026 and 1028.....	.50	.50
Pin Connecting Lever and Rod, Figs. 1026 and 1028.....	.15	.15
Rod Coupling, Figs. 1026 and 1028.....	.10	.10
Standard and Spout complete; no Pipes or Rod, Figs. 1025 and 1027.....	6.50	6.50
Standard and Spout complete; no Pipes or Rod, Figs. 1026 and 1028.....	7.25	7.25
Set-Length complete, Pipes, Rod and Upper Cylinder, Figs. 1025 and 1027.....	5.00	6.00
Set-Length complete, Pipes, Rod and Upper Cylinder, Figs. 1026 and 1028.....	7.50	8.50
Air Chamber Pipe.....	.50	.50
Air Chamber Pipe Cap.....	.15	.15
Discharge Pipe.....	.50	.50
Three-Way Cock.....	2.25	2.25
Three-Way Cock Lever.....	.15	.15
Three-Way Cock Rod and Coupling.....	.50	.50
Three-Way Cock Coupling only.....	.10	.10
Brass-Lined Upper Cylinder complete.....	4.00	5.00
Brass-Lined Upper Cylinder only.....	2.00	2.75
Bottom Attachment.....	1.00	1.00
Plunger and Short Rod.....	1.00	1.25
Plunger Rod only.....	.50	.50
Plunger Discs (2) each.....	.15	.15
Plunger Nuts (2) each.....	.05	.05
Plunger Leather.....	.10	.15
Plunger Rod Coupling.....	.10	.10
Strainer.....	.60	.60
Lever, Link, Stock Bolts and Set Screws, each.....	.08	.08
Lower Cylinder Shell, Brass Body.....	4.50	5.25
Lower Cylinder Shell, Brass-Lined.....	4.00	4.50
Lower Cylinder, Brass Lining only.....	1.50	1.75
Lower Cylinder, Top Attachment.....	.75	.75
Lower Cylinder, Leather Lower Valve, complete.....	.25	.25
Lower Cylinder, Plunger complete, no rod.....	2.75	3.00
Lower Cylinder, Plunger Rod.....	.15	.15
Lower Cylinder, Brass Plunger Cage only.....	.75	.90
Lower Cylinder, Brass Poppet Valve.....	.20	.30
Lower Cylinder, Plunger Follower, Iron.....	.85	1.00
Lower Cylinder, Plunger Follower Ring, Iron.....	.25	.30
Lower Cylinder, Plunger Crimped Leathers (2) each.....	.15	.25
Lower Cylinder, Bottom Attachment with "Universal" Bronze Lower Valve and Seat, complete.....	2.25	2.25
Lower Cylinder, Bottom Attachment only.....	1.00	1.00
Lower Cylinder, "Universal" Bronze Lower Valve and Seat, complete.....	1.25	1.20
Lower Cylinder, "Universal" Bronze Seat and Cage only.....	1.00	1.00
Lower Cylinder, "Universal" Cage, Top only.....	.25	.25
Lower Cylinder Poppet (leather-faced) for "Universal" Lower Valve.....	.25	.25
Lower Cylinder, Leather Face for Poppet, for "Universal" Lower Valve.....	.10	.10
Lower Cylinder, Ring Packings, each.....	.10	.10
Universal Bushing, for Deep Wells.....	1.00	1.00

**GOULDS "ADVANCE" DOUBLE-ACTING WELL FORCE PUMPS,  
Figs. 1146, 1147 and 1148.**

No.....	2	4
DIAMETER OF LOWER CYLINDER, INCHES.....	2½	3
Lever or Handle, Fig. 1146.....	\$1.00	\$1.00
Lever or Handle, Figs. 1147 and 1148.....	1.25	1.25
Bearer, Fig. 1146.....	1.15	1.15
Bearer, Figs. 1147 and 1148.....	1.35	1.35
Bearer Link, Figs. 1147 and 1148.....	.35	.35
Bearer Pin.....	.10	.10
Lever Pin.....	.10	.10
Link Pin, Figs. 1147 and 1148.....	.10	.10
Crosshead, Fig. 1146.....	.25	.25
Pipe Clamp with Bolts.....	.75	.75
Spout.....	.50	.50
Spout Swivel Nut.....	.25	.25
Spout Swivel Pipe Coupling.....	.25	.25
Spout Hose Tube.....	.25	.25
Spout Hose Tube Nut.....	.25	.25
Base.....	1.75	1.75
Rod Guide.....	.25	.25
Air Chamber Pipe or Standard, Fig. 1146.....	.50	.50
Air Chamber Pipe or Standards, Figs. 1147 and 1148.....	.55	.55
Discharge Pipe.....	.35	.35
Differential Plunger Rod, Fig. 1146.....	.75	.75
Flat Wind Mill Rod, Figs. 1147 and 1148.....	.50	.50
Differential Plunger Rods, Figs. 1147 and 1148.....	.75	.75
Short Lower Plunger Rod.....	.15	.15
Lower Plunger Rod Nuts (2) each.....	.05	.05
Upper Rod Couplings, Figs. 1147 and 1148.....	.25	.25
Lower Rod Coupling.....	.10	.10
Rod Guide, Fig. 1148.....	.25	.25
Upper Cylinder, Top Attachment.....	1.00	1.15
Upper Cylinder or Working Head, Fig. 1146.....	1.50	1.75
Upper Cylinder or Working Head, Figs. 1147 and 1148.....	1.75	2.00
Brass Differential Cylinder, Fig. 1146.....	1.00	1.25
Brass Differential Cylinder, Figs. 1147 and 1148.....	1.15	1.40
Differential Plunger Plate (upper).....	.15	.15
Differential Plunger Plate (lower).....	.15	.15
Differential Plunger Leather.....	.10	.15
Differential Plunger Nuts (2) each.....	.05	.05
Lower Cylinder Shell (Brass Lined) Fig. 1146.....	4.00	4.50
Lower Cylinder Shell (Brass Lined) Figs. 1147 and 1148.....	4.70	5.30
Lower Cylinder Shell (Brass Body) Fig. 1146.....	4.50	5.25
Lower Cylinder Shell (Brass Body) Figs. 1147 and 1148.....	6.00	7.00
Lower Cylinder Top Attachment.....	1.00	1.00
Lower Cylinder Plunger Complete, no Rod.....	2.75	3.00
Lower Cylinder Plunger Rod.....	.15	.15
Lower Cylinder, Brass Plunger Cage only.....	.75	.90
Lower Cylinder, Brass Poppet and Valve.....	.20	.30
Lower Cylinder Plunger Crimps (2) each.....	.15	.25
Lower Cylinder Plunger Follower, iron.....	.85	1.00
Lower Cylinder Plunger Follower Ring, iron.....	.25	.30
Lower Cylinder Bottom Attachment with "Universal" Bronze Valve and Seat Complete.....	2.25	2.25
Lower Cylinder "Universal" Bronze Lower Valve and Seat Complete.....	1.25	1.25
Lower Cylinder "Universal" Bronze Seat and Cage only.....	1.00	1.00
Lower Cylinder "Universal" Cage Top only.....	.25	.25
Lower Cylinder Poppet (Leather Faced) for "Universal" Lower Valve.....	.25	.25
Lower Cylinder Leather Face for Poppet "Universal" Lower Valve.....	.10	.10
Lower Cylinder Ring Packings, each.....	.10	.10
Three-Way Valve Case, Fig. 1148.....	1.50	1.50
Three-Way Valve Seat, Fig. 1148.....	.50	.50
Three-Way Valve Lever, Fig. 1148.....	.25	.25
Three-Way Valve Upper Rod, Fig. 1148.....	.50	.50

**GOULDS "ADVANCE" DOUBLE-ACTING WELL FORCE PUMPS,  
FIGS. 1146, 1147 AND 1148.—Continued.**

No.....	2	4
DIAMETER OF LOWER CYLINDER, INCHES.....	2½	3
Three-Way Valve Lower Rod, Fig. 1148.....	\$1.00	\$1.00
Three-Way Valve Rod Coupling, Fig. 1148.....	.10	.10
Three-Way Valve Rubber Discs (2) each, Fig. 1148.....	.25	.25
Three-Way Valve Washer, Fig. 1148.....	.05	.05
Three-Way Valve Nuts (2) each, Fig. 1148.....	.05	.05
Three-Way Valve Lever Fulcrum Collar, Fig. 1148.....	.50	.50
Three-Way Valve Lever Fulcrum Bolt, Fig. 1148.....	.10	.10
Three-Way Rod Bolt, Fig. 1148.....	.25	.25
Three-Way Valve Brass Gland, Fig. 1148.....	1.00	1.00
Three-Way Valve Discharge Elbow, Fig. 1148.....	.50	.50
Three-Way Valve Discharge Elbow Nut, Fig. 1148.....	.50	.50
Three-Way Valve Discharge Packing, Fig. 1148.....	.10	.10
Strainer.....	.60	.60
Universal Bushing for Deep Wells.....	1.00	1.00

**GOULDS "STAR" WELL PUMP STANDARDS, FIGS. 846, 849, 850.**

No.....	3	4	5
Lever or Handle.....	\$1.00	\$1.25	\$1.25
Fulcrum or Bearer Top, Figs. 846, 849.....	.90	1.10	1.10
Fulcrum or Bearer Top, Fig. 850.....	1.15	1.35	1.35
Stock or Standard only.....	3.75	4.25	4.75
Links, Fig. 850, per pair.....	.25	.25	.25
Crosshead, including Nut and Set Screws, do.....	.50	.50	.50
Connecting Rod, Figs. 846, 849.....	.25	.25	.25
Polished Round Rod, Fig. 850.....	.60	.60	.60
Brace.....	.50	.50	.50
Lever, Bearer, Brace Bolts and Set Screws.....	.08	.08	.08

**GOULDS WELL PUMP STANDARD, FIG. 486.**

Lever or Handle.....	\$1.50
Stock or Standard only.....	5.00
Cap for Standard.....	.30
Connecting Rod.....	.25
Spout.....	.50
Brace.....	.50
Leather Packing for Spout.....	.25
Lever, Bearer, Cap, Spout and Brace Bolts.....	.08

**GOULDS HEAVY DEEP WELL PUMP STANDARDS, FIGS. 236, 237, 887.**

Lever.....	\$1.75
Top Section.....	3.00
Intermediate Flange, 1¼ in.....	.50
Intermediate Flange 1½ or 2 in.....	.60
Bottom Section.....	4.00
Brace.....	.60
Top-Knot, no link.....	.35
Link for same.....	.15
Polished Round Rod.....	.60
Cap, Fig. 236.....	.50
Cap, Figs. 237, 887.....	.75
Gland, Figs. 237, 887.....	.50
Spout, Fig. 236.....	.50
Air Chamber only, Figs. 237, 887.....	3.50
Air Chamber Cap, Figs. 237, 887.....	.50
Air Chamber Cock Nut, Figs. 237, 887.....	.50
Hose Tube, Figs. 237, 887.....	.35
Hose Tube Nut, Figs. 237, 887.....	.35
Air Chamber Inside Tube, Fig. 237, 887.....	.30
Intermediate Spout Elbow, Fig. 237.....	.75
Cock, Fig. 887.....	3.00
Leather Packings for Spout Intermediate Flange or A. C.....	.15
Leather Ring Packings, A. C. Cap, Cock Nut or Hose Tube Nut.....	.10
Lever, Bearer, Flange and Brace Bolts, Etc.....	.12
A. C. Complete.....	5.50



## GOULDS HEAVY DEEP WELL PUMP STANDARDS, FIGS. 592, 593, 763.

Lever, Figs. 592, 593.....	\$2.75
Lever for Wood Brake, Fig. 763.....	2.75
Wood Brakes, Fig. 763, each.....	.50
Fulcrum or Bearer Top.....	3.00
Top Section.....	4.00
Intermediate Flange, 1¼ inch pipe.....	.50
Intermediate Flange, 1½, 2 and 2½ inch pipe.....	.60
Bottom Section.....	6.50
Links, per pair.....	.40
Crosshead, including Nuts and Set Screws.....	.70
Polished Round Rod.....	.60
Cap, Fig. 592.....	.50
Cap, Figs. 593, 763.....	.90
Glands, Figs. 593, 763.....	.50
Spout, Fig. 592.....	.75
Air Chamber only, Figs. 593, 763.....	4.00
Air Chamber, Cap, Figs. 593, 763.....	.50
Air Chamber Inside Tube, ditto.....	.35
Hose Tube Nut, ditto.....	.35
Hose Tube, ditto.....	.35
Braces, each.....	.75
Leather Packing for Spout, Intermediate Flange or Air Chamber.....	.25
Leather Ring Packing, Air Chamber and Hose Tube Nuts.....	.10
Flange, Hook and Brace Bolts.....	.12
Lever and Bearer Pins, only.....	.15
Spring Cotters for ditto.....	.05
Thumb Screw, Fig. 763.....	.25

## GOULDS WELL PUMP STANDARDS, FIGS. 857, 858.

Lever or Handle.....	\$1.25
Fulcrum or Bearer Top.....	1.25
Stock or Standard only, Fig. 857.....	6.50
Top Section only, Fig. 858.....	2.40
Intermediate Flange, Fig. 858, 1¼ in.....	.50
Intermediate Flange, Fig. 858, 1½, 2, 2½ in.....	.60
Bottom Section.....	3.60
Links, per pair.....	.25
Crosshead, including Nuts and Set Screws.....	.50
Polished Round Rod.....	.60
Brass Gland.....	.75
Stuffing Box Plug.....	.25
Air Chamber only.....	3.00
Air Chamber Cap.....	.35
Air Chamber Inside Tube.....	.30
Air Chamber Nut.....	.50
Air Chamber Spout Piece.....	.25
Air Chamber Hose Tube Nut.....	.25
Air Chamber Hose Tube.....	.25
Brace.....	.50
Leather Packing for Intermediate Flange or Air Chamber.....	.25
Lever Bearer, Flange, Hook and and Brace Bolts.....	.08
Leather Ring Packing.....	.10

## GOULDS WIND MILL PUMP STANDARDS, FIGS. 762, 780.

No.....	3	4	5
Lever or Handle, Fig. 762.....	\$1.25	\$1.40	\$1.40
Lever or Handle, Fig. 780.....		1.75	1.75
Fulcrum or Bearer Top, Fig. 762, 6-in. stroke.....	1.25	1.35	1.35
Fulcrum or Bearer Top, Fig. 762, 10-in. stroke.....		1.50	1.50
Fulcrum or Bearer Top, Fig. 780.....		2.00	2.00
Bearer Link, Fig. 762, 6-in. stroke.....	.50	.50	.50
Bearer Link, Fig. 762, 10-in. stroke and Fig. 780.....		.75	.75
Stock or Standard only.....	3.75	4.25	4.75
Flat Rod.....	.60	.60	.60

## GOULDS WIND MILL PUMP STANDARDS, FIGS. 762, 780.—Continued.

No.....	3	4	5
Wind Mill Slide.....	\$0.50	\$0.50	\$0.50
Female Wood Rod Coupling.....	.25	.25	.25
Rod Coupling.....	.10	.10	.10
Pin.....	.15	.15	.15
Brace.....	.50	.50	.50
Lever, Bearer, Brace Bolts and Set Screws.....	.08	.08	.08

## GOULDS "STAR" WIND MILL PUMP STANDARD, FIG. 412.

Lever or Handle.....	\$1.40
Fulcrum or Bearer Top, 6-in. Stroke.....	1.35
Fulcrum or Bearer Top, 10-in. Stroke.....	1.50
Bearer Link, 6-in. Stroke.....	.50
Bearer Link, 10-in. Stroke.....	.75
Top Section.....	2.40
Intermediate Flange, 1¼-in. Pipe.....	.50
Intermediate Flange, 1½, 2, 2½-in. Pipe.....	.60
Bottom Section.....	3.60
Flat Rod.....	.60
Brace.....	.50
Pin.....	.15
Wind Mill Slide.....	.50
Female Wood Rod Coupling.....	.25
Leather Packing Intermediate Flange.....	.25
Lever Bearer Flange, Brace Bolts and Set Screws.....	.08

## GOULDS WIND MILL PUMP STANDARDS, FIG. 764, 765.

Lever or Handle.....	\$2.00
Fulcrum or Bearer Top, 6-in. Stroke.....	3.50
Fulcrum or Bearer Top, 10-in. Stroke.....	4.25
Bearer Link, 6-in. Stroke.....	.75
Bearer Link, 10-in. Stroke.....	1.00
Top Section.....	4.00
Intermediate Flange, 1¼-in. Pipe.....	.50
Intermediate Flange, 1½, 2, 2½-in. Pipe.....	.60
Bottom Section.....	6.50
Short Flat Rod.....	.50
Pin through Flat Rod.....	.15
Rod Connection and Set Screw.....	.25
Polished Round Rod.....	.60
Cap, Fig. 764.....	.50
Cap, Fig. 765.....	.90
Gland, Fig. 765.....	.50
Spout, Fig. 765.....	.25
Air Chamber Spout Nut, Fig. 765.....	.50
Spout, Fig. 764.....	.75
Air Chamber only, Fig. 765.....	4.00
Air Chamber Cap, Fig. 765.....	.50
Air Chamber Inside Tube, Fig. 765.....	.35
Hose Tube Nut, Fig. 765.....	.35
Hose Tube, Fig. 765.....	.35
Braces, each.....	.75
Leather Packing for Spout, Intermediate Flange or Air Chamber.....	.25
Leather Ring Packing.....	.10
Female Wood Rod Coupling.....	.25
Wind Mill Slide.....	.50
Lever, Bearer, Flange, Hook and Brace Bolts.....	.12

## GOULDS "STAR" WIND MILL FORCE PUMP STANDARDS, FIGS. 401, 402.

Lever or Handle.....	\$1.40
Fulcrum or Bearer Top, 6-in. stroke.....	1.50
Fulcrum or Bearer Top, 10-in. stroke.....	1.75
Bearer Link, 6-in. stroke.....	.50
Bearer Link, 10-in. stroke.....	.75



GOULDS "STAR" WIND MILL FORCE PUMP STANDARDS,  
FIGS. 401, 402.—Continued.

Stock or Standard only, Fig. 401 .....	\$6.50
Top Section, Fig. 402 .....	2.40
Intermediate Flange, 1 $\frac{1}{4}$ in., Fig. 402 .....	.50
Intermediate Flange, 1 $\frac{1}{2}$ , 2, 2 $\frac{1}{2}$ in., Fig. 402 .....	.60
Bottom Section, Fig. 402 .....	3.60
Short Flat Rod .....	.50
Rod Coupling and Set Screw .....	.15
Polished Round Rod .....	.60
Brass Gland .....	.75
Stuffing Box Plug .....	.25
Air Chamber only .....	3.00
Air Chamber Cap .....	.35
Air Chamber Tube .....	.35
Air Chamber Nut .....	.45
Air Chamber Spout .....	.25
Hose Tube Nut .....	.25
Hose Tube .....	.25
Brace .....	.50
Leather Packing Intermediate Flange or Air Chamber .....	.25
Leather Ring Packings .....	.10
Lever, Bearer, Flange, Hook, Brace Bolts, Etc. ....	.08
Wind Mill Slide .....	.50
Female Wood Rod Coupling .....	.25
Pin Connecting Lever and Rod .....	.15

GOULDS WIND MILL DISTRIBUTING HEADS, FIGS. 1031, 1033,  
1061, 1045 AND 1048.

Standard, Brace, Bearer, Lever, Link, Flat-Rod and Coupling, 6-in. Stroke .....	\$7.25
Standard, Brace, Bearer, Lever, Link, Flat-Rod and Coupling, 10-in. Stroke .....	8.25
Standard, Brace, Bearer, Lever, Link, Flat-Rod and Coupling, Adjustable Stroke .....	9.25
Standard only .....	4.00
Brace .....	.50
Fulcrum or Bearer Top, 6-in. Stroke .....	1.25
Fulcrum or Bearer Top, 10-in. Stroke .....	1.50
Fulcrum or Bearer Top, Adjustable Stroke .....	2.00
Bearer Link, 6-in. Stroke .....	.50
Bearer Link, 10-in. Stroke .....	.75
Bearer Link, Adjustable Stroke .....	.75
Lever or Handle, 6-in. Stroke .....	1.00
Lever or Handle, 10-in. Stroke .....	1.35
Lever or Handle, Adjustable Stroke .....	1.75
Bearer, Brace, Link and Lever Bolts, each .....	.08
Base or Platform and Set-Length Complete, including Working Head, Discharge Pipe and Spout, Figs. 1031 and 1048 .....	13.50
Base or Platform and Set-Length Complete, including Working Head, Discharge Pipe and Spout, Figs. 1033 and 1045 .....	15.00
Base or Platform, Figs. 1031 and 1048 .....	1.75
Base or Platform, Figs. 1033 and 1045 .....	2.00
Guide Plate .....	.25
Tap Bolts, Set Screws for Base Guide Plate and Discharge Pipe, each .....	.08
Spout .....	1.00
Spout Hose Tube .....	.25
Spout Hose Tube Nut .....	.25
Wheel Handle .....	.25
Lock Nut .....	.25
Valve Rod Brass Screw .....	1.00
Valve Rod Gland .....	.50
Valve Rod .....	.75
Discharge Pipe .....	2.25
Air Chamber Pipe, Figs. 1031 and 1048 .....	2.00
Air Chamber Pipe, Figs. 1033 and 1045 .....	2.75
Working Head Complete .....	7.00

GOULDS WIND MILL DISTRIBUTING HEADS, FIGS. 1031, 1033,  
1061, 1045 AND 1048.—Continued

Working Head only, Figs. 1031 and 1048 .....	\$2.25
Working Head only, Figs. 1033 and 1045 .....	2.50
Working Head Stuffing Box .....	.50
Working Head Gland .....	.50
Working Head Lower Flange .....	.50
Working Head Elbow .....	.40
Working Head Elbow Nut .....	.25
Valve Case only .....	.50
Valve Case Lock Nut .....	.35
Valve Discs, (2) each .....	.25
Valve Plate .....	.25
Valve Rod Nut .....	.05
Flat Wind Mill Rod, 6-in. Stroke .....	.50
Flat Wind Mill Rod, 10-in. Stroke .....	.60
Flat Wind Mill Rod, Adjustable Stroke .....	.65
Long Round Middle Rod .....	.50
Brass Cased Plunger Rod .....	.75
Rod Couplings, each .....	.15
Wind Mill Connection .....	.50
Wind Mill Rod Pin .....	.10
Leather Packing Rings, each .....	.08
Wrench .....	.25
Suction Flange Leather .....	.20
Sundry Bolts and Set Screws, each .....	.80
Fig. 1061, Forked Rod .....	2.00
Fig. 1061, Rod for Weight .....	.50
Fig. 1061, Weight .....	2.00
Fig. 1061, Regulator Cylinder .....	10.00
Fig. 1061, Chain .....	.50
Fig. 1061, Spring .....	1.25

Repairs for Cylinders, see page 582.

GOULDS "SOUTHERN STAR" WIND MILL FORCE PUMP STANDARD,  
FIG. 413.

Lever or Handle .....	\$1.40
Fulcrum or Bearer Top, 6-in. stroke .....	1.50
Fulcrum or Bearer Top, 10-in. stroke .....	1.75
Bearer Link, 6-in. stroke .....	.50
Bearer Link 10-in. stroke .....	.75
Stock or Standard only .....	6.00
Intermediate Flange, 1 $\frac{1}{4}$ -in. pipe .....	.50
Intermediate Flange, 1 $\frac{1}{2}$ , 2, 2 $\frac{1}{2}$ -in pipe .....	.60
Base .....	2.00
Short Flat Rod .....	.50
Rod Coupling and Set Screw .....	.15
Brass Cased Rod .....	1.00
Brass Gland .....	.75
Stuffing Box Plug .....	.25
Air Chamber only .....	3.00
Air Chamber Discharge Nut .....	.45
Air Chamber Brass Discharge Tube, 1 $\frac{1}{4}$ in. ....	.50
Air Chamber Inside Tube .....	.30
Air Chamber Cock Nut .....	.50
Air Chamber Valve complete .....	.35
Air Chamber Valve, leather only .....	.20
Air Chamber Valve Weight only .....	.15
Air Chamber Valve Screw and Washer .....	.05
Cock .....	2.50
Cock Handle .....	.25
Brace .....	.50
Wind Mill Slide .....	.50
Female Wood Rod Coupling .....	.25
Leather Packing Intermediate Flange .....	.25
Leather Ring Packing A. C. Cap or Cock Nut .....	.10
Lever, Bearer Flange, Brace and Hook Bolts .....	.08
Pin Connecting Lever and Rod .....	.15

## GOULDS WIND MILL DISTRIBUTING HEADS, FIG. 862, 866.

Fig. 862, Standard Complete, 6-in. stroke, including Rod and Coupling.....	\$7.50
Fig. 862, Standard Complete, 10-in. stroke including Rod and Coupling .....	9.00
Fig. 866, Standard Complete, including Rod and Coupling.....	10.00
Set Length Complete, including Pipe and Valve Rod.....	12.50
Fig. 862, Lever or Handle.....	1.40
Fig. 862, Fulcrum or Bearer Top, 6-in. stroke.....	1.35
Fig. 862, Fulcrum or Bearer Top, 10-in. stroke.....	1.50
Fig. 862, Bearer Link, 6-in. stroke.....	.50
Fig. 862, Bearer Link, 10-in. stroke.....	.75
Fig. 866, Lever or Handle.....	1.75
Fig. 866, Fulcrum or Bearer Top.....	2.50
Fig. 866, Bearer Link.....	.75
Stock only, two sides.....	4.00
Spout.....	.50
Spout Hose Attachment.....	.25
Lower Working Head only.....	2.00
Working Head Stuffing Box.....	.50
Discharge Pipe.....	1.20
Working Head Brass Glands, two, each.....	.50
Working Head Plates, two, each.....	.25
Working Head Valve Seat.....	.75
Working Head Lock Nut.....	.25
Working Head Valve Disc.....	.25
Working Head Valve Rubbers, two.....	.25
Working Head Elbow Nut.....	.35
Working Head Brass Elbow.....	1.00
Working Head Suction Flange.....	.50
Flat and Round Plunger Rod.....	1.00
Brass-Cased Plunger Rod.....	.75
Upper Valve Rod.....	.50
Lower Valve Rod, Brass Cased.....	.75
Valve Handle.....	.25
Valve Handle Stop.....	.15
Valve Rod Coupling and Set Screw.....	.25
Gas Pipe Cap.....	.15
Pin.....	.15

## GOULDS WIND MILL DISTRIBUTING HEADS, FIGS. 862, 866.—Continued.

Bolts and Set Screws.....	\$0.08
Wind Mill Slide.....	.50
Female Wood Rod Coupling.....	.25
Air Chamber Pipe.....	2.00

## GOULDS WIND MILL FORCE PUMP, FIG. 863.

Standard Complete, including Rod and Coupling.....	\$7.00
Set Length Complete, including Pipe and Valve Rod.....	12.00
Lever or Handle.....	1.25
Fulcrum or Bearer Top.....	1.25
Bearer Link.....	.50
Stock, two sides.....	3.50
Spout.....	.50
Hose Connection.....	.25
Lower Working Head only.....	1.50
Lower Brass Glands, each.....	.50
Lower Working Head Valve, Seat.....	.50
Lower Working Head Lock Nut.....	.25
Lower Working Head Valve Disc.....	.25
Lower W. H. Rubbers, two, each.....	.25
Elbow Nut.....	.35
Brass Elbow.....	1.00
Flat and Round Rod.....	1.00
Rod Coupling.....	.10
Brass Cased Plunger Rod.....	.75
Valve Handle.....	.25
Valve Handle Stop.....	.15
Upper Valve Rod.....	.50
Valve Rod, Coupling and Set Screw.....	.25
Brass Cased Valve Rod.....	.50
Gas Pipe Cap.....	.15
Wind Mill Slide.....	.50
Female Wood Rod Coupling.....	.25
Pin.....	.15
Bolts and Set Screws.....	.08
Small Nut and Washer.....	.05

## CYLINDERS OR WORKING BARRELS, FIGS. 1230, 1231, 1235, 1236, 1267, 1268

No.....	0	1	2	3	4	5	6	8	10	12	16	24
DIAMETER CYLINDER, INCHES.....	2	2¼	2½	2¾	3	3¼	3½	4	4½	5	6	8
Shell or Body, Iron, 10½ in.....	\$1.50	\$1.50	\$1.60	\$1.80	\$2.00	\$2.25	\$2.50	\$3.25	.....	.....	.....	.....
Shell or Body, Iron, 12 in.....	2.25	2.30	2.45	2.45	2.70	3.00	3.50	3.80	.....	.....	.....	.....
Shell or Body, Iron, 14 in.....	2.75	2.75	2.75	2.95	3.20	3.50	3.75	4.55	\$8.00	\$11.50	\$15.50	.....
Shell or Body, Iron, 16 in.....	3.00	3.00	3.00	3.30	3.55	3.80	4.05	4.80	8.25	14.50	18.25	.....
Shell or Body, Iron, 18 in.....	.....	.....	.....	.....	.....	.....	.....	.....	9.00	16.00	20.00	\$30.00
Shell or Body, Iron, 20 in.....	.....	4.30	4.55	4.80	5.05	5.30	5.50	8.00	.....	.....	.....	.....
Shell or Body, Iron, 22 in.....	.....	.....	.....	.....	.....	.....	.....	.....	12.50	20.00	27.50	37.50
Shell or Body, Brass-Lined, 10½ in.....	2.75	3.00	3.25	3.50	3.75	4.00	4.25	5.00	.....	.....	.....	.....
Shell or Body, Brass-Lined, 12 in.....	3.15	3.65	4.00	4.10	4.50	5.00	5.35	6.20	.....	.....	.....	.....
Shell or Body, Brass-Lined, 14 in.....	4.25	4.40	4.70	4.90	5.30	5.85	6.20	7.35	11.50	17.00	22.00	.....
Shell or Body, Brass-Lined, 16 in.....	4.50	4.75	5.05	5.40	5.80	6.30	6.65	8.75	12.25	19.50	26.00	.....
Shell or Body, Brass-Lined, 18 in.....	.....	.....	.....	.....	.....	.....	.....	.....	14.00	22.50	30.00	40.00
Shell or Body, Brass-Lined, 20 in.....	6.00	6.25	6.50	7.00	7.50	8.00	9.00	11.00	.....	.....	.....	.....
Shell or Body, Brass-Lined, 22 in.....	.....	.....	.....	.....	.....	.....	.....	.....	17.50	27.50	37.50	50.00
Shell or Body, Brass, 10½ in.....	3.50	3.50	4.00	4.25	4.75	5.00	5.50	6.75	.....	.....	.....	.....
Shell or Body, Brass, 12 in.....	4.00	4.00	4.50	4.75	5.25	5.75	6.25	7.25	.....	.....	.....	.....
Shell or Body, Brass, 14 in.....	4.75	4.75	5.25	5.50	6.25	6.75	7.25	10.50	17.00	25.75	40.00	.....
Shell or Body, Brass, 16 in.....	5.25	5.25	6.00	6.25	7.00	7.50	8.25	11.00	19.50	29.75	45.00	.....
Shell or Body, Brass, 18 in.....	.....	.....	.....	.....	.....	.....	.....	.....	24.00	34.75	50.00	100.00
Shell or Body, Brass, 20 in.....	6.50	6.50	7.50	7.75	8.75	9.25	10.25	16.00	29.00	39.75	55.25	110.50
Shell or Body, Brass, 22 in.....	.....	.....	.....	.....	.....	.....	.....	.....	30.00	42.50	62.50	125.00
"AA," Iron Plunger, no rod.....	.75	.75	.80	.90	1.00	1.25	1.60	2.00	.....	.....	.....	.....
"AA," Brass Cage and Valve Plunger, no rod.....	1.15	1.15	1.25	1.35	1.50	2.00	2.50	3.00	.....	.....	.....	.....
"AA," All Brass Plunger, no rod.....	1.50	1.50	1.60	1.80	2.00	2.50	3.25	4.00	.....	.....	.....	.....
"BB," Iron Plunger, no rod.....	1.60	1.60	1.75	1.75	2.00	2.50	3.00	4.00	5.25	7.00	10.00	15.00







## GOULDS "PACIFIC" WIND MILL FORCE PUMPS, FIGS. 674, 601.

No.....	2	4	6	8
DIAMETER CYLINDER, INCHES.....	2½	3	3½	4
Lever or Handle.....	\$1.50	\$1.50	\$2.00	\$2.00
Fulcrum or Bearer Top.....	2.00	2.00	3.50	3.50
Bearer Link.....	.50	.50	.50	.50
Cylinder.....	5.00	5.00	7.00	8.00
Brass-Lined Cylinder.....	7.00	7.00	10.00	12.00
Brass Cylinder.....	10.00	10.00	15.00	20.00
Iron Top Section for Brass Cylinder Pump.....	2.75	2.75	4.00	4.75
Base, Fig. 674.....	2.00	2.00	2.25	2.25
Bottom Cap, Fig. 601.....	.75	.75	1.25	1.25
Short Flat Rod.....	.50	.50	.50	.50
Pin.....	.15	.15	.15	.15
Rod Coupling and Set Screw.....	.25	.25	.25	.25
Plunger Rod Brass Cased.....	1.00	1.00	1.25	1.75
Brass Gland.....	.75	.75	1.00	1.00
Stuffing Box Plug.....	.25	.25	.25	.25
Plunger Complete, No Rod.....	.80	1.00	1.30	1.50
Plunger Cage.....	.40	.50	.65	.75
Plunger Follower.....	.40	.50	.65	.75
Plunger Poppet Valve, Brass.....	.20	.20	.30	.30
Brass Plunger Complete, No Rod.....	1.60	2.00	2.60	3.00
Brass Plunger Cage.....	.80	1.00	1.30	1.50
Brass Plunger Follower.....	.80	1.00	1.30	1.50
Plunger Leather or Packing.....	.15	.15	.20	.20
Lower Valve Complete.....	.25	.25	.35	.35
Lower Valve Leather.....	.15	.15	.20	.20
Lower Valve Weight.....	.10	.10	.15	.15
Lower Valve Screw and Washer.....	.05	.05	.05	.05
Check Valve and parts same as Lower Valve.....				
Air Chamber only.....	2.00	2.00	3.00	3.00
Air Chamber Discharge Nut.....	.35	.35	.45	.60
Air Chamber Discharge Tube.....	.50	.50	.75	1.00
Air Chamber Inside Tube.....	.30	.30	.40	.40
Air Chamber Cock Nut.....	.50	.50	.75	.75
Cock.....	2.00	2.00	3.00	3.00
Cock Handle only.....	.25	.25	.25	.25
Forked Rod.....	1.50	1.50	1.50	1.50
Hose Tube.....	.25	.25	.25	.25
Leather Ring Packing Cock and Air Chamber Nuts.....	.10	.10	.10	.10
Leather Ring Packing under Fulcrum.....	.15	.15	.20	.20
Lever Bearer, Base Flange and Hook Bolts.....	.08	.08	.08	.08

## GOULDS HOUSE FORCE PUMPS.

FIGS. 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 264.

No.....	0	2	4	6	8
DIAMETER CYLINDER, INCHES.....	2	2½	3	3½	4
Lever or Handle.....	\$1.00	\$1.00	\$1.00	\$1.50	\$1.50
Fulcrum or Bearer Top.....	1.25	1.25	1.50	1.75	1.75
Cylinder.....	3.00	3.50	4.00	6.00	7.50
Brass-Lined Cylinder.....	5.00	5.50	6.00	9.00	11.50
Brass Cylinders.....	6.00	7.00	8.00	12.00	15.00
Iron Top Section for Brass Cyl. Pump.....	2.50	2.75	2.75	4.00	4.75
Base, Figs. 390, 392, 394, 396, 398, 264.....	1.10	1.10	1.25	1.75	2.00
Bottom Cap, Figs. 391, 393, 395, 397, 399.....	.50	.50	.50	.85	1.50
Links per pair.....	.25	.25	.25	.30	.30
Cross Head, including Nuts and Set Screws.....	.50	.50	.50	.60	.60
Cap.....	.50	.50	.50	.75	.75
Brass Gland.....	.75	.75	.75	1.00	1.00
Plunger Rod, Brass Cased.....	1.00	1.00	1.00	1.25	1.75
Plunger Complete, No Rod.....	.70	.80	1.00	1.30	1.50
Plunger Cage.....	.35	.40	.50	.65	.75
Plunger Follower.....	.35	.40	.50	.65	.75

## GOULDS HOUSE FORCE PUMPS.

FIGS. 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 264.—Con.

No.....	0	2	4	6	8
DIAMETER CYLINDER, INCHES.....	2	2½	3	3½	4
Plunger Poppet Valve.....	\$0.10	\$0.10	\$0.15	\$0.15	\$0.15
Brass Plunger Complete, No Rod.....	1.40	1.60	2.00	2.60	3.00
Brass Plunger Cage.....	.70	.80	1.00	1.30	1.50
Brass Plunger Follower.....	.70	.80	1.00	1.30	1.50
Brass Plunger Poppet Valve.....	.20	.20	.30	.30	.30
Plunger Leather or Packing.....	.15	.15	.15	.20	.20
Lower Valve Complete.....	.25	.25	.25	.35	.35
Lower Valve Leather.....	.15	.15	.15	.20	.20
Lower Valve Weight.....	.10	.10	.10	.15	.15
Brass Valve Plate.....	.50	.50	.50	.50	.75
Brass Valve Seat and Tube.....	1.00	1.00	1.25	1.25	1.50
Brass Tubes for Iron or Lead Pipe.....	.50	.50	.50	.75	1.00
Iron Pipe Nut.....	.35	.35	.35	.45	.60
Lead Pipe Nut.....	.25	.25	.25	.35	.50
Drip Plug.....	.25	.25	.25	.25	.25
Check Valve Case only, Figs 390, 391.....	1.25	1.25	1.25	1.50	1.50
Check Valve Nut.....	.35	.35	.35	.45	.60
Check Valve Tube, Brass.....	.50	.50	.50	.75	1.00
Air Chamber only, Figs. 392, 393, 394, 395, 396, 397, 398, 399.....	2.00	2.00	2.00	3.00	3.00
Air Chamber Inside Tube.....	.30	.30	.30	.40	.40
Air Chamber Cap.....	.35	.35	.35	.45	.45
Air Chamber Discharge Nut.....	.35	.35	.35	.45	.60
Air Chamber Cock Nut.....	.50	.50	.50	.75	.75
Air Chamber Brass Tube.....	.50	.50	.50	.75	1.00
Spout, Figs. 396, 397, 398, 399.....	.35	.35	.35	.50	.50
Cock Spout, Figs. 394, 395, 264.....	2.00	2.00	2.00	3.00	3.00
Cock Handle.....	.25	.25	.25	.25	.25
Hose Tube.....	.25	.25	.25	.25	.25
Leather Ring Packing.....	.10	.10	.10	.10	.10
Lever, Bearer, Base, Air Chamber, or Bracket Flange Bolts.....	.08	.08	.08	.08	.08
Plank, Figs. 391, 393, 395, 397, 399.....	.75	.75	.75	.75	.75
Extra Connecting Pipe and Rod, Fig. 264, per foot.....	.50	.50	.50	.50	.50
Cylinder Repairs, Fig. 264, see page 582.					

## GOULDS "UNIVERSE" FORCE PUMPS, FIGS. 1168 AND 1169.

No.....	2	6
DIAMETER CYLINDER, INCHES.....	2½	3½
Base.....	\$0.85	\$1.25
Cylinder (Iron).....	1.50	2.25
Cylinder (Brass) Nickel Plated.....	3.00	4.25
Top for Brass Cylinder Pump.....	1.00	1.50
Bolt Ring.....	.25	.50
Spout, 1168.....	.35	.50
Spout Complete, 1169.....	2.00	3.00
Stuff Box Cap.....	.75	1.00
Gland.....	.75	1.00
Cross Head.....	.25	.25
Cross Head Link and Lever Pins.....	.10	.10
Bearer Link.....	.25	.40
Lever.....	.75	1.00
Plunger, No rod.....	.80	1.60
Brass-Cased Plunger Rod.....	1.00	1.25
Plunger Cage.....	.35	.60
Plunger Follower.....	.35	.60
Plunger Poppet Valve.....	.10	.15
Plunger Leather.....	.15	.35
G. P. Plug.....	.25	.25
Thumb Screw.....	.25	.25
Lower Valve complete.....	.25	.35

GOULDS HOUSE FORCE PUMPS, SINGLE ACTING, FIGS. 440, 441, 442,  
714, 480, 281, 712, 713, 449.

No.	0	2	3	4	5	6
DIAMETER CYLINDER, INCHES.....	2	2½	2¾	3	3¼	3½
Lever or Handle, Figs. 440, 441, 442, 480, 281.....	\$2.00	\$2.00	\$2.00	\$2.00	\$2.00	\$2.00
Fulcrum, Figs. 440, 441, 442, 480, 281.....	2.00	2.00	2.00	2.00	2.00	2.00
Pitman, Figs. 440, 441, 442, 281.....	1.00	1.00	1.00	1.00	1.00	1.00
Pitman, Figs. 714, 480.....	2.50	2.50	2.50	2.50	2.50	2.50
Lever Fork for welding, Fig. 480.....	.75	.75	.75	.75	.75	.75
Guide.....	.75	.75	.75	.75	.75	.75
Guide Rod.....	.60	.60	.60	.60	.60	.60
Cross Head.....	.50	.50	.50	.50	.50	.50
Brass Bowl.....	1.25	1.25	1.25	1.25	1.25	1.25
Cap.....	.65	.65	.65	.65	.75	1.00
Brass Gland.....	.50	.50	.50	.50	.75	.75
Iron Cylinder.....	3.50	4.00	4.25	4.50	5.00	6.00
Brass-Lined Cylinder.....	5.50	6.00	6.50	7.00	8.50	10.00
Brass Cylinder.....	7.00	8.00	8.00	9.00	10.00	12.50
Iron Top Section for Brass Cylinder Pump.....	2.50	2.75	2.75	2.75	3.25	4.00
Brass-Cased Plunger Rod.....	1.00	1.00	1.00	1.00	1.25	1.25
Plunger Complete, No Rod.....	.70	.80	.90	1.00	1.15	1.30
Plunger Cage.....	.30	.35	.40	.45	.50	.60
Plunger Follower.....	.30	.35	.40	.45	.50	.60
Plunger Poppet Valve.....	.10	.10	.10	.10	.15	.15
Brass Plunger Complete, No Rod.....	1.40	1.60	1.80	2.00	2.30	2.50
Brass Plunger Cage.....	.60	.70	.80	.90	1.00	1.20
Brass Plunger Follower.....	.60	.70	.80	.90	1.00	1.20
Brass Plunger Poppet Valve.....	.....	.20	.20	.30	.30	.30
Plunger Leather.....	.15	.15	.15	.15	.20	.20
Suction or Discharge Valve Complete.....	.25	.25	.25	.25	.35	.35
Suction or Discharge Valve Leather.....	.15	.15	.15	.15	.20	.20
Suction or Discharge Valve Weight.....	.10	.10	.10	.10	.15	.15
Suction or Discharge Valve Screw and Washer.....	.05	.05	.05	.05	.05	.05
Bottom Cap or Attachment.....	1.00	1.00	1.00	1.00	1.25	1.25
Nut for I. or L. P. Tube.....	.35	.35	.35	.35	.45	.45
Brass Tube for I. or L. P.....	.50	.50	.50	.50	.75	.75
Brass Drip Plug.....	.25	.25	.25	.25	.25	.25
Machine Bolts, Set Screws, Lag Screws each.....	.08	.08	.08	.08	.08	.08
Plank, Figs. 440, 441, 442, 714, 712, 713.....	1.50	1.50	1.50	1.50	1.50	1.50
Check Valve Case, Figs. 440, 480, 712.....	.75	.75	.75	.75	1.00	1.00
Check Valve Nut, Figs. 440, 480, 712.....	.35	.35	.35	.35	.45	.45
Check Valve Brass Tube, Figs. 440, 480, 712.....	.50	.50	.50	.50	.75	.75
Air Chamber, Figs. 441, 442, 714, 281, 713, 449.....	2.00	2.00	2.00	2.00	3.00	3.00
Air Chamber Inside Tube, Figs. 441, 442, 714, 281, 713, 449.....	.30	.30	.30	.30	.30	.30
Air Chamber Nut, Figs. 441, 442, 442, 714, 281, 713, 449.....	.35	.35	.35	.35	.45	.45
Air Chamber Brass Tube, Figs. 441, 714, 281, 713, 449.....	.50	.50	.50	.50	.75	.75
Cock Spout, Fig. 442.....	2.00	2.00	2.00	2.00	3.00	3.00
Spout Air Chamber, Fig. 281.....	2.50	2.50	2.50	2.50	3.50	3.50
Spout Air Chamber Nut.....	.35	.35	.35	.35	.45	.45
Spout Air Chamber Brass Tube.....	.50	.50	.50	.50	.75	.75
Rod Coupling and Set Screw, Fig. 281.....	.25	.25	.25	.25	.25	.25
Bracket with two Caps, Figs. 712, 713.....	5.00	5.00	5.00	6.00	6.00	6.00
Bracket only, Figs. 712, 713.....	3.50	3.50	3.50	4.50	4.50	4.50
Bracket Caps (2) each, Figs. 712, 713.....	.75	.75	.75	.75	.75	.75
Crank Shaft, Figs. 712, 713.....	3.50	3.50	3.50	5.00	5.00	5.00
Pitman, Figs. 712, 713.....	1.50	1.50	1.50	2.00	2.00	2.00
Pitman Head and Cap, Fig. 712, 713.....	1.25	1.25	1.25	1.25	1.25	1.25
Pitman Head only, Figs. 712, 713.....	.75	.75	.75	.75	.75	.75
Pitman Cap only, Fig. 712, 713.....	.50	.50	.50	.50	.50	.50

GOULDS HOUSE FORCE PUMPS, SINGLE ACTING, FIGS. 440, 441, 442,  
714, 480, 281, 712, 713, 449.—Continued.

No.	0	2	3	4	5	6
DIAMETER CYLINDER, INCHES.....	2	2½	2¾	3	3¼	3½
Balance Wheel, Figs. 712, 713.....	\$7.50	\$7.50	\$7.50	\$7.50	\$7.50	\$7.50
Balance Wheel Handle, Figs. 712, 713.....	.50	.50	.50	.50	.50	.50
Balance Wheel, Fig. 449.....	\$12.50	12.50	12.50	12.50	12.50	12.50
Balance Wheel Handle, Fig. 449.....	1.25	1.25	1.25	1.25	1.25	1.25
Crank and Winch Handle, Fig. 449.....	2.50	2.50	2.50	2.50	2.50	2.50
Crank only, Fig. 449.....	1.25	1.25	1.25	1.25	1.25	1.25
Winch Handle, Fig. 449.....	1.25	1.25	1.25	1.25	1.25	1.25
Crank Shaft, Fig. 449.....	3.50	3.50	3.50	3.50	3.50	3.50
Crank Shaft Box and Cap (2) each, Complete, Fig. 449.....	2.00	2.00	2.00	2.00	2.00	2.00
Crank Shaft Box only (2), each.....	1.25	1.25	1.25	1.25	1.25	1.25
Crank Shaft Cap only (2), each.....	.75	.75	.75	.75	.75	.75
Pitman, Fig. 449.....	1.50	1.50	1.50	1.50	1.50	1.50
Pitman Head and Cap, Fig. 449.....	1.25	1.25	1.25	1.25	1.25	1.25
Pitman Head only, Fig. 449.....	.75	.75	.75	.75	.75	.75
Pitman Cap only, Fig. 449.....	.50	.50	.50	.50	.50	.50

GOULDS DOUBLE-ACTING FORCE PUMPS, FIGS. 271, 272,  
273, 450 AND 452.

No.	0	1	2	3	4	6	8	10
DIAMETER CYL., INCHES..	2	2¼	2½	2¾	3	3½	4	4½
Lever or Handle, Figs. 271, 272, 273.....	\$2.00	\$2.00	\$2.00	\$2.00	\$2.00	\$3.00	\$3.00	\$3.00
Fulcrum, Figs. 271, 272, 273.....	2.00	2.00	2.00	2.00	2.00	2.50	2.50	2.50
Pitman, Figs. 271, 272, 273.....	1.00	1.00	1.00	1.00	1.00	.....	.....	.....
Pitman Straps (2) each.....	.....	.....	.....	.....	.....	1.00	1.00	1.00
Guide.....	.75	.75	.75	.75	.75	1.50	1.50	1.50
Guide Rod.....	.60	.60	.60	.60	.60	1.00	1.00	1.00
Cross Head.....	.50	.50	.50	.50	.50	.75	1.00	1.00
Brass-Cased Piston Rod.....	1.00	1.00	1.00	1.00	1.00	1.25	1.75	2.25
Cylinder.....	4.00	4.00	5.50	6.00	6.50	8.00	11.00	14.00
Brass-Lined Cylinder.....	6.00	6.00	8.25	9.00	9.75	12.00	16.50	21.00
Brass Cylinder.....	15.00	16.00	17.00	18.00	22.50	27.50	30.00	45.00
Cylinder Brass Bowl.....	1.25	1.25	1.25	1.25	1.25	1.50	1.75	1.75
Cylinder Brass Gland.....	.50	.50	.50	.50	.75	1.00	1.00	1.00
Cylinder Head of Cap.....	.65	.65	.65	.65	.65	1.00	1.25	1.25
Piston Complete, No Rod ..	.75	.75	.75	1.00	1.10	1.45	1.80	2.60
Piston Plates (3) each.....	.15	.15	.15	.20	.20	.25	.30	.50
Crimped Piston Packings (2) each.....	.15	.15	.15	.20	.25	.35	.45	.55
Brass Piston Complete.....	1.50	1.50	1.50	2.00	2.20	2.90	3.60	5.20
Brass Piston Plates, each.....	.50	.50	.50	.65	.75	1.00	1.20	1.75
Bottom Attachment.....	1.50	1.50	1.50	1.50	1.50	1.75	2.25	2.75
Nut for Iron or Lead Pipe Tube.....	.35	.35	.35	.35	.35	.45	.60	.75
Brass Tube for Iron and Lead Pipe.....	.50	.50	.50	.50	.50	.75	1.00	1.25
Suction or Discharge Valve Complete.....	.75	.75	.75	.75	.75	1.05	1.05	1.05
Suction or Discharge Valve Leather.....	.50	.50	.50	.50	.50	.70	.70	.70
Suction or Discharge Valve Weights (2) each.....	.10	.10	.10	.10	.10	.15	.15	.15
Suction or Discharge Valve Screws and Washers.....	.05	.05	.05	.05	.05	.05	.05	.05
Fig. 271, Check Valve Case.....	.75	.75	.75	.75	.75	1.00	1.50	2.00
Fig. 271, Check Valve Nut.....	.35	.35	.35	.35	.35	.45	.60	.75
Fig. 271, Check Valve Tube.....	.50	.50	.50	.50	.50	.75	1.00	1.25
Figs. 272, 273, 450 Air Chambr Figs. 272, 273, 450 Air Cham- ber Inside Tube.....	2.00	2.00	2.00	3.50	3.50	5.00	6.50	8.00
	.30	.30	.30	.30	.30	.40	.40	.40



**GOULDS DOUBLE ACTING FORCE PUMPS, FIGS. 271, 272, 273, 450  
AND 452.—Continued.**

No.....	0	1	2	3	4	6	8	10
DIAMETER CYL., IN.....	2	2¼	2½	2¾	3	3½	4	4½
Figs. 272, 273, 450, Air Cham- ber Discharge Nut.....	\$0.35	\$0.35	\$0.35	\$0.35	\$0.35	\$0.45	\$0.60	\$0.75
Figs. 272, 273, 450, Air Cham- ber Discharge Tube.....	.50	.50	.50	.50	.50	.75	1.00	1.25
Fig. 273, Cock.....	2.00	2.00	2.00	2.00	2.00	3.00	3.00	3.00
Fig. 273, Cock Nut.....	.50	.50	.50	.50	.50	.75	.75	.75
Fig. 273, Hose Attachment...	.25	.25	.25	.25	.25	.....	.....	.....
Fig. 273, Hose Tube.....	.....	.....	.....	.....	.....	.35	.35	.35
Fig. 273, Hose Tube Nut.....	.....	.....	.....	.....	.....	.35	.35	.35
Fig. 450, Balance Wheel.....	12.50	12.50	12.50	12.50	12.50	12.50	12.50	12.50
Fig. 450, Balance Wheel Handle.....	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25
Fig. 450, Crank and Winch Handle.....	2.50	2.50	2.50	2.50	2.50	2.50	2.50	2.50
Fig. 450, Crank only.....	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25
Fig. 450, Winch Handle only.....	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25
Fig. 450, Crank Shaft.....	3.50	3.50	3.50	3.50	3.50	5.00	5.00	5.00
Fig. 450, Crank Shaft Box and Cap (2), each complete	2.00	2.00	2.00	2.00	2.00	2.50	2.50	2.50
Fig. 450, Crank Shaft Box only (2), each.....	1.25	1.25	1.25	1.25	1.25	1.75	1.75	1.75
Fig. 450, Crank Shaft Cap only (2), each.....	.75	.75	.75	.75	.75	.75	.75	.75
Fig. 450, Pitman.....	1.50	1.50	1.50	1.50	1.50	2.00	2.00	2.00
Fig. 450, Pitman Box and Cap	1.25	1.25	1.25	1.25	1.25	1.50	1.50	1.50
Fig. 450, Pitman Box only....	.75	.75	.75	.75	.75	1.00	1.00	1.00
Fig. 450, Pitman Cap only....	.50	.50	.50	.50	.50	.50	.50	.50
Fig. 450, Brass Oil Cup.....	.50	.50	.50	.50	.50	.50	.50	.50
Figs. 271, 272, 273, 450, Plank..	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00
Flange Bolts, Set Screws, Lag Screws and Cap Screws.....	.08	.08	.08	.08	.08	.08	.08	.08
Fulcrum Bolt.....	.20	.20	.20	.20	.20	.20	.20	.20
Pins or Bolts for Pitman (2), each.....	.15	.15	.15	.15	.15	.15	.15	.15
Leather Ring Packing.....	.10	.10	.10	.10	.10	.10	.10	.10
Pitman, Fig. 452.....	2.50	2.50	2.50	2.50	2.50	2.50	2.50	2.50
Plank, Fig. 452.....	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00
Air Chamber, Fig. 452.....	2.00	2.00	2.00	3.50	3.50	5.00	6.50	8.00
Air Chamber Inside Tube, Fig. 452.....	.30	.30	.30	.30	.30	.40	.40	.40
Air Chamber Discharge Nut, Fig. 452.....	.35	.35	.35	.35	.35	.45	.60	.75
Air Chamber Discharge Tube, Fig. 452.....	.50	.50	.50	.50	.50	.75	1.00	1.25

**GOULDS HYDRAULIC RAMS, FIGS. 345, 345½, 346, 346½.**

No.....	2	3	4	5	6	7	8
Impetus Valve and Case Com- plete.....	\$4.00	\$4.50	\$6.50	\$10.00	\$14.00	\$22.00	\$32.50
Impetus Valve and Stem, with Nut Bumper only...	1.50	1.75	2.75	4.00	6.00	9.50	12.50
Impetus Valve only.....	1.25	1.50	2.25	3.50	5.00	7.50	6.00
Impetus Valve Stem, with Nut and Set Screw only, Figs. 346, 346½.....	.....	.....	.....	.....	.....	.....	5.00
Impetus Valve Stem Brass Nut only.....	.25	.25	.35	.50	.50	.75	1.00
Impetus Valve Stem Rubber Bumper only.....	.10	.10	.10	.10	.15	.15	.15
Impetus Valve Stem Cotter Pin only.....	.05	.05	.05	.10	.10	.15	.15
Impetus Valve Case Adjust- able Nut and Lock Nut...	2.25	2.75	4.00	5.50	7.00	10.00	20.00

**GOULDS HYDRAULIC RAMS, FIGS. 345, 345½, 346, 346½.—Continued.**

No.....	2	3	4	5	6	7	8
Impetus Valve Case only.....	\$1.50	\$2.00	\$3.00	\$4.00	\$6.00	\$7.00	\$12.00
Impetus Valve Case Cover.....	.....	.....	.....	.....	.....	.....	5.00
Impetus Valve Case Surface Packing.....	.10	.10	.15	.20	.25	.35	.35
Impetus Valve Case Cover Bolts (6) each.....	.....	.....	.....	.....	.....	.....	.08
Brass Studs, or Bolts and Nuts for Impetus Valve Case Cover (each).....	.20	.20	.20	.....	.....	.....	.....
Impetus Valve Case Bolts or Studs and Nuts (each).....	.....	.....	.....	.08	.08	.08	.08
Impetus Valve Case Adjust- ing Nut (brass).....	.50	.50	.75	1.00	1.25	2.00	3.00
Impetus Valve Case Lock Nut (brass).....	.25	.25	.25	.50	.50	.75	1.00

**GOULDS "ALERT" DOUBLE-ACTING FORCE PUMP, FIG. 747.**

No.....	2	4	6	8
DIAMETER CYLINDER, INCHES.....	2½	3	3½	4
Lever and Wood Handle.....	\$1.50	\$1.50	\$1.50	\$1.50
Wood Handle only.....	.25	.25	.25	.25
Link.....	.50	.50	.75	.75
Cross Head.....	.35	.35	.50	.50
Air Chamber.....	2.50	2.50	3.50	3.50
Valve Plate.....	1.75	1.75	2.75	2.75
Cylinder.....	4.50	5.50	7.00	9.00
Brass-Lined Cylinder.....	7.00	8.50	10.50	13.00
Front Head.....	1.25	1.50	1.75	2.25
Back Head.....	.75	1.00	1.25	1.75
Brass Gland.....	.40	.40	.50	.50
Brass Cap.....	.75	.75	.75	.75
Brass-Cased Piston Rod.....	1.00	1.00	1.25	1.25
Piston Complete, No Rod.....	.75	1.10	1.45	1.80
Piston Plates (3), each.....	.15	.20	.25	.30
Crimped Piston Packings (2) each.....	.15	.25	.35	.45
Nut on end Piston Rod.....	.05	.05	.05	.05
Suction or Discharge Valve Complete.....	.75	.75	1.05	1.05
Suction or Discharge Valve Leather.....	.50	.50	.70	.70
Suction or Discharge Valve Weights (2) each.....	.10	.10	.15	.15
Suction or Discharge Valve Screw and Washers	.05	.05	.05	.05
Brass Drip Plugs, each.....	.25	.25	.25	.25
Suction Pipe Plug.....	.25	.25	.35	.35
Discharge Pipe Plug.....	.15	.15	.25	.25
Air Chamber, Link, Lever and Plank Bolts.....	.08	.08	.08	.08
Plank.....	.50	.50	.50	.50

**GOULDS "NEW DELUGE" PUMPS, FIGS. 829, 836.**

DIAMETER CYLINDER, INCHES.....	6	8½
Wrought Iron Lever.....	\$3.00	\$3.50
Lever Socket.....	1.25	1.50
Large Steel Pin.....	.75	.75
Small Steel Pin.....	.50	.50
Cylinder, Brass-Lined.....	10.50	13.50
Cylinder, Brass Lining only.....	2.00	3.50
Plunger Complete, including Valve.....	3.50	4.00
Plunger only, No Valve.....	2.50	3.00
Plunger Valve or Poppet.....	1.00	1.00
Lower Valve Complete.....	1.00	1.00
Base only, No Suction Flange, Fig. 829.....	5.00	6.00
Suction Flange, Fig. 829.....	1.25	1.50
Base only, No Suction Flange, Fig. 836.....	6.00	7.00
Suction Flange, Fig. 836.....	1.25	1.50
Leather Packing, either Base or Suction Flange.....	.60	.75
Rubber Packing, Plunger or Lower Valve.....	.40	.50
Rubber Bumpers.....	.40	.40
Bolts for Base or Suction Flange.....	.15	.15



"CHALLENGE" D. A. FORCE PUMPS. FIGS. 494, 470, 562, 774,  
581, 770, 604.

No.	2	4	8	12	16
DIAMETER CYLINDER, INCHES.....	2½	3	4	5	6
Air Chamber .....	\$2.50	\$2.50	\$3.00	\$5.00	\$6.00
Brass-Lined Cylinder and Two Valve Seats.....	11.00	11.00	12.00	16.00	20.00
Brass Valve Seats (4) each.....	.50	.50	.65	.80	1.00
Base with Two Brass Valve Seats.....	5.00	5.00	5.00	7.50	9.00
Front Cylinder Head only.....	1.25	1.25	1.25	5.00	6.00
Back Cylinder Head only.....	1.00	1.00	1.00	4.00	5.00
Brass Stuffing Box Cap.....	.50	.50	.75	1.00	1.25
Brass Stuffing Box Gland .....	.40	.40	.50	.75	.85
Leather Packed Piston and Rod complete, except Fig. 604 .....	2.25	2.60	3.30	4.25	4.70
Brass-Cased Plunger Rod only, except Figs. 604.....	1.50	1.50	1.50	2.00	2.00
Leather Packed Piston, complete, No Rod.....	.75	1.10	1.80	2.25	2.70
Piston Plates (3) each.....	.15	.20	.30	.35	.40
Piston Crimp Leather (2) each.....	.15	.25	.45	.60	.75
Nut on Piston Rod.....	.05	.05	.05	.05	.05
Fibre-Packed Piston, complete, No Rod .....	1.75	1.75	2.50	3.50	5.00
Spring-Packed Piston, complete, No Rod.....	7.50	7.50	10.00	12.50	17.50
Leather-Packed Brass Piston, complete, No Rod.....	2.50	2.50	3.50	5.00	7.50
Fibre-Packed, Brass Piston, complete, No Rod.....	4.50	4.50	7.00	10.00	15.00
Spring-Packed Brass Piston, complete, No Rod.....	10.00	10.00	15.00	22.50	30.00
Brass Poppet Valves (4) each.....	.50	.50	.65	.80	1.00
Leather Valves Complete (2) each.....	1.25	1.25	.....	.....	.....
Leather Valves only (2) each.....	.75	.75	.....	.....	.....
Leather Valve Weights only (4) each.....	.25	.25	.....	.....	.....
Leather Valve Screw and Washer.....	.05	.05	.....	.....	.....
Horse-Shoe Links, Front or Back, each.....	.50	.50	.75	1.25	1.25
Knuckle for Plunger Rod.....	.50	.50	.50	.75	.75
Lever Sockets, Front or Back, each.....	1.50	1.75	1.75	2.00	2.25
Lever and Wood Handle .....	1.50	1.50	1.50	2.25	2.25
Lever only.....	1.20	1.20	1.20	1.75	1.75
Wood Handle only.....	.30	.30	.30	.50	.50
Hose Wrench, Figs. 494, 470, 562, 774, 604.....	.25	.25	.25	.50	.50
Brass Suction Bushing .....	1.00	1.00	1.25	1.50	2.25
Brass Discharge Bushing.....	1.00	1.00	1.00	1.25	1.50
Brass Half Suction Coupling.....	.55	.55	.78	1.33	2.07
Brass Suction Swivel or Nut only.....	.35	.35	.50	.85	1.75
Brass Suction Hose Tube.....	.20	.20	.28	.48	.92
Brass Half Discharge Coupling.....	.50	.50	.55	.78	1.33
Brass Discharge Swivel or Nut only.....	.30	.30	.35	.50	.85
Brass Discharge Hose Tube.....	.20	.20	.20	.28	.48
Iron Pipe Suction Nut.....	.35	.35	.45	.60	.75
Iron Pipe Discharge Nut.....	.35	.35	.35	.45	.60
Brass Lead Pipe Elbow and Unions, each.....	1.25	1.25	1.50	.....	.....
Brass Drip and Priming Plugs.....	.25	.25	.25	.35	.35
Rubber Packing, Base or Air Chamber.....	.30	.30	.30	.50	.50
Rubber Packing, Cylinder Heads.....	.20	.20	.20	.30	.30
Long Bolt for Horse-Shoe Link.....	.25	.25	.25	.30	.40
Lever Bolts.....	.15	.15	.15	.20	.20
Cylinder Head Bolts.....	.08	.08	.08	.08	.08
Long Cylinder Bolts with Brass Nuts (4), each complete.....	.35	.35	.35	.35	.....
Long Cylinder Bolts only (4) each.....	.20	.20	.20	.20	.....
Short Cylinder Bolts with Brass Nuts (8) each complete.....	.....	.....	.....	.35	.35
Short Cylinder Bolts only (8) each.....	.....	.....	.....	.20	.20
Brass Nuts for Cylinder Bolts, each.....	.15	.15	.15	.15	.15
Fig. 470, Plank.....	1.00	1.00	1.00	1.00	.....
Fig. 470, Plank Coach Screws (4) each .....	.08	.08	.08	.08	.....
Fig. 562, Cross Bar.....	.....	.....	.....	.75	.75
Fig. 562, Cross Bar Pins and Spring Cotters.....	.....	.....	.....	.25	.25

"CHALLENGE" D. A. FORCE PUMPS. FIGS. 494, 470, 562, 774,  
581, 770, 604.—Continued.

No.	2	4	8	12	16
DIAMETER CYLINDER, INCHES.....	2½	3	4	5	6
Figs. 581, 582, Suction Elbow.....	.....	.....	.....	.....	\$2.75
Figs. 581, 582, Suction Pipe Flange.....	.....	.....	.....	.....	1.25
Figs. 581, 582, Brass Priming Plug.....	.....	.....	.....	.....	.50
Figs. 581, 582, Brass Suction Flange.....	.....	.....	.....	.....	1.50
Figs. 581, 582, Brass Hose Sleeve.....	.....	.....	.....	.....	3.00
Figs. 581, 582, Hose Discharge Piece.....	.....	.....	.....	.....	1.00
Figs. 581, 582, Hose Discharge Piece Bolt.....	.....	.....	.....	.....	.50
Figs. 581, 582, Hose Discharge Nut.....	.....	.....	.....	.....	.50
Figs. 581, 582, Brass Half Discharge Coupling	.....	.....	.....	.....	1.33
Figs. 581, 582, Brass Discharge Swivel or Nut only .....	.....	.....	.....	.....	.85
Figs. 581, 582, Brass Discharge Hose Tube.....	.....	.....	.....	.....	.48

GOULDS "THRESHER" TANK FORCE PUMP, FIG. 1145.

No.	12
DIAMETER CYLINDER, INCHES.....	5
Cylinder .....	\$8.00
Cylinder Front Head .....	1.25
Cylinder Back Head.....	1.00
Cylinder Top Caps or Plugs, Leather-Faced, (2) each.....	.50
Cylinder Poppet Valves, Leather-Faced, (4) each.....	.25
Cylinder Brass Stuffing Box.....	.75
Plunger and Rod Complete.....	3.25
Plunger Rod only .....	1.00
Plunger Complete, no Rod.....	2.25
Plunger Disc .....	.35
Plunger Plates, (2) each .....	.35
Plunger Crimped Packings, (2) each.....	.60
Knuckle for Plunger Rod.....	.50
Link .....	.50
Lever Socket .....	1.50
Wood Lever.....	1.00
Suction Nut .....	.50
Suction Hose Tube.....	.35
Spout Nut.....	.50
Spout .....	.75
Discharge Nut .....	.35
Discharge Hose Tube .....	.35
Rubber Packing, Front and Back Cylinder Head, each.....	.20
Leather Ring Packing for Plugs and Poppet Valves, each.....	.10
Brass Thumb Screws .....	.25
Bolts and Nuts, each.....	.08

GOULDS DIAPHRAGM SUCTION PUMPS. FIGS. 1222 AND 1223.

DIAMETER OF DIAPHRAGM, 13 INCHES .....	Fig. 1222.	Fig. 1223.
Base.....	\$4.50	\$6.00
Head or Top Section.....	3.80	3.80
Plunger Top or Standard.....	1.00	1.00
Plunger Bottom or Spider.....	.90	.90
Brake or Wrought Iron Lever .....	2.50	2.50
Brake or Lever Socket.....	.70	.70
Socket Cross Bar.....	.45	.45
Brass Socket Rocker Pin and Nuts.....	.50	.50
Plunger Valve.....	1.25	.65
Plunger Valve Rubber.....	.45	.45
Plunger Tee Bolts and Nuts, (2) each.....	.35	.35
Long Bolt and Nut, (4) each.....	.25	.25
Lower Valve .....	1.25	.....
Lower Valve Rubber .....	.40	.....
Brass Suction Valve Case.....	.....	2.25
Brass Suction Valve Weight .....	.....	.50
Brass Suction Valve Binders, (2) each .....	.....	.25

## GOULDS DIAPHRAGM SUCTION PUMPS, FIGS. 1222, AND 1223.—Cont.

Diameter of Diaphragm, 13 Inches.....	Fig. 1222	Fig. 1223.
Suction Valve Rubber.....		\$0.40
Suction Valve Brass Binder Screws, (4) each.....		.10
Suction Valve Case Brass Bolts, (4) each.....		.20
Suction Valve Case Rubber Packing.....		.40
Diaphragm.....	\$2.50	2.50

## GOULDS ROTARY FORCE PUMPS, FIGS. 297, 297½, 464, 665, 821, 819.

No.....	1	2	3	4	5	6
Case, Cover, Stuffing Boxes and Caps.....	\$8.00	\$9.00	\$10.00	\$15.00	\$17.00	\$20.00
Case, only.....	5.00	6.00	7.00	10.00	11.00	13.50
Cover, only.....	2.50	2.50	2.50	3.50	4.00	4.50
Cams, each.....	3.50	4.00	4.50	6.00	6.50	9.00
Stuffing Boxes.....	.50	.50	.50	.75	.75	.75
Tight Caps (3) each.....				.50	.50	.50
Base and Drip Plug, Figs. 297, 297½, 819.....	3.00	3.00	3.50	6.00	7.00	8.50
Base and Drip Plug, Fig. 665.....	3.50	3.50	4.25	7.50	9.00	
Base and Drip Plug, Fig. 821.....	3.50	3.50	4.25	7.50	9.00	
Lower Valve Complete.....	.25	.25	.25	.35	.35	.50
Lower Valve Leather, only.....	.15	.15	.15	.20	.20	.30
Lower Valve Weight.....	.10	.10	.10	.15	.15	.20
Lower Valve Screw and Washer.....	.05	.05	.05	.05	.05	.05
Spout and Cap.....	1.00	1.00	1.50	2.00	2.50	3.25
Spout, only.....	.75	.75	.75	1.50	2.00	2.50
Balance Wheel, 14½-in. Dia.....	1.00	1.00	1.00			
Balance Wheel, 20-in. Dia.....	2.00	2.00	2.00	3.00	3.00	
Balance Wheel 36-in Dia.....				6.00	6.00	6.00
Brass Drip Plugs and Priming Plugs.....	.25	.25	.25	.25	.25	.25
Round Head Machine Screws.....	.05	.05	.05	.05	.05	.05
Bolts and Set Screws.....	.08	.08	.08	.08	.08	.08
Metallic Lower Valve extra.....	1.00	1.00	1.00	1.50	1.75	2.50
Fig. 821, Suction Hose Half Coupling.....	.50	.50	.50	.90	1.50	
Fig. 821, Swivel, only, Suction Coupling.....	.25	.25	.25	.40	.75	
Fig. 821, Hose Tube, only, Suction Coupling.....	.25	.25	.25	.40	.75	
Fig. 819, Pulley.....	5.25	5.25	5.25	13.80	13.80	
Fig. 819, Outside Standard and Cap.....	2.00	2.00	2.00	5.00	5.00	
Fig. 819, Outside Standard, only.....	1.50	1.50	1.50	4.25	4.25	
Fig. 819, Outside Standard Cap, only.....	.50	.50	.50	.75	.75	
Fig. 464, Crank.....	.50	.50	.50			
Fig. 464, Suction Nut.....	.35	.35	.35			
Fig. 464, Suction Pipe.....	1.00	1.00	1.25			
Fig. 464, Barrel Attachment or Holder.....	2.00	2.00	2.00			
Fig. 464, Hook.....	.35	.35	.35			
Fig. 464, Discharge Hose Couplings, per pair.....	.37	.37	.37			
Fig. 464, Hose Bands per pair.....	.05	.05	.05			

## GOULDS POWER ROTARY FORCE PUMP, FIGS. 1185½ AND 1281.

No.....	1	2	3	4	5	6
Case, Cover, Stuffing Boxes and Caps.....	\$8.00	\$9.00	\$10.00	\$15.00	\$17.00	\$20.00
Case only.....	5.00	6.00	7.00	10.00	11.00	13.50
Cover Only.....	2.50	2.50	2.50	3.50	4.00	4.50
Stuffing Boxes.....	.50	.50	.50	.75	.75	.75

## GOULDS POWER ROTARY FORCE PUMP, FIGS. 1185½ AND 1281.—Cont.

No.....	1	2	3	4	5	6
Tight Caps, 3 (each).....				\$0.50	\$0.50	\$0.50
Cam with Short Shaft.....	\$3.50	\$4.00	\$4.50	6.00	6.50	9.00
Cam with Long Shaft.....	5.00	5.50	6.00	7.50	8.00	12.00
Intermediate Base.....	1.50	1.50	1.75			
Bed Plate.....	4.00	4.50	5.00	7.00	8.00	20.00
Valve Plate.....				1.50	1.50	3.00
Spout and Cap.....	1.00	1.00	1.50	2.00	2.50	3.25
Spout only.....	.75	.75	1.25	1.50	2.00	2.50
Cap only.....	.35	.35	.35	.50	.50	.75
Pulleys, each.....	2.50	2.50	2.50	4.00	4.00	7.50
Outside Standard Complete.....	1.00	1.25	1.25	2.00	2.50	5.50
Outside Standard only.....				1.25	1.75	4.50
Outside Standard Cap only.....				.75	.75	1.00
Lower Valve.....	.25	.25	.25	.35	.35	.50
Lower Valve Leather.....	.15	.15	.15	.20	.20	.30
Lower Valve Weight.....	.10	.10	.10	.15	.15	.20
Lower Valve Screw and Washer.....	.05	.05	.05	.05	.05	.05
Brass Drip and Priming Plugs.....	.25	.25	.25	.25	.25	.25
Round Head Machine Screws.....	.05	.05	.05	.05	.05	.05
Bolts and Set Screws.....	.08	.08	.08	.08	.08	.08
Metallic Lower Valve.....	1.00	1.00	1.00	1.50	1.75	2.50

## GOULDS SEMI-ROTARY CLOCK FORCE PUMPS, FIGS. 965, 982, 985, 995, 998 AND 1149.

No.....	1	2	3	4	5	6
Iron Case.....	\$1.50	\$1.75	\$2.50	\$3.00	\$3.50	\$4.50
Brass Case.....	3.50	4.00	5.75	6.75	8.00	11.00
Iron Cover.....	.45	.55	.75	.85	1.00	1.20
Brass Cover.....	1.00	1.25	1.50	1.85	2.25	2.75
Iron Gland Cap.....	.15	.15	.25	.35	.50	.65
Brass Gland Cap.....	.35	.35	.60	.75	1.10	1.35
Brass Gland.....	.25	.30	.35	.35	.40	.50
Suction Valve Frame or Seats.....	.75	.90	1.10	1.25	1.50	2.00
Suction Valves, (2) each.....	.25	.30	.35	.40	.45	.50
Discharge Valve Frame or Seats.....	1.00	1.25	1.50	2.00	2.50	3.50
Discharge Valves, (2) each.....	.25	.30	.35	.40	.45	.50
Discharge and Suction Valve Cotter Pins, (4) each.....	.05	.05	.08	.08	.10	.10
Discharge Flange.....	.15	.20	.25	.35	.35	.50
Suction Flange.....	.15	.20	.25	.35	.35	.50
Flange and Case Cover Bolts, each.....	.08	.08	.08	.08	.08	.08
Wrought Iron Lever.....	.25	.30	.35	.45	.50	.50
Wood Handle.....	.25	.30	.35	.45	.50	.50
Iron Handle Nut.....	.05	.05	.05	.08	.08	.08
Wind Mill Crank Arm, Fig. 998.....						.75
Wind Mill Stub End, Fig. 998.....						1.00
Suction and Discharge Surface Packing, each.....	.05	.05	.08	.10	.10	.12
Brass Thumb Screw.....	.10	.10	.10	.10	.10	.10
Discharge Hose Bushing, Fig. 985.....	.35		.35			
Discharge Plug, Fig. 985.....	.04		.04			
Standard or Bracket, Figs. 995 and 982.....	1.00	1.25	1.50	2.00	2.50	3.00
Air Chamber only, Fig. 995.....			1.50	2.25	3.00	4.00
Air Chamber Tube, Fig. 995.....			.15	.20	.25	.30
Air Chamber Tube Nut, Fig. 995.....			.35	.35	.35	.45
Air Chamber Spout, Fig. 995.....			2.00	2.00	3.00	3.00
Air Chamber Spout Nut, Fig. 995.....			.50	.50	.75	.75
Discharge Hose Tube, Fig. 995.....					.25	.25
Discharge Hose Tube Nut, Fig. 995.....					.35	.35
Air Chamber, Fig. 985.....	2.50		3.75			
Base, Fig. 985.....	2.25		3.25			



## GOULDS VERTICAL PISTON PUMPS, FIGS. 1204, 1205.

No.	4	6
DIAMETER CYLINDER, INCHES.....	3	3½
Air Chamber and Crank Case.....	\$9.00	\$11.25
Hand Hole Plate.....	1.00	1.25
Gland.....	.50	.75
Cylinder.....	3.00	4.00
Base.....	3.25	4.00
Crank Shaft Complete with Arm, Fig. 1204.....	3.00	3.50
Crank Shaft Complete with Arm, Fig. 1205.....	4.00	4.50
Crank Shaft Arm.....	1.00	1.00
Crank Shaft Brass Washer.....	.10	.10
Crank Shaft Nut.....	.05	.05
Plunger and Rod Complete.....	4.00	4.50
Plunger Rod.....	.75	.75
Plunger Pin.....	.25	.25
Plunger Complete, No Rod or Pin.....	3.00	3.50
Plunger Top.....	1.50	1.75
Plunger Bottom.....	1.00	1.20
Plunger Brass Poppet Valve.....	.30	.30
Plunger Crimped Packing.....	.25	.35
Lower Valve Complete.....	.35	.35
Lower Valve Leather.....	.20	.20
Lower Valve Weight.....	.15	.15
Lower Valve Screw and Washer.....	.05	.05
Pulley only, Fig. 1204.....	5.25	5.25
Pulley Handle, Fig. 1204.....	.25	.25
Pulleys, Fig. 1205, (2) each.....	5.25	5.25
Shaft Collar, Fig. 1205.....	.50	.50
Rubber Hand Hole Packing.....	.35	.35
Sundry Bolts and Set Screw each.....	.08	.08
Cylinder Packing under Crank Case.....	.25	.25

## GOULDS PORTABLE BRASS AQUAJECT, FIG. 561½.

Handle.....	\$0.50
Brass Plunger Rod.....	1.00
Air Chamber only.....	.75
Air Chamber Brass Gland.....	.25
Air Chamber Ring Packing.....	.10
Brass Cylinder.....	2.00
Brass Plunger Complete, No Rod.....	1.10
Brass Plunger Cage.....	.50
Brass Plunger Follower.....	.35
Ball Valve.....	.10
Plunger Packing.....	.15
Lower Valve Complete.....	.25
Lower Valve Leather.....	.15
Lower Valve Weight.....	.10
Lower Valve Screw.....	.05
Stirrup or Foot Piece.....	.75
Suction Hose Half Coupling, Basket and Bands Complete.....	1.00
Suction Hose only.....	.75
Suction Hose Half Coupling.....	.15
Suction Hose Basket.....	.25
Suction Hose Bands.....	.15
Discharge Hose, Half Coupling, Bands and Nozzle.....	1.75
Discharge Hose only.....	.75
Discharge Hose Half Coupling.....	.10
Discharge Hose Pair Bands.....	.15
Brass Spray Nozzle.....	.75

## GOULDS PORTABLE BRASS FORCE PUMP. FIG. 1129.

Handle Complete.....	\$0.50
Plunger and Rod Complete.....	1.25
Plunger Rod only.....	.75
Plunger and Valve.....	.50

## GOULDS PORTABLE BRASS FORCE PUMP. FIG. 1129.—Continued.

Plunger Valve only.....	\$0.15
Air Chamber.....	1.50
Stuffing Box Cap.....	.25
Brass Cylinder Body.....	1.50
Suction Attachment and Valve.....	.75
Suction Valve only.....	.15
Foot Rest Complete.....	1.25
Foot Rest Clamp or Cap only.....	.20
Foot Rest Standard with Cotter only.....	1.00
Foot Rest Thumb Screw only.....	.10
Discharge Hose, Half Coupling, Connection and Nozzle Complete.....	2.00
Discharge Hose only.....	.75
Discharge Hose Half Coupling only.....	.25
Discharge Hose Nozzle Connection only.....	.25
Discharge or Spray Nozzle only.....	.90
Hose Bands, per pair.....	.15

## GOULDS DOUBLE-ACTING SPRAY PUMPS. FIGS. 905, 905½, 1012.

No.	2	4
DIAMETER OUTER CYLINDER, Inches.....	2½	3
Lever.....	\$0.75	\$0.80
Link.....	.40	.40
Brass-Cased Plunger Complete.....	2.25	2.50
Brass-Cased Plunger Top and Cage only.....	1.75	2.00
Brass Poppet Valve.....	.25	.25
Plunger Leather.....	.15	.15
Plunger Follower.....	.35	.35
Top Cap or Stuffing Box.....	.50	.60
Gland.....	.30	.35
Base.....	1.25	1.35
Lower Valve Complete.....	.25	.25
Lower Valve Leather.....	.15	.15
Lower Valve Weight.....	.10	.10
Cylinder Chamber, Brass-Lined.....	2.50	2.75
Lower Valve Screw and Washer.....	.05	.05
Brass Discharge Bushing.....	.35	.35
Discharge Plug.....	.05	.05
Brass Suction Bushing.....	.50	.65
Brass Suction Basket or Strainer.....	.50	.65
Malleable Pins and Cotters for Link (2), each.....	.15	.15
Malleable Pin and Cotter for Lever.....	.15	.15
Rubber Packing for Top Cap.....	.10	.10
Square Packing for Stuffing Box.....	.20	.25
Sundry Bolts each.....	.08	.08
Suction Pipe for Side of Barrel.....	.35	.50
Suction Pipe for End of Barrel.....	.50	.75
Air Chamber, Fig. 905½.....	1.00	1.25

## GOULDS "CRESCENT" YARD HYDRANTS.

FIGS.	860	811	813	1123	1040
Stock, two Sides.....	\$2.00	\$2.50	.....	.....	\$2.00
Wheel Handle.....	.40	.40	\$0.40	\$0.40	.....
Spring Cutter.....	.02	.02	.02	.02	.....
Brass Screw.....	1.00	1.00	1.00	1.00	.....
Top Cap.....	.30	.30	.50	.50	1.00
Spout.....	.40	.50	.35	.35	.40
Brass Hose Bushing.....	.25	.25	.25	.25	.25
Knuckle or Socket.....	.30	.30	.....	.....	.....
Adjusting Nut.....	.05	.05	.....	.....	.....
Plunger Rod Disc.....	.....	.....	.15	.15	.....
Pipe Clamp.....	.....	.....	.25	.25	.....
Spout Elbow.....	.....	.....	.15	.15	.....
Bolts.....	.10	.10	.....	.....	.10
Brass Valve Case.....	1.25	2.00	2.00	1.25	1.25



## GOULDS "CRESCENT" YARD HYDRANTS.—Continued.

FIGS.	860	811	813	1123	1040
Brass Plunger, with Packings	\$0.80	\$1.00	\$1.00	\$0.80	\$0.80
Brass Swivel	.40	.60	.60	.40	.40
Brass Tube	.35	.50	.50	.35	.35
Plunger Cup Leather	.10	.10	.10	.10	.10
Leather Valve Disc	.02	.02	.02	.02	.02
Screw and Washer	.05	.05	.05	.05	.05
Shield for Valve Case	.40	.40	.40	.40	.40
Lever					.65
Locking Piece					.50

## GOULDS "CRESCENT" STREET WASHERS.

FIGS.	861	812	1240
Top only	\$0.80	\$1.00	\$0.80
Cover	.25	.40	.25
Screw Plate	.20	.20	.20
Key	.20	.20	.20
Brass Hose Bushing	.20	.20	
Brass Screw	1.00	1.00	1.00
Malleable Knuckle	.30	.30	.30
Adjusting Nut	.02	.02	.02
Brass Valve Case	1.25	2.00	1.25
Brass Plunger with Packings	.80	1.00	.80
Brass Swivel	.40	.60	.40
Brass Tube	.35	.50	.35
Plunger Cup Leather	.10	.10	.10
Leather Valve Disc	.02	.02	.02
Screw and Washer	.05	.05	.05
Machine Screws	.05	.05	.05
Discharge Swivel Elbow Complete			1.25
Shield for Valve Case	.40	.40	.40

## GOULDS "STAR" YARD HYDRANT, FIG. 646.

SIZE.	¾ in.	1 in.
Stock Complete, no Pipe or Rod	\$4.40	\$4.40
Stock only	3.00	3.00
Top Cap	.50	.50
Bolts for ditto each	.08	.08
Spout	.40	.50
Flange for Spout	.10	.10
Wheel Handle	.25	.25
Spring Cotter	.02	.02
Brass Screw	1.00	1.00
Malleable Elbow	.40	.50
Bottom Attachment Lock Nut	.35	.35
Bottom Attachment	.75	.90
Bottom Cap	.25	.30
Brass Valve Seat Complete	2.50	3.75
Brass Valve Seat only	1.50	2.25
Plunger Valve with Packing	1.00	1.50
Top Part Plunger Valve	.40	.60
Bottom Part of Plunger Valve	.60	.90
Plunger Valve Packing only	.15	.20
Leather Valve Disc	.05	.05
Screw and Washer	.05	.05
Nut for Bottom Cap	.05	.05
Brass Swivel	.50	.75
Brass Tube for Iron Pipe	.50	.85
Brass Tube for Lead Pipe	.50	.65

## GOULDS "STAR" STREET WASHER, FIG. 647.

SIZE.	¾ in.	1 in.
Case and Cover	\$1.50	\$1.50
Case only	1.00	1.00
Cover only	.40	.40
Inside Plate	.25	.25
Inside Plate Bolts, each	.08	.08
Brass Screw	1.00	1.00
Malleable Discharge Crook	.50	.60
Key	.20	.20
Brass Valve Seat Complete	2.50	3.75
Brass Valve Seat only	1.50	2.25
Plunger Valve with Packing	1.00	1.50
Top Part of Plunger Valve	.40	.60
Bottom Part of Plunger Valve	.60	.90
Plunger Valve Packing only	.15	.20
Leather Valve Disc	.05	.05
Screw and Washer	.05	.05
Brass Swivel	.50	.75
Brass Tube for Iron Pipe	.50	.75
Brass Tube for Lead Pipe	.50	.75
Bottom Cap	.25	.30
Bottom Attachment	.75	.90
Bottom Attachment Lock Nut	.35	.35
Nut for Bottom Cap	.05	.05

## GOULDS ADJUSTABLE CURB BOXES. FIGS. 1159 and 1184.

EXTREME LENGTH, INCHES.	62	72	84
Cap, Fig. 1159	\$0.75	\$0.75	\$0.75
Brass Plug, Fig. 1184	.25	.25	.25
Cap, Fig. 1184	.60	.60	.60
Case or Standard	1.25	1.25	1.25
Key or Wrench	.50	.50	.50
Encasing Pipe	.75	1.05	1.25
Wrought Rod with Fork	.50	.60	.75
Malleable Fork only	.10	.10	.10
Brass Spring	.10	.10	.10

## GOULDS "SUN" AND "NO-SHOCK" HYDRANTS.

FIGS.	1174	1116
Inlet Tube	\$0.50	\$0.50
Inlet Nut or Swivel	.60	.65
Inlet Packing	.05	.05
Valve Case	.75	.70
Bottom Attachment	.50	.50
Automatic Check Valve	.30	.30
Guard Case	.50	.50
Guard Case Set Screw	.05	.05
Lock Nut	.35	.35
Base	.75	.75
Top Attachment	.50	.50
Cap	.50	.50
Cap Bolts (2) each	.25	.25
Lever		.50
Lever Latch		.15
Plunger Complete	1.50	1.50
Plunger Top	.50	.50
Plunger Bottom	.50	.50
Plunger or Valve Nut	.05	.05
Valve Disc	.10	.10
Plunger Crimp	.10	.10
Discharge Spout	.50	.50
Plunger Spring		.25
Brass Screw	1.00	
Wheel Handle	.25	

# INDEX TO FIGURES.

591

FIG.	PAGE.
9	Wood Rod Coupling..... 302
11	Hydraulic and Jetting Swivel..... 310
13	Sand and Clay Auger ..... 309
15	Clay Auger ..... 309
16	Tubular Well Cylinder Shoe..... 303
21	Lifting or Holding Tongs..... 311
23	Sliding or Friction Tongs..... 311
25	Casing Swivel..... 310
32	Earth and Sand Boring Auger..... 309
36	Galvanized Wrought Strainer..... 202
48	Bamboo Extension and Stop Cock..... 266
49	Brass Y Connection..... 265
49½	Brass Y Connection..... 265
51	"Cyclone" Spray Nozzle..... 264
52	"Pacific Cyclone" Spray Nozzle..... 264
55	"Vermorel" Spray Nozzle..... 263
62	"Masson" Spray Nozzle..... 264
65	Coupling for Hose and Iron Pipe..... 265
67	Connection for Hose and Iron Pipe..... 265
68	Forged Coupling for Wood Sucker Rod..... 70
69	"Calla" Spray Nozzle..... 264
69½	"Calla" Spray Nozzle..... 264
70	Brass Suction Pipe Strainer..... 265
71	Brass Suction Pipe Strainer..... 265
76	Valve Rod for Artesian Pump..... 70
77	Wood Sucker Rod and Coupling..... 70
81	"Seneca" Spray Nozzle..... 264
85	Brass Stop Cock..... 265
138	"Goulds Special" Drive Well Point..... 297
138½	Single Screen Well Point..... 298
139	"Goulds Special" Tubular Well Point..... 297
139½	Single Screen Well Point..... 298
140	"Banner" Drive Well Point..... 297
140½	Single Screen Well Point..... 298
141	Water Works Well Point..... 299
141½	Water Works Strainer ..... 300
142	"Eureka" Tubular Well Cylinder..... 304
144	Tubular Well Cylinder..... 305
145	Tubular Well Valve, Two Leather Ball Plunger..... 306
146	Tubular Well Valve, Bale Top, Ball Check..... 306
147	Tubular Well Valve, Two Leather Poppet Plunger..... 306
148	Tubular Well Valve, Bale Top, Poppet Check..... 306
149	Tubular Well Valve, Marcy Plunger..... 306
150	Tubular Well Valve, Marcy Check..... 306
151	Tubular Well Valve, Screw Top, Poppet Check..... 306
151½	Tubular Well Valve, Screw Top, Ball Check..... 306
153	Tubular Well Valve, Four Leather Poppet Plunger..... 306
153½	Tubular Well Valve, Four Leather Ball Plunger..... 306
158	Tubular Well Valve, Bremer Check..... 306
158½	Tubular Well Valve, Bremer Plunger..... 306

FIG.	PAGE.
159	Copper Tank Float..... 81
159½	"Monitor" Pipe Holder..... 312
160	Turned Coupling..... 309
160½	"Little Giant" Pipe Holder ..... 312
161	Special Tool Coupling ..... 309
164	Drop Paddy Drill..... 308
165	Drop Paddy Drill..... 308
166	"Gopher" Drill..... 308
167	Drop Paddy Drill..... 308
168	Rotary Paddy Drill..... 308
168½	Drop Paddy Drill..... 308
169	Round Drill ..... 307
170	Twist Drill..... 307
171	Chisel Drill..... 307
171½	Pipe Lifting Clevis..... 311
172	Hydraulic "Z" Drill ..... 307
172½	W. M. Tank Valve..... 81
173	Twist Drill, Leather Valve..... 307
174	Chisel Drill, Leather Valve ..... 307
175	Enlarging Drill..... 307
176	Clay and Cobblestone Auger..... 309
178	Solid Cross Drill ..... 310
179	Taper Tap..... 311
180	Taper Die..... 311
180½	Rod Lifter..... 310
181	Steel Drive Head..... 303
181½	Rope Hook ..... 310
184	Pipe Lift..... 303
184½	Standard Automatic Pipe Lifter and Holder..... 312
185	Drive Plate..... 303
186½	Babcock Pipe Lift and Holder ..... 312
187	Eastern Steel Shoe..... 303
187½	"Little's" Automatic Pipe Holder..... 312
188½	Inside Pipe Puller..... 311
189	Water Swivel ..... 310
192	Blind or Check Valve..... 309
192½	Outside Pipe Puller..... 312
194	Hydraulic and Jetting Swivel..... 310
194½	Spring Grab..... 311
195	End Pipe Reamer..... 309
195½	Friction Grab..... 311
196	Pulley Block..... 310
196½	Strainer Grab..... 311
197	Drive Top ..... 303
197½	Valve Grab..... 311
200	Cistern Suction Pump, Bolted High Base..... 1
201	Cistern Suction Pump, Large Pattern..... 2
202½	Cistern Suction Pump on Brackets..... 1
205	Pitcher Spout Suction Pump, Open Top..... 5
205½	Pitcher Spout Suction Pump, Closed Top..... 5



FIG.		PAGE.	FIG.		PAGE.
206	"Star" Well Lift Pump, Cast Set.....	14	386	Wrought-Iron Press Screw.....	287
207	"Star" Well Lift Pump, Wrought Set.....	14	390	House Force Pump with Check Valve, on Base.....	115
208	Pitcher Spout Suction Pump, Vacuum Base.....	6	391	House Force Pump with Check Valve, on Plank.....	115
209	Pitcher Spout Suction Pump, Closed Spout.....	6	392	House Force Pump with Air Chamber, on Base.....	116
210	Cistern Suction Pump, Double Rod.....	2	393	House Force Pump with Air Chamber, on Plank.....	116
216	W. M. Force Pump Packing Box Head.....	56	394	House Force Pump with Air Chamber and Cock, on Base..	117
217	W. M. Force Pump Packing Box Head.....	56	395	House Force Pump with Air Chamber and Cock, on Plank	117
232	Malleable Rod Coupling.....	302	398	House Force Pump with Air Chamber, on Base.....	118
232½	Pipe Rod Coupling.....	302	399	House Force Pump with Air Chamber, on Plank.....	118
233½	Hexagon Rod Coupling.....	302	401	"Star" W. M. Force Pump Standard.....	48
234½	Reducer Rod Coupling.....	302	402	"Star" W. M. Force Pump Standard.....	48
236	Deep Well Lift Pump Standard Tight Top.....	34	403	Sewer Trap.....	290
237	Deep Well Force Pump Standard.....	38	407	Goose Neck or Spout.....	81
264	Well Force Pump with Cock Spout.....	22	407 L	Lunkenheimer Globe Valve.....	424
266	W. M. Well Force Pump with Air Chamber.....	84	408 L	Lunkenheimer Angle Valve.....	434
271	D. A. House Force Pump with Check Valve.....	126	412	"Star" W. M. Lift Pump Standard.....	44
273	D. A. House Force Pump with Air Chamber and Cock Spout	126	413	"Southern" W. M. Force Pump Standard.....	49
278	Hand Force Pump.....	129	414 L	Lunkenheimer Horizontal Check Valve.....	425
279	House Force Pump with Pitman for Power.....	129	415 L	Lunkenheimer Angle Check Valve.....	425
281	House Force Pump with Spout Air Chamber.....	123	416	Sewer Trap and Slop Sink.....	291
283	Two-Cylinder Force Pump.....	151	416 L	Lunkenheimer Ball Check Valve.....	425
284	Two-Cylinder Force Pump with Folding Brakes.....	151	417	Cellar Trap.....	291
285	Two-Cylinder Force Pump with Folding Brakes.....	272	417 L	Lunkenheimer Brass Ball.....	425
289	Hand Boiler Feed Pump on Plank.....	237	418	Half Circle Sink.....	290
292	Power Boiler Feed Pump.....	239	418 L	Lunkenheimer Vertical Check Valve.....	425
297	Rotary Force Pump.....	153	419	Slop Sink.....	290
297¼	Large Rotary Force Pump.....	153	420	Hydrant Cess Pool.....	291
299	Sectional View Rotary Pump.....	152	421	Hydrant Cess Pool with Bell Trap.....	291
300	Sectional View Rotary Pump.....	152	422	"Star" W. M. Force Pump Standard.....	46
301	Power Rotary Force Pump.....	162	423	"Star" W. M. Force Pump Standard with Cock Spout.....	47
302	Power Rotary Force Pump.....	163	423 L	Lunkenheimer Composition Disc Globe Valve.....	427
302½	Power Rotary Fire Pump.....	165	424	"Star" Well Force Pump.....	20, 21
303	Electric Rotary Pump.....	167	424 L	Lunkenheimer Composition Disc Radiator Valve.....	427
304	Garden or Fire Engine.....	268	426	"Star" Well Force Pump with Cock Spout.....	20, 21
309	Garden or Fire Engine, Side Suction.....	268	427 L	Lunkenheimer Double Disc Gate Valve.....	429
322	Plumbers' Brass Force Pump.....	243	428	Plumbers' Square Sink.....	289
323	Gas Companies' and Plumbers' Drip Pump.....	244	429	Corner Sink.....	290
338	"Star" D. A. Railroad Force Pump, with Brake.....	88	429 L	Lunkenheimer Quick-Opening Gate Valve.....	429
339	"Star" D. A. Railroad Force Pump, for Power.....	88	430	Burrall's Iron Corn Sheller.....	286
345	Hydraulic Ram.....	137	430 L	Lunkenheimer "Handy" Gate Valve.....	431
345½	Hydraulic Ram.....	137	431	Burrall's Iron Sheller Pieces.....	286
346	Double Hydraulic Ram.....	137	431 L	Lunkenheimer Brass Body Lever Throttle Valve.....	431
346½	Hydraulic Ram.....	137	432 L	Lunkenheimer Iron Body Lever Throttle Valve.....	431
350	Hydraulic Air Chamber.....	81	433 L	Lunkenheimer Pop Safety Valve.....	432
353	Large Steel Amalgam Bell.....	285	434	Sink Coupling for Lead Pipe.....	292
366	Sink Coupling for Iron Pipe.....	292	434 L	Lunkenheimer Pop Safety Valve.....	432
368	Sink Bolt.....	292	435	Sink Strainer.....	292
369	Stable Cess Pool.....	291	440	House Force Pump with Check Valve.....	122
379	Wrought-Iron Press Screw.....	287	441	House Force Pump with Air Chamber.....	122
383	Wrought-Iron Jack Screw.....	286	442	House Force Pump with Air Chamber and Cock Spout.....	123
385	Cast-Iron Jack Screw.....	287	444	Molasses or Hot Liquid Pump.....	3



FIG.	PAGE.
445 L Lunkenheimer "Mocking Bird" Whistle.....	433
446 Artesian Well Working Head.....	59
446 L Lunkenheimer Combination Whistle.....	434
447 L Lunkenheimer Single Bell Chime Whistle.....	433
448 Wind Mill D. A. Well Force Pump.....	84
448 L Lunkenheimer Single Bell Chime Whistle.....	433
449 House Force Pump with Crank Shaft and Fly-Wheel.....	127
449 L Lunkenheimer Single Bell Chime Whistle.....	433
450 D. A. House Force Pump with Crank Shaft and Fly-Wheel..	127
464 Rotary Barrel Force Pump.....	155
465 Swan-Neck Village Fire Engine.....	275
470 "Challenge" D. A. Force Pump.....	142
471 Suction Pipe Foot Valve and Strainer.....	72
473 Suction Pipe Foot Valve and Strainer.....	72
475 Suction Pipe Foot Valve and Strainer.....	72
476 Vertical Check Valve.....	72
480 House Force Pump with Check Valve.....	124
482 Power Boiler Feed Pump.....	238
482 L Lunkenheimer "Senior" Sight Feed Lubricator.....	435
484 Power Boiler Feed Pump.....	238
485 Power Boiler Feed Pump.....	239
486 Well Lift Pump Standard, Open Top.....	33
486 L Lunkenheimer "Junior" Sight Feed Lubricator.....	435
488 L Lunkenheimer "Bull's Eye" for Oil Injector.....	438
489 L Lunkenheimer "Banner" Sight Feed Lubricator.....	440
490 Lever Handle Cock Spout.....	81
491 L Lunkenheimer "Vulcan" Force Feed Lubricator.....	440
492 L Lunkenheimer "Standard" Boiler Oil Injector.....	438
493 L Lunkenheimer "Emerald" Boiler Oil Injector.....	438
495 Hand Boiler Feed Pump on Base.....	237
495 L Lunkenheimer Glass Body Oil Pump.....	436
496 L Lunkenheimer Automatic Needle Valve Oil Feeder.....	437
510 Malleable Drive Cap.....	303
510 L Lunkenheimer "Ideal" Automatic Grease Cup.....	441
511 L Lunkenheimer "Jewel" Automatic Grease Cup.....	442
512 L Lunkenheimer Screw Feed "Marine" Grease Cup.....	443
513 L Lunkenheimer "Tiger" Plain Brass Grease Cup.....	444
514 L Lunkenheimer "Rex" Plain Brass Grease Cup.....	445
514½ "Syphon" W. M. Well Force Pump.....	82
515 Well Rod Joint and Brass Bush.....	96
515 L Lunkenheimer "Pioneer" Glass Oil Cup.....	446
516 Roller Guide for Well Rod.....	96
516 L Lunkenheimer "Victor" Index Glass Oil Cup.....	447
517 L Lunkenheimer "Royal" Sight Feed Oil Cup.....	449
518 Two-Cylinder Force Pump, Wood Levers.....	150
518 L Lunkenheimer "Crown" Index Sight Feed Oil Cup.....	448
520 Two-Cylinder Force Pump, Wrought-Iron Levers.....	150
523 L Lunkenheimer Automatic Rod Cup.....	451
524 Brass Jacket Drive Well Point.....	295
524 L Lunkenheimer Automatic Rod Cup Needle Valve.....	451
524½ Open End Well Point Extension.....	296

FIG.	PAGE.
526 L Lunkenheimer Cylindrical Glass.....	455
526½ Single Barrel Pump.....	96
527 L Lunkenheimer Urn-Shaped Glass.....	455
527½ Double Barrel Pump.....	96
528 L Lunkenheimer Oil Gauge Plain.....	454
529 L Lunkenheimer Oil Gauge with Drain Cock.....	454
530 Factory Hose Cart.....	277
533 L Lunkenheimer Shaft Oiler.....	452
534 L Lunkenheimer Shaft Oiler with Wood Plug.....	452
537 L Lunkenheimer Brass Loose Pulley Oiler.....	453
539 Village Fire Engine.....	276
542 Balanced Hose Cart.....	277
546 L Lunkenheimer "Sentinel" Snap Lever Sight Feed Oil Cup	450
547 Manual Pumping Apparatus for Deep Wells.....	100
547½ Manual and Power Pumping Apparatus for Deep Wells....	100
548 Deep Well Pump Cylinder with Air Chamber.....	66
550 "Star" Well Lift Pump, Open Top.....	8, 9
551 "Star" Well Lift Pump, Open Top.....	8, 9
552 "Stock" Pump.....	15
553 "Star" Well Pump.....	12, 13
553 L Lunkenheimer "Paragon" Lubricator.....	439
554 "Star" Well Pump.....	12, 13
554 L Lunkenheimer Re-grinding Swinging Check Valve.....	426
556 L Lunkenheimer "Gem" Plain Brass Grease Cup.....	445
559½ Deep Well Cylinder with Air Chamber.....	33, 66
561½ Portable Brass Force Pump.....	252
562 "Challenge" Double-Acting Force Pump.....	142
562 L Lunkenheimer Quick Opening Gate Valve.....	429
578 Ship's Main and Bilge Pump, Wood Lever.....	149
579 Ship's Main and Bilge Pump.....	149
581 "Monitor" D. A. Suction Pump.....	143
582 "Monitor" Combined Bilge and Force Pump.....	143
588 L Lunkenheimer Re-grinding Cross Valve.....	424
589 Power Pumping Apparatus for Deep Wells.....	101
591 L Lunkenheimer "Champion" Rod Oil Cup.....	451
592 Deep Well Lift Pump Standard.....	34
593 Deep Well Force Pump Standard.....	39
597 Strong Pony or One-horse Power.....	94
597 L Lunkenheimer Regrinding Swinging Check Valves, Screwed Ends.....	426
597½ Heavy Iron Horse Power.....	94
598 L Lunkenheimer Regrinding Swinging Check, Flanged.....	426
599 L Lunkenheimer Plain Glass Engine Oiler.....	453
600 L Lunkenheimer Double Seated "Clip" Gate, Screwed.....	428
601 "Pacific" W. M. Force Pump on Brackets.....	85
602 L Lunkenheimer "Victor" Gate Valve Screwed Ends.....	430
603 L Lunkenheimer "Victor" Gate Valve Flanged Ends.....	430
604 "Challenge" D. A. Force Pump with Pitman for Power..	144
605 Air Compressor or Vacuum Pump with Pitman Power....	247
607 "Southern Star" Suction Pump.....	7
608 "Southern Star" Force Pump.....	7

FIG.		PAGE.	FIG.		PAGE.
618	Deep Well Cylinders, flanged.....	66	772	Air Compressor or Vacuum Pump with Brake Top.....	247
621	Double-Acting Pump Cylinder.....	66	773	Brass Two-Cylinder Force Pump.....	144
628 L	Lunkenheimer "Handy" Gate Valve, Iron.....	431	774	"Challenge" D. A. Force Pump on Truck.....	271
629 L	Lunkenheimer Pop Safety Valve Angle Outlet.....	432	776½	"Syphon" Wind Mill Well Force Pump.....	82
630	Double-Acting Garden or Fire Engine.....	269	780	Wind Mill Lift Pump Standard, Adjustable Stroke.....	44
630 L	Lunkenheimer Pop Safety Valve Flanged End.....	432	785½	"Alert" Double-Acting Power Pump.....	174
636 L	Lunkenheimer Double-Seated "Victor" Gate, Screwed.....	430	789	Hydraulic Test Pump.....	243
637 L	Lunkenheimer Double-Seated "Victor" Gate, Flanged.....	430	811	"Crescent" Yard Hydrant.....	280
638 L	Lunkenheimer Double-Seated "Clip" Gate, Flanged.....	428	812	"Crescent" Street Washer.....	280
646	"Star" Yard Hydrant.....	282	813	"Crescent" Yard Hydrant.....	281
647	"Star" Street Washer.....	282	814	Adjustable Sink Bracket.....	289
650	Geared Driving Shaft.....	103	819	Power Rotary Force Pump.....	154
650½	Geared Driving Shaft.....	102	821	Rotary Force Pump.....	154
653	D. A. Garden or Fire Engine.....	269	824½	"Challenge" D. A. Power Pump.....	175
656	Wind Mill Tank Valve.....	81	826	Suction Pipe Strainer.....	72
657	Wind Mill Tank Valve.....	81	827	Curb Block.....	284
658	Suction Pipe Strainer.....	300	829	"New Deluge" Suction Pump.....	146
659	Suction Pipe Strainer.....	300	836	"New Deluge" Suction Pump.....	146
660	Suction Pipe Strainer.....	300	845	"Star" Well Lift Pump Standard.....	33
661	Drive Well Washer Point.....	299	846	"Star" Well Lift Pump Standard, Open Top.....	31
662	Brass Jacket Tubular Well Point.....	296	848	"Star" Well Lift Pump.....	10, 11
665	Rotary Force Pump.....	155	848½	"Star" Well Lift Pump, Tight Top.....	10, 11
667	Vertical Check Valve.....	72	850	"Star" Well Lift Pump Standard, Tight Top.....	32
674	"Pacific" Wind Mill Force Pump.....	85	852½	"Star" Well Force Pump.....	18, 19
685	Wind Mill Force Pump Working Head.....	57	853	"Star" Well Force Pump Standard.....	35
686	Wind Mill, Force Pump Working Head.....	57	854	Well Force Pump.....	22
687	Royal Steam Boiler Feed Pump.....	240	855	"Northern Star" Well Force Pump Standard.....	37
690	W. M. Force Pump Working Head.....	57	858	Well Force Pump Standard.....	37
691	Brass-Anchored Cylinder.....	71	860	"Crescent" Yard Hydrant.....	280
692	Gun Packer, with brass attached.....	71	861	"Crescent" Street Washer.....	280
693	Centrifugal Pump.....	169	862	Three-Way Distributing Head.....	54
694	Vertical Submerged Centrifugal Pump.....	169	863	Three-Way Distributing Head.....	54
695	Horizontal Centrifugal Pump.....	170	866	Three-Way Distributing Head.....	54
696	Horizontal Centrifugal Pump, with Primer.....	170	867	Hydraulic Pressure or Test Pump.....	241
707	Wind Mill Force Pump Packing Box Head.....	56	872	Manual and Power Pumping Apparatus for Deep Wells.....	99
711	Overhead Counter-Shaft.....	102	882½	"Star" Well Force Pump with Cock Spout.....	18, 19
712	House Force Pump, with Crank Shaft and Fly-Wheel.....	125	883	"Star" Well Force Pump Standard with Cock Spout.....	36
713	House Force Pump, with Crank Shaft and Fly-Wheel.....	125	884	Strong Pony or One-Horse Gear Pumping Apparatus.....	94
714	House Force Pump, with Pitman for Power.....	124	885	Heavy Horse Gear Pumping Apparatus.....	94
720	Horse Gear and Double Barrel Pump.....	97	887	Deep Well Force Pump Standard.....	38
728	Tubular Well Cylinder.....	305	888	Manual and Power Pumping Apparatus for Deep Wells.....	101
729	Sand Pump and Drill Combined.....	307	894	Horse Gear Pumping Apparatus.....	95
742	Horizontal Check Valve.....	72	895	Power Rotary Fire Pump with Frictional Gearing.....	166
747	"Alert" Double-Acting Force Pump.....	139	896	Power Rotary Fire Pump.....	164
758	Steel Amalgam Bell.....	285	904	Brass Artesian Deep Well Pump.....	68, 69
760	Suction Pipe Foot Valve and Strainer.....	72	905	Standard D. A. Spray Pump.....	254
762	"Star" W. M. Lift Pump Standard.....	42	905½	Standard D. A. Spray Pump with Air Chamber.....	255
763	Deep Well Force Pump Standard, Brake Top.....	39	914	Double-Geared Horse-Power.....	93
764	Wind Mill Well Lift Pump Standard.....	45	920	Triplex Power Water Works Pump.....	194-195
765	Wind Mill Deep Well Force Pump Standard.....	45	922	"Magic" Ham Curing Pump.....	244
766	Union Hand Fire Engine.....	270	923	"Duke" Pitcher Spout Suction Pump.....	4



FIG.	PAGE.
924	Triplex Power Pump..... 181
935	Duplex Water Lifter..... 132
941	High Service Pressure or Test Pump..... 241
944	Special Rotary Force Pump..... 156
947	Triplex Power Suction Pump..... 216
956	Triplex Power Suction Pump..... 217
957	Triplex Power Water Supply Pump..... 180
963	"Sentinel" D. A. Spray Pump..... 258
964	Strainer for Triplex Pumps..... 202
965	Semi-Rotary "Clock" Force Pump..... 158
966	Horizontal Triplex Electric Mine Pump..... 212
969	Triplex Power Stuff Pump..... 230
971	Differential Power Working Head..... 104, 105
978	Differential Power Working Head..... 58
979	Artesian Well Working Head..... 58
982	Semi-Rotary "Clock" Force Pump..... 158
989	"Handy" Knapsack Spray Pump..... 253
995	Semi-Rotary "Clock" Force Pump with Air Chamber..... 159
997	Triplex Power Pressure Pump..... 187
1004	Double-Acting Power Pump..... 174
1007	W. M. Force Pump Packing Box Head..... 56
1008 <sup>1</sup> / <sub>2</sub>	D. A. Garden and Fire Engine..... 270
1009	Triplex Power Pump..... 183
1010	Triplex Power Pump..... 91
1012	Barrel Spray Cart..... 261
1017	Triplex Power Pump for Semi-Fluids..... 231
1018	Well Lift Pump, Open Top..... 8, 9
1019	Well Lift Pump, Tight Top..... 10, 11
1022	D. A. Suction or Vacuum Pump..... 218, 219
1023	New Well Lift Pump Standard, Open Top..... 31
1024	New Well Lift Pump Standard, Tight Top..... 32
1025	"Empire" D. A. Force Pump, Common Top..... 26
1026	"Empire" D. A. Force Pump, Wind Mill Top..... 26
1027	"Empire" D. A. Force Pump, Common Top and Three-way..... 27
1028	"Empire" D. A. Force Pump, W. M. Top and Three-way..... 27
1029	Power Air Pressure or Vacuum Pump..... 248
1030	Differential Power Working Head..... 112
1031	Anti-Freezing W. M. Force Pump Head..... 52
1032	W. M. Lift Pump Standard..... 42
1033	Anti-Freezing W. M. Force Pump Head..... 53
1034	Triplex Hydraulic Pressure Pump..... 235
1035	Plumbers' Brass Force Pump..... 243
1039	Well Lift Pump, Tight Top..... 12, 13
1040	"Crescent" Yard Hydrant..... 281
1043	"New Deluge" Power Suction Pump..... 89
1043 <sup>1</sup> / <sub>2</sub>	"New Deluge" Power Suction Pump..... 89
1045	Anti-Freezing W. M. Force Pump..... 53
1048	Anti-Freezing W. M. Force Pump..... 52
1049	Double-Acting Suction or Vacuum Pump..... 220, 221
1055	W. M. Lift Pump Standard..... 43
1056	W. M. Lift Pump, Top and Base..... 43

FIG.	PAGE.
1057	Artesian Steam Pumping Engine..... 113
1059	Triplex Power Brine Pump..... 233
1061	W. M. Regulator Force Pump Head..... 55
1062	Geared Driving Shaft and Treble Barrel Pump..... 110, 111
1064	Irrigation Pump Cylinder..... 89
1065	Gas Fitters' Proving Pump..... 245
1067	Compression Bibb..... 81
1068	Bucket Spray Pump..... 252
1072	Separate Triplex Power Pump..... 234
1074	Brass "Y"..... 265
1079	Dash Agitator..... 262
1082	Cistern Suction Pump..... 3
1083	Soda Water Pressure Pump..... 242
1084	"Seneca" Spray Nozzles with extension..... 266
1085	"Seneca" Spray Nozzle with extension..... 266
1086	Soda Water Pressure Pump..... 242
1087	Double-Acting Deep Well Working Head..... 108, 109
1088	Double-Acting Deep Well Pump..... 108, 109
1091	Siphon Well Force Pump..... 83
1092	Brass Shut-off..... 265
1095	Double-Acting Triplex Power Pump..... 196-197
1096	Air Compressor or Vacuum Pump..... 247
1100	"Pomona" Spray Pump..... 257
1102	Revolving Agitator..... 262
1103	Two-Discharge "Vermorel" Nozzle..... 263
1104	Three-Discharge "Vermorel"..... 263
1105	Triplex Power Stuff Pump..... 226, 227
1109	Iron Extension Pipe..... 266
1111	"Utility" Well Force Pump..... 23
1113	"Aura" Well Force Pump..... 23
1114	Horizontal Tank Pump..... 176, 177
1116	"No Shock" Self-Closing Hydrant..... 283
1120	Special Lift and Force Oil Pump..... 244
1121	Combined Triplex Pump and Horse Power..... 92
1122	Improved Brass House Force Pump..... 120
1123	"Crescent" Hydrant..... 281
1124	Vertical Suction Pump..... 222, 223
1127	Artesian Well Working Head..... 59
1128	Triplex Stuff Pump, Heavy Pattern..... 228, 229
1129	"Bordeaux" Brass Spray Pump..... 252
1130	Double-Acting Gas or Air Pump..... 245
1131	Two-Row Spraying Attachment..... 266
1132	Four-Row Spraying Attachment..... 266
1135	All Brass Artesian Well Cylinder with Ball Valves..... 67
1135 <sup>1</sup> / <sub>2</sub>	All Brass Artesian Well Cylinder with Spool Valves..... 67
1136	Triplex Vacuum Pump..... 224, 225
1140	Triplex Power Pump for Tank Service..... 182
1141	Deep Well Force Pump Standard..... 49
1145	"Thresher" Double-Acting Force Pump..... 145
1146	"Advance" Double-Acting Well Force Pump..... 28
1147	"Advance" Double-Acting Well Force Pump..... 28



FIG.		PAGE.	FIG.		PAGE.
1148	"Advance" Double-Acting Well Force Pump.....	29	1229	"Universal" Bronze Valve and Seat.....	61
1149	Semi-Rotary "Clock" Force Pump.....	159	1230	Cylinder or Working Barrel, Outside Capped.....	62, 63
1153	Anti-Freezing Well Pump.....	16	1231	Cylinder or Working Barrel, Inside Capped.....	62, 63
1156	"Star" Wall Hydrant and Washer.....	284	1232	Mushroom Strainer.....	72
1157	"Triplex High Pressure Boiler Feed Pump.....	186	1233	D. A. House Force Pump with Crank.....	128
1159	Adjustable Curb Box.....	284	1234	D. A. House Force Pump with Crank.....	128
1161	Odorless Diaphragm Pump.....	148	1235	Cylinder or Working Barrel, Outside Capped.....	64, 65
1162	Two-Cylinder Suction Pump.....	148	1236	Cylinder or Working Barrel, Inside Capped.....	64, 65
1164	Brass Tubular Well Cylinder.....	71	1237	Electric Mine Sinking Pump.....	213
1168	"Universe" House Force Pump.....	119	1238	Large "Kerowater" Spray Pump.....	260
1169	"Universe" House Force Pump.....	119	1239	Rotary Pump.....	156
1170	Brass Cylinder Pitcher Pump.....	4	1240	"Crescent" Street Washer.....	281
1171	"Baltic" Hand Fire Engine.....	271	1241	Brass House Force Pump.....	
1174	"Sun" Hydrant.....	283	1242	Force Pump with Wheel Handle.....	121
1175	"Sun" Street Washer.....	283	1243	Force Pump with Wheel Handle.....	121
1176	Air Pressure Pump.....	249	1244	"Star" Well Force Pump.....	18, 19
1177	Double-Acting Triplex Pump.....	198, 199	1245	"Star" Well Force Pump with Cock.....	18, 19
1181	Centrifugal Dredging Pump.....	172	1246	Cast Cider Press Screw.....	287
1182	Swan-Neck Village Fire Engine.....	273	1247	"Star" Well Force Pump.....	20, 21
1183	Swan-Neck Village Fire Engine.....	274	1248	"Star" Well Force Pump with Cock.....	20, 21
1184	Extension Curb Box.....	284	1249	Working Head.....	58
1185½	Power Rotary Pump.....	157	1250	"New Duplex" Water Lifter.....	131
1186	Double Discharge Shut-off.....	265	1251	Roller Guide.....	110
1187	"Kerowater" Spray Pump.....	259	1252	Well Lift Pump.....	16
1188	"Fruitall" Spray Pump.....	256	1253	Water Conductor.....	81
1190	Power Air Pressure or Vacuum Pump.....	248	1255	"Albany" D. A. Horizontal Force Pump.....	139
1191	Artesian Well Power Working Head.....	106, 107	1257	Centrifugal Pump.....	171
1192	"Vim" Syphon W. M. Force Pump.....	83	1259	Foot Valve.....	72
1193	Power Air Pressure Pump.....	249	1260	Working Head.....	56
1195	Triplex Power Ammonia Pump.....	232	1261	"Stock" Pump.....	15
1196	"Lightning" Air Pressure Pump.....	256	1262	Triplex Working Head.....	110, 111
1203	Brass Air Pump.....	246	1263	Knapsack "Kerowater" Pump.....	253
1204	Vertical Power Pump.....	236	1265	Tank Valve.....	81
1205	Vertical Power Pump.....	236	1266	Barrel Spray Cart.....	261
1206	Heavy Deep Well Lift Pump.....	17	1267	Cylinder or Working Barrel.....	63
1207	Heavy Deep Well Force Pump.....	17	1268	Cylinder or Working Barrel.....	65
1209	Brass Air Pump.....	246	1274	"Seneca" D. A. Force Pump.....	25
1210	Hand Air Pump.....	250	1275	"Seneca" D. A. Force Pump.....	25
1211	"Atlantic" Force Pump with Wood Lever.....	87	1276	"Seneca" D. A. Force Pump.....	29
1212	"Atlantic" Force Pump for Power.....	87	1277	Three-Way Distributing Head.....	51
1213	"Rocker" D. A. Force Pump with lugs.....	140	1278	Three-Way Distributing Head.....	51
1214	"Rocker" D. A. Force Pump with feet.....	140	1279	Cook Strainer.....	300
1215	"Rocker" D. A. Force Pump with A. C. and Cock.....	141	1280	Power, Hand and W. M. Working Head.....	99
1216	"Atlantic" W. M. Force Pump on base.....	86	1281	Power Rotary Force Pump.....	157
1217	"Atlantic" W. M. Force Pump on plank.....	86	1301	"Columbus" Steel Sink.....	288
1218	Horizontal Triplex Mine Pump.....	203, 209	1302	"New Era" Steel Sink.....	288
1219	"Rocker" D. A. Force Pump for Hose.....	141	1303	"New Era" R. R. Steel Sink.....	288
1220	Triplex Electric House Pump.....	205	1304	Sink Backs.....	288
1221	Horizontal D. A. Triplex Mine Pump.....	210, 211	1305	Sink Brackets.....	288
1222	Diaphragm Pump, Bottom Inlet.....	147	1306	Iron Sink Plug.....	292
1223	Diaphragm Pump, Side Inlet.....	147	1307	Iron Sink Back.....	292
1227	D. A. Triplex Power Pump.....	192, 193			



SEP 27 1900





SENECA FALLS, N. Y., U. S. A.

*Dear Sirs :*

It affords us much pleasure to present to you with our compliments a copy of our new and complete catalogue "Pumps for every Service."

In the compiling of this catalogue no effort has been spared to include all data that would be of interest to our friends engaged in the sale and use of Pumps, Hydraulic Machinery, Well Supplies, etc.

We call attention particularly to our complete line of Wrought-Iron Pipe ; Cast and Malleable Fittings ; Brass Goods for steam and water ; Oil Cups ; Pipe Tools, etc.

We trust you will give our book a careful inspection and that you will have occasion to refer to it very often in making up orders for goods in our line. Additional copies of this catalogue will be sent on application.

Thanking you in advance for the acknowledgment of the safe receipt of our book, we remain,

Yours cordially,

THE GOULDS MFG. CO.

---

**Sehr geehrte Herren !**

Unter gleichzeitiger Darbringung unserer besten Grüße haben wir die Ehre, Ihnen ein Exemplar unseres neuen und vollständigen Katalogs, „Pumpen für alle Zwecke,“ zu überreichen.

Bei der Zusammenstellung dieses Katalogs ist die größte Mühe darauf verwandt worden, alle diejenigen Punkte darin zu verzeichnen, die für unsere Freunde von Interesse sein könnten, welche Pumpen, hydraulische Maschinen, Bedarfsgegenstände für Brunnenmacher, u. s. w., entweder selbst gebrauchen, oder welche damit Handel treiben.

Wir machen Sie besonders aufmerksam auf unsere schmiedeeisernen Röhren jeder Art, sowie auf unsere gegossenen und hämmerbaren Zubehörteile ; ferner auf unsere Messinggegenstände für Dampf- und Wasserleitungen, auf unsere Ölkannen, unsere Werkzeuge für die Anlage von Rohrleitungen, u. s. w.

Wir hoffen, daß Sie unser Buch aufmerksam durchsehen werden, und daß sich Ihnen recht oft Gelegenheit bieten wird, dasselbe zu Rate zu ziehen, wenn Sie Bestellungen für die Artikel, welche wir führen, zu machen haben. Auf Wunsch werden Ihnen weitere Exemplare dieses Katalogs zugesandt werden.

Mit der Bitte, uns von dem richtigen Empfange dieses Buches gefälligst unterrichten zu wollen, verbleiben wir,

Hochachtungsvoll,

THE GOULDS MFG. CO.

*Messieurs :*

Nous avons l'honneur de vous adresser avec nos compliments un exemplaire de notre dernier catalogue complet : " Pompes à tous usages."

L'édition de ce catalogue a reçu notre meilleure attention, et tout y est compris ce qui pourrait être d'intérêt à nos amis, faisant le commerce et l'usage de pompes, machines hydrauliques, accessoires de puits, etc.

Nous avons l'avantage d'appeler votre attention particulièrement sur notre assortiment complet de tuyaux en fer forgé, sur nos accessoires fondus et malléables, sur nos appareils de cuivre à vapeur et à eau, sur nos godets à l'huile, sur nos outils pour installer les conduites de tuyaux, etc.

Nous osons espérer que vous examinerez soigneusement notre catalogue et que vous aurez l'occasion d'y revenir souvent, en nous passant des commandes dans notre branche. On enverra d'autres exemplaires de ce livre sur demande.

En vous remerciant d'avance de nous vouloir bien accuser réception du reçu de notre catalogue, agréez, Messieurs, l'expression de

Notre haute considération,

THE GOULDS MFG. CO.

---

*Muy Señores nuestros :*

Tenemos el gusto de remitirles con nuestros respetos, un ejemplar de nuestro nuevo y completo catálogo de bombas para todos los usos.

En la preparación de este catálogo no hemos economizado esfuerzos para conseguir que incluya todos los datos que puedan interesar á nuestros amigos que venden ó usan Bombas, Maquinaria hidráulica, Pertrechos para pozos & &.

Llamamos su atención particularmente á nuestro completo renglón de tubería de hierro forjado, accesorios de hierro fundido y maleable, artículos de latón para agua y vapor, copas de aceite lubricantes, herramientas para trabajos de tubería &.

Suplicanos á Vds. que examinen nuestro libro cuidadosamente, y esperamos que tendrán ocasión de consultarlo á menudo al darnos sus órdenes. Si Vds. lo desearan, podríamos remitirles otros ejemplares para distribución.

Dando á Vds. las gracias anticipadas por su acuse de recibo de nuestro libro, quedamos de Vds. atentos S. S.


THE GOULDS MFG. CO.







LIBRARY OF CONGRESS



0 033 266 353 7